

**SOUTHERN INDIANA GAS AND ELECTRIC COMPANY
d/b/a VECTREN ENERGY DELIVERY OF INDIANA, INC.
(VECTREN SOUTH)**

IURC CAUSE NO. 44910

OFFICIAL
EXHIBITS

**DIRECT TESTIMONY
OF
STEVEN A. HOOVER
DIRECTOR, ENGINEERING**

**IURC
PETITIONER'S 6**
EXHIBIT NO. 6-17
DATE REPORTER

ON

COST ESTIMATES

**SPONSORING PETITIONER'S EXHIBIT NO. 6,
ATTACHMENTS SAH-1 THROUGH SAH-2**

DIRECT TESTIMONY OF STEVEN A. HOOVER

I. INTRODUCTION

Q. Please state your name and business address.

A. My name is Steven A. Hoover. My address is One Vectren Square, Evansville, Indiana, 47708.

Q. By whom are you employed and in what capacity?

A. I am the Director of Engineering for Vectren Utility Holdings, Inc. ("VUHI"), the parent company of Southern Indiana Gas and Electric Company d/b/a Vectren Energy Delivery of Indiana, Inc. ("Vectren South"), Indiana Gas Company, Inc. d/b/a Vectren Energy Delivery of Indiana, Inc. ("Vectren North"), and Vectren Energy Delivery of Ohio.

Q. Please describe your educational background.

A. I received a Bachelor of Science degree in Mechanical Engineering Technology from the University of Southern Indiana in 1990.

Q. Please describe your professional experience.

A. I began my career with Vectren South in 1993 as a plant engineer. Over the years, I have held positions of increasing responsibility, including reliability engineer, performance engineer, production coordinator, and engineering manager of gas distribution engineering, southwest division. Prior to becoming director of gas and electric engineering in July 2016, I was chief engineer of gas engineering.

Q. What are your present duties?

A. I have responsibility for gas and electric engineering and technical support for the utility operations of all three VUHI utilities. My specific responsibilities include gas and electric transmission and distribution engineering, gas and electric transmission project management, gas and electric system planning, electric system asset management, and geospatial systems.

Q. Have you previously testified before the Indiana Utility Regulatory Commission ("Commission")?

1 A. Yes. I most recently provided testimony on behalf of Vectren South and Vectren North
2 in Cause No. 44894 in support of the application for certificates of public convenience
3 and necessity to provide natural gas service to various areas in the joint applicants'
4 territory. I provided testimony on behalf of Vectren South in Cause No. 44429 TDSIC-5
5 and Vectren North in Cause No. 44430 TDSIC-5 in support of capital investments
6 related to compliance and TDSIC projects. I provided testimony on behalf of Vectren
7 North in support of the engineering evaluation and estimated costs for the Lafayette
8 Area Gas System Reliability Improvements in Cause No. 44430 TDSIC-3 and also
9 testified in Cause No. 44563 to describe how Vectren North planned to assume
10 responsibility for customers formerly served by Snow & Ogden.

11
12 **Q. What is the purpose of your testimony in this proceeding?**

13 A. I will describe the methodology utilized by Vectren South to develop cost estimates for
14 the projects that make-up our seven year transmission and distribution system
15 improvement plan (the "TDSIC Plan"). I will also sponsor the cost estimates for
16 individual projects.

17
18 **Q. Are you sponsoring any exhibits in this proceeding?**

19 A. Yes. I am sponsoring the following exhibits in this proceeding:

- 20 • Petitioner's Exhibit No. 6, Attachment SAH-1: Project Cost Estimation Level 2
- 21 • Petitioner's Exhibit No. 6, Attachment SAH-2: Project Cost Estimation Level 4

22
23
24 **II. COST ESTIMATES**

25
26 **Q. Please describe the methodology utilized by Vectren South to develop criteria for
27 estimates of the projects that comprise the TDSIC Plan.**

28 A. Vectren South's methodology for developing cost estimates was a comprehensive and
29 detailed process utilizing both internal and external subject matter experts. The first step
30 in the cost estimation process was to identify those projects to be included in the TDSIC
31 Plan. Projects were identified using a three pronged approach including risk modeling,
32 subject matter expert assessment of existing equipment and systems, and subject
33 matter expert evaluation of emerging technologies. The testimony of Vectren South's

1 witness Lynnae K. Wilson describes the project identification and selection process in
2 greater detail. From this process, over 2,300 potential projects were identified. Vectren
3 South intends to pursue 825 of these projects during the seven year plan and has
4 developed cost estimates for an additional 556 projects that may be substituted into the
5 TDSIC Plan. Vectren South made its initial prioritizations based on risk analysis and
6 efficiencies in combining like work in close geographic proximity. Vectren South then
7 developed high level preliminary estimates based on the type and quantity of work for
8 each project – the “work scope” - and historical cost information for the work activities.
9 The projects were tentatively grouped into each year of the program using the individual
10 preliminary estimates and the projected annual TDSIC Plan budget. Thus, the
11 preliminary estimates and priorities were used to develop a draft schedule for the TDSIC
12 Plan. The Vectren South Engineering team then determined all projects in the TDSIC
13 Plan would be estimated consistent with the recommended practices of AACE
14 International (“AACE”), formerly Association for the Advancement of Cost Engineering
15 International.
16

17 **Q. What is the AACE and why did Vectren South use this organization’s**
18 **recommended practices for classifying the estimates?**

19 A. AACE is an association dedicated to furthering the concepts for total cost management
20 and cost engineering. The association is a recognized leader in the field of cost
21 estimating and has published many guides and recommended practices referenced and
22 utilized by a variety of industries to establish standardized criteria and ranges for project
23 estimates. Vectren South understands the need to provide accurate estimates with the
24 appropriate level of precision for the TDSIC Plan and the AACE’s recommended
25 practices establish a well-known and trusted framework to accomplish this objective.
26 AACE specifies five estimate classes, with Class 1 estimates representing those projects
27 that have greatest level of detail and an accuracy range of -10% to 15% and Class 5
28 having the least amount of detail with an expected accuracy range of -50% to 100%.
29

30 **Q. What AACE cost estimate class did Vectren South utilize for the projects in the**
31 **TDSIC Plan?**

32 A. Projects planned to be completed in the first two years of the TDSIC Plan were designed
33 to a Class 2 criteria and the remaining projects have been designed to AACE Class 4

estimate criteria. Class 2 estimates, which have accuracy ranges of -15% to +20%, balance the level of detail and confidence in design with appropriate engineering resource utilization to ensure accurate estimates and work plans are developed for projects to be executed in the next one to two years. Class 4 estimates have an accuracy ranges of -30% to +50% and are appropriate for projects to be completed beyond the two year horizon by balancing a reasonable level of work scope detail and estimate accuracy while effectively utilizing engineering resources. The following table describes the characteristics of Class 4 and Class 2 cost estimates:

ESTIMATE CLASS	PRIMARY CHARACTERISTICS	SECONDARY CHARACTERISTICS		
	MATURITY LEVEL OF PROJECT DEFINITION DELIVERABLES Expressed as % of complete definition	END USAGE Typical purpose of estimate	METHODOLOGY Typical estimating method	EXPECTED ACCURACY RANGE Typical variation in low and high ranges
Class 4	1% to 15%	Study or feasibility	Equipment factored or parametric models	L: -15% to -30% H: +20% to +50%
Class 2	30% to 75%	Control or bid/tender	Detailed unit cost with forced detailed takeoff	L: -5% to -15% H: +5% to +20%

Note: The above table has been re-produced using data from "AACE International Recommended Practice No.18R-97: COST ESTIMATE CLASSIFICATION SYSTEM - AS APPLIED IN ENGINEERING, PROCUREMENT, AND CONSTRUCTION FOR THE PROCESS INDUSTRIES, Rev. November 29,2011; http://www.aacei.org/toc/toc_18R-97.pdf"

Designing all projects to a Class 2 accuracy level is not an effective or efficient use of resources due to potential changes in work scope and fluctuating material and labor

costs that occur with the passage of time. The Class 4 estimates will be refined about a year in advance of execution and then updated in the TDSIC Plan. This level of detail is consistent with the requirements of Senate Bill 560¹ (the "TDSIC Statute") as they have been construed by the Commission in previous orders. With this criteria established, the estimates were developed with a combination of internal and external engineering resources using Vectren South's engineering systems and standards.

Q. Why did Vectren South utilize external engineering firms to assist in the development of the cost estimates?

A. Over 2,300 projects were identified for potential inclusion in the TDSIC Plan, of which 1,381 total projects were selected for detailed analysis, including design and estimation, in the seven year plan and as potential substitution projects. Vectren South's electric engineering department has enough internal resources to manage only a portion of the project load included in the TDSIC Plan. Given the volume of work necessary to conduct the appropriate cost analysis, Vectren South leveraged the expertise, experience, and different perspective of external engineering firms for the development of estimates for some distribution projects and the more complex transmission and substation projects.

Q. Which engineering firms were utilized to develop these cost estimates?

A. Black and Veatch ("B&V"), EN Engineering ("ENE") and Commonwealth Associates ("CA") were employed to develop Vectren South's cost estimates. B&V and CA were engaged to complete estimates for some transmission and substation projects. ENE provided estimating services for some distribution projects.

Q. Why did Vectren South select these firms?

A. Vectren South, through various engineering services engagements with B&V over the years, has developed a good understanding of their capabilities and quality of work. In addition, B&V recently worked with Duke and NIPSCO providing similar plan development services. B&V was engaged to supplement internal Vectren South resources in the design and estimation of transmission and substation projects. Vectren South also has worked with CA on transmission line projects. Because B&V focuses

¹ Indiana Code Chapter 8-1-39 ("TDSIC Statute").

1 their engineering efforts on the transmission and substation areas and does not maintain
2 internal resources to perform design and estimating for electric distribution projects, ENE
3 was engaged to supplement the distribution design and estimating activities related to
4 the TDSIC Plan. ENE has been working with Vectren South for the past eight years
5 providing various engineering services. ENE is familiar with Vectren South's system,
6 estimating applications, standards and estimating methodology which prepared them to
7 develop estimates for the distribution projects. These three firms supplemented Vectren
8 South's design and estimating expertise for the TDSIC Plan development.
9

10 **Q. Which projects in the TDSIC Plan were estimated in collaboration with B&V, CA**
11 **and ENE resources?**

12 A. Vectren South's engineering group collaborated with B&V, CA and ENE resources to
13 develop estimates for projects in the following programs:

- 14 • Optical Ground Wire ("OPGW") installation
- 15 • Supervisory Control and Data Acquisition ("SCADA") Upgrades
- 16 • Transmission Line Looping
- 17 • System Protection Relay Upgrades
- 18 • 12kV Circuit Rebuilds and Looping
- 19 • 4kV Conversions
- 20 • Distribution Capacitor Replacements
- 21 • Underground Cable Replacements and Looping
- 22 • Underground Network Upgrades
- 23 • Substation Circuit Breaker Replacements
- 24 • Substation Transformer Replacements
- 25 • Transmission Line Rebuilds
- 26 • Transmission Capacitor Replacements
- 27 • East West Transmission Line
- 28 • Instrument Transformer Replacements
- 29 • Underslung Replacements

30
31 **Q. Did Vectren South develop any project cost estimates without the assistance of**
32 **these external firms?**

1 A. Yes. Vectren South's transmission, substation and distribution engineering and
2 information technology teams completed 100% of the estimating efforts for the following
3 programs:

- 4 • Substation Battery System Replacements
- 5 • Substation Arrestor Replacements
- 6 • Substation Physical Security Upgrades
- 7 • PCB Transformer Replacements
- 8 • Distribution Automation
- 9 • Wood Pole Replacements
- 10 • Mobile Asset Data Collection
- 11 • Geomagnetic Disturbance Protection

12
13 **Q. Did Vectren South incur costs in the development and support of the TDSIC Plan?**

14 A. Yes. Vectren South will incur an estimated \$3.7 million in costs with external firms,
15 made up of plan development, engineering/cost estimation, risk model creation, and
16 case support.

17
18 **Q. How were the project cost estimates developed?**

19 A. The process used for all project estimations considered material and labor quantities
20 associated with the defined scopes of work and Vectren South's Engineering and
21 Construction Standards. All estimators, whether internal Vectren South or external B&V,
22 CA or ENE resources, used a consistent set of base cost assumptions including
23 appropriate labor rates, material costs, and other factors such as complexity of the work
24 and location. Supplementing these base assumptions were additional activities and data
25 sources:

- 26 • Site visits with engineering teams to assess locational factors including accessibility
27 and other physical constraints. Where site visits were not completed, aerial
28 photography or geospatial data was utilized to assess locational factors;
- 29 • Costs of recently completed projects of a similar scope;
- 30 • National Electrical Contractors Association ("NECA") Manual of Labor Units;
- 31 • Material and equipment costs from Vectren South's inventory management system
32 supplemented as needed with recent pricing from vendors that supply electric
33 equipment to Vectren South;

- 1 • Overhead costs and labor and material loadings from Vectren South's accounting
- 2 system; and
- 3 • For transmission and substation projects, labor and material data from similar
- 4 projects previously estimated and/or completed by B&V was considered in the
- 5 development of estimates.

6 The specific activities and work items necessary to complete each project were identified
7 and documented to define the work scope. Labor rates and material costs associated
8 with each activity were applied to the appropriate units of the activity to be completed.
9 Labor rates were determined from historical project information and regional labor rate
10 information provided by B&V. Material costs were estimated based on historical project
11 information or quotes from suppliers. The cost estimates include contingency and
12 standard overhead costs (administration, general, engineering, supervision, and material
13 loadings).

14
15 Projects in years one and two of the TDSIC Plan were defined to the level necessary to
16 ensure estimates were sufficiently detailed to comply with AACE Class 2 accuracy
17 ranges. Estimates for transmission, substation and distribution projects planned for
18 years three through seven were primarily developed using estimates for projects with
19 similar scope from years one and two as the basis. Adjustments to the base estimates
20 were made to incorporate significant labor or material differences identified in the years
21 three through seven projects.

22
23 **Q. Do the detailed cost estimates include an escalation to reflect inflation based on**
24 **the year a project is proposed to be constructed?**

25 A. No. Escalation cost was not included in the detailed cost estimates for discrete projects.
26 Instead, escalation for material, labor, and services inflation is calculated in the plan
27 summary worksheet to arrive at the anticipated overall cost of the TDSIC Plan. This
28 eliminates the need to create a new detailed estimate for each project if its scheduled
29 execution year is changed. Vectren South worked with B&V to determine the escalation
30 at 2.7% per year starting in 2018.

31
32 The escalated cost for each project, based on the proposed construction year, is
33 provided in witness Wilson's, Petitioner's Exhibit No. 2, Attachment LKW-1.

1
2 **Q. What is the definition of contingency?**

3 A. Vectren South uses the definition provided by AACE. AACE has defined contingency as
4 an amount added to an estimate to allow for items, conditions, or events for which the
5 state, occurrence, or effect is uncertain and that experience shows will likely result, in
6 aggregate, in additional costs.
7

8 **Q. Has Vectren South included contingencies in the cost estimates?**

9 A. Yes. Estimates for years one and two transmission and substation projects include a
10 15% contingency placed on the labor and engineering. Material contingency was
11 assigned on a sliding scale based on the overall cost of each project. Larger projects
12 received less material contingency compared to smaller projects. This was done to
13 prevent single, large material purchases on projects driving unnecessarily high material
14 contingencies.
15

16 Vectren South, in consultation with B&V, determined to establish the labor, subcontract,
17 equipment, and engineering contingency at 40% for transmission and substation
18 projects in years three through seven of the TDSIC Plan. The higher contingency was
19 necessary to compensate for the reduced project scope definition and engineering
20 development of those projects in the later years of the program.
21

22 Estimates for years one and two distribution projects include a 5% contingency placed
23 on the entire estimate to account for potential unknown labor or material factors. The
24 lower contingency was determined to be suitable for the distribution projects because
25 the project scopes were defined to a high level of detail. Estimates for years three
26 through seven include a 12-18% contingency based on the type of project.
27

28 **Q. How were contingencies used to improve the project estimates?**

29 A. Appropriate levels of contingencies were added to each project cost estimate dependent
30 upon the completeness of the work scope and detailed engineering and complexity of
31 the project. The level of contingency applied to estimates was not the same for all
32 projects. Projects with well-defined work scopes, complete detailed engineering, and
33 less complexity – underground distribution cable replacement, for example – require less

1 contingency. Projects such as transmission line looping are larger in scope and
2 complexity and were not engineered to the same level of detail due to their placement in
3 years three through seven of the TDSIC Plan and therefore received a higher level of
4 contingency.

5
6 All year one and two projects were estimated to meet AACE Class 2 accuracy ranges.
7 However, site visits were conducted for all year one and two distribution and substation
8 projects resulting in a lower applied contingency because project unknowns were
9 minimized. Year one and two transmission projects used Vectren South's engineering
10 documents along with aerial photography and geospatial data instead of site visits, due
11 to terrain and accessibility, and larger contingencies were applied. Detailed engineering
12 has not yet been completed on projects in years three through seven and these Class 4
13 estimates received a higher contingency for unknown factors that can influence project
14 cost.

15
16 **Q. Why is it important to include a contingency in a best estimate?**

17 A. Vectren South's charge is to provide the best estimate for the TDSIC Plan. For projects
18 that extend over multiple years, are very complex, are scheduled for later years in the
19 TDSIC Plan, or where complete detailed engineering has not yet been completed, there
20 are many possible risks and uncertainties that could cause project cost increases. This
21 likelihood must be recognized in a fully transparent "best estimate" and Vectren South's
22 contingency addresses those project uncertainties.

23
24 **Q. Is it common estimating practice to include both contingency and the application
25 of class estimate ranges?**

26 A. Yes. A cost estimate is a prediction of the final, "most likely" cost of a project to be
27 completed in the future. This prediction carries risk and uncertainty which the estimate
28 ranges attempt to address by establishing potential minimum and maximum project
29 costs based on the level of definition of the project work scope. Contingency is a
30 necessary component of the cost estimate which is intended to address items that
31 cannot be quantified at the current level of project definition, but will be necessary to
32 complete the project. The contingency enhances confidence that the project final cost
33 will be within the upper and lower limits of the estimate range.

1
2 **Q. Is Vectren South submitting the project cost estimates to support its TDSIC Plan?**

3 A. Yes, two project cost estimate examples are attached to my testimony as Petitioner's
4 Exhibit No. 6, Attachment SAH-1 and Attachment SAH-2. The other project cost
5 estimates have been submitted as work papers.
6

7 **Q. What level of detail is included in the cost estimates?**

8 A. Vectren South has created a cost estimate for each project included in the TDSIC Plan.
9 The cost estimates include line item break down of the costs of each project including
10 contract labor, material, internal labor, material and labor loadings, engineering costs,
11 land, and contingency. For further detail refer to Petitioner's Exhibit No. 6, Attachment
12 SAH-1 and Attachment SAH-2 which contains example project estimates. All detailed
13 individual project estimate information is included in my work papers.
14

15 **Q. What level of confidence does Vectren South have in its cost estimates?**

16 A. Vectren South has high confidence in the accuracy and completeness of the TDSIC
17 Plan's project cost estimates. Years one and two projects were estimated to meet
18 AACE Class 2 estimate ranges of -15% to +20%. The remaining projects, including the
19 potential substitution projects, were estimated to AACE Class 4 criteria with an expected
20 variance range of -30% to +50%. With the appropriate use of contingency values to
21 account for uncertainty in the project, the projects' actual costs can be expected to fall
22 within these variance ranges.
23

24 **Q. Provide a detailed example of an AACE Class 2 Estimate.**

25 A. Each AACE Class 2 Project Cost Estimate consists of a Preliminary Estimate Summary
26 sheet and a Detailed Estimate Report (labeled Design Estimate Summary Report –
27 Project Cost Summary for Distribution projects). Attached to my testimony as
28 Petitioner's Exhibit No. 6, Attachment SAH-1 is a sample of a Class 2 estimate. As can
29 be seen in the example, the Preliminary Estimate Summary contains a basic description
30 of the work, preliminary estimate details, and a total project cost summary section which
31 provides multiple breakdowns of the construction costs including loadings, overheads,
32 and contingency. The Detailed Estimate Report contains summary pages of the project
33 cost roll-up, detailed lists of activities at each work station – location where construction

1 is being performed, detailed Bill of Materials, and a detailed estimate of labor and
2 material costs for construction activity. Loadings and contingencies for transmission and
3 substation projects are not included on the detailed estimate sheets. Contingencies for
4 distribution projects are not included on the detailed estimate sheets. These cost
5 components are only incorporated in the Preliminary Estimate Summary.
6

7 **Q. Provide a detailed example of a Class 4 Estimate.**

8 A. Each AACE Class 4 Project Cost Estimate consists of a Preliminary Estimate Summary
9 sheet and a Detailed Estimate Report. Attached to my testimony as Petitioner's Exhibit
10 No. 6, Attachment SAH-2 is a sample of a Class 4 estimate. As with the AACE Class 2
11 estimates, the AACE Class 4 Preliminary Estimate Summary for years three through
12 seven projects contains a basic description of the work, preliminary estimate details, and
13 a total project cost summary section. The Detailed Estimate Report sheets contain
14 detailed lists of activities and materials. Loadings and contingencies for transmission
15 and substation projects are not included on the detailed estimate sheets. Contingencies
16 for distribution projects are not included on the detailed estimate sheets. These cost
17 components are only incorporated in the Preliminary Estimate Summary. These details
18 can be seen in the example attached to my testimony.
19

20 **Q. Were any projects estimated differently?**

21 A. Yes. Projects supporting the Substation Physical Security Upgrades program were
22 estimated based on the Standard Vectren South bid process. Vectren South chose to
23 select the largest site as the baseline. Responses from the bid process provided the
24 figures that Vectren South then applied to the other sites to understand the range of total
25 costs of the program.
26

27 The Advanced Distribution Management System and Advanced Metering Infrastructure
28 ("AMI") Programs both went through Vectren South's standard Request for Proposal
29 process. Details related to AMI will be discussed in the testimony of Vectren South
30 witnesses Daniel C. Bugher and Andrew L. Trump.
31

32 **Q. Did Vectren South take any additional steps to assess the accuracy and**
33 **completeness of the estimates?**

1 A. Yes. First, Vectren South engaged B&V to perform a cost estimate review of a minimum
2 of 10% of all transmission and substation projects by an AACE Certified engineer.
3 Second, a minimum of 10% of all distribution projects were reviewed for estimate
4 accuracy by a Vectren South engineer different from the original estimator. Items
5 considered in the secondary review are the cost estimating methodology and historical
6 or other information used in the estimate as compared to the AACE requirements for
7 Class 2 and Class 4 estimates. Information reviewed includes equipment costs, material
8 costs, labor costs bases, and man-hour bases. The reviews found costs of equipment
9 and materials, labor productivity assumptions, and labor rates were reasonable based
10 on comparison against historical data, quotes for recent similar projects, and B&V labor
11 rate studies applicable to project locations.

12
13 In addition to verifying the costs and labor hour bases used for the estimate, the
14 methodology was reviewed for appropriateness of the stated estimate classification in
15 accordance with the AACE. This approach is consistent with how B&V has conducted
16 similar cost estimate reviews for other utility clients for long-range planning studies. As
17 indicated in the AACE table earlier in this testimony, AACE Class 2 and Class 4
18 estimates are applicable to the Vectren South projects and the level of project definition
19 determines the estimate class level.

20
21 Many factors can cause significant changes in material and labor costs from month to
22 month and year to year. In today's global economy, market forces frequently impact
23 major equipment suppliers and their costs. These market impacts to costs are then
24 passed on to equipment suppliers with resulting routine changes to material price
25 quotes. Similarly, contract labor costs can fluctuate significantly in the energy industry
26 based on demand. From a labor cost standpoint, many factors can change the level of
27 effort and cost required to complete a project. Unforeseen changes in site conditions
28 can increase the project duration significantly for one project, when compared to a
29 similar project elsewhere with ideal conditions. This results in the potential for a variety
30 of labor costs depending on a variety of factors.

31
32 It is in this context that reviews were performed with consideration for the expected
33 accuracy range identified for each AACE estimate class. No two cost estimators will

1 arrive at exactly the same cost estimate, even when given the same general scope
2 description of a project. Differences can result from a variety of factors, including the
3 following:

- 4 • Fluctuations and market forces impact material prices every day and can result in
5 large changes to material costs
- 6 • Contract labor costs can fluctuate as demand for experienced labor changes
- 7 • The projects state of development/definition
 - 8 ○ This impacts the level of detailed specification an estimator has for material
9 and equipment, as well as labor cost impacts
- 10 • Understanding of site conditions
 - 11 ○ Not all site conditions can be defined fully when estimating a project cost

12
13 These uncertainty factors with respect to cost estimates are important to keep in context,
14 and thus range percentages and contingency are used to provide realistic estimate class
15 accuracy.

16
17 Vectren South's internal review and B&V's review indicated the cost estimating process
18 and the estimates are reasonable. The level of detail used to develop the Vectren South
19 transmission and distribution project cost estimates is consistent with common practice
20 within the industry.

21
22 **Q. Do these estimates constitute Vectren South's best estimate of the costs for the**
23 **projects in the TDSIC Plan?**

24 **A. Yes.**
25
26

27 **III. CONCLUSION**
28

29 **Q. Does this conclude your direct testimony?**

30 **A. Yes.**

VERIFICATION

I, Steven A. Hoover, Director of Engineering for Vectren Utility Holdings, Inc., under penalty of perjury, affirm that the foregoing representations are true and correct to the best of my knowledge, information and belief.

SOUTHERN INDIANA GAS AND
ELECTRIC COMPANY D/B/A VECTREN
ENERGY DELIVERY OF INDIANA, INC.

By: 

Steven A. Hoover
Director, Engineering

Dated: February 22, 2017

Distribution Modernization Preliminary Estimate Summary			Group ID	Cass AVE CKT	Planned Year	2018		
Maximo WO Number	Oracle Number	Total Project Cost	Maximo Short Description					
13745088			E560_Elec Dist_Cass AVE CKT_4KV CONV_Cass Ave CKT CONV (Riverside Sub) Ph II					
ABM	OC	City	TDSIC Program Category	Project Engineer (VEC/EN)				
Elec System Improve - Distr TDSIC	Evansville	Evansville	4kV Conv	Chapman, Jody	Gravino, H			
Maximo Long Description of Work								
This work order is phase 2 of the Cass Ave 4 kV conversion project. There are total of 3 phases to complete the Cass Ave 4 kV to 12 kV conversion. The Project will transfer the load to Riverside 12 kV. Phase 2 construction includes a circuit tie with John Street 12 kV circuit just North of the Monroe and Venice Street intersection. It consists of 50 new poles,6400' of 336AA sper,2150' of 3/o AWAC msngr,1900' of 310AAAC,1800' of 110AAAC,300' of 310TX,1 -900A Horizontal GOAB Switch, and 35-1PH pole top transformers.								
Preliminary Estimate Details								
Activity Description			Units	UoM	Unit Cost	Extended Cost		
Poles, Towers & Fixtures (Account 364)				Ea				
Overhead Conductors & Devices (Account 365)				Lft				
Underground Conductors & Devices (Account 366 & 367)				Lft				
Line Transformers (Account 368)				Ea				
Services (Account 369 & 370)				Lft				
Street Lighting & Signal systems				Ea				
Removal of Existing Facilities (Poles, OH/UG Conductor, Transformers (Account 373)				LS				
Land				LS				
Permit				LS				
Tree Trimming				LS				
Traffic Control				LS				
Engineering				LS				
					Subtotal			
Total Project Cost Summary								
Cost Category		Project Cost Calculations						
Contract Labor and Overheads						Subtotal		
Engineering		Contingency - Labor and Material						
Material		Subtotal + Contingency						
Land		Administrative & General Loading / Engineering, Supervision & Material Loading						
		Total Project Cost (Subtotal + Contingency + Loadings)						

*Total project cost is in 2016 dollars.

Design Estimate Summary Report – Project Cost Summary

Engineer Lead: HGRAVINO		Cost Center:			Print Date: 09-Dec-16 12:59 PM	
Maximo WO Number 13745088	Oracle Number	Total Project Cost [REDACTED]	Capital Hours [REDACTED]	Service Hours [REDACTED]	Total Hours [REDACTED]	Construction Resource [REDACTED]
Customer Name: Customer Address: Customer Phone:	Invest (Install)					
	Description	Account	Material	Labor	Tool	Total
	ELECTRIC SERVICES	369	[REDACTED]			
	OVERHEAD CONDUCTORS & DEVICES	365				
	POLES, TOWERS, AND FIXTURES	364				
	Invest (Install) Sub Total					
	Loadings (Mtl and Labor)					
	Invest (Install) Total					
Retire (Abandon & Remove)						
Description	Account	Material	Labor	Tool	Total	
LINE TRANSFORMERS	368	[REDACTED]				
OVERHEAD CONDUCTORS & DEVICES	365					
POLES, TOWERS, AND FIXTURES	364					
Retire (Abandon & Remove) Sub Total						
Loadings (Mtl and Labor)						
Retire (Abandon & Remove) Total						
General Description: This work order is phase 2 of the Cass Ave 4 kV conversion project. There are total of 3 phases to complete the Cass Ave 4 k	Electric Transformers (Install)					
	Description	Account	Material	Labor	Tool	Total
	LINE TRANSFORMERS	368	[REDACTED]			
	Electric Transformers (Install) Sub Total					
	Loadings (Mtl and Labor)					
	Electric Transformers (Install) Total					
	Electric Transformers (Remove)					
	Description	Account	Material	Labor	Tool	Total
LINE TRANSFORMERS	368	[REDACTED]				
Electric Transformers (Remove) Sub Total						
Loadings (Mtl and Labor)						
Electric Transformers (Remove) Total						
CUE Numbers and Status Maximo WO#: 13745088 Maximo CUE Number: 78162 Ver: 1 Status: ESTIMATED						

Design Estimate Summary Report – Project Cost Summary

Engineer Lead: HGRAVINO		Cost Center:			Print Date: 09-Dec-16 12:59 PM	
Maximo WO Number 13745088	Oracle Number	Total Project Cost	Capital Hours	Service Hours	Total Hours	Construction Resource
Total Project Cost Summary						
Loading Used for Calculations		Install Plant / Capital Transformer Labor & Tooling (If CPE) Overheads (A&G and E&S) Install: Total Capital Expenditure Retire (Abandon & Remove) Power Plant Project Cost Services				
A&G (Install Only)						
E&S (Install Only)						
Mtl Stores Loading						
Labor Loading						
Travel Time Multiplier						
Loading Rates Current as of		Transformer Labor & Tool (If Not CPE) & Meter Labor & Tool				
12/09/2016 12:54:59 PM		Overheads for Services, Transformers, Meters (A&G and E&S)				
		Services Total				
		Transformers and Meters (Materials Only)				
		Services Total + Meter & Transformer Material				
		Total Project Cost				

Design Estimate Summary Report – Supervisor's Construction

Engineer Lead: HGRAVINO				Cost Center:		Print Date: 09-Dec-16 12:59 PM					
Maximo WO Number 13745088		Oracle Number		Total Project Cost		Capital Hours	Service Hours	Total Hours	Construction Resource		
Station	G- Macro CU	Macro CU	CU	Grand Macro/ Macro / CU Assembly Description					Qty	Operation	Time Rqd
1			0601401	LABOR CONTINGENCIES - OH ELEC DIST / SECONDARY CONDUCTORS						Install	
WO Number: 13745088									Station 1 Sub Total:		0.00
2			0104612	INS POLE BRKT ASSY, SINGLE EQUIP BRKT						Install	
2			0108110	NEUTRAL BRKT ASSEMBLY						Remove	
2			0108110	NEUTRAL BRKT ASSEMBLY						Install	
2			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY						Install	
2			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY						Remove	
2			0306001	CROSS ARM PIN ASSY 8-10 ARM						Install	
2			0308112	8FT SINGLE ARM BRACE ASSY						Remove	
2			0311112	11FT SINGLE ARM BRACE ASSY						Install	
2			0401210	SECONDARY CLEVIS AND SPOOL INSULATOR						Remove	
2			0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDUCT.						Install	
2			0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDUCT.						Remove	
2			0701401	LABOR CONTINGENCIES - ELEC SERVICE						Install	
2			0803002	LTNG ARR ASSY,LINE,3KV						Remove	
2			0809002	LTNG ARR ASSY,LINE 9KV						Install	
2			0821042	POLE GROUND ASSY,ROD						Install	
2			0925010NG	FUSE CUTOOUT ASSY:100A,10T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU						Install	
2			0925015NG	FUSE CUTOOUT ASSY:100A,15T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU						Remove	
2			1005301	TRANS CONNECTION ASSY, W/ANIMAL PROTECTOR 7.2KV/DUAL VOLTAGE (10 TO 333KVA)						Install	
2			1010025	TRANSFORMER, 1PH, PT, CONV, 2400-120/240V, 25KVA						Remove	
2			1030025	TRANSFORMER, 1PH, PT, CONV, 2400X7200-120/240V, 25KVA						Install	
WO Number: 13745088									Station 2 Sub Total:		0.00
3			0104612	INS POLE BRKT ASSY, SINGLE EQUIP BRKT						Install	
3			0104612	INS POLE BRKT ASSY, SINGLE EQUIP BRKT						Remove	
3			0108110	NEUTRAL BRKT ASSEMBLY						Remove	
3			0306001	CROSS ARM PIN ASSY 8-10 ARM						Install	
3			0308112	8FT SINGLE ARM BRACE ASSY						Remove	
3			0311112	11FT SINGLE ARM BRACE ASSY						Install	
3			0401210	SECONDARY CLEVIS AND SPOOL INSULATOR						Remove	
3			0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDUCT.						Remove	
3			0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDUCT.						Install	
3			0601401	LABOR CONTINGENCIES - OH ELEC DIST / SECONDARY CONDUCTORS						Install	
3			0701401	LABOR CONTINGENCIES - ELEC SERVICE						Install	
3			0803002	LTNG ARR ASSY,LINE,3KV						Remove	
3			0809002	LTNG ARR ASSY,LINE 9KV						Install	
3			0821042	POLE GROUND ASSY,ROD						Install	
3			0925015NG	FUSE CUTOOUT ASSY:100A,15T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU						Install	
3			0925040NG	FUSE CUTOOUT ASSY:100A,40T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU						Remove	
3			1005301	TRANS CONNECTION ASSY, W/ANIMAL PROTECTOR 7.2KV/DUAL VOLTAGE (10 TO 333KVA)						Install	

Design Estimate Summary Report – Supervisor's Construction

Engineer Lead: HGRAVINO			Cost Center:		Print Date: 09-Dec-16 12:59 PM				
Maximo WO Number 13745088		Oracle Number		Total Project Cost	Capital Hours	Service Hours	Total Hours	Construction Resource	
Station	G- Macro CU	Macro CU	CU	Grand Macro/ Macro / CU Assembly Description			Qty	Operation	Time Rqd
3			1010050	TRANSFORMER, 1PH, PT, CONV, 2400-120/240V, 50KVA				Remove	
3			1030050	TRANSFORMER, 1PH, PT, CONV, 2400X7200-120/240V, 50KVA				Install	
WO Number: 13745088							Station 3 Sub Total:		0.00
4			0108110	NEUTRAL BRKT ASSEMBLY				Remove	
4			0114712	DEADEND BRKT ASSEMBLY, SPACER				Install	
4			0306001	CROSS ARM PIN ASSY 8-10 ARM				Install	
4			0308216	8FT STD DBLARM BRACE ASSY				Remove	
4			0311218	11FT DOUBLE ARM BRACE ASSY				Install	
4			0401210	SECONDARY CLEVIS AND SPOOL INSULATOR				Install	
4			0403247	CONDUCTOR DEADEND ASSEMBLY, 336 SPC				Install	
4			0405208	PIN INSULATOR ASSY W/ TIE WIRE, DOUBLE, ALUMINUM CONDUCT.				Install	
4			0405208	PIN INSULATOR ASSY W/ TIE WIRE, DOUBLE, ALUMINUM CONDUCT.				Remove	
4			0601401	LABOR CONTINGENCIES - OH ELEC DIST / SECONDARY CONDUCTORS				Install	
4			0701401	LABOR CONTINGENCIES - ELEC SERVICE				Install	
4			0809002	LTNG ARR ASSY,LINE 9KV				Install	
4			0815008	NEUTRAL DEADEND CLAMP ASSY, #6 SOL CU				Remove	
4			0816030	GRIP, PREFORMED, CONDUCTOR, 3/0 AAAC				Install	
4			0816043	GRIP, PREFORMED, CONDUCTOR, 3/0 AWAC				Install	
WO Number: 13745088							Station 4 Sub Total:		0.00
5			0108110	NEUTRAL BRKT ASSEMBLY				Remove	
5			0108110	NEUTRAL BRKT ASSEMBLY				Install	
5			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY				Install	
5			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY				Remove	
5			0306001	CROSS ARM PIN ASSY 8-10 ARM				Install	
5			0308112	8FT SINGLE ARM BRACE ASSY				Remove	
5			0311112	11FT SINGLE ARM BRACE ASSY				Install	
5			0401210	SECONDARY CLEVIS AND SPOOL INSULATOR				Install	
5			0401210	SECONDARY CLEVIS AND SPOOL INSULATOR				Remove	
5			0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDUCT.				Install	
5			0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDUCT.				Remove	
5			0601401	LABOR CONTINGENCIES - OH ELEC DIST / SECONDARY CONDUCTORS				Install	
5			0816130	GRIP PREFORMED, AT EYE NUT, 3/0 ALUM, SERVICE				Install	
5			0821042	POLE GROUND ASSY,ROD				Install	
WO Number: 13745088							Station 5 Sub Total:		0.00
6			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY				Install	
6			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY				Remove	
6			0306001	CROSS ARM PIN ASSY 8-10 ARM				Install	
6			0308216	8FT STD DBLARM BRACE ASSY				Remove	
6			0310216	10FT DBL ARM BRACE ASSY				Install	
6			0401210	SECONDARY CLEVIS AND SPOOL INSULATOR				Install	
6			0403203	CONDUCTOR DEADEND ASSEMBLY, .3-.6 in, 1/0-3/0 ACSR/AAAC				Install	

Design Estimate Summary Report – Supervisor's Construction

Engineer Lead: HGRAVINO				Cost Center:	Print Date: 09-Dec-16 12:59 PM				
Maximo WO Number 13745088		Oracle Number		Total Project Cost	Capital Hours	Service Hours	Total Hours	Construction Resource	
Station	G- Macro CU	Macro CU	CU	Grand Macro/ Macro / CU Assembly Description			Qty	Operation	Time Rqd
6			0403208	CONDUCTOR DEADEND ASSEMBLY, #6 SOL CU				Remove	
6			0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDUCT.				Remove	
6			0405208	PIN INSULATOR ASSY W/ TIE WIRE, DOUBLE, ALUMINUM CONDUCT.				Install	
6			0501016	GUY STRAND ASSY 16M				Install	
6			0501016	GUY STRAND ASSY 16M				Install	
6			0601401	LABOR CONTINGENCIES - OH ELEC DIST / SECONDARY CONDUCTORS				Install	
6			0701401	LABOR CONTINGENCIES - ELEC SERVICE				Install	
6			0815003	NEUTRAL DEADEND CLAMP ASSY, 1/0 - 3/0 ACSR/AAAC				Install	
6			0815008	NEUTRAL DEADEND CLAMP ASSY, #6 SOL CU				Remove	
6			0816130	GRIP PREFORMED, AT EYE NUT, 3/0 ALUM, SERVICE				Install	
6			0821042	POLE GROUND ASSY,ROD				Install	
WO Number: 13745088							Station 6 Sub Total:		0.00
7			0106108	POLE TOP PIN ASSY				Install	
7			0106108	POLE TOP PIN ASSY				Remove	
7			0108110	NEUTRAL BRKT ASSEMBLY				Remove	
7			0108110	NEUTRAL BRKT ASSEMBLY				Install	
7			0135401	POLE:WOOD,35FT LG,4,EMBEDDED EARTH ONLY				Remove	
7			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY				Install	
7			0306001	CROSS ARM PIN ASSY 8-10 ARM				Install	
7			0306001	CROSS ARM PIN ASSY 8-10 ARM				Remove	
7			0308112	8FT SINGLE ARM BRACE ASSY				Remove	
7			0310112	10FT SINGLE ARM BRACE ASSY				Install	
7			0401210	SECONDARY CLEVIS AND SPOOL INSULATOR				Remove	
7			0401210	SECONDARY CLEVIS AND SPOOL INSULATOR				Install	
7			0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDUCT.				Install	
7			0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDUCT.				Remove	
7			0601401	LABOR CONTINGENCIES - OH ELEC DIST / SECONDARY CONDUCTORS				Install	
7			0701401	LABOR CONTINGENCIES - ELEC SERVICE				Install	
7			0821042	POLE GROUND ASSY,ROD				Install	
WO Number: 13745088							Station 7 Sub Total:		0.00
8			0104612	INS POLE BRKT ASSY, SINGLE EQUIP BRKT				Install	
8			0104612	INS POLE BRKT ASSY, SINGLE EQUIP BRKT				Install	
8			0104612	INS POLE BRKT ASSY, SINGLE EQUIP BRKT				Remove	
8			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY				Remove	
8			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY				Install	
8			0306001	CROSS ARM PIN ASSY 8-10 ARM				Install	
8			0306001	CROSS ARM PIN ASSY 8-10 ARM				Remove	
8			0308216	8FT STD DBLARM BRACE ASSY				Remove	
8			0310216	10FT DBL ARM BRACE ASSY				Install	
8			0403203	CONDUCTOR DEADEND ASSEMBLY, .3-.6 in, 1/0-3/0 ACSR/AAAC				Install	
8			0403208	CONDUCTOR DEADEND ASSEMBLY, #6 SOL CU				Remove	

Design Estimate Summary Report – Supervisor's Construction

Engineer Lead: HGRAVINO				Cost Center:		Print Date: 09-Dec-16 12:59 PM						
Maximo WO Number 13745088		Oracle Number		Total Project Cost		Capital Hours		Service Hours	Total Hours	Construction Resource		
Station	G- Macro CU	Macro CU	CU	Grand Macro/ Macro / CU Assembly Description					Qty	Operation	Time Rqd	
8			0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDUCT.						Remove		
8			0405208	PIN INSULATOR ASSY W/ TIE WIRE, DOUBLE, ALUMINUM CONDUCT.						Install		
8			0601401	LABOR CONTINGENCIES - OH ELEC DIST / SECONDARY CONDUCTORS						Install		
8			0701401	LABOR CONTINGENCIES - ELEC SERVICE						Install		
8			0803002	LTNG ARR ASSY,LINE,3KV						Remove		
8			0809002	LTNG ARR ASSY,LINE 9KV						Install		
8			0815003	NEUTRAL DEADEND CLAMP ASSY, 1/0 - 3/0 ACSR/AAAC						Install		
8			0815008	NEUTRAL DEADEND CLAMP ASSY, #6 SOL CU						Remove		
8			0816130	GRIP PREFORMED, AT EYE NUT, 3/0 ALUM, SERVICE						Install		
8			0821042	POLE GROUND ASSY,ROD						Install		
8			0925006NG	FUSE CUTOOUT ASSY:100A,6T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU						Remove		
8			0925010NG	FUSE CUTOOUT ASSY:100A,10T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU						Install		
8			1005301	TRANS CONNECTION ASSY, W/ANIMAL PROTECTOR 7.2KV/DUAL VOLTAGE (10 TO 333KVA)						Install		
8			1010015	TRANSFORMER, 1PH, PT, CONV, 2400-120/240V, 15KVA						Remove		
8			1030025	TRANSFORMER, 1PH, PT, CONV, 2400X7200-120/240V, 25KVA						Install		
WO Number: 13745088										Station 8 Sub Total:		0.00
9			0109310	EQUIPMENT MOUNT ASSY 3-PHASE							Install	
9			0110112	TRANSF CLUSTER MT ASSY 25-100KVA							Install	
9			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY					Remove			
9			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY					Install			
9			0306001	CROSS ARM PIN ASSY 8-10 ARM					Install			
9			0308216	8FT STD DBLARM BRACE ASSY					Remove			
9			0310216	10FT DBL ARM BRACE ASSY					Install			
9			0401210	SECONDARY CLEVIS AND SPOOL INSULATOR					Install			
9			0403203	CONDUCTOR DEADEND ASSEMBLY, .3-.6 in, 1/0-3/0 ACSR/AAAC					Install			
9			0403208	CONDUCTOR DEADEND ASSEMBLY, #6 SOL CU					Remove			
9			0405208	PIN INSULATOR ASSY W/ TIE WIRE, DOUBLE, ALUMINUM CONDUCT.					Install			
9			0601401	LABOR CONTINGENCIES - OH ELEC DIST / SECONDARY CONDUCTORS					Install			
9			0701401	LABOR CONTINGENCIES - ELEC SERVICE					Install			
9			0803002	LTNG ARR ASSY,LINE,3KV					Remove			
9			0809002	LTNG ARR ASSY,LINE 9KV					Install			
9			0809002	LTNG ARR ASSY,LINE 9KV					Install			
9			0809002	LTNG ARR ASSY,LINE 9KV					Install			
9			0815003	NEUTRAL DEADEND CLAMP ASSY, 1/0 - 3/0 ACSR/AAAC					Install			
9			0815008	NEUTRAL DEADEND CLAMP ASSY, #6 SOL CU					Remove			
9			0816130	GRIP PREFORMED, AT EYE NUT, 3/0 ALUM, SERVICE					Install			
9			0821042	POLE GROUND ASSY,ROD					Install			
9			0925015NG	FUSE CUTOOUT ASSY:100A,15T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU					Install			
9			0925015NG	FUSE CUTOOUT ASSY:100A,15T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU					Install			
9			0925015NG	FUSE CUTOOUT ASSY:100A,15T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU					Install			

Design Estimate Summary Report – Supervisor's Construction

Engineer Lead: HGRAVINO				Cost Center:		Print Date: 09-Dec-16 12:59 PM				
Maximo WO Number 13745088		Oracle Number		Total Project Cost		Capital Hours	Service Hours	Total Hours	Construction Resource	
Station	G- Macro CU	Macro CU	CU	Grand Macro/ Macro / CU Assembly Description				Qty	Operation	Time Rqd
9			0925025NG	FUSE CUTOOUT ASSY:100A,25T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU					Remove	
9			1005301	TRANS CONNECTION ASSY, W/ANIMAL PROTECTOR 7.2KV/DUAL VOLTAGE (10 TO 333KVA)					Install	
9			1005301	TRANS CONNECTION ASSY, W/ANIMAL PROTECTOR 7.2KV/DUAL VOLTAGE (10 TO 333KVA)					Install	
9			1005301	TRANS CONNECTION ASSY, W/ANIMAL PROTECTOR 7.2KV/DUAL VOLTAGE (10 TO 333KVA)					Install	
9			1030050	TRANSFORMER, 1PH, PT, CONV, 2400X7200-120/240V, 50KVA					Install	
9			1030050	TRANSFORMER, 1PH, PT, CONV, 2400X7200-120/240V, 50KVA					Install	
9			1030050	TRANSFORMER, 1PH, PT, CONV, 2400X7200-120/240V, 50KVA					Install	
9			1042075	TRANSFORMER, 3PH, PM, 2400/4160Y-208/120V, 75KVA.					Remove	
WO Number: 13745088									Station 9 Sub Total:	
10			0135401	POLE:WOOD,35FT LG,4,EMBEDDED EARTH ONLY					Remove	
10			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY					Install	
10			0501016	GUY STRAND ASSY 16M					Install	
10			0516201	16M GUY & ANCHOR ASSY,10IN TWIN HELIX,24IN FBGL STRAIN INS					Install	
10			0601401	LABOR CONTINGENCIES - OH ELEC DIST / SECONDARY CONDUCTORS					Install	
WO Number: 13745088								Station 10 Sub Total:		0.00
11			0104612	INS POLE BRKT ASSY, SINGLE EQUIP BRKT					Install	
11			0108110	NEUTRAL BRKT ASSEMBLY					Remove	
11			0114712	DEADEND BRKT ASSEMBLY, SPACER					Install	
11			0306001	CROSS ARM PIN ASSY 8-10 ARM					Remove	
11			0308112	8FT SINGLE ARM BRACE ASSY					Remove	
11			0403247	CONDUCTOR DEADEND ASSEMBLY, 336 SPC					Install	
11			0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDUCT.					Remove	
11			0501016	GUY STRAND ASSY 16M					Install	
11			0532201	16M DBL GUY & ANCHOR ASSEMBLY, TRIPLE HELIX ANCHOR					Install	
11			0601401	LABOR CONTINGENCIES - OH ELEC DIST / SECONDARY CONDUCTORS					Install	
11			0701401	LABOR CONTINGENCIES - ELEC SERVICE					Install	
11			0803002	LTNG ARR ASSY,LINE,3KV					Remove	
11			0809002	LTNG ARR ASSY,LINE 9KV					Install	
11			0816043	GRIP, PREFORMED, CONDUCTOR, 3/0 AWAC					Install	
11			0821042	POLE GROUND ASSY,ROD					Install	
11			0925006NG	FUSE CUTOOUT ASSY:100A,6T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU					Remove	
11			0925010NG	FUSE CUTOOUT ASSY:100A,10T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU					Install	
11			1005301	TRANS CONNECTION ASSY, W/ANIMAL PROTECTOR 7.2KV/DUAL VOLTAGE (10 TO 333KVA)					Install	
11			1010025	TRANSFORMER, 1PH, PT, CONV, 2400-120/240V, 25KVA					Remove	
11			1030025	TRANSFORMER, 1PH, PT, CONV, 2400X7200-120/240V, 25KVA					Install	
WO Number: 13745088									Station 11 Sub Total:	
12			0104612	INS POLE BRKT ASSY, SINGLE EQUIP BRKT					Install	
12			0108110	NEUTRAL BRKT ASSEMBLY					Remove	

Design Estimate Summary Report – Supervisor's Construction

Engineer Lead: HGRAVINO				Cost Center:		Print Date: 09-Dec-16 12:59 PM						
Maximo WO Number 13745088		Oracle Number		Total Project Cost		Capital Hours	Service Hours	Total Hours	Construction Resource			
Station	G- Macro CU	Macro CU	CU	Grand Macro/ Macro / CU Assembly Description					Qty	Operation	Time Rqd	
12			0114102	MESSENGER BRKT ASSEMBLY						Install		
12			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY						Remove		
12			0145201	POLE:WOOD,45FT LG,2,EMBEDDED EARTH ONLY						Install		
12			0306001	CROSS ARM PIN ASSY 8-10 ARM						Remove		
12			0308112	8FT SINGLE ARM BRACE ASSY						Remove		
12			0401210	SECONDARY CLEVIS AND SPOOL INSULATOR						Install		
12			0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDUCT.						Remove		
12			0601401	LABOR CONTINGENCIES - OH ELEC DIST / SECONDARY CONDUCTORS						Install		
12			0701401	LABOR CONTINGENCIES - ELEC SERVICE						Install		
12			0803002	LTNG ARR ASSY,LINE,3KV						Remove		
12			0809002	LTNG ARR ASSY,LINE 9KV						Install		
12			0816130	GRIP PREFORMED, AT EYE NUT, 3/0 ALUM, SERVICE						Install		
12			0821042	POLE GROUND ASSY,ROD						Install		
12			0925015NG	FUSE CUTOOUT ASSY:100A,15T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU						Install		
12			0925040NG	FUSE CUTOOUT ASSY:100A,40T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU						Remove		
12			1005301	TRANS CONNECTION ASSY, W/ANIMAL PROTECTOR 7.2KV/DUAL VOLTAGE (10 TO 333KVA)						Install		
12			1010050	TRANSFORMER, 1PH, PT, CONV, 2400-120/240V, 50KVA						Remove		
12			1030050	TRANSFORMER, 1PH, PT, CONV, 2400X7200-120/240V, 50KVA						Install		
WO Number: 13745088										Station 12 Sub Total:		0.00
13			0114102	MESSENGER BRKT ASSEMBLY							Install	
13			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY					Remove			
13			0145201	POLE:WOOD,45FT LG,2,EMBEDDED EARTH ONLY					Install			
13			0306001	CROSS ARM PIN ASSY 8-10 ARM					Remove			
13			0308112	8FT SINGLE ARM BRACE ASSY					Remove			
13			0401210	SECONDARY CLEVIS AND SPOOL INSULATOR					Remove			
13			0401210	SECONDARY CLEVIS AND SPOOL INSULATOR					Install			
13			0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDUCT.					Remove			
13			0701401	LABOR CONTINGENCIES - ELEC SERVICE					Install			
13			0816130	GRIP PREFORMED, AT EYE NUT, 3/0 ALUM, SERVICE					Install			
13			0821042	POLE GROUND ASSY,ROD					Install			
WO Number: 13745088									Station 13 Sub Total:		0.00	
14			0104612	INS POLE BRKT ASSY, SINGLE EQUIP BRKT						Install		
14			0114102	MESSENGER BRKT ASSEMBLY						Install		
14			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY						Remove		
14			0145201	POLE:WOOD,45FT LG,2,EMBEDDED EARTH ONLY						Install		
14			0306001	CROSS ARM PIN ASSY 8-10 ARM						Remove		
14			0308112	8FT SINGLE ARM BRACE ASSY						Remove		
14			0401210	SECONDARY CLEVIS AND SPOOL INSULATOR						Remove		
14			0401210	SECONDARY CLEVIS AND SPOOL INSULATOR						Install		
14			0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDUCT.						Remove		

Design Estimate Summary Report – Supervisor's Construction

Engineer Lead: HGRAVINO				Cost Center:		Print Date: 09-Dec-16 12:59 PM				
Maximo WO Number 13745088		Oracle Number		Total Project Cost		Capital Hours	Service Hours	Total Hours	Construction Resource	
Station	G- Macro CU	Macro CU	CU	Grand Macro/ Macro / CU Assembly Description				Qty	Operation	Time Rqd
14			0601401	LABOR CONTINGENCIES - OH ELEC DIST / SECONDARY CONDUCTORS					Install	
14			0701401	LABOR CONTINGENCIES - ELEC SERVICE					Install	
14			0809002	LTNG ARR ASSY,LINE 9KV					Install	
14			0816130	GRIP PREFORMED, AT EYE NUT, 3/0 ALUM, SERVICE					Install	
14			0821042	POLE GROUND ASSY,ROD					Install	
14			0925010NG	FUSE CUTOOUT ASSY:100A,10T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU					Install	
14			1005301	TRANS CONNECTION ASSY, W/ANIMAL PROTECTOR 7.2KV/DUAL VOLTAGE (10 TO 333KVA)					Install	
14			1030025	TRANSFORMER, 1PH, PT, CONV, 2400X7200-120/240V, 25KVA					Install	
WO Number: 13745088									Station 14 Sub Total:	
15			0104612	INS POLE BRKT ASSY, SINGLE EQUIP BRKT					Install	
15			0108110	NEUTRAL BRKT ASSEMBLY					Install	
15			0109310	EQUIPMENT MOUNT ASSY 3-PHASE					Remove	
15			0114102	MESSENGER BRKT ASSEMBLY					Install	
15			0145201	POLE:WOOD,45FT LG,2,EMBEDDED EARTH ONLY					Install	
15			0306001	CROSS ARM PIN ASSY 8-10 ARM					Remove	
15			0308112	8FT SINGLE ARM BRACE ASSY					Remove	
15			0401210	SECONDARY CLEVIS AND SPOOL INSULATOR					Install	
15			0401210	SECONDARY CLEVIS AND SPOOL INSULATOR					Remove	
15			0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDUCT.					Remove	
15			0701401	LABOR CONTINGENCIES - ELEC SERVICE					Install	
15			0803002	LTNG ARR ASSY,LINE,3KV					Remove	
15			0809002	LTNG ARR ASSY,LINE 9KV					Install	
15			0816130	GRIP PREFORMED, AT EYE NUT, 3/0 ALUM, SERVICE					Install	
15			0821042	POLE GROUND ASSY,ROD					Install	
15			0925010NG	FUSE CUTOOUT ASSY:100A,10T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU					Install	
15			0925025NG	FUSE CUTOOUT ASSY:100A,25T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU					Remove	
15			1005301	TRANS CONNECTION ASSY, W/ANIMAL PROTECTOR 7.2KV/DUAL VOLTAGE (10 TO 333KVA)					Install	
15			1030025	TRANSFORMER, 1PH, PT, CONV, 2400X7200-120/240V, 25KVA					Install	
15			1204030	CAPACITOR ASSY, FIXED BANK, 4KV, 300KVAR					Remove	
15			1204030	CAPACITOR ASSY, FIXED BANK, 4KV, 300KVAR				Remove		
15			1204030	CAPACITOR ASSY, FIXED BANK, 4KV, 300KVAR				Remove		
WO Number: 13745088								Station 15 Sub Total:		0.00
16			0104612	INS POLE BRKT ASSY, SINGLE EQUIP BRKT					Remove	
16			0401210	SECONDARY CLEVIS AND SPOOL INSULATOR					Install	
16			0403247	CONDUCTOR DEADEND ASSEMBLY, 336 SPC					Install	
16			0601401	LABOR CONTINGENCIES - OH ELEC DIST / SECONDARY CONDUCTORS					Install	
16			0701401	LABOR CONTINGENCIES - ELEC SERVICE					Install	
16			0803002	LTNG ARR ASSY,LINE,3KV					Remove	
16			0816043	GRIP, PREFORMED, CONDUCTOR, 3/0 AWAC					Remove	
16			0816130	GRIP PREFORMED, AT EYE NUT, 3/0 ALUM, SERVICE					Install	

Design Estimate Summary Report – Supervisor's Construction

Engineer Lead: HGRAVINO				Cost Center:		Print Date: 09-Dec-16 12:59 PM							
Maximo WO Number 13745088		Oracle Number		Total Project Cost		Capital Hours	Service Hours	Total Hours	Construction Resource				
Station	G- Macro CU	Macro CU	CU	Grand Macro/ Macro / CU Assembly Description					Qty	Operation	Time Rqd		
16			0821042	POLE GROUND ASSY,ROD						Install			
16			0925040NG	FUSE CUTOOUT ASSY:100A,40T,1PH,14.4KV,NON-LOADBREAK,,NON-GRAPHICAL CU						Remove			
16			1010050	TRANSFORMER, 1PH, PT, CONV, 2400-120/240V, 50KVA						Remove			
WO Number: 13745088											Station 16 Sub Total:		0.00
17			0104612	INS POLE BRKT ASSY, SINGLE EQUIP BRKT						Install			
17			0114712	DEADEND BRKT ASSEMBLY, SPACER						Install			
17			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY						Remove			
17			0145201	POLE:WOOD,45FT LG,2,EMBEDDED EARTH ONLY						Install			
17			0308216	8FT STD DBLARM BRACE ASSY						Remove			
17			0401210	SECONDARY CLEVIS AND SPOOL INSULATOR						Install			
17			0403208	CONDUCTOR DEADEND ASSEMBLY, #6 SOL CU						Remove			
17			0403247	CONDUCTOR DEADEND ASSEMBLY, 336 SPC						Install			
17			0501016	GUY STRAND ASSY 16M						Install			
17			0516201	16M GUY & ANCHOR ASSY,10IN TWIN HELIX,24IN FBGL STRAIN INS						Install			
17			0516701	16M HEAD GUY ASSY,24IN FBGL STRAIN INS						Install			
17			0601401	LABOR CONTINGENCIES - OH ELEC DIST / SECONDARY CONDUCTORS						Install			
17			0701401	LABOR CONTINGENCIES - ELEC SERVICE						Install			
17			0809002	LTNG ARR ASSY,LINE 9KV						Install			
17			0815008	NEUTRAL DEADEND CLAMP ASSY, #6 SOL CU						Remove			
17			0816043	GRIP, PREFORMED, CONDUCTOR, 3/0 AWAC						Install			
17			0816130	GRIP PREFORMED, AT EYE NUT, 3/0 ALUM, SERVICE						Install			
17			0816130	GRIP PREFORMED, AT EYE NUT, 3/0 ALUM, SERVICE						Remove			
17			0821042	POLE GROUND ASSY,ROD						Install			
17			0925010NG	FUSE CUTOOUT ASSY:100A,10T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU						Install			
17			1005301	TRANS CONNECTION ASSY, W/ANIMAL PROTECTOR 7.2KV/DUAL VOLTAGE (10 TO 333KVA)						Install			
17			1030025	TRANSFORMER, 1PH, PT, CONV, 2400X7200-120/240V, 25KVA						Install			
WO Number: 13745088											Station 17 Sub Total:		0.00
18			0104612	INS POLE BRKT ASSY, SINGLE EQUIP BRKT						Remove			
18			0104612	INS POLE BRKT ASSY, SINGLE EQUIP BRKT						Install			
18			0114512	ANGLE BRACKET ASSEMBLY, 5-50 DEG, SPACER						Install			
18			0310112	10FT SINGLE ARM BRACE ASSY						Remove			
18			0401210	SECONDARY CLEVIS AND SPOOL INSULATOR						Install			
18			0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDUCT.						Install			
18			0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDUCT.						Remove			
18			0501016	GUY STRAND ASSY 16M						Install			
18			0516201	16M GUY & ANCHOR ASSY,10IN TWIN HELIX,24IN FBGL STRAIN INS						Install			
18			0601401	LABOR CONTINGENCIES - OH ELEC DIST / SECONDARY CONDUCTORS						Install			
18			0701401	LABOR CONTINGENCIES - ELEC SERVICE						Install			
18			0803002	LTNG ARR ASSY,LINE,3KV						Remove			
18			0809002	LTNG ARR ASSY,LINE 9KV						Install			

Design Estimate Summary Report – Supervisor's Construction

Engineer Lead: HGRAVINO				Cost Center:		Print Date: 09-Dec-16 12:59 PM					
Maximo WO Number 13745088		Oracle Number		Total Project Cost		Capital Hours	Service Hours	Total Hours	Construction Resource		
Station	G- Macro CU	Macro CU	CU	Grand Macro/ Macro / CU Assembly Description				Qty	Operation	Time Rqd	
18			0816043	GRIP, PREFORMED, CONDUCTOR, 3/0 AWAC					Install		
18			0816130	GRIP PREFORMED, AT EYE NUT, 3/0 ALUM, SERVICE					Install		
18			0817035	NEUTRAL SWINGING CORNER ASSY, #2-3/0 ACSR/AAAC					Install		
18			0821042	POLE GROUND ASSY,ROD					Install		
18			0925015NG	FUSE CUTOOUT ASSY:100A,15T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU					Install		
18			0925040NG	FUSE CUTOOUT ASSY:100A,40T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU					Remove		
18			1005301	TRANS CONNECTION ASSY, W/ANIMAL PROTECTOR 7.2KV/DUAL VOLTAGE (10 TO 333KVA)					Install		
18			1010050	TRANSFORMER, 1PH, PT, CONV, 2400-120/240V, 50KVA					Remove		
18			1030050	TRANSFORMER, 1PH, PT, CONV, 2400X7200-120/240V, 50KVA					Install		
WO Number: 13745088									Station 18 Sub Total:		0.00
19			0114512	ANGLE BRACKET ASSEMBLY, 5-50 DEG, SPACER					Install		
19			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY					Remove		
19			0145201	POLE:WOOD,45FT LG,2,EMBEDDED EARTH ONLY					Install		
19			0306001	CROSS ARM PIN ASSY 8-10 ARM					Remove		
19			0308216	8FT STD DBLARM BRACE ASSY					Remove		
19			0401210	SECONDARY CLEVIS AND SPOOL INSULATOR					Install		
19			0403208	CONDUCTOR DEADEND ASSEMBLY, #6 SOL CU					Remove		
19			0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDUCT.					Install		
19			0405208	PIN INSULATOR ASSY W/ TIE WIRE, DOUBLE, ALUMINUM CONDUCT.					Remove		
19			0601401	LABOR CONTINGENCIES - OH ELEC DIST / SECONDARY CONDUCTORS					Install		
19			0815008	NEUTRAL DEADEND CLAMP ASSY, #6 SOL CU					Remove		
19			0816043	GRIP, PREFORMED, CONDUCTOR, 3/0 AWAC					Install		
19			0817035	NEUTRAL SWINGING CORNER ASSY, #2-3/0 ACSR/AAAC					Install		
19			0821042	POLE GROUND ASSY,ROD				Install			
WO Number: 13745088								Station 19 Sub Total:		0.00	
20			0108110	NEUTRAL BRKT ASSEMBLY					Remove		
20			0109310	EQUIPMENT MOUNT ASSY 3-PHASE					Remove		
20			0114102	MESSENGER BRKT ASSEMBLY					Install		
20			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY					Remove		
20			0145201	POLE:WOOD,45FT LG,2,EMBEDDED EARTH ONLY					Install		
20			0310112	10FT SINGLE ARM BRACE ASSY					Remove		
20			0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDUCT.					Remove		
20			0803002	LTNG ARR ASSY,LINE,3KV					Remove		
20			0821042	POLE GROUND ASSY,ROD					Install		
20			0925025NG	FUSE CUTOOUT ASSY:100A,25T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU					Remove		
20			1204030	CAPACITOR ASSY, FIXED BANK, 4KV, 300KVAR					Remove		
20			1204030	CAPACITOR ASSY, FIXED BANK, 4KV, 300KVAR					Remove		
20			1204030	CAPACITOR ASSY, FIXED BANK, 4KV, 300KVAR					Remove		
WO Number: 13745088									Station 20 Sub Total:		0.00
21			0104612	INS POLE BRKT ASSY, SINGLE EQUIP BRKT						Install	

Design Estimate Summary Report – Supervisor's Construction

Engineer Lead: HGRAVINO				Cost Center:		Print Date: 09-Dec-16 12:59 PM							
Maximo WO Number 13745088		Oracle Number		Total Project Cost		Capital Hours	Service Hours	Total Hours	Construction Resource				
Station	G- Macro CU	Macro CU	CU	Grand Macro/ Macro / CU Assembly Description					Qty	Operation	Time Rqd		
21			0108110	NEUTRAL BRKT ASSEMBLY						Remove			
21			0114102	MESSENGER BRKT ASSEMBLY						Install			
21			0308112	8FT SINGLE ARM BRACE ASSY						Remove			
21			0308216	8FT STD DBLARM BRACE ASSY						Remove			
21			0403203	CONDUCTOR DEADEND ASSEMBLY, .3-.6 in, 1/0-3/0 ACSR/AAAC						Install			
21			0403208	CONDUCTOR DEADEND ASSEMBLY, #6 SOL CU						Remove			
21			0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDUCT.						Remove			
21			0601401	LABOR CONTINGENCIES - OH ELEC DIST / SECONDARY CONDUCTORS						Install			
21			0699101	MATERIAL CONTINGENCIES - OH ELEC DIST / SECONDARY CONDUCTORS						Install			
21			0809002	LTNG ARR ASSY,LINE 9KV						Install			
21			0815003	NEUTRAL DEADEND CLAMP ASSY, 1/0 - 3/0 ACSR/AAAC						Install			
21			0815008	NEUTRAL DEADEND CLAMP ASSY, #6 SOL CU						Remove			
21			0821042	POLE GROUND ASSY,ROD						Install			
21			0925025NG	FUSE CUTOOUT ASSY:100A,25T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU						Install			
WO Number: 13745088										Station 21 Sub Total:		0.00	
22			0106108	POLE TOP PIN ASSY							Remove		
22			0106108	POLE TOP PIN ASSY							Install		
22			0108110	NEUTRAL BRKT ASSEMBLY							Remove		
22			0108110	NEUTRAL BRKT ASSEMBLY							Install		
22			0401210	SECONDARY CLEVIS AND SPOOL INSULATOR					Install				
22			0401210	SECONDARY CLEVIS AND SPOOL INSULATOR					Remove				
22			0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDUCT.					Remove				
22			0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDUCT.					Install				
22			0501016	GUY STRAND ASSY 16M					Install				
22			0516201	16M GUY & ANCHOR ASSY,10IN TWIN HELIX,24IN FBGL STRAIN INS					Install				
22			0699101	MATERIAL CONTINGENCIES - OH ELEC DIST / SECONDARY CONDUCTORS					Install				
22			0821042	POLE GROUND ASSY,ROD					Install				
WO Number: 13745088											Station 22 Sub Total:		0.00
23			0104612	INS POLE BRKT ASSY, SINGLE EQUIP BRKT							Install		
23			0106108	POLE TOP PIN ASSY						Remove			
23			0106108	POLE TOP PIN ASSY						Install			
23			0108110	NEUTRAL BRKT ASSEMBLY						Install			
23			0401210	SECONDARY CLEVIS AND SPOOL INSULATOR						Remove			
23			0401210	SECONDARY CLEVIS AND SPOOL INSULATOR						Install			
23			0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDUCT.						Remove			
23			0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDUCT.						Install			
23			0601401	LABOR CONTINGENCIES - OH ELEC DIST / SECONDARY CONDUCTORS						Install			
23			0699101	MATERIAL CONTINGENCIES - OH ELEC DIST / SECONDARY CONDUCTORS						Install			
23			0701401	LABOR CONTINGENCIES - ELEC SERVICE						Install			
23			0809002	LTNG ARR ASSY,LINE 9KV						Install			
23			0816130	GRIP PREFORMED, AT EYE NUT, 3/0 ALUM, SERVICE						Install			

Design Estimate Summary Report – Supervisor's Construction

Engineer Lead: HGRAVINO				Cost Center:		Print Date: 09-Dec-16 12:59 PM					
Maximo WO Number 13745088		Oracle Number		Total Project Cost		Capital Hours	Service Hours	Total Hours	Construction Resource		
Station	G- Macro CU	Macro CU	CU	Grand Macro/ Macro / CU Assembly Description				Qty	Operation	Time Rqd	
23			0821042	POLE GROUND ASSY,ROD					Install		
23			0925010NG	FUSE CUTOOUT ASSY:100A,10T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU					Install		
23			1005301	TRANS CONNECTION ASSY, W/ANIMAL PROTECTOR 7.2KV/DUAL VOLTAGE (10 TO 333KVA)					Install		
23			1030025	TRANSFORMER, 1PH, PT, CONV, 2400X7200-120/240V, 25KVA					Install		
WO Number: 13745088								Station 23 Sub Total:		0.00	
24			0104612	INS POLE BRKT ASSY, SINGLE EQUIP BRKT					Install		
24			0104612	INS POLE BRKT ASSY, SINGLE EQUIP BRKT					Remove		
24			0106108	POLE TOP PIN ASSY					Install		
24			0106108	POLE TOP PIN ASSY					Remove		
24			0108110	NEUTRAL BRKT ASSEMBLY					Install		
24			0401210	SECONDARY CLEVIS AND SPOOL INSULATOR					Install		
24			0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDUCT.					Remove		
24			0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDUCT.					Install		
24			0701401	LABOR CONTINGENCIES - ELEC SERVICE					Install		
24			0803002	LTNG ARR ASSY,LINE,3KV					Remove		
24			0809002	LTNG ARR ASSY,LINE 9KV					Install		
24			0816130	GRIP PREFORMED, AT EYE NUT, 3/0 ALUM, SERVICE					Install		
24			0821042	POLE GROUND ASSY,ROD					Install		
24			0925015NG	FUSE CUTOOUT ASSY:100A,15T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU					Install		
24			0925040NG	FUSE CUTOOUT ASSY:100A,40T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU					Remove		
24			1005301	TRANS CONNECTION ASSY, W/ANIMAL PROTECTOR 7.2KV/DUAL VOLTAGE (10 TO 333KVA)					Install		
24			1010050	TRANSFORMER, 1PH, PT, CONV, 2400-120/240V, 50KVA				Remove			
24			1030050	TRANSFORMER, 1PH, PT, CONV, 2400X7200-120/240V, 50KVA				Install			
WO Number: 13745088								Station 24 Sub Total:		0.00	
25			0106108	POLE TOP PIN ASSY					Remove		
25			0106108	POLE TOP PIN ASSY					Install		
25			0108110	NEUTRAL BRKT ASSEMBLY					Install		
25			0401210	SECONDARY CLEVIS AND SPOOL INSULATOR					Remove		
25			0401210	SECONDARY CLEVIS AND SPOOL INSULATOR					Install		
25			0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDUCT.					Install		
25			0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDUCT.					Remove		
25			0601401	LABOR CONTINGENCIES - OH ELEC DIST / SECONDARY CONDUCTORS					Install		
25			0699101	MATERIAL CONTINGENCIES - OH ELEC DIST / SECONDARY CONDUCTORS					Install		
25			0821042	POLE GROUND ASSY,ROD				Install			
WO Number: 13745088								Station 25 Sub Total:		0.00	
26			0104612	INS POLE BRKT ASSY, SINGLE EQUIP BRKT					Install		
26			0104612	INS POLE BRKT ASSY, SINGLE EQUIP BRKT					Remove		
26			0106108	POLE TOP PIN ASSY					Remove		
26			0106108	POLE TOP PIN ASSY					Install		
26			0108110	NEUTRAL BRKT ASSEMBLY					Install		

Design Estimate Summary Report – Supervisor's Construction

Engineer Lead: HGRAVINO			Cost Center:		Print Date: 09-Dec-16 12:59 PM						
Maximo WO Number 13745088		Oracle Number		Total Project Cost		Capital Hours	Service Hours	Total Hours	Construction Resource		
Station	G- Macro CU	Macro CU	CU	Grand Macro/ Macro / CU Assembly Description				Qty	Operation	Time Rqd	
26			0401210	SECONDARY CLEVIS AND SPOOL INSULATOR					Install		
26			0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDUCT.					Remove		
26			0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDUCT.					Install		
26			0699101	MATERIAL CONTINGENCIES - OH ELEC DIST / SECONDARY CONDUCTORS					Install		
26			0701401	LABOR CONTINGENCIES - ELEC SERVICE					Install		
26			0803002	LTNG ARR ASSY,LINE,3KV					Remove		
26			0809002	LTNG ARR ASSY,LINE 9KV					Install		
26			0816130	GRIP PREFORMED, AT EYE NUT, 3/0 ALUM, SERVICE					Install		
26			0821042	POLE GROUND ASSY,ROD					Install		
26			0925010NG	FUSE CUTOOUT ASSY:100A,10T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU					Install		
26			0925015NG	FUSE CUTOOUT ASSY:100A,15T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU					Remove		
26			1005301	TRANS CONNECTION ASSY, W/ANIMAL PROTECTOR 7.2KV/DUAL VOLTAGE (10 TO 333KVA)					Install		
26			1010025	TRANSFORMER, 1PH, PT, CONV, 2400-120/240V, 25KVA					Remove		
26			1030025	TRANSFORMER, 1PH, PT, CONV, 2400X7200-120/240V, 25KVA					Install		
WO Number: 13745088									Station 26 Sub Total:		0.00
27			0104612	INS POLE BRKT ASSY, SINGLE EQUIP BRKT						Remove	
27			0104612	INS POLE BRKT ASSY, SINGLE EQUIP BRKT				Install			
27			0106108	POLE TOP PIN ASSY				Remove			
27			0401210	SECONDARY CLEVIS AND SPOOL INSULATOR				Install			
27			0403203	CONDUCTOR DEADEND ASSEMBLY, .3-.6 in, 1/0-3/0 ACSR/AAAC				Install			
27			0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDUCT.				Remove			
27			0601401	LABOR CONTINGENCIES - OH ELEC DIST / SECONDARY CONDUCTORS				Install			
27			0699101	MATERIAL CONTINGENCIES - OH ELEC DIST / SECONDARY CONDUCTORS				Install			
27			0701401	LABOR CONTINGENCIES - ELEC SERVICE				Install			
27			0803002	LTNG ARR ASSY,LINE,3KV				Remove			
27			0809002	LTNG ARR ASSY,LINE 9KV				Install			
27			0815003	NEUTRAL DEADEND CLAMP ASSY, 1/0 - 3/0 ACSR/AAAC				Install			
27			0816130	GRIP PREFORMED, AT EYE NUT, 3/0 ALUM, SERVICE				Install			
27			0821042	POLE GROUND ASSY,ROD				Install			
27			0925015NG	FUSE CUTOOUT ASSY:100A,15T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU				Install			
27			0925040NG	FUSE CUTOOUT ASSY:100A,40T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU				Remove			
27			1005301	TRANS CONNECTION ASSY, W/ANIMAL PROTECTOR 7.2KV/DUAL VOLTAGE (10 TO 333KVA)				Install			
27			1010050	TRANSFORMER, 1PH, PT, CONV, 2400-120/240V, 50KVA				Remove			
27			1030050	TRANSFORMER, 1PH, PT, CONV, 2400X7200-120/240V, 50KVA				Install			
WO Number: 13745088								Station 27 Sub Total:		0.00	
28			0135401	POLE:WOOD,35FT LG,4,EMBEDDED EARTH ONLY					Install		
28			0501008	GUY STRAND ASSY 8M					Install		
28			0501016	GUY STRAND ASSY 16M					Install		
28			0508601	8M SIDEWALK GUY ASSY,FIBERGLASS STRAIN INS					Install		
28			0516701	16M HEAD GUY ASSY,24IN FBGL STRAIN INS					Install		

Design Estimate Summary Report – Supervisor's Construction

Engineer Lead: HGRAVINO				Cost Center:		Print Date: 09-Dec-16 12:59 PM				
Maximo WO Number 13745088		Oracle Number		Total Project Cost		Capital Hours	Service Hours	Total Hours	Construction Resource	
Station	G- Macro CU	Macro CU	CU	Grand Macro/ Macro / CU Assembly Description				Qty	Operation	Time Rqd
				WO Number: 13745088				Station 28 Sub Total:		0.00
29			0401210	SECONDARY CLEVIS AND SPOOL INSULATOR					Install	
29			0501016	GUY STRAND ASSY 16M					Install	
29			0516201	16M GUY & ANCHOR ASSY,10IN TWIN HELIX,24IN FBGL STRAIN INS					Install	
29			0699101	MATERIAL CONTINGENCIES - OH ELEC DIST / SECONDARY CONDUCTORS					Install	
29			0701401	LABOR CONTINGENCIES - ELEC SERVICE					Install	
29			0816130	GRIP PREFORMED, AT EYE NUT, 3/0 ALUM, SERVICE					Install	
				WO Number: 13745088				Station 29 Sub Total:		0.00
30			0114712	DEADEND BRKT ASSEMBLY, SPACER					Install	
30			0145201	POLE:WOOD,45FT LG,2,EMBEDDED EARTH ONLY					Install	
30			0403247	CONDUCTOR DEADEND ASSEMBLY, 336 SPC					Install	
30			0501016	GUY STRAND ASSY 16M					Install	
30			0532201	16M DBL GUY & ANCHOR ASSEMBLY, TRIPLE HELIX ANCHOR					Install	
30			0816043	GRIP, PREFORMED, CONDUCTOR, 3/0 AWAC					Install	
30			0821042	POLE GROUND ASSY,ROD					Install	
				WO Number: 13745088				Station 30 Sub Total:		0.00
31			0109310	EQUIPMENT MOUNT ASSY 3-PHASE					Install	
31			0114712	DEADEND BRKT ASSEMBLY, SPACER					Install	
31			0308216	8FT STD DBLARM BRACE ASSY					Remove	
31			0403203	CONDUCTOR DEADEND ASSEMBLY, ,3-.6 in, 1/0-3/0 ACSR/AAAC					Install	
31			0403208	CONDUCTOR DEADEND ASSEMBLY, #6 SOL CU					Remove	
31			0403247	CONDUCTOR DEADEND ASSEMBLY, 336 SPC					Install	
31			0501016	GUY STRAND ASSY 16M					Install	
31			0516701	16M HEAD GUY ASSY,24IN FBGL STRAIN INS					Install	
31			0532201	16M DBL GUY & ANCHOR ASSEMBLY, TRIPLE HELIX ANCHOR					Install	
31			0601401	LABOR CONTINGENCIES - OH ELEC DIST / SECONDARY CONDUCTORS					Install	
31			0803002	LTNG ARR ASSY,LINE,3KV					Remove	
31			0809002	LTNG ARR ASSY,LINE 9KV					Install	
31			0815003	NEUTRAL DEADEND CLAMP ASSY, 1/0 - 3/0 ACSR/AAAC					Install	
31			0815008	NEUTRAL DEADEND CLAMP ASSY, #6 SOL CU					Remove	
31			0816043	GRIP, PREFORMED, CONDUCTOR, 3/0 AWAC					Remove	
31			0821042	POLE GROUND ASSY,ROD					Install	
31			0925025NG	FUSE CUTOOUT ASSY:100A,25T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU				Install		
31			0925040NG	FUSE CUTOOUT ASSY:100A,40T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU				Remove		
31			0925065NG	FUSE CUTOOUT ASSY:100A,65T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU				Install		
				WO Number: 13745088				Station 31 Sub Total:		0.00
32			0109310	EQUIPMENT MOUNT ASSY 3-PHASE					Install	
32			0114102	MESSENGER BRKT ASSEMBLY					Install	
32			0308112	8FT SINGLE ARM BRACE ASSY					Remove	
32			0311218	11FT DOUBLE ARM BRACE ASSY					Install	
32			0401210	SECONDARY CLEVIS AND SPOOL INSULATOR					Install	

Design Estimate Summary Report – Supervisor's Construction

Engineer Lead: HGRAVINO				Cost Center:		Print Date: 09-Dec-16 12:59 PM					
Maximo WO Number 13745088		Oracle Number		Total Project Cost		Capital Hours	Service Hours	Total Hours	Construction Resource		
Station	G- Macro CU	Macro CU	CU	Grand Macro/ Macro / CU Assembly Description					Qty	Operation	Time Rqd
32			0403203	CONDUCTOR DEADEND ASSEMBLY, .3-.6 in, 1/0-3/0 ACSR/AAAC						Install	
32			0403208	CONDUCTOR DEADEND ASSEMBLY, #6 SOL CU						Remove	
32			0601401	LABOR CONTINGENCIES - OH ELEC DIST / SECONDARY CONDUCTORS						Install	
32			0809002	LTNG ARR ASSY,LINE 9KV						Install	
32			0815003	NEUTRAL DEADEND CLAMP ASSY, 1/0 - 3/0 ACSR/AAAC						Install	
32			0815008	NEUTRAL DEADEND CLAMP ASSY, #6 SOL CU						Remove	
32			0816130	GRIP PREFORMED, AT EYE NUT, 3/0 ALUM, SERVICE						Install	
32			0821042	POLE GROUND ASSY,ROD						Install	
32			0925065NG	FUSE CUTOOUT ASSY:100A,65T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU						Remove	
WO Number: 13745088										Station 32 Sub Total:	
33			0104612	INS POLE BRKT ASSY, SINGLE EQUIP BRKT						Install	
33			0114102	MESSENGER BRKT ASSEMBLY						Install	
33			0135401	POLE:WOOD,35FT LG,4,EMBEDDED EARTH ONLY						Remove	
33			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY						Install	
33			0306001	CROSS ARM PIN ASSY 8-10 ARM						Remove	
33			0308216	8FT STD DBLARM BRACE ASSY						Remove	
33			0401210	SECONDARY CLEVIS AND SPOOL INSULATOR						Remove	
33			0403203	CONDUCTOR DEADEND ASSEMBLY, .3-.6 in, 1/0-3/0 ACSR/AAAC						Remove	
33			0405208	PIN INSULATOR ASSY W/ TIE WIRE, DOUBLE, ALUMINUM CONDOC.						Remove	
33			0601401	LABOR CONTINGENCIES - OH ELEC DIST / SECONDARY CONDUCTORS						Install	
33			0809002	LTNG ARR ASSY,LINE 9KV					Install		
33			0815003	NEUTRAL DEADEND CLAMP ASSY, 1/0 - 3/0 ACSR/AAAC					Remove		
33			0821042	POLE GROUND ASSY,ROD					Install		
WO Number: 13745088									Station 33 Sub Total:		0.00
34			0104612	INS POLE BRKT ASSY, SINGLE EQUIP BRKT						Remove	
34			0104612	INS POLE BRKT ASSY, SINGLE EQUIP BRKT						Install	
34			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY						Install	
34			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY						Remove	
34			0403203	CONDUCTOR DEADEND ASSEMBLY, .3-.6 in, 1/0-3/0 ACSR/AAAC						Install	
34			0403208	CONDUCTOR DEADEND ASSEMBLY, #6 SOL CU						Remove	
34			0601401	LABOR CONTINGENCIES - OH ELEC DIST / SECONDARY CONDUCTORS						Install	
34			0701401	LABOR CONTINGENCIES - ELEC SERVICE						Install	
34			0803002	LTNG ARR ASSY,LINE,3KV						Remove	
34			0809002	LTNG ARR ASSY,LINE 9KV						Install	
34			0815003	NEUTRAL DEADEND CLAMP ASSY, 1/0 - 3/0 ACSR/AAAC					Install		
34			0815008	NEUTRAL DEADEND CLAMP ASSY, #6 SOL CU					Remove		
34			0821042	POLE GROUND ASSY,ROD					Install		
34			0925010NG	FUSE CUTOOUT ASSY:100A,10T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU					Install		
34			0925015NG	FUSE CUTOOUT ASSY:100A,15T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU					Remove		
34			1005301	TRANS CONNECTION ASSY, W/ANIMAL PROTECTOR 7.2KV/DUAL VOLTAGE (10 TO 333KVA)					Install		

Design Estimate Summary Report – Supervisor's Construction

Engineer Lead: HGRAVINO			Cost Center:		Print Date: 09-Dec-16 12:59 PM				
Maximo WO Number 13745088		Oracle Number		Total Project Cost	Capital Hours	Service Hours	Total Hours	Construction Resource	
Station	G- Macro CU	Macro CU	CU	Grand Macro/ Macro / CU Assembly Description			Qty	Operation	Time Rqd
34			1010025	TRANSFORMER, 1PH, PT, CONV, 2400-120/240V, 25KVA				Remove	
34			1030025	TRANSFORMER, 1PH, PT, CONV, 2400X7200-120/240V, 25KVA				Install	
WO Number: 13745088							Station 34 Sub Total:		0.00
35			0104612	INS POLE BRKT ASSY, SINGLE EQUIP BRKT				Install	
35			0104612	INS POLE BRKT ASSY, SINGLE EQUIP BRKT				Remove	
35			0108110	NEUTRAL BRKT ASSEMBLY				Remove	
35			0114102	MESSENGER BRKT ASSEMBLY				Install	
35			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY				Install	
35			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY				Remove	
35			0308112	8FT SINGLE ARM BRACE ASSY				Remove	
35			0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDUCT.				Remove	
35			0601401	LABOR CONTINGENCIES - OH ELEC DIST / SECONDARY CONDUCTORS				Install	
35			0701401	LABOR CONTINGENCIES - ELEC SERVICE				Install	
35			0803002	LTNG ARR ASSY,LINE,3KV				Remove	
35			0809002	LTNG ARR ASSY,LINE 9KV				Install	
35			0821042	POLE GROUND ASSY,ROD				Install	
35			0925010NG	FUSE CUTOOUT ASSY:100A,10T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU				Install	
35			0925015NG	FUSE CUTOOUT ASSY:100A,15T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU				Remove	
35			1005301	TRANS CONNECTION ASSY, W/ANIMAL PROTECTOR 7.2KV/DUAL VOLTAGE (10 TO 333KVA)				Install	
35			1010025	TRANSFORMER, 1PH, PT, CONV, 2400-120/240V, 25KVA				Remove	
35			1030025	TRANSFORMER, 1PH, PT, CONV, 2400X7200-120/240V, 25KVA				Install	
WO Number: 13745088							Station 35 Sub Total:		0.00
36			0104612	INS POLE BRKT ASSY, SINGLE EQUIP BRKT				Install	
36			0114102	MESSENGER BRKT ASSEMBLY				Install	
36			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY				Remove	
36			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY				Install	
36			0308112	8FT SINGLE ARM BRACE ASSY				Remove	
36			0403203	CONDUCTOR DEADEND ASSEMBLY, .3-.6 in, 1/0-3/0 ACSR/AAAC				Install	
36			0403208	CONDUCTOR DEADEND ASSEMBLY, #6 SOL CU				Remove	
36			0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDUCT.				Remove	
36			0501008	GUY STRAND ASSY 8M				Install	
36			0508601	8M SIDEWALK GUY ASSY,FIBERGLASS STRAIN INS				Install	
36			0601401	LABOR CONTINGENCIES - OH ELEC DIST / SECONDARY CONDUCTORS				Install	
36			0809002	LTNG ARR ASSY,LINE 9KV				Install	
36			0815003	NEUTRAL DEADEND CLAMP ASSY, 1/0 - 3/0 ACSR/AAAC				Install	
36			0815008	NEUTRAL DEADEND CLAMP ASSY, #6 SOL CU				Remove	
36			0821042	POLE GROUND ASSY,ROD				Install	
WO Number: 13745088							Station 36 Sub Total:		0.00
37			0104612	INS POLE BRKT ASSY, SINGLE EQUIP BRKT				Remove	
37			0104612	INS POLE BRKT ASSY, SINGLE EQUIP BRKT				Install	

Design Estimate Summary Report – Supervisor's Construction

Engineer Lead: HGRAVINO				Cost Center:		Print Date: 09-Dec-16 12:59 PM				
Maximo WO Number 13745088		Oracle Number		Total Project Cost		Capital Hours	Service Hours	Total Hours	Construction Resource	
Station	G- Macro CU	Macro CU	CU	Grand Macro/ Macro / CU Assembly Description				Qty	Operation	Time Rqd
37			0135401	POLE:WOOD,35FT LG,4,EMBEDDED EARTH ONLY					Remove	
37			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY					Install	
37			0403203	CONDUCTOR DEADEND ASSEMBLY, .3-.6 in, 1/0-3/0 ACSR/AAAC					Install	
37			0403208	CONDUCTOR DEADEND ASSEMBLY, #6 SOL CU					Remove	
37			0601401	LABOR CONTINGENCIES - OH ELEC DIST / SECONDARY CONDUCTORS					Install	
37			0701401	LABOR CONTINGENCIES - ELEC SERVICE					Install	
37			0803002	LTNG ARR ASSY,LINE,3KV					Remove	
37			0809002	LTNG ARR ASSY,LINE 9KV					Install	
37			0815003	NEUTRAL DEADEND CLAMP ASSY, 1/0 - 3/0 ACSR/AAAC					Install	
37			0815008	NEUTRAL DEADEND CLAMP ASSY, #6 SOL CU					Remove	
37			0821042	POLE GROUND ASSY,ROD					Install	
37			0925015NG	FUSE CUTOOUT ASSY:100A,15T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU					Install	
37			0925040NG	FUSE CUTOOUT ASSY:100A,40T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU					Remove	
37			1005301	TRANS CONNECTION ASSY, W/ANIMAL PROTECTOR 7.2KV/DUAL VOLTAGE (10 TO 333KVA)					Install	
37			1010050	TRANSFORMER, 1PH, PT, CONV, 2400-120/240V, 50KVA					Remove	
37			1030050	TRANSFORMER, 1PH, PT, CONV, 2400X7200-120/240V, 50KVA					Install	
WO Number: 13745088								Station 37 Sub Total:		0.00
38			0104612	INS POLE BRKT ASSY, SINGLE EQUIP BRKT					Install	
38			0104612	INS POLE BRKT ASSY, SINGLE EQUIP BRKT					Remove	
38			0135401	POLE:WOOD,35FT LG,4,EMBEDDED EARTH ONLY					Remove	
38			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY					Install	
38			0401210	SECONDARY CLEVIS AND SPOOL INSULATOR					Remove	
38			0403203	CONDUCTOR DEADEND ASSEMBLY, .3-.6 in, 1/0-3/0 ACSR/AAAC					Install	
38			0403208	CONDUCTOR DEADEND ASSEMBLY, #6 SOL CU					Remove	
38			0601401	LABOR CONTINGENCIES - OH ELEC DIST / SECONDARY CONDUCTORS					Install	
38			0701401	LABOR CONTINGENCIES - ELEC SERVICE					Install	
38			0803002	LTNG ARR ASSY,LINE,3KV					Remove	
38			0809002	LTNG ARR ASSY,LINE 9KV					Install	
38			0815003	NEUTRAL DEADEND CLAMP ASSY, 1/0 - 3/0 ACSR/AAAC					Install	
38			0815008	NEUTRAL DEADEND CLAMP ASSY, #6 SOL CU					Remove	
38			0816130	GRIP PREFORMED, AT EYE NUT, 3/0 ALUM, SERVICE					Remove	
38			0821042	POLE GROUND ASSY,ROD					Install	
38			0925025NG	FUSE CUTOOUT ASSY:100A,25T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU					Install	
38			0925040NG	FUSE CUTOOUT ASSY:100A,40T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU					Remove	
38			1005301	TRANS CONNECTION ASSY, W/ANIMAL PROTECTOR 7.2KV/DUAL VOLTAGE (10 TO 333KVA)					Install	
38			1010050	TRANSFORMER, 1PH, PT, CONV, 2400-120/240V, 50KVA					Remove	
38			1030101	TRANSFORMER, 1PH, PT, CONV, 2400X7200-120/240V, 100KVA					Install	
WO Number: 13745088								Station 38 Sub Total:		0.00
39			0104612	INS POLE BRKT ASSY, SINGLE EQUIP BRKT					Install	
39			0114102	MESSENGER BRKT ASSEMBLY					Install	

Design Estimate Summary Report – Supervisor's Construction

Engineer Lead: HGRAVINO				Cost Center:		Print Date: 09-Dec-16 12:59 PM						
Maximo WO Number 13745088		Oracle Number		Total Project Cost		Capital Hours	Service Hours	Total Hours	Construction Resource			
Station	G- Macro CU	Macro CU	CU	Grand Macro/ Macro / CU Assembly Description					Qty	Operation	Time Rqd	
39			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY						Install		
39			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY						Remove		
39			0306001	CROSS ARM PIN ASSY 8-10 ARM						Remove		
39			0308112	8FT SINGLE ARM BRACE ASSY						Remove		
39			0401210	SECONDARY CLEVIS AND SPOOL INSULATOR						Install		
39			0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDUCT.						Remove		
39			0601401	LABOR CONTINGENCIES - OH ELEC DIST / SECONDARY CONDUCTORS						Install		
39			0701401	LABOR CONTINGENCIES - ELEC SERVICE						Install		
39			0803002	LTNG ARR ASSY,LINE,3KV						Remove		
39			0809002	LTNG ARR ASSY,LINE 9KV						Install		
39			0821042	POLE GROUND ASSY,ROD						Install		
39			0925015NG	FUSE CUTOOUT ASSY:100A,15T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU						Install		
39			0925040NG	FUSE CUTOOUT ASSY:100A,40T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU						Remove		
39			1005301	TRANS CONNECTION ASSY, W/ANIMAL PROTECTOR 7.2KV/DUAL VOLTAGE (10 TO 333KVA)						Install		
39			1010050	TRANSFORMER, 1PH, PT, CONV, 2400-120/240V, 50KVA						Remove		
39			1030050	TRANSFORMER, 1PH, PT, CONV, 2400X7200-120/240V, 50KVA						Install		
WO Number: 13745088										Station 39 Sub Total:		0.00
40			0106108	POLE TOP PIN ASSY							Remove	
40			0114712	DEADEND BRKT ASSEMBLY, SPACER							Install	
40			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY					Install			
40			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY					Remove			
40			0401210	SECONDARY CLEVIS AND SPOOL INSULATOR					Remove			
40			0401210	SECONDARY CLEVIS AND SPOOL INSULATOR					Install			
40			0403247	CONDUCTOR DEADEND ASSEMBLY, 336 SPC					Install			
40			0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDUCT.					Remove			
40			0501016	GUY STRAND ASSY 16M					Install			
40			0516201	16M GUY & ANCHOR ASSY,10IN TWIN HELIX,24IN FBGL STRAIN INS					Install			
40			0815008	NEUTRAL DEADEND CLAMP ASSY, #6 SOL CU					Remove			
40			0816043	GRIP, PREFORMED, CONDUCTOR, 3/0 AWAC					Install			
40			0816130	GRIP PREFORMED, AT EYE NUT, 3/0 ALUM, SERVICE					Remove			
40			0816130	GRIP PREFORMED, AT EYE NUT, 3/0 ALUM, SERVICE					Install			
40			0821042	POLE GROUND ASSY,ROD					Install			
WO Number: 13745088									Station 40 Sub Total:		0.00	
41			0114712	DEADEND BRKT ASSEMBLY, SPACER						Install		
41			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY						Install		
41			0403247	CONDUCTOR DEADEND ASSEMBLY, 336 SPC						Install		
41			0501016	GUY STRAND ASSY 16M						Install		
41			0516201	16M GUY & ANCHOR ASSY,10IN TWIN HELIX,24IN FBGL STRAIN INS						Install		
41			0816043	GRIP, PREFORMED, CONDUCTOR, 3/0 AWAC						Install		
41			0821042	POLE GROUND ASSY,ROD						Install		

Design Estimate Summary Report – Supervisor's Construction

Engineer Lead: HGRAVINO				Cost Center:		Print Date: 09-Dec-16 12:59 PM				
Maximo WO Number 13745088		Oracle Number		Total Project Cost		Capital Hours	Service Hours	Total Hours	Construction Resource	
Station	G- Macro CU	Macro CU	CU	Grand Macro/ Macro / CU Assembly Description				Qty	Operation	Time Rqd
				WO Number: 13745088				Station 41 Sub Total:		0.00
42			0104612	INS POLE BRKT ASSY, SINGLE EQUIP BRKT					Install	
42			0104612	INS POLE BRKT ASSY, SINGLE EQUIP BRKT					Remove	
42			0106108	POLE TOP PIN ASSY					Remove	
42			0114712	DEADEND BRKT ASSEMBLY, SPACER					Install	
42			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY					Install	
42			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY					Remove	
42			0401210	SECONDARY CLEVIS AND SPOOL INSULATOR					Install	
42			0403247	CONDUCTOR DEADEND ASSEMBLY, 336 SPC					Install	
42			0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDUCT.					Remove	
42			0501016	GUY STRAND ASSY 16M					Install	
42			0516201	16M GUY & ANCHOR ASSY,10IN TWIN HELIX,24IN FBGL STRAIN INS					Install	
42			0601401	LABOR CONTINGENCIES - OH ELEC DIST / SECONDARY CONDUCTORS					Install	
42			0701401	LABOR CONTINGENCIES - ELEC SERVICE					Install	
42			0803002	LTNG ARR ASSY,LINE,3KV					Remove	
42			0809002	LTNG ARR ASSY,LINE 9KV					Install	
42			0816043	GRIP, PREFORMED, CONDUCTOR, 3/0 AWAC					Install	
42			0821042	POLE GROUND ASSY,ROD					Install	
42			0925015NG	FUSE CUTOOUT ASSY:100A,15T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU					Install	
42			0925040NG	FUSE CUTOOUT ASSY:100A,40T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU					Remove	
42			1005301	TRANS CONNECTION ASSY, W/ANIMAL PROTECTOR 7.2KV/DUAL VOLTAGE (10 TO 333KVA)					Install	
42			1010050	TRANSFORMER, 1PH, PT, CONV, 2400-120/240V, 50KVA					Remove	
42			1030050	TRANSFORMER, 1PH, PT, CONV, 2400X7200-120/240V, 50KVA					Install	
				WO Number: 13745088				Station 42 Sub Total:		0.00
43			0114102	MESSENGER BRKT ASSEMBLY					Install	
43			0135401	POLE:WOOD,35FT LG,4,EMBEDDED EARTH ONLY					Remove	
43			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY					Install	
43			0401210	SECONDARY CLEVIS AND SPOOL INSULATOR					Install	
43			0403208	CONDUCTOR DEADEND ASSEMBLY, #6 SOL CU					Remove	
43			0601401	LABOR CONTINGENCIES - OH ELEC DIST / SECONDARY CONDUCTORS					Install	
43			0701401	LABOR CONTINGENCIES - ELEC SERVICE					Install	
43			0815008	NEUTRAL DEADEND CLAMP ASSY, #6 SOL CU					Remove	
43			0816130	GRIP PREFORMED, AT EYE NUT, 3/0 ALUM, SERVICE					Install	
43			0821042	POLE GROUND ASSY,ROD					Install	
				WO Number: 13745088				Station 43 Sub Total:		0.00
44			0109310	EQUIPMENT MOUNT ASSY 3-PHASE					Install	
44			0145201	POLE:WOOD,45FT LG,2,EMBEDDED EARTH ONLY					Install	
44			0310216	10FT DBL ARM BRACE ASSY					Install	
44			0310401	10FT HEAVY DUTY FIBERGLASS DEAD END CROSSARM					Install	
44			0403247	CONDUCTOR DEADEND ASSEMBLY, 336 SPC					Install	

Design Estimate Summary Report – Supervisor's Construction

Engineer Lead: HGRAVINO				Cost Center:		Print Date: 09-Dec-16 12:59 PM					
Maximo WO Number 13745088		Oracle Number		Total Project Cost		Capital Hours	Service Hours	Total Hours	Construction Resource		
Station	G- Macro CU	Macro CU	CU	Grand Macro/ Macro / CU Assembly Description				Qty	Operation	Time Rqd	
44			0501016	GUY STRAND ASSY 16M					Install		
44			0532201	16M DBL GUY & ANCHOR ASSEMBLY, TRIPLE HELIX ANCHOR					Install		
44			0809002	LTNG ARR ASSY,LINE 9KV					Install		
44			0816043	GRIP, PREFORMED, CONDUCTOR, 3/0 AWAC					Install		
44			0821042	POLE GROUND ASSY,ROD					Install		
44			0821401	GOAB SWITCH GROUND ASSEMBLY					Install		
44			0936601	SWITCH:14.4KV,900A,GOAB,HORIZONTAL,LOADBREAK					Install		
				WO Number: 13745088					Station 44 Sub Total:		0.00
45			0104612	INS POLE BRKT ASSY, SINGLE EQUIP BRKT					Install		
45			0104612	INS POLE BRKT ASSY, SINGLE EQUIP BRKT					Remove		
45			0114102	MESSENGER BRKT ASSEMBLY					Install		
45			0114102	MESSENGER BRKT ASSEMBLY					Remove		
45			0114712	DEADEND BRKT ASSEMBLY, SPACER					Install		
45			0401210	SECONDARY CLEVIS AND SPOOL INSULATOR					Install		
45			0403203	CONDUCTOR DEADEND ASSEMBLY, .3-.6 in, 1/0-3/0 ACSR/AAAC					Install		
45			0403208	CONDUCTOR DEADEND ASSEMBLY, #6 SOL CU					Remove		
45			0403247	CONDUCTOR DEADEND ASSEMBLY, 336 SPC					Install		
45			0601401	LABOR CONTINGENCIES - OH ELEC DIST / SECONDARY CONDUCTORS					Install		
45			0699101	MATERIAL CONTINGENCIES - OH ELEC DIST / SECONDARY CONDUCTORS					Install		
45			0701401	LABOR CONTINGENCIES - ELEC SERVICE					Install		
45			0803002	LTNG ARR ASSY,LINE,3KV					Remove		
45			0809002	LTNG ARR ASSY,LINE 9KV					Install		
45			0815003	NEUTRAL DEADEND CLAMP ASSY, 1/0 - 3/0 ACSR/AAAC					Install		
45			0815008	NEUTRAL DEADEND CLAMP ASSY, #6 SOL CU					Remove		
45			0816043	GRIP, PREFORMED, CONDUCTOR, 3/0 AWAC					Install		
45			0816130	GRIP PREFORMED, AT EYE NUT, 3/0 ALUM, SERVICE					Install		
45			0816130	GRIP PREFORMED, AT EYE NUT, 3/0 ALUM, SERVICE					Remove		
45			0821042	POLE GROUND ASSY,ROD					Install		
45			0925015NG	FUSE CUTOOUT ASSY:100A,15T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU				Install			
45			0925025NG	FUSE CUTOOUT ASSY:100A,25T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU				Install			
45			0925040NG	FUSE CUTOOUT ASSY:100A,40T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU				Remove			
45			1005301	TRANS CONNECTION ASSY, W/ANIMAL PROTECTOR 7.2KV/DUAL VOLTAGE (10 TO 333KVA)				Install			
				WO Number: 13745088				Station 45 Sub Total:		0.00	
46			0104612	INS POLE BRKT ASSY, SINGLE EQUIP BRKT					Install		
46			0145101	POLE:WOOD,45FT LG,1,EMBEDDED EARTH ONLY					Install		
46			0145201	POLE:WOOD,45FT LG,2,EMBEDDED EARTH ONLY					Remove		
46			0310216	10FT DBL ARM BRACE ASSY					Install		
46			0310216	10FT DBL ARM BRACE ASSY					Remove		
46			0403203	CONDUCTOR DEADEND ASSEMBLY, .3-.6 in, 1/0-3/0 ACSR/AAAC					Install		
46			0403203	CONDUCTOR DEADEND ASSEMBLY, .3-.6 in, 1/0-3/0 ACSR/AAAC					Remove		

Design Estimate Summary Report – Supervisor's Construction

Engineer Lead: HGRAVINO				Cost Center:		Print Date: 09-Dec-16 12:59 PM					
Maximo WO Number 13745088		Oracle Number		Total Project Cost		Capital Hours	Service Hours	Total Hours	Construction Resource		
Station	G- Macro CU	Macro CU	CU	Grand Macro/ Macro / CU Assembly Description				Qty	Operation	Time Rqd	
46			0601401	LABOR CONTINGENCIES - OH ELEC DIST / SECONDARY CONDUCTORS					Install		
46			0701401	LABOR CONTINGENCIES - ELEC SERVICE					Install		
46			0809002	LTNG ARR ASSY,LINE 9KV					Install		
46			0815003	NEUTRAL DEADEND CLAMP ASSY, 1/0 - 3/0 ACSR/AAAC					Install		
46			0815003	NEUTRAL DEADEND CLAMP ASSY, 1/0 - 3/0 ACSR/AAAC					Remove		
46			0816130	GRIP PREFORMED, AT EYE NUT, 3/0 ALUM, SERVICE					Install		
46			0821042	POLE GROUND ASSY,ROD					Install		
46			0925025NG	FUSE CUTOOUT ASSY:100A,25T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU					Install		
46			1005301	TRANS CONNECTION ASSY, W/ANIMAL PROTECTOR 7.2KV/DUAL VOLTAGE (10 TO 333KVA)					Install		
46			1010333	TRANSFORMER, 1PH, PT, CONV, 2400-120/240V, 333KVA					Remove		
46			1010333	TRANSFORMER, 1PH, PT, CONV, 2400-120/240V, 333KVA					Remove		
46			1030101	TRANSFORMER, 1PH, PT, CONV, 2400X7200-120/240V, 100KVA					Install		
WO Number: 13745088									Station 46 Sub Total:		0.00
47			0104612	INS POLE BRKT ASSY, SINGLE EQUIP BRKT						Install	
47			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY						Remove	
47			0145101	POLE:WOOD,45FT LG,1,EMBEDDED EARTH ONLY						Install	
47			0310216	10FT DBL ARM BRACE ASSY				Remove			
47			0403203	CONDUCTOR DEADEND ASSEMBLY, .3-.6 in, 1/0-3/0 ACSR/AAAC				Install			
47			0403203	CONDUCTOR DEADEND ASSEMBLY, .3-.6 in, 1/0-3/0 ACSR/AAAC				Remove			
47			0701401	LABOR CONTINGENCIES - ELEC SERVICE				Install			
47			0809002	LTNG ARR ASSY,LINE 9KV				Install			
47			0815003	NEUTRAL DEADEND CLAMP ASSY, 1/0 - 3/0 ACSR/AAAC				Install			
47			0815003	NEUTRAL DEADEND CLAMP ASSY, 1/0 - 3/0 ACSR/AAAC				Remove			
47			0816130	GRIP PREFORMED, AT EYE NUT, 3/0 ALUM, SERVICE				Install			
47			0821042	POLE GROUND ASSY,ROD				Install			
47			0925025NG	FUSE CUTOOUT ASSY:100A,25T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU				Install			
47			1005301	TRANS CONNECTION ASSY, W/ANIMAL PROTECTOR 7.2KV/DUAL VOLTAGE (10 TO 333KVA)				Install			
47			1030101	TRANSFORMER, 1PH, PT, CONV, 2400X7200-120/240V, 100KVA				Install			
WO Number: 13745088								Station 47 Sub Total:		0.00	
48			0104612	INS POLE BRKT ASSY, SINGLE EQUIP BRKT					Install		
48			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY					Install		
48			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY					Remove		
48			0306001	CROSS ARM PIN ASSY 8-10 ARM					Remove		
48			0308112	8FT SINGLE ARM BRACE ASSY					Remove		
48			0403203	CONDUCTOR DEADEND ASSEMBLY, .3-.6 in, 1/0-3/0 ACSR/AAAC					Install		
48			0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDUCT.					Remove		
48			0501016	GUY STRAND ASSY 16M					Install		
48			0516201	16M GUY & ANCHOR ASSY,10IN TWIN HELIX,24IN FBGL STRAIN INS					Install		
48			0701401	LABOR CONTINGENCIES - ELEC SERVICE					Install		
48			0803002	LTNG ARR ASSY,LINE,3KV					Remove		

Design Estimate Summary Report – Supervisor's Construction

Engineer Lead: HGRAVINO				Cost Center:		Print Date: 09-Dec-16 12:59 PM				
Maximo WO Number 13745088		Oracle Number		Total Project Cost		Capital Hours	Service Hours	Total Hours	Construction Resource	
Station	G- Macro CU	Macro CU	CU	Grand Macro/ Macro / CU Assembly Description				Qty	Operation	Time Rqd
48			0809002	LTNG ARR ASSY,LINE 9KV					Install	
48			0815003	NEUTRAL DEADEND CLAMP ASSY, 1/0 - 3/0 ACSR/AAAC					Install	
48			0821042	POLE GROUND ASSY,ROD					Install	
48			0925010NG	FUSE CUTOOUT ASSY:100A,10T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU					Install	
48			0925015NG	FUSE CUTOOUT ASSY:100A,15T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU					Remove	
48			0925025NG	FUSE CUTOOUT ASSY:100A,25T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU					Remove	
48			1005301	TRANS CONNECTION ASSY, W/ANIMAL PROTECTOR 7.2KV/DUAL VOLTAGE (10 TO 333KVA)					Install	
48			1010025	TRANSFORMER, 1PH, PT, CONV, 2400-120/240V, 25KVA					Remove	
48			1030025	TRANSFORMER, 1PH, PT, CONV, 2400X7200-120/240V, 25KVA					Install	
WO Number: 13745088									Station 48 Sub Total:	
49			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY					Install	
49			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY					Remove	
49			0310112	10FT SINGLE ARM BRACE ASSY					Remove	
49			0403203	CONDUCTOR DEADEND ASSEMBLY, .3-.6 in, 1/0-3/0 ACSR/AAAC					Install	
49			0403203	CONDUCTOR DEADEND ASSEMBLY, .3-.6 in, 1/0-3/0 ACSR/AAAC					Remove	
49			0701401	LABOR CONTINGENCIES - ELEC SERVICE					Install	
49			0815003	NEUTRAL DEADEND CLAMP ASSY, 1/0 - 3/0 ACSR/AAAC					Install	
49			0815003	NEUTRAL DEADEND CLAMP ASSY, 1/0 - 3/0 ACSR/AAAC					Remove	
49			0821042	POLE GROUND ASSY,ROD					Install	
WO Number: 13745088									Station 49 Sub Total:	
50			0104612	INS POLE BRKT ASSY, SINGLE EQUIP BRKT					Remove	
50			0104612	INS POLE BRKT ASSY, SINGLE EQUIP BRKT					Install	
50			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY					Remove	
50			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY					Install	
50			0401210	SECONDARY CLEVIS AND SPOOL INSULATOR					Install	
50			0401210	SECONDARY CLEVIS AND SPOOL INSULATOR					Remove	
50			0403203	CONDUCTOR DEADEND ASSEMBLY, .3-.6 in, 1/0-3/0 ACSR/AAAC					Install	
50			0403208	CONDUCTOR DEADEND ASSEMBLY, #6 SOL CU					Remove	
50			0601401	LABOR CONTINGENCIES - OH ELEC DIST / SECONDARY CONDUCTORS					Install	
50			0701401	LABOR CONTINGENCIES - ELEC SERVICE					Install	
50			0803002	LTNG ARR ASSY,LINE,3KV					Remove	
50			0809002	LTNG ARR ASSY,LINE 9KV					Install	
50			0815003	NEUTRAL DEADEND CLAMP ASSY, 1/0 - 3/0 ACSR/AAAC					Install	
50			0815008	NEUTRAL DEADEND CLAMP ASSY, #6 SOL CU					Remove	
50			0816130	GRIP PREFORMED, AT EYE NUT, 3/0 ALUM, SERVICE					Install	
50			0821042	POLE GROUND ASSY,ROD					Install	
50			0925015NG	FUSE CUTOOUT ASSY:100A,15T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU					Install	
50			0925040NG	FUSE CUTOOUT ASSY:100A,40T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU					Remove	
50			1005301	TRANS CONNECTION ASSY, W/ANIMAL PROTECTOR 7.2KV/DUAL VOLTAGE (10 TO 333KVA)					Install	
50			1010050	TRANSFORMER, 1PH, PT, CONV, 2400-120/240V, 50KVA					Remove	

Design Estimate Summary Report – Supervisor's Construction

Engineer Lead: HGRAVINO				Cost Center:		Print Date: 09-Dec-16 12:59 PM					
Maximo WO Number 13745088		Oracle Number		Total Project Cost		Capital Hours	Service Hours	Total Hours	Construction Resource		
Station	G- Macro CU	Macro CU	CU	Grand Macro/ Macro / CU Assembly Description					Qty	Operation	Time Rqd
50			1030050	TRANSFORMER, 1PH, PT, CONV, 2400X7200-120/240V, 50KVA						Install	
				WO Number: 13745088				Station 50 Sub Total:		0.00	
51			0104612	INS POLE BRKT ASSY, SINGLE EQUIP BRKT						Install	
51			0135401	POLE:WOOD,35FT LG,4,EMBEDDED EARTH ONLY						Remove	
51			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY						Install	
51			0308216	8FT STD DBLARM BRACE ASSY						Remove	
51			0401210	SECONDARY CLEVIS AND SPOOL INSULATOR						Install	
51			0403203	CONDUCTOR DEADEND ASSEMBLY, .3-.6 in, 1/0-3/0 ACSR/AAAC						Install	
51			0403208	CONDUCTOR DEADEND ASSEMBLY, #6 SOL CU						Remove	
51			0601401	LABOR CONTINGENCIES - OH ELEC DIST / SECONDARY CONDUCTORS						Install	
51			0701401	LABOR CONTINGENCIES - ELEC SERVICE						Install	
51			0809002	LTNG ARR ASSY,LINE 9KV						Install	
51			0815003	NEUTRAL DEADEND CLAMP ASSY, 1/0 - 3/0 ACSR/AAAC						Install	
51			0815008	NEUTRAL DEADEND CLAMP ASSY, #6 SOL CU						Remove	
51			0816130	GRIP PREFORMED, AT EYE NUT, 3/0 ALUM, SERVICE						Install	
51			0821042	POLE GROUND ASSY,ROD						Install	
51			0925006NG	FUSE CUTOOUT ASSY:100A,6T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU						Install	
51			1005301	TRANS CONNECTION ASSY, W/ANIMAL PROTECTOR 7.2KV/DUAL VOLTAGE (10 TO 333KVA)						Install	
51			1030015	TRANSFORMER, 1PH, PT, CONV, 2400X7200-120/240V, 15KVA						Install	
				WO Number: 13745088				Station 51 Sub Total:		0.00	
52			0104612	INS POLE BRKT ASSY, SINGLE EQUIP BRKT						Install	
52			0106108	POLE TOP PIN ASSY						Install	
52			0108110	NEUTRAL BRKT ASSEMBLY						Install	
52			0108110	NEUTRAL BRKT ASSEMBLY						Remove	
52			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY						Install	
52			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY						Remove	
52			0306001	CROSS ARM PIN ASSY 8-10 ARM						Remove	
52			0308112	8FT SINGLE ARM BRACE ASSY						Remove	
52			0401210	SECONDARY CLEVIS AND SPOOL INSULATOR						Install	
52			0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDUCT.						Remove	
52			0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDUCT.						Install	
52			0701401	LABOR CONTINGENCIES - ELEC SERVICE						Install	
52			0803002	LTNG ARR ASSY,LINE,3KV						Remove	
52			0809002	LTNG ARR ASSY,LINE 9KV						Install	
52			0816130	GRIP PREFORMED, AT EYE NUT, 3/0 ALUM, SERVICE						Install	
52			0821042	POLE GROUND ASSY,ROD						Install	
52			0925015NG	FUSE CUTOOUT ASSY:100A,15T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU						Install	
52			0925040NG	FUSE CUTOOUT ASSY:100A,40T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU						Remove	
52			1005301	TRANS CONNECTION ASSY, W/ANIMAL PROTECTOR 7.2KV/DUAL VOLTAGE (10 TO 333KVA)						Install	
52			1010050	TRANSFORMER, 1PH, PT, CONV, 2400-120/240V, 50KVA						Remove	

Design Estimate Summary Report – Supervisor's Construction

Engineer Lead: HGRAVINO				Cost Center:		Print Date: 09-Dec-16 12:59 PM					
Maximo WO Number 13745088		Oracle Number		Total Project Cost		Capital Hours		Service Hours	Total Hours	Construction Resource	
Station	G- Macro CU	Macro CU	CU	Grand Macro/ Macro / CU Assembly Description					Qty	Operation	Time Rqd
52			1030050	TRANSFORMER, 1PH, PT, CONV, 2400X7200-120/240V, 50KVA						Install	
				WO Number: 13745088					Station 52 Sub Total:		0.00
53			0104612	INS POLE BRKT ASSY, SINGLE EQUIP BRKT						Install	
53			0106108	POLE TOP PIN ASSY						Install	
53			0108110	NEUTRAL BRKT ASSEMBLY						Remove	
53			0108110	NEUTRAL BRKT ASSEMBLY						Install	
53			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY						Remove	
53			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY						Install	
53			0306001	CROSS ARM PIN ASSY 8-10 ARM						Remove	
53			0308112	8FT SINGLE ARM BRACE ASSY						Remove	
53			0401210	SECONDARY CLEVIS AND SPOOL INSULATOR						Install	
53			0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDUCT.						Install	
53			0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDUCT.						Remove	
53			0601401	LABOR CONTINGENCIES - OH ELEC DIST / SECONDARY CONDUCTORS						Install	
53			0701401	LABOR CONTINGENCIES - ELEC SERVICE						Install	
53			0803002	LTNG ARR ASSY,LINE,3KV						Remove	
53			0809002	LTNG ARR ASSY,LINE 9KV						Install	
53			0816130	GRIP PREFORMED, AT EYE NUT, 3/0 ALUM, SERVICE						Install	
53			0821042	POLE GROUND ASSY,ROD						Install	
53			0925006NG	FUSE CUTOOUT ASSY:100A,6T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU						Install	
53			0925010NG	FUSE CUTOOUT ASSY:100A,10T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU						Remove	
53			1005301	TRANS CONNECTION ASSY, W/ANIMAL PROTECTOR 7.2KV/DUAL VOLTAGE (10 TO 333KVA)						Install	
53			1010015	TRANSFORMER, 1PH, PT, CONV, 2400-120/240V, 15KVA						Remove	
53			1030015	TRANSFORMER, 1PH, PT, CONV, 2400X7200-120/240V, 15KVA						Install	
				WO Number: 13745088					Station 53 Sub Total:		0.00
54			0106108	POLE TOP PIN ASSY						Install	
54			0108110	NEUTRAL BRKT ASSEMBLY						Remove	
54			0108110	NEUTRAL BRKT ASSEMBLY						Install	
54			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY						Install	
54			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY						Remove	
54			0306001	CROSS ARM PIN ASSY 8-10 ARM						Remove	
54			0308112	8FT SINGLE ARM BRACE ASSY						Remove	
54			0401210	SECONDARY CLEVIS AND SPOOL INSULATOR						Install	
54			0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDUCT.						Install	
54			0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDUCT.						Remove	
54			0816130	GRIP PREFORMED, AT EYE NUT, 3/0 ALUM, SERVICE						Install	
54			0821042	POLE GROUND ASSY,ROD						Install	
				WO Number: 13745088					Station 54 Sub Total:		0.00
55			0108110	NEUTRAL BRKT ASSEMBLY						Remove	
55			0145201	POLE:WOOD,45FT LG,2,EMBEDDED EARTH ONLY						Install	

Design Estimate Summary Report – Supervisor's Construction

Engineer Lead: HGRAVINO				Cost Center:		Print Date: 09-Dec-16 12:59 PM							
Maximo WO Number 13745088		Oracle Number		Total Project Cost		Capital Hours		Service Hours		Total Hours		Construction Resource	
Station	G- Macro CU	Macro CU	CU	Grand Macro/ Macro / CU Assembly Description						Qty	Operation	Time Rqd	
55			0145201	POLE:WOOD,45FT LG,2,EMBEDDED EARTH ONLY							Remove		
55			0310216	10FT DBL ARM BRACE ASSY							Remove		
55			0401210	SECONDARY CLEVIS AND SPOOL INSULATOR							Install		
55			0403203	CONDUCTOR DEADEND ASSEMBLY, .3-.6 in, 1/0-3/0 ACSR/AAAC							Remove		
55			0403203	CONDUCTOR DEADEND ASSEMBLY, .3-.6 in, 1/0-3/0 ACSR/AAAC							Install		
55			0405208	PIN INSULATOR ASSY W/ TIE WIRE, DOUBLE, ALUMINUM CONDUCT.							Remove		
55			0601401	LABOR CONTINGENCIES - OH ELEC DIST / SECONDARY CONDUCTORS							Install		
55			0815003	NEUTRAL DEADEND CLAMP ASSY, 1/0 - 3/0 ACSR/AAAC							Install		
55			0815003	NEUTRAL DEADEND CLAMP ASSY, 1/0 - 3/0 ACSR/AAAC							Remove		
55			0821042	POLE GROUND ASSY,ROD							Install		
WO Number: 13745088											Station 55 Sub Total:		0.00
56			0104612	INS POLE BRKT ASSY, SINGLE EQUIP BRKT							Remove		
56			0104612	INS POLE BRKT ASSY, SINGLE EQUIP BRKT							Install		
56			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY							Remove		
56			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY							Install		
56			0401210	SECONDARY CLEVIS AND SPOOL INSULATOR							Install		
56			0403203	CONDUCTOR DEADEND ASSEMBLY, .3-.6 in, 1/0-3/0 ACSR/AAAC							Install		
56			0403208	CONDUCTOR DEADEND ASSEMBLY, #6 SOL CU							Remove		
56			0501016	GUY STRAND ASSY 16M							Install		
56			0516201	16M GUY & ANCHOR ASSY,10IN TWIN HELIX,24IN FBGL STRAIN INS							Install		
56			0701401	LABOR CONTINGENCIES - ELEC SERVICE							Install		
56			0803002	LTNG ARR ASSY,LINE,3KV							Remove		
56			0809002	LTNG ARR ASSY,LINE 9KV							Install		
56			0815003	NEUTRAL DEADEND CLAMP ASSY, 1/0 - 3/0 ACSR/AAAC							Install		
56			0815008	NEUTRAL DEADEND CLAMP ASSY, #6 SOL CU							Remove		
56			0816130	GRIP PREFORMED, AT EYE NUT, 3/0 ALUM, SERVICE							Remove		
56			0816130	GRIP PREFORMED, AT EYE NUT, 3/0 ALUM, SERVICE							Install		
56			0821042	POLE GROUND ASSY,ROD							Install		
56			0925010NG	FUSE CUTOOUT ASSY:100A,10T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU							Install		
56			0925015NG	FUSE CUTOOUT ASSY:100A,15T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU							Remove		
56			1005301	TRANS CONNECTION ASSY, W/ANIMAL PROTECTOR 7.2KV/DUAL VOLTAGE (10 TO 333KVA)							Install		
56			1010025	TRANSFORMER, 1PH, PT, CONV, 2400-120/240V, 25KVA							Remove		
56			1030025	TRANSFORMER, 1PH, PT, CONV, 2400X7200-120/240V, 25KVA						Install			
WO Number: 13745088										Station 56 Sub Total:		0.00	
57			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY							Install		
57			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY							Remove		
57			0308216	8FT STD DBLARM BRACE ASSY							Remove		
57			0401210	SECONDARY CLEVIS AND SPOOL INSULATOR							Install		
57			0403203	CONDUCTOR DEADEND ASSEMBLY, .3-.6 in, 1/0-3/0 ACSR/AAAC							Install		
57			0403208	CONDUCTOR DEADEND ASSEMBLY, #6 SOL CU							Remove		

Design Estimate Summary Report – Supervisor's Construction

Engineer Lead: HGRAVINO				Cost Center:		Print Date: 09-Dec-16 12:59 PM					
Maximo WO Number 13745088		Oracle Number		Total Project Cost		Capital Hours	Service Hours	Total Hours	Construction Resource		
Station	G- Macro CU	Macro CU	CU	Grand Macro/ Macro / CU Assembly Description				Qty	Operation	Time Rqd	
57			0601401	LABOR CONTINGENCIES - OH ELEC DIST / SECONDARY CONDUCTORS					Install		
57			0701401	LABOR CONTINGENCIES - ELEC SERVICE					Install		
57			0815003	NEUTRAL DEADEND CLAMP ASSY, 1/0 - 3/0 ACSR/AAAC					Install		
57			0815008	NEUTRAL DEADEND CLAMP ASSY, #6 SOL CU					Remove		
57			0816130	GRIP PREFORMED, AT EYE NUT, 3/0 ALUM, SERVICE					Install		
57			0816130	GRIP PREFORMED, AT EYE NUT, 3/0 ALUM, SERVICE					Remove		
57			0821042	POLE GROUND ASSY,ROD					Install		
				WO Number: 13745088				Station 57 Sub Total:		0.00	
58			0104612	INS POLE BRKT ASSY, SINGLE EQUIP BRKT					Remove		
58			0104612	INS POLE BRKT ASSY, SINGLE EQUIP BRKT					Install		
58			0106108	POLE TOP PIN ASSY					Install		
58			0108110	NEUTRAL BRKT ASSEMBLY					Install		
58			0108110	NEUTRAL BRKT ASSEMBLY					Remove		
58			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY					Remove		
58			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY					Install		
58			0306001	CROSS ARM PIN ASSY 8-10 ARM					Remove		
58			0308112	8FT SINGLE ARM BRACE ASSY					Remove		
58			0401210	SECONDARY CLEVIS AND SPOOL INSULATOR					Install		
58			0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDUCT.					Install		
58			0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDUCT.					Remove		
58			0701401	LABOR CONTINGENCIES - ELEC SERVICE					Install		
58			0803002	LTNG ARR ASSY,LINE,3KV					Remove		
58			0809002	LTNG ARR ASSY,LINE 9KV					Install		
58			0816130	GRIP PREFORMED, AT EYE NUT, 3/0 ALUM, SERVICE					Install		
58			0821042	POLE GROUND ASSY,ROD					Install		
58			0925015NG	FUSE CUTOOUT ASSY:100A,15T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU					Install		
58			0925015NG	FUSE CUTOOUT ASSY:100A,15T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU					Remove		
58			1005301	TRANS CONNECTION ASSY, W/ANIMAL PROTECTOR 7.2KV/DUAL VOLTAGE (10 TO 333KVA)					Install		
58			1010025	TRANSFORMER, 1PH, PT, CONV, 2400-120/240V, 25KVA				Remove			
58			1030050	TRANSFORMER, 1PH, PT, CONV, 2400X7200-120/240V, 50KVA				Install			
				WO Number: 13745088				Station 58 Sub Total:		0.00	
59			0106108	POLE TOP PIN ASSY					Install		
59			0108110	NEUTRAL BRKT ASSEMBLY					Install		
59			0108110	NEUTRAL BRKT ASSEMBLY					Remove		
59			0135401	POLE:WOOD,35FT LG,4,EMBEDDED EARTH ONLY					Remove		
59			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY					Install		
59			0306001	CROSS ARM PIN ASSY 8-10 ARM					Remove		
59			0310216	10FT DBL ARM BRACE ASSY					Remove		
59			0403203	CONDUCTOR DEADEND ASSEMBLY, .3-.6 in, 1/0-3/0 ACSR/AAAC					Install		
59			0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDUCT.					Install		

Design Estimate Summary Report – Supervisor's Construction

Engineer Lead: HGRAVINO				Cost Center:		Print Date: 09-Dec-16 12:59 PM				
Maximo WO Number 13745088		Oracle Number		Total Project Cost		Capital Hours	Service Hours	Total Hours	Construction Resource	
Station	G- Macro CU	Macro CU	CU	Grand Macro/ Macro / CU Assembly Description				Qty	Operation	Time Rqd
59			0405208	PIN INSULATOR ASSY W/ TIE WIRE, DOUBLE, ALUMINUM CONDUCT.					Remove	
59			0701401	LABOR CONTINGENCIES - ELEC SERVICE					Install	
59			0815003	NEUTRAL DEADEND CLAMP ASSY, 1/0 - 3/0 ACSR/AAAC					Install	
59			0816130	GRIP PREFORMED, AT EYE NUT, 3/0 ALUM, SERVICE					Remove	
59			0821042	POLE GROUND ASSY,ROD					Install	
WO Number: 13745088								Station 59 Sub Total:		0.00
60			0106108	POLE TOP PIN ASSY					Install	
60			0108110	NEUTRAL BRKT ASSEMBLY					Remove	
60			0108110	NEUTRAL BRKT ASSEMBLY					Install	
60			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY					Install	
60			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY					Remove	
60			0306001	CROSS ARM PIN ASSY 8-10 ARM					Remove	
60			0308112	8FT SINGLE ARM BRACE ASSY					Remove	
60			0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDUCT.					Remove	
60			0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDUCT.					Install	
60			0601401	LABOR CONTINGENCIES - OH ELEC DIST / SECONDARY CONDUCTORS					Install	
60			0701401	LABOR CONTINGENCIES - ELEC SERVICE					Install	
60			0821042	POLE GROUND ASSY,ROD					Install	
WO Number: 13745088								Station 60 Sub Total:		0.00
61			0108110	NEUTRAL BRKT ASSEMBLY					Install	
61			0109310	EQUIPMENT MOUNT ASSY 3-PHASE					Install	
61			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY					Remove	
61			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY					Install	
61			0310216	10FT DBL ARM BRACE ASSY					Remove	
61			0401210	SECONDARY CLEVIS AND SPOOL INSULATOR					Install	
61			0403203	CONDUCTOR DEADEND ASSEMBLY, .3-.6 in, 1/0-3/0 ACSR/AAAC					Install	
61			0403208	CONDUCTOR DEADEND ASSEMBLY, #6 SOL CU					Remove	
61			0701401	LABOR CONTINGENCIES - ELEC SERVICE					Install	
61			0803002	LTNG ARR ASSY,LINE,3KV					Remove	
61			0809002	LTNG ARR ASSY,LINE 9KV					Install	
61			0809002	LTNG ARR ASSY,LINE 9KV					Install	
61			0815003	NEUTRAL DEADEND CLAMP ASSY, 1/0 - 3/0 ACSR/AAAC					Install	
61			0815008	NEUTRAL DEADEND CLAMP ASSY, #6 SOL CU					Remove	
61			0816130	GRIP PREFORMED, AT EYE NUT, 3/0 ALUM, SERVICE					Install	
61			0821042	POLE GROUND ASSY,ROD					Install	
61			0925010NG	FUSE CUTOOUT ASSY:100A,10T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU					Install	
61			0925025NG	FUSE CUTOOUT ASSY:100A,25T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU					Install	
61			0925025NG	FUSE CUTOOUT ASSY:100A,25T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU					Install	
61			0925040NG	FUSE CUTOOUT ASSY:100A,40T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU					Remove	
61			1005301	TRANS CONNECTION ASSY, W/ANIMAL PROTECTOR 7.2KV/DUAL VOLTAGE (10 TO 333KVA)					Install	

Design Estimate Summary Report – Supervisor's Construction

Engineer Lead: HGRAVINO				Cost Center:		Print Date: 09-Dec-16 12:59 PM				
Maximo WO Number 13745088		Oracle Number		Total Project Cost		Capital Hours	Service Hours	Total Hours	Construction Resource	
Station	G- Macro CU	Macro CU	CU	Grand Macro/ Macro / CU Assembly Description				Qty	Operation	Time Rqd
61			1030025	TRANSFORMER, 1PH, PT, CONV, 2400X7200-120/240V, 25KVA					Install	
WO Number: 13745088								Station 61 Sub Total:		0.00
62			0106108	POLE TOP PIN ASSY					Install	
62			0108110	NEUTRAL BRKT ASSEMBLY					Install	
62			0108110	NEUTRAL BRKT ASSEMBLY					Remove	
62			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY					Install	
62			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY					Remove	
62			0306001	CROSS ARM PIN ASSY 8-10 ARM					Remove	
62			0308112	8FT SINGLE ARM BRACE ASSY					Remove	
62			0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDUCT.					Remove	
62			0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDUCT.					Install	
62			0701401	LABOR CONTINGENCIES - ELEC SERVICE					Install	
62			0821042	POLE GROUND ASSY,ROD					Install	
WO Number: 13745088								Station 62 Sub Total:		0.00
63			0104612	INS POLE BRKT ASSY, SINGLE EQUIP BRKT					Install	
63			0106108	POLE TOP PIN ASSY					Install	
63			0108110	NEUTRAL BRKT ASSEMBLY					Remove	
63			0108110	NEUTRAL BRKT ASSEMBLY					Install	
63			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY					Remove	
63			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY					Install	
63			0306001	CROSS ARM PIN ASSY 8-10 ARM					Remove	
63			0308112	8FT SINGLE ARM BRACE ASSY					Remove	
63			0401210	SECONDARY CLEVIS AND SPOOL INSULATOR					Install	
63			0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDUCT.					Remove	
63			0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDUCT.					Install	
63			0701401	LABOR CONTINGENCIES - ELEC SERVICE					Install	
63			0803002	LTNG ARR ASSY,LINE,3KV					Remove	
63			0809002	LTNG ARR ASSY,LINE 9KV					Install	
63			0816130	GRIP PREFORMED, AT EYE NUT, 3/0 ALUM, SERVICE					Install	
63			0821042	POLE GROUND ASSY,ROD					Install	
63			0925015NG	FUSE CUTOOUT ASSY:100A,15T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU					Install	
63			0925040NG	FUSE CUTOOUT ASSY:100A,40T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU					Remove	
63			1005301	TRANS CONNECTION ASSY, W/ANIMAL PROTECTOR 7.2KV/DUAL VOLTAGE (10 TO 333KVA)					Install	
63			1010050	TRANSFORMER, 1PH, PT, CONV, 2400-120/240V, 50KVA					Remove	
63			1030050	TRANSFORMER, 1PH, PT, CONV, 2400X7200-120/240V, 50KVA					Install	
WO Number: 13745088								Station 63 Sub Total:		0.00
64			0106108	POLE TOP PIN ASSY					Install	
64			0108110	NEUTRAL BRKT ASSEMBLY					Install	
64			0108110	NEUTRAL BRKT ASSEMBLY					Remove	
64			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY					Install	

Design Estimate Summary Report – Supervisor's Construction

Engineer Lead: HGRAVINO				Cost Center:		Print Date: 09-Dec-16 12:59 PM							
Maximo WO Number 13745088		Oracle Number		Total Project Cost		Capital Hours		Service Hours		Total Hours		Construction Resource	
Station	G- Macro CU	Macro CU	CU	Grand Macro/ Macro / CU Assembly Description							Qty	Operation	Time Rqd
64			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY								Remove	
64			0306001	CROSS ARM PIN ASSY 8-10 ARM								Remove	
64			0308112	8FT SINGLE ARM BRACE ASSY								Remove	
64			0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDUCT.								Remove	
64			0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDUCT.								Install	
64			0701401	LABOR CONTINGENCIES - ELEC SERVICE								Install	
64			0821042	POLE GROUND ASSY,ROD								Install	
WO Number: 13745088										Station 64 Sub Total:		0.00	
65			0106108	POLE TOP PIN ASSY								Install	
65			0108110	NEUTRAL BRKT ASSEMBLY								Remove	
65			0108110	NEUTRAL BRKT ASSEMBLY								Install	
65			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY								Install	
65			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY								Remove	
65			0306001	CROSS ARM PIN ASSY 8-10 ARM								Remove	
65			0308112	8FT SINGLE ARM BRACE ASSY								Remove	
65			0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDUCT.								Install	
65			0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDUCT.								Remove	
65			0601401	LABOR CONTINGENCIES - OH ELEC DIST / SECONDARY CONDUCTORS								Install	
65			0701401	LABOR CONTINGENCIES - ELEC SERVICE								Install	
65			0821042	POLE GROUND ASSY,ROD								Install	
WO Number: 13745088										Station 65 Sub Total:		0.00	
66			0104612	INS POLE BRKT ASSY, SINGLE EQUIP BRKT								Install	
66			0104612	INS POLE BRKT ASSY, SINGLE EQUIP BRKT								Remove	
66			0106108	POLE TOP PIN ASSY								Install	
66			0106108	POLE TOP PIN ASSY								Remove	
66			0108110	NEUTRAL BRKT ASSEMBLY								Remove	
66			0108110	NEUTRAL BRKT ASSEMBLY								Install	
66			0306001	CROSS ARM PIN ASSY 8-10 ARM								Remove	
66			0308112	8FT SINGLE ARM BRACE ASSY								Remove	
66			0401210	SECONDARY CLEVIS AND SPOOL INSULATOR								Install	
66			0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDUCT.								Install	
66			0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDUCT.								Remove	
66			0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDUCT.								Remove	
66			0601401	LABOR CONTINGENCIES - OH ELEC DIST / SECONDARY CONDUCTORS								Install	
66			0701401	LABOR CONTINGENCIES - ELEC SERVICE								Install	
66			0803002	LTNG ARR ASSY,LINE,3KV								Remove	
66			0809002	LTNG ARR ASSY,LINE 9KV								Install	
66			0816130	GRIP PREFORMED, AT EYE NUT, 3/0 ALUM, SERVICE								Install	
66			0821042	POLE GROUND ASSY,ROD								Install	
66			0925010NG	FUSE CUTOOUT ASSY:100A,10T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU								Install	
66			0925015NG	FUSE CUTOOUT ASSY:100A,15T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU								Remove	

Design Estimate Summary Report – Supervisor's Construction

Engineer Lead: HGRAVINO				Cost Center:		Print Date: 09-Dec-16 12:59 PM					
Maximo WO Number 13745088		Oracle Number		Total Project Cost		Capital Hours	Service Hours	Total Hours	Construction Resource		
Station	G- Macro CU	Macro CU	CU	Grand Macro/ Macro / CU Assembly Description					Qty	Operation	Time Rqd
66			1005301	TRANS CONNECTION ASSY, W/ANIMAL PROTECTOR 7.2KV/DUAL VOLTAGE (10 TO 333KVA)						Install	
66			1010025	TRANSFORMER, 1PH, PT, CONV, 2400-120/240V, 25KVA						Remove	
66			1030025	TRANSFORMER, 1PH, PT, CONV, 2400X7200-120/240V, 25KVA						Install	
WO Number: 13745088								Station 66 Sub Total:		0.00	
67			0106108	POLE TOP PIN ASSY						Install	
67			0108110	NEUTRAL BRKT ASSEMBLY						Install	
67			0108110	NEUTRAL BRKT ASSEMBLY						Remove	
67			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY						Install	
67			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY						Remove	
67			0306001	CROSS ARM PIN ASSY 8-10 ARM						Remove	
67			0308112	8FT SINGLE ARM BRACE ASSY						Remove	
67			0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDUCT.						Remove	
67			0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDUCT.						Install	
67			0701401	LABOR CONTINGENCIES - ELEC SERVICE						Install	
67			0821042	POLE GROUND ASSY,ROD						Install	
WO Number: 13745088								Station 67 Sub Total:		0.00	
68			0104612	INS POLE BRKT ASSY, SINGLE EQUIP BRKT						Remove	
68			0104612	INS POLE BRKT ASSY, SINGLE EQUIP BRKT						Install	
68			0106108	POLE TOP PIN ASSY						Install	
68			0108110	NEUTRAL BRKT ASSEMBLY						Remove	
68			0108110	NEUTRAL BRKT ASSEMBLY						Install	
68			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY						Remove	
68			0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY						Install	
68			0306001	CROSS ARM PIN ASSY 8-10 ARM						Remove	
68			0308216	8FT STD DBLARM BRACE ASSY						Remove	
68			0401210	SECONDARY CLEVIS AND SPOOL INSULATOR						Install	
68			0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDUCT.						Install	
68			0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDUCT.						Remove	
68			0601401	LABOR CONTINGENCIES - OH ELEC DIST / SECONDARY CONDUCTORS						Install	
68			0701401	LABOR CONTINGENCIES - ELEC SERVICE						Install	
68			0803002	LTNG ARR ASSY,LINE,3KV						Remove	
68			0809002	LTNG ARR ASSY,LINE 9KV						Install	
68			0816130	GRIP PREFORMED, AT EYE NUT, 3/0 ALUM, SERVICE						Install	
68			0821042	POLE GROUND ASSY,ROD						Remove	
68			0925010NG	FUSE CUTOOUT ASSY:100A,10T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU						Install	
68			0925015NG	FUSE CUTOOUT ASSY:100A,15T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU						Remove	
68			1005301	TRANS CONNECTION ASSY, W/ANIMAL PROTECTOR 7.2KV/DUAL VOLTAGE (10 TO 333KVA)						Install	
68			1010025	TRANSFORMER, 1PH, PT, CONV, 2400-120/240V, 25KVA						Remove	
68			1030025	TRANSFORMER, 1PH, PT, CONV, 2400X7200-120/240V, 25KVA						Install	

Design Estimate Summary Report – Supervisor's Construction													
Engineer Lead: HGRAVINO				Cost Center:			Print Date: 09-Dec-16 12:59 PM						
Maximo WO Number 13745088		Oracle Number		Total Project Cost		Capital Hours		Service Hours		Total Hours		Construction Resource	
Station	G- Macro CU	Macro CU	CU	Grand Macro/ Macro / CU Assembly Description						Qty	Operation	Time Rqd	
WO Number: 13745088										Station 68 Sub Total:		0.00	
69			0701401	LABOR CONTINGENCIES - ELEC SERVICE							Install		
69			0809102	LTNG ARR ASSY,LINE,9KV,URD							Install		
WO Number: 13745088										Station 69 Sub Total:		0.00	

Design Estimate Summary Report – Bill of Materials

Engineer Lead: HGRAVINO		Cost Center:		Print Date: 09-Dec-16 12:59 PM				
Maximo WO Number 13745088		Oracle Number	Total Project Cost	Capital Hours	Service Hours	Total Hours	Construction Resource	
QTY Req	Description					Stock #	Unit of Measure	Qty Issued
WO Number: 13745088								
	INSULATOR: PIN TYPE, 15 KV, 5-1/2" DIA X 5" TALL, 1 PIN HOLE, PE, USE W/ SPACER CABLE					103110	EACH	
	CLAMP: SUSPENSION, ANGLE, ALUM, WIRE RANGE .50" TO 1.25", 12000 LB MAX, 80 DEG					103112	EACH	
	CROSSARM: DEAD END, 10 FT, 4 POSITION MIN. 8,000 LB UBS/POSITION, 2-WAY DEADEND HARDWARE, DE					103273	EACH	
	HARDWARE AND PIN HOLE SPACING PER M.S. 03-11-500							
	TRANSFORMER: POLE MOUNT, 15 KVA, DUAL VOLTAGE 2400/4160X7200/12470Y, 120/240, SINGLE PH, W/O TAPS, CONVENTIONAL					103437	EACH	
	GUARD: ANIMAL, 10", POLYMER, ELECTROSTATIC, TRANSFORMER BUSHING, RED, W/ TEETH					104060	EACH	
	WIRE: CONDUCTOR, ELECTRICAL, BARE, COPPER CLAD STL, 4 AWG, SOLID, 0.204" OD, 40% CONDUCTIVITY, 8.5 FT/LB					104174	FOOT	
	WIRE: CONDUCTOR, ELECTRICAL, BARE, COPPER CLAD STL, 4 AWG, SOLID, 0.204" OD, 40% CONDUCTIVITY, 8.5 FT/LB					104174	FOOT	
	STAPLE: FENCE. SERRATED, 2" X 3/8" X .131", GALV OR COPPERWELD					104189	EACH	
	STAPLE: FENCE. SERRATED, 2" X 3/8" X .131", GALV OR COPPERWELD					104189	EACH	
	MOLDING: GROUND WIRE, HDPE, 1" WD, 10' LG					104227	EACH	
	HOOK: GUY, 7/16" MAX WIRE SIZE, 12400 LB, ALUM ALLOY					106845	EACH	
	WIRE: CABLE, ELECTRICAL, POLE RISER, 15000 V, 1 CONDUCTOR, 4 AWG, CU, 7 STR, 150 MIL TPR INSULATION, NON-SHIELDED 4.44 FT/LB					113453	FOOT	
	EXTENSION: ANCHOR ROD, 1-1/2" SQ SHAFT X 42" LG, GALV STL, FOR TRIPLE HELIX ANCHOR					114101	EACH	
	CLAMP: END FITTING, SIDEWALK GUY, W/ CLAMP, FOR 2" PIPE, HOT DIP GALV					117885	EACH	
	WASHER: FLAT, ROUND, 9/16" ID, 1-3/8" OD, GALV					121645	EACH	
	FUSE: FUSELINK, 65 AMP, TYPE T, 23" LG					123413	EACH	
	INSULATOR: SUSPENSION, 15 KV, POLYMER, 3" DIA X 12-1/2" LG					123653	EACH	
	INSULATOR: SUSPENSION, 15 KV, POLYMER, 3" DIA X 12-1/2" LG					123653	EACH	
	WASHER: FLAT, ROUND, 11/16" ID, 1-3/4" OD, GALV					126941	EACH	
	WASHER: FLAT, ROUND, 11/16" ID, 1-3/4" OD, GALV					126941	EACH	
	WASHER: FLAT, ROUND, 11/16" ID, 1-3/4" OD, GALV					126941	EACH	
	WASHER: FLAT, ROUND, 11/16" ID, 1-3/4" OD, GALV					126941	EACH	
	BOLT: MACHINE, SQ HEAD, 3/4" DIA X 12" LG, GALV					127845	EACH	
	BOLT: MACHINE, SQ HEAD, 3/4" DIA X 12" LG, GALV					127845	EACH	
	BOLT: MACHINE, SQ HEAD, 3/4" DIA X 10" LG, GALV					148485	EACH	
	BRACE: CROSSARM, 10' & 11', 60" SPACING X 30" DROP					148653	PAIR	
	BRACE: CROSSARM, 10' & 11', 60" SPACING X 30" DROP					148653	PAIR	
	BRACE: CROSSARM, 10' & 11', 60" SPACING X 30" DROP					148653	PAIR	
	BRACE: CROSSARM, 10' & 11', 60" SPACING X 30" DROP					148653	PAIR	
	CLEVIS: SECONDARY, GALV STL					151661	EACH	
	ARRESTER: HEAVY DUTY CLASS, DISTRIBUTION, 9 KV, 7.65 KV MCOV, NON-GAPPED, GRAY OR BLACK ISOLATOR, FOR URD RISERS					151693	EACH	
	BOLT: DOUBLE ARMING, 5/8" DIA X 18" LG, GALV					155421	EACH	
	BOLT: DOUBLE ARMING, 5/8" DIA X 18" LG, GALV					155421	EACH	
	PLATE: POLE EYE, 3/4" MAX CLEVIS PIN, 21000 LB, DUCTILE IRON, HOT DIP GALV					155733	EACH	
	PLATE: POLE EYE, 3/4" MAX CLEVIS PIN, 21000 LB, DUCTILE IRON, HOT DIP GALV					155733	EACH	
	FUSE: FUSELINK, 6 AMP, TYPE T, 23" LG					158341	EACH	
	WASHER: LOCK, STAR, 1/2", GALV					158805	EACH	
	WASHER: LOCK, STAR, 1/2", GALV					158805	EACH	
	BOLT: MACHINE, SQ HEAD, 1/2" DIA X 2" LG, GALV, W/ NUT					160685	EACH	

Design Estimate Summary Report – Bill of Materials

Engineer Lead: HGRAVINO		Cost Center:		Print Date: 09-Dec-16 12:59 PM		
Maximo WO Number 13745088	Oracle Number	Total Project Cost	Capital Hours	Service Hours	Total Hours	Construction Resource
QTY Req	Description			Stock #	Unit of Measure	Qty Issued
	DEADEND: PREFORMED, GUY WIRE, 8 MM			166189	EACH	
	STIRRUP: MESSENGER BRACKET, BOLT ON W/ 1/2" X 3" HEX HEAD BOLT, NUT, FLAT & LOCK WASHER, HOT DIP GALV, FOR MB-14			168861	EACH	
	CLEVIS: THIMBLE, MALLEABLE IRON			170301	EACH	
	CLEVIS: THIMBLE, MALLEABLE IRON			170301	EACH	
	CLEVIS: THIMBLE, MALLEABLE IRON			170301	EACH	
	TRANSFORMER: POLE MOUNT, 25 KVA, DUAL VOLTAGE 2400/4160X7200/12470Y, 120/240, SINGLE PH, W/O TAPS, CONVENTIONAL			170437	EACH	
	POLE: POWER, WOOD, 40', CLASS 2			170525	EACH	
	WASHER: CURVED, SQ, 11/16" ID, 2-1/4" X 2-1/4", GALV			172997	EACH	
	RACK: CLUSTER, TRANSFORMER, MEDIUM (5 TO 100 KVA)			174629	EACH	
	ROD: GROUND, 5/8" DIA, 10' LG, COPPERWELD			176517	EACH	
	BOLT: MACHINE, SQ HEAD, 3/4" DIA X 14" LG, GALV			187741	EACH	
	ARRESTER: HEAVY DUTY CLASS, DISTRIBUTION, 9 KV, 7.65 KV MCOV, BLUE ISOLATOR			189061	EACH	
	DEADEND: PREFORMED, 3/0 AWG, 4/3 AWAC CONDUCTOR			189189	EACH	
	GUARD: GUY, 1.75" DIA X 8' LG, W/ CLAMP, YELLOW, PLASTIC			189429	EACH	
	GUARD: GUY, 1.75" DIA X 8' LG, W/ CLAMP, YELLOW, PLASTIC			189429	EACH	
	GUARD: GUY, 1.75" DIA X 8' LG, W/ CLAMP, YELLOW, PLASTIC			189429	EACH	
	FUSE: FUSELINK, 25 AMP, TYPE T, 23" LG			194645	EACH	
	CLEVIS: THIMBLE, 10,000 LB, PRESSED STL			194669	EACH	
	BRACKET: SPACER CABLE, ANTI-SWAY, 13" LG, PLASTIC			196373	EACH	
	ANCHOR: POWER, SCREW, TWIN HELIX, 8", STL, W/ 3/4" DIA X 84" LG GALV STL ROD, TRIPLE EYE			301302	EACH	
	BOLT: MACHINE, SQ HEAD, 5/8" DIA X 14" LG, GALV			313298	EACH	
	BOLT: MACHINE, SQ HEAD, 5/8" DIA X 14" LG, GALV			313298	EACH	
	BOLT: MACHINE, SQ HEAD, 5/8" DIA X 14" LG, GALV			313298	EACH	
	STAPLE: MOULDING, SERRATED, 2" X 5/8" X .162", GALV OR CU COATED			315658	EACH	
	BRACKET: SPACER CABLE, MESSENGER, HOT DIP GALV, W/MC2 CLAMP			317618	EACH	
	CROSSARM: 11' LG X 3-3/4" X 5-3/4", FIR, HIGH LINE			318378	EACH	
	CROSSARM: 11' LG X 3-3/4" X 5-3/4", FIR, HIGH LINE			318378	EACH	
	BRACKET: NEUTRAL, FORGED STL, HOT-DIP GALV			322618	EACH	
	BOLT: MACHINE, SQ HEAD, 5/8" DIA X 12" LG, GALV			324634	EACH	
	BOLT: MACHINE, SQ HEAD, 5/8" DIA X 12" LG, GALV			324634	EACH	
	BOLT: MACHINE, SQ HEAD, 5/8" DIA X 12" LG, GALV			324634	EACH	
	BOLT: MACHINE, SQ HEAD, 5/8" DIA X 12" LG, GALV			324634	EACH	
	BOLT: MACHINE, SQ HEAD, 5/8" DIA X 12" LG, GALV			324634	EACH	
	BOLT: MACHINE, SQ HEAD, 5/8" DIA X 12" LG, GALV			324634	EACH	
	BOLT: MACHINE, SQ HEAD, 5/8" DIA X 12" LG, GALV			324634	EACH	
	BOLT: MACHINE, SQ HEAD, 5/8" DIA X 12" LG, GALV			324634	EACH	
	BOLT: MACHINE, SQ HEAD, 5/8" DIA X 12" LG, GALV			324634	EACH	
	FUSE: FUSELINK, 10 AMP, TYPE T, 23" LG			326698	EACH	
	TRANSFORMER: POLE MOUNT, 50 KVA, DUAL VOLTAGE, 2400/4160X7200/12470Y, 120/240, SINGLE PH, W/O TAPS, CONVENTIONAL			326754	EACH	
	PLATE: POLE, SIDEWALK GUY, FOR 2" PIPE, HOT DIP GALV			327674	EACH	
	FUSE: FUSELINK, 15 AMP, TYPE T, 23" LG			335674	EACH	
	BOLT: MACHINE, SQ HEAD, 5/8" DIA X 8" LG, GALV			341458	EACH	
	BOLT: MACHINE, SQ HEAD, 5/8" DIA X 8" LG, GALV			341458	EACH	

Design Estimate Summary Report – Bill of Materials

Engineer Lead: HGRAVINO		Cost Center:		Print Date: 09-Dec-16 12:59 PM		
Maximo WO Number 13745088	Oracle Number	Total Project Cost	Capital Hours	Service Hours	Total Hours	Construction Resource
QTY Req	Description			Stock #	Unit of Measure	Qty Issued
	WIRE: TIE, BARE, ALUM, 4 AWG, SOLID			342074	FOOT	
	WIRE: TIE, BARE, ALUM, 4 AWG, SOLID			342074	FOOT	
	DEADEND: PREFORMED, 3/0 AWG TXS, ACSR MESSENGER			343706	EACH	
	DEADEND: PREFORMED, GUY WIRE, 16 M			349538	EACH	
	DEADEND: PREFORMED, GUY WIRE, 16 M			349538	EACH	
	DEADEND: PREFORMED, GUY WIRE, 16 M			349538	EACH	
	WIRE: CONDUCTOR, ELECTRICAL, BARE, AAAC, 3/0 AWG, 7 STR, OD .502", 5.4 FT/LB, CODE NAME AMHERST			350090	FOOT	
	WIRE: CABLE, ELECTRICAL, 600 V, SECONDARY, OVERHEAD, TRIPLEX, 2, 3/0 AWG, ALUM, 19 STR, XLPE, CONDUCTORS & 1, 3/0 AWG, ACSR, 6/1 STR, BARE, NEUTRAL, 1.56 FT/LB, CODE NAME MURISA			350946	FOOT	
	WIRE: CONDUCTOR, ELECTRICAL, BARE, CU, SOFT DRAWN, 4 AWG, SOLID, OD .204", 7.9 FT/LB			352210	FOOT	
	WIRE: CONDUCTOR, ELECTRICAL, BARE, CU, SOFT DRAWN, 4 AWG, SOLID, OD .204", 7.9 FT/LB			352210	FOOT	
	WIRE: CONDUCTOR, ELECTRICAL, BARE, CU, SOFT DRAWN, 4 AWG, SOLID, OD .204", 7.9 FT/LB			352210	FOOT	
	DEADEND: PREFORMED, 336 MCM, ALUM COVERED, 10/64" CONDUCTOR, PRECOATED			353114	EACH	
	WIRE: GUY, 8M, 7 STR, ALUMOWELD, 500' COIL			355506	FOOT	
	CUTOUT: FUSED, NON LOADBREAK, 100 AMP, 7.8/15 KV, SILICONE OR POLYMER			356370	EACH	
	CUTOUT: FUSED, NON LOADBREAK, 100 AMP, 7.8/15 KV, SILICONE OR POLYMER			356370	EACH	
	CUTOUT: FUSED, NON LOADBREAK, 100 AMP, 7.8/15 KV, SILICONE OR POLYMER			356370	EACH	
	CUTOUT: FUSED, NON LOADBREAK, 100 AMP, 7.8/15 KV, SILICONE OR POLYMER			356370	EACH	
	CUTOUT: FUSED, NON LOADBREAK, 100 AMP, 7.8/15 KV, SILICONE OR POLYMER			356370	EACH	
	INSULATOR: GUY STRAIN, 24" LG, FIBERGLASS, 21 M LBS			362290	EACH	
	INSULATOR: GUY STRAIN, 24" LG, FIBERGLASS, 21 M LBS			362290	EACH	
	INSULATOR: GUY STRAIN, 24" LG, FIBERGLASS, 21 M LBS			362290	EACH	
	SWITCH: DISCONNECT, LOAD INTERRUPTER, 14.4 KV, 900 AMP, GANG OPERATED, UPRIGHT MOUNT			364514	EACH	
	PIN: INSULATOR, POLE TOP, 15", 1" NYLON HEAD			370074	EACH	
	POLE: POWER, WOOD, 45', CLASS 2			370202	EACH	
	CONDUIT: RIGID, 2" X 10' LG, STL, GALV			372922	FOOT	
	INSULATOR: SPOOL, 3" DIA X 3" WD, FOR SECONDARY CLEVIS/RACK			372986	EACH	
	POLE: POWER, WOOD, 35', CLASS 4			373882	EACH	
	DEADEND: PREFORMED, 3/0 AWG, AAAC CONDUCTOR			377458	EACH	
	INSULATOR: GUY STRAIN, 24" LG, FIBERGLASS, 11 M LBS			380970	EACH	
	PIN: INSULATOR, CROSSARM, 5/8" X 5-3/4", 1" NYLON HEAD, GALV STL			387546	EACH	
	POLE: POWER, WOOD, 45', CLASS 1			388794	EACH	
	ANCHOR: POWER, SCREW, TRIPLE HELIX, 10", 12", 14", W/ 1-1/2" SQ SHAFT, GALV STL			391050	EACH	
	CONNECTOR: ELECTRICAL, GROUND, TRANSFORMER TANK, 1/2"-13 THD, CABLE RANGE 2/0 STR TO #8 SOLID			392970	EACH	
	CROSSARM: 10' LG X 3-3/4" X 4-3/4", FIR, DISTRIBUTION			394178	EACH	
	CROSSARM: 10' LG X 3-3/4" X 4-3/4", FIR, DISTRIBUTION			394178	EACH	
	BRACKET: SPACER CABLE, ANGLE, W/ MESSENGER ATTACHMENT			394394	EACH	
	CLAMP: SUSPENSION, ALUM, WIRE RANGE .30" TO .70"			394586	EACH	
	BOLT: MACHINE, SQ HEAD, 5/8" DIA X 18" LG, GALV			412481	EACH	
	TRANSFORMER: POLE MOUNT, 100 KVA, DUAL VOLTAGE 2400/4160X7200/12470Y, 120/240, SINGLE PH, W/O TAPS, CONVENTIONAL			417017	EACH	
	NUT: LOCK, 5/8", GALV			419921	EACH	
	NUT: LOCK, 5/8", GALV			419921	EACH	
	NUT: LOCK, 5/8", GALV			419921	EACH	
	NUT: LOCK, 5/8", GALV			419921	EACH	
	NUT: LOCK, 5/8", GALV			419921	EACH	

Design Estimate Summary Report – Bill of Materials

Engineer Lead: HGRAVINO		Cost Center:		Print Date: 09-Dec-16 12:59 PM		
Maximo WO Number 13745088	Oracle Number	Total Project Cost	Capital Hours	Service Hours	Total Hours	Construction Resource
QTY Req	Description			Stock #	Unit of Measure	Qty Issued
	NUT: LOCK, 5/8", GALV			419921	EACH	
	NUT: LOCK, 5/8", GALV			419921	EACH	
	NUT: LOCK, 5/8", GALV			419921	EACH	
	NUT: LOCK, 5/8", GALV			419921	EACH	
	NUT: LOCK, 5/8", GALV			419921	EACH	
	NUT: LOCK, 5/8", GALV			419921	EACH	
	NUT: LOCK, 5/8", GALV			419921	EACH	
	ANCHOR: POWER, SCREW, TWIN HELIX, 10", STL, W/ 1" DIA X 84" LG GALV STL ROD, TRIPLE EYE, 6000 LB			426281	EACH	
	BRACKET: SPACER CABLE, DEAD END, GALV STL			429409	EACH	
	BRACKET: POLE, 18", CUT-OUT & ARRESTER FOR ARMLESS CONSTRUCTION, FIBERGLASS			432769	EACH	
	NUT: LOCK, 3/4", GALV			437105	EACH	
	NUT: LOCK, 3/4", GALV			437105	EACH	
	NUT: LOCK, 3/4", GALV			437105	EACH	
	NUT: LOCK, 3/4", GALV			437105	EACH	
	CLAMP: STRAIN, STRAIGHT LINE, .30" TO .60" CABLE, ALUM, 8000 LB CAP			439865	EACH	
	CLAMP: STRAIN, STRAIGHT LINE, .30" TO .60" CABLE, ALUM, 8000 LB CAP			439865	EACH	
	INSULATOR: PIN TYPE, 13.2 KV, 1" PIN HOLE			444153	EACH	
	INSULATOR: PIN TYPE, 13.2 KV, 1" PIN HOLE			444153	EACH	
	SPACER: 3 PH, FOR SPACER CABLE			444825	EACH	
	WASHER: FLAT, SQ, 13/16" ID, 2-1/4" X 2-1/4", 3/16" THK, GALV			446361	EACH	
	WASHER: FLAT, SQ, 13/16" ID, 2-1/4" X 2-1/4", 3/16" THK, GALV			446361	EACH	
	WIRE: TIE, COVERED, ALUM, 4 AWG, SOLID			449665	FOOT	
	TAP: COMPRESSION, CU, GROOVE-A, 4 TO 8 SOLID - GROOVE-B, 4 TO 8 SOLID			451377	EACH	
	TAP: COMPRESSION, CU, GROOVE-A, 4 TO 8 SOLID - GROOVE-B, 4 TO 8 SOLID			451377	EACH	
	TAP: COMPRESSION, CU, GROOVE-A, 4 TO 8 SOLID - GROOVE-B, 4 TO 8 SOLID			451377	EACH	
	TAP: COMPRESSION, CU, GROOVE-A, 4 TO 8 SOLID - GROOVE-B, 4 TO 8 SOLID			451377	EACH	
	SCREW: LAG, 1/2" DIA X 4" LG, TWIST DRIVE, GALV			453121	EACH	
	SCREW: LAG, 1/2" DIA X 4" LG, TWIST DRIVE, GALV			453121	EACH	
	SCREW: LAG, 1/2" DIA X 4" LG, TWIST DRIVE, GALV			453121	EACH	
	SCREW: LAG, 1/2" DIA X 4" LG, TWIST DRIVE, GALV			453121	EACH	
	SCREW: LAG, 1/2" DIA X 4" LG, TWIST DRIVE, GALV			453121	EACH	
	WIRE: CONDUCTOR, ELECTRICAL, SPACER, ALUM, 336.4 MCM COMPACT CONDUCTOR, 19 STR, 150 MIL INSULATION, OD .192", FOR USE ON 15 KV. 0.49040 lbs per ft.			453145	FOOT	
	CLAMP: GROUND ROD, 5/8"			454561	EACH	
	WIRE: GUY, 16M, 7 STR, ALUMOWELD, 250' COIL			455625	FOOT	
	SHACKLE: ANCHOR, 15000 LB LOAD, CLEVIS PIN & COTTER KEY, FORGED STL, HOT DIP GALV			455841	EACH	
	SHACKLE: ANCHOR, 15000 LB LOAD, CLEVIS PIN & COTTER KEY, FORGED STL, HOT DIP GALV			455841	EACH	
	PIN: INSULATOR, CROSSARM, 5/8" X 2-1/2", 1" NYLON HEAD, GALV STL			457177	EACH	
	NUT: LOCK, 1/2", GALV			458153	EACH	
	WASHER: CURVED, SQ, 13/16" ID, 4" X 4", GALV			464961	EACH	
	WASHER: CURVED, SQ, 13/16" ID, 4" X 4", GALV			464961	EACH	
	BRACKET: 3 PH EQUIPMENT, FIBERGLASS			467641	EACH	
	BOLT: MACHINE, SQ HEAD, 5/8" DIA X 6" LG, GALV			471689	EACH	
	BOLT: MACHINE, SQ HEAD, 5/8" DIA X 6" LG, GALV			471689	EACH	
	WASHER: FLAT, SQ, 11/16" ID, 2" X 2", 1/8 THK, GALV			471913	EACH	
	WASHER: FLAT, SQ, 11/16" ID, 2" X 2", 1/8 THK, GALV			471913	EACH	

Design Estimate Summary Report – Bill of Materials							
Engineer Lead: HGRAVINO			Cost Center:		Print Date: 09-Dec-16 12:59 PM		
Maximo WO Number 13745088		Oracle Number	Total Project Cost	Capital Hours	Service Hours	Total Hours	Construction Resource
QTY Req	Description				Stock #	Unit of Measure	Qty Issued
	WASHER: FLAT, SQ, 11/16" ID, 2" X 2", 1/8 THK, GALV				471913	EACH	
	WASHER: FLAT, SQ, 11/16" ID, 2" X 2", 1/8 THK, GALV				471913	EACH	
	WASHER: FLAT, SQ, 11/16" ID, 2" X 2", 1/8 THK, GALV				471913	EACH	
	WASHER: FLAT, SQ, 11/16" ID, 2" X 2", 1/8 THK, GALV				471913	EACH	
	WASHER: FLAT, SQ, 11/16" ID, 2" X 2", 1/8 THK, GALV				471913	EACH	
	WASHER: FLAT, SQ, 11/16" ID, 2" X 2", 1/8 THK, GALV				471913	EACH	
	WASHER: FLAT, SQ, 11/16" ID, 2" X 2", 1/8 THK, GALV				471913	EACH	
	WASHER: FLAT, SQ, 11/16" ID, 2" X 2", 1/8 THK, GALV				471913	EACH	
	WASHER: FLAT, SQ, 11/16" ID, 2" X 2", 1/8 THK, GALV				471913	EACH	
	ADAPTER: HEAD, ANCHOR ROD, TRIPLE EYE, 1-1/2" SQ SHAFT, FOR TRIPLE HELIX, GALV STL				473097	EACH	
	WIRE: ALUMOWELD, AWAC, 3/0 AWG, 4/3 STR, 2700' REEL				474865	FOOT	
	WIRE: CONDUCTOR, ELECTRICAL, BARE, AAAC, 1/0 AWG, 7 STR, OD 0.398", 8.6 FT/LB, CODE NAME, AZUSA				480073	FOOT	

Design Estimate Summary Report – Detail Cost Estimate

Engineer Lead: HGRAVINO			Cost Center:		Print Date: 09-Dec-16 12:59 PM				
Maximo WO Number 13745088	Oracle Number	Total Project Cost	Capital Hours	Service Hours	Total Hours	Construction Resource			

Electric Transformers (Install)

Account # - Description	CU	CU Desc	Qty	Operation	Material Cost	Total Hours	Labor Cost	Tooling Cost	Total Cost
368-LINE TRANSFORMERS	1005301	TRANS CONNECTION ASSY, W/ANIMAL PROTECTOR 7.2KV/DUAL VOLTAGE (10 TO 333KVA)							
	1030015	TRANSFORMER, 1PH, PT, CONV, 2400X7200-120/240V, 15KVA							
	1030025	TRANSFORMER, 1PH, PT, CONV, 2400X7200-120/240V, 25KVA							
	1030050	TRANSFORMER, 1PH, PT, CONV, 2400X7200-120/240V, 50KVA							
	1030101	TRANSFORMER, 1PH, PT, CONV, 2400X7200-120/240V, 100KVA							
Sub Total Costs & Labor Hours (with travel loadings)									

Electric Transformers (Remove)

Account # - Description	CU	CU Desc	Qty	Operation	Material Cost	Total Hours	Labor Cost	Tooling Cost	Total Cost
368-LINE TRANSFORMERS	1010015	REMOVAL ONLY, TRANSFORMER, 1PH, PT, CONV, 2400-120/240V, 15KVA							
	1010025	TRANSFORMER, 1PH, PT, CONV, 2400-120/240V, 25KVA							
	1010050	TRANSFORMER, 1PH, PT, CONV, 2400-120/240V, 50KVA							
	1010333	TRANSFORMER, 1PH, PT, CONV, 2400-120/240V, 333KVA							
	1042075	TRANSFORMER, 3PH, PM, 2400/4160Y-208/120V, 75KVA.							
Sub Total Costs & Labor Hours (with travel loadings)									

Invest (Install & Transfer)

Account # - Description	CU	CU Desc	Qty	Operation	Material Cost	Total Hours	Labor Cost	Tooling Cost	Total Cost
364-POLES, TOWERS, AND FIXTURES	0106108	POLE TOP PIN ASSY							
	0108110	NEUTRAL BRKT ASSEMBLY							
	0110112	TRANSF CLUSTER MT ASSY 25-100KVA							
	0114001	SPACER CABLE,ANTI-SWAY BRACKET							
	0114102	MESSENGER BRKT ASSEMBLY							
	0114512	ANGLE BRACKET ASSEMBLY, 5-50 DEG, SPACER							
	0114712	DEADEND BRKT ASSEMBLY, SPACER							
	0135401	POLE:WOOD,35FT LG,4,EMBEDDED EARTH ONLY							
	0140201	POLE:WOOD,40FT LG,2,EMBEDDED EARTH ONLY							
	0145101	POLE:WOOD,45FT LG,1,EMBEDDED EARTH ONLY							

Design Estimate Summary Report – Detail Cost Estimate

Engineer Lead: HGRAVINO			Cost Center:		Print Date: 09-Dec-16 12:59 PM		
Maximo WO Number	Oracle Number	Total Project Cost	Capital Hours	Service Hours	Total Hours	Construction Resource	
13745088							
	0145201	POLE:WOOD,45FT LG,2,EMBEDDED EARTH ONLY					
	0306001	CROSS ARM PIN ASSY 8-11 ARM					
	0310112	10FT SINGLE ARM BRACE ASSY					
	0310216	10FT DBL ARM BRACE ASSY					
	0310401	10FT HEAVY DUTY FIBERGLASS DEAD END CROSSARM					
	0311112	11FT SINGLE ARM BRACE ASSY					
	0311218	11FT DOUBLE ARM BRACE ASSY					
	0401210	SECONDARY CLEVIS AND SPOOL INSULATOR					
	0501008	GUY STRAND ASSY 8M					
	0501016	GUY STRAND ASSY 16M					
	0508601	8M SIDEWALK GUY ASSY,FIBERGLASS STRAIN INS					
	0516201	16M GUY & ANCHOR ASSY,10IN TWIN HELIX,24IN FBGL STRAIN INS					
	0516701	16M HEAD GUY ASSY,24IN FBGL STRAIN INS					
	0532201	16M DBL GUY & ANCHOR ASSEMBLY, TRIPLE HELIX ANCHOR					
	Sub Total Costs & Labor Hours (with travel loadings)						
365-OVERHEAD CONDUCTORS & DEVICES	0104612	INS POLE BRKT ASSY, SINGLE EQUIP BRKT					
	0109310	EQUIPMENT MOUNT ASSY 3-PHASE					
	0403203	CONDUCTOR DEADEND ASSEMBLY, .3-.6 in, 1/0-3/0 ACSR/AAAC					
	0403247	CONDUCTOR DEADEND ASSEMBLY, 336 SPC					
	0405207	PIN INSULATOR ASSY W/ TIE WIRE, SINGLE, ALUMINUM CONDOC.					
	0405208	PIN INSULATOR ASSY W/ TIE WIRE, DOUBLE, ALUMINUM CONDOC.					
	0601401	LABOR CONTINGENCIES - OH ELEC DIST / SECONDARY CONDUCTORS					
	0610211	CONDUCTOR AAAC, 1/0AWG, 7 STRAND, BARE					
	0630143	CONDUCTORS ALUM 3/0AWG, 7 STRAND, TX, XLP, 600V					
	0630211	CONDUCTOR AAAC, 3/0AWG, 7 STRAND, BARE					
	0699101	MATERIAL CONTINGENCIES - OH ELEC DIST / SECONDARY CONDUCTORS					
	0809002	LTNG ARR ASSY,LINE 9KV					
	0809102	LTNG ARR ASSY,LINE,9KV,URD					
	0815003	NEUTRAL DEADEND CLAMP ASSY, 1/0 - 3/0 ACSR/AAAC					
	0816030	GRIP, PREFORMED, CONDUCTOR, 3/0 AAAC					
	0816043	GRIP, PREFORMED, CONDUCTOR, 3/0 AWAC					
	0816130	GRIP PREFORMED, AT EYE NUT, 3/0 ALUM, SERVICE					
	0817035	NEUTRAL SWINGING CORNER ASSY, #2-3/0 ACSR/AAAC					
	0821042	POLE GROUND ASSY,ROD					
	0821401	GOAB SWITCH GROUND ASSEMBLY					

Design Estimate Summary Report – Detail Cost Estimate							
Engineer Lead: HGRAVINO			Cost Center:		Print Date: 09-Dec-16 12:59 PM		
Maximo WO Number		Oracle Number	Total Project Cost	Capital Hours	Service Hours	Total Hours	Construction Resource
13745088							
	0405208	PIN INSULATOR ASSY W/ TIE WIRE, DOUBLE, ALUMINUM CONDUCT.					
	0606530	REMOVAL ONLY, WIRE COPPER #6AWG, SOLID, PE					
	0610510	WIRE COPPER 1/0AWG, SOLID, BARE					
	0803002	LTNG ARR ASSY,LINE,3KV					
	0815003	NEUTRAL DEADEND CLAMP ASSY, 1/0 - 3/0 ACSR/AAAC					
	0815008	NEUTRAL DEADEND CLAMP ASSY, #6 SOL CU					
	0816043	GRIP, PREFORMED, CONDUCTOR, 3/0 AWAC					
	0816130	GRIP PREFORMED, AT EYE NUT, 3/0 ALUM, SERVICE					
	0821042	POLE GROUND ASSY,ROD					
	0925006NG	FUSE CUTOOUT ASSY:100A,6T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU					
	0925010NG	FUSE CUTOOUT ASSY:100A,10T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU					
	0925015NG	FUSE CUTOOUT ASSY:100A,15T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU					
	0925025NG	FUSE CUTOOUT ASSY:100A,25T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU					
	0925040NG	FUSE CUTOOUT ASSY:100A,40T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU					
	0925065NG	FUSE CUTOOUT ASSY:100A,65T,1PH,14.4KV,NON-LOADBREAK, NON-GRAPHICAL CU					
	Sub Total Costs & Labor Hours (with travel loadings)						
	1204030	CAPACITOR ASSY, FIXED BANK, 4KV, 300KVAR	6	Remove			
	Sub Total Costs & Labor Hours (with travel loadings)						

Design Estimate Summary Report – Address Summary							
Engineer Lead: HGRAVINO			Cost Center:		Print Date: 09-Dec-16 12:59 PM		
Maximo WO Number 13745088	Oracle Number	Total Project Cost	Capital Hours	Service Hours	Total Hours	Construction Resource	
Customer Name	Customer Phone	Customer Address		Short Description of Work Order		WONUM	
		- - -		E560_Elec Dist_Cass AVE CKT_4KV CONV_Cass Ave CKT CONV (Riverside Sub) Ph II		13745088	

Child Work Orders				
Work Order	Short Description	Work Type	Work Sub Type	Status

Related Work Orders				
Work Order	Short Description	Work Type	Work Sub Type	Status

Transmission Modernization Preliminary Estimate Summary			Group ID	BOONVILLE PIONEER	Planned Year	2021
Maximo WO Number	Oracle Number	Total Project Cost	Maximo Short Description			
13964154	TBD		E560_Electric Distribution Substation_BOONVILLE PIONEER_Substation Circuit Breaker Replacements_BOONVILLE PIONEER 188 - 4842773			
ABM	OC	City	TDSIC Program Category	Project Engineer (VEC/BV)		
Elec Substation - Distr TDSIC	Boonville	Boonville	Substation Circuit Breaker Replacement	Horn, Andrew	JJK	
Maximo Long Description of Work						
The project involves replacing 12kV circuit breakers and associated foundation. The existing relaying and control is located in the breaker control panel that will be upgraded with the new breaker. This Level estimate uses BV Project S1021 / Vectren Maximo 13626331 as the basis for this estimate.						
Preliminary Estimate Details						
Activity Description			Units	UoM	Unit Cost	Extended Cost
Mobilization			1	Lot		
Breaker Replacement			1	Lot		
Test Check Out			1	Lot		
Demobilization			1	Lot		
Engineering/Operations/Equipment			1	Lot		
					Subtotal	\$104,111
Total Project Cost Summary						
Cost Category		Project Cost Calculations				
Contract Labor and Overheads		Subtotal				
Engineering		Contingency - Labor and Material				
Materials		Subtotal + Contingency				
Land		Administrative & General Loading / Engineering & Supervision Loading				
		Total Project Cost (Subtotal + Contingency + Loadings)				

Maximo Work Order :	13964154							Crew Rate			
Work Order Desc:	E560_Electric Distribution Substation_BOONVILLE PIONEER_Substation Circuit Breaker Replacements_BOONVILLE PIONEER 188 - 4842773										
BV Project ID:	S-4004										
BV Estimate Basis :	S1021										
Estimator:	JJK										
				MATERIAL COST	Material Cost w/ Tx	LABOR INSTALL	Mhr Unit	Subcontract	Total Mhrs	Total Cost	
	Lot	Mobilization									
	EA	Circuit breaker, Vacuum 15kV, 1200A, 20kAIC, 2 sets of 1200:5A MR CTs									
	FT	Conductor, 500 kcmil copper									
	EA	Conductor, #4/0 bare copper									
	EA	Grounding conductor fittings									
	FT	2" RGS Conduit									
	FT	2" Flexible metal conduit									
	CY	Foundation - See Substation Project Summary									
	Lot	Remove circuit breaker, associated conductors, and foundation.									
	EA	Lug, bolted, 500 kcmil, CU, 4-Hole Pad									
	EA	Transition plates									
	EA	Magnecraft/Struthers-Dunn General Purpose Octal Plug-In Relay, Class 250, 240VAC, 10A (trip ckt loss of AC, close ckt loss of AC, reclose indication)									
	EA	Magnecraft/Struthers-Dunn General Purpose Relay, 24VDC, 13A, Class 388Ml. (reclose cutoff, reclose cutoff reset, inst. reclosing cutoff)									
	EA	ABB Type FT-1 Test Switch, 10 potential poles (1 per M571)									
	EA	2-pole fuse block, 250V, 30A									
	EA	250V, 10A fuses									
	EA	Bitronics Type M571 IED									
	EA	Bitronics Type M570DA remote display									
	EA	ABB Type FT-1 Test Switch, 4 potential poles & 6 current poles (1 per M571)									
	FT	600V cable, two pair #20 AWG, shielded, for direct burial									

Maximo Work Order :		13964154						Crew Rate					
Work Order Desc:		E560_Electric Distribution Substation_BOONVILLE PIONEER_Substation Circuit Breaker Replacements_BOONVILLE PIONEER 188 - 4842773											
BV Project ID:		S-4004											
BV Estimate Basis :		S1021											
Estimator:		JJK											
				MATERIAL COST		Material Cost w/ Tx		LABOR INSTALL		Mhr Unit		Subcontract	
										Total Mhrs		Total Cost	
		EA	SEL-451 Protection, Automation, & Bay Control System Relay										
		EA	ABB Type FT-1 Test Switch, 4 potential poles & 6 current poles										
		EA	ABB Type FT-1 Test Switch, 10 potential poles										
		lot	Test & Checkout										
		lot	Demobilization										
		Lot	Misc Material @ 5%										
			Totals										