

STATE OF INDIANA

INDIANA UTILITY REGULATORY COMMISSION

| | | |
|---|---|------------------------|
| IN THE MATTER OF THE PETITION BY |) | |
| CAVALRY ENERGY CENTER, LLC FOR |) | |
| CERTAIN DETERMINATIONS BY THE |) | CAUSE NO. 45474 |
| COMMISSION WITH RESPECT TO ITS |) | |
| JURISDICTION OVER PETITIONER'S |) | |
| ACTIVITIES AS A GENERATOR OF |) | |
| ELECTRIC POWER |) | |

CAVALRY ENERGY CENTER, LLC'S QUARTERLY REPORT:
SECOND QUARTER 2023

This Quarterly Report ("Report") is filed as required by the Commission's Order in this Cause issued on May 26, 2021. This Report provides the required information to the extent such information is known and available. The requested information is as follows:

(1) Any changes to the information provided in the Initial Report.

The information provided in the Initial Report, as updated by the Second Quarter 2022 Report, remains accurate and there are no changes to report

(2) Any reports of Interconnection System Impact Studies not previously submitted to the Commission.

The Phase II and Phase III System Impact Studies for queue position J1067 were provided with the Second Quarter 2022 Report. All other system impact studies for J1067 have previously been provided.

The Phase I SIS for queue position J1810 is now available, a copy of which is provided with this Report. Additional interconnection studies for J1810 are not yet available.

(3) Copy of the GIA as filed with the FERC.

The GIA for J1067 has been executed and filed with FERC. A copy of the signed GIA was included with the Fourth Quarter 2021 Report.

The interconnection agreement for J1810 is not yet complete.

(4) Notice of the establishment of an independent financial instrument, including its form and amount.

In accordance with the Road Use Agreement executed with White County, a performance bond in the amount of \$4,000,000 has been posted.

- (5) **Achievement of construction milestones described in the GIA and such events as the procurement of major equipment, the receipt of major permits material to the construction and operation of the Facility, construction start-up, initial energization, and commercial operation.**

Formal construction began in October 2022.

- (6) **When commercial operation is achieved, the nameplate capacity, term, and identity of the purchaser(s) for contracts then existing for utility sales, contingency plans (if any) detailing response plans to emergency conditions as required by state or local units of government, the interconnecting transmission owner and/or MISO, and the Facility's certified (or accredited) dependable capacity rating.**

Not applicable.

- (7) **A copy of the decommissioning plan agreed to with White County.**

A copy of the decommissioning plan agreement with White County was provided with the Second Quarter 2022 Report.

VERIFICATION


The undersigned, Anthony Pedroni, being first duly sworn upon his oath, states that he is the Vice President of Cavalry Energy Center, LLC; that he prepared or supervised the preparation of Cavalry Energy Center, LLC's Second Quarter 2023 Report; and that the statements contained therein are true to the best of his knowledge, information, and belief.

By: Anthony Pedroni

STATE OF FLORIDA)
)
COUNTY OF PALM BEACH)

SS:

Subscribed and sworn to before me, a Notary Public, in and for said State and County this 31 day of July, 2023.




Signature Jennifer Reynoso
Printed Jennifer Reynoso

My Commission Expires:
2-21-25

My County of Residence:
Palm Beach

Respectfully submitted,



Randolph L. Seger (240-49)
Michael T. Griffiths (26384-49)
Dentons Bingham Greenebaum LLP
2700 Market Tower
10 West Market Street
Indianapolis, Indiana 46204
Telephone: (317) 635-8900
Fax: (317) 236-9907
randy.seger@dentons.com
michael.griffiths@dentons.com

Attorneys for Petitioner,
Cavalry Energy Center, LLC

CERTIFICATE OF SERVICE

The undersigned hereby certifies that a copy of the foregoing was electronically delivered this 1st day of August, 2023, to the following:

Office of Utility Consumer Counselor
115 West Washington Street, Suite 1500 South
Indianapolis, Indiana 46204
thaas@oucc.in.gov
infomgt@oucc.in.gov



An attorney for Petitioner,
Cavalry Energy Center, LLC



MISO DPP 2020 Central Area Study Phase 1 Final Report

June 22nd, 2023

Revision 2

MISO
720 City Center
Drive Carmel
Indiana 46032

<http://www.misoenergy.org>



Table of Contents

| | |
|--|-----------|
| 1. Executive Summary | 4 |
| 1.1. Project List..... | 4 |
| 1.2. Total Network Upgrades | 9 |
| 2. FERC Order 827 Compliance Review..... | 21 |
| 3. Model Development and Study Assumptions..... | 25 |
| 3.1 Base Case Models | 25 |
| 3.2 Monitored Elements | 25 |
| 3.3 Contingencies..... | 25 |
| 3.4 Study Methodology | 25 |
| 3.5 Performance Criteria | 26 |
| 4. Voltage Analysis | 26 |
| 5. Thermal Analysis | 26 |
| 6. Deliverability Analysis | 26 |
| 6.1 Determining the MW Restriction | 26 |
| 6.2 Deliverability Study Results..... | 27 |
| 7. Shared Network Upgrades Analysis | 29 |
| 8. Cost Allocation | 30 |
| 8.1 Cost Assumptions for Network Upgrades | 30 |
| 8.2 Cost Allocation Methodology..... | 30 |
| Appendix A – Cost Allocation Summary (CEII)..... | 32 |
| Appendix B – Network Upgrade Table Per Project (CEII) | 32 |
| Appendix C – MISO ERIS Analysis (CEII) | 32 |
| Appendix D – MISO Deliverability Analysis (CEII) | 32 |
| Appendix E- Ameren System LPC..... | 32 |
| Appendix F- LPC Results | 32 |



| | |
|---|----|
| Table 1: List of Withdrawn DPP 2020 Central Projects | 4 |
| Table 2: List of Active DPP 2020 Central Phase 1 Projects | 4 |
| Table 3: Total Cost of Network Upgrade for DPP 2020 Central Phase 1 Projects..... | 9 |
| Table 4: ERIS & NRIS Upgrades Required for Interconnection Service | 13 |
| Table 5: FERC Order 827 Review Results | 22 |
| Table 6: Deliverability Results (NRIS) | 27 |
| Table 7: Shared Network Upgrade Cost Allocation | 30 |

1. Executive Summary

This report presents the results of a System Impact Study performed to evaluate the interconnection of the generators in the DPP 2020 Central Phase 1. The study was performed under the direction of MISO and reviewed by an ad hoc study group. The ad hoc study group was formed to review the study scope, methodology, models and results. The ad hoc study group consisted of representatives from the interconnection customers and the following utility companies – Ameren, Big Rivers Electric Cooperation, City of Springfield Water Light & Power, City of Columbia, MO, Duke Energy Midwest, Henderson Municipal Power and Light, Hoosier Energy Rural Electric Cooperative, Indiana Municipal Power Agency, Indianapolis Power & Light Company, Northern Indiana Public Service Company, Prairie Power Inc, Southern Illinois Power Cooperative, Southern Indiana Gas & Electric Co, and Wabash Valley Power Association.

1.1. Project List

The original interconnection requests for DPP 2020 Central had a total of 122 generation projects. 36 projects withdrew prior to the start of DPP Phase 1. Withdrawn projects are listed in Table 1. Therefore, there are 85 generation projects with a combined nameplate rating of 249.2 MW of Energy Resource Interconnection Service (ERIS) & 18,793.02 MW of Network Resource Interconnection Service (NRIS). The detailed list of Central Area DPP projects is shown below in

Table 1: List of Withdrawn DPP 2020 Central Projects

| Withdrawn Projects | | | | | | | |
|--------------------|-------|-------|-------|-------|-------|-------|-------|
| J1501 | J1617 | J1662 | J1689 | J1702 | J1741 | J1771 | J1837 |
| J1535 | J1623 | J1675 | J1690 | J1715 | J1742 | J1799 | |
| J1548 | J1627 | J1682 | J1692 | J1717 | J1757 | J1807 | |
| J1601 | J1628 | J1683 | J1694 | J1718 | J1764 | J1825 | |
| J1606 | J1650 | J1688 | J1700 | J1731 | J1768 | J1828 | |

2, and the Phase 1 study was kicked off on March 15th 2021.

Table 1: List of Withdrawn DPP 2020 Central Projects

| Withdrawn Projects | | | | | | | |
|--------------------|-------|-------|-------|-------|-------|-------|-------|
| J1501 | J1617 | J1662 | J1689 | J1702 | J1741 | J1771 | J1837 |
| J1535 | J1623 | J1675 | J1690 | J1715 | J1742 | J1799 | |
| J1548 | J1627 | J1682 | J1692 | J1717 | J1757 | J1807 | |
| J1601 | J1628 | J1683 | J1694 | J1718 | J1764 | J1825 | |
| J1606 | J1650 | J1688 | J1700 | J1731 | J1768 | J1828 | |

Table 2: List of Active DPP 2020 Central Phase 1 Projects

| Project | Fuel Type | Transmission Owner | County | State | Service Requested | MW | Point of Interconnection |
|---------|-----------------|------------------------------------|------------|-------|-------------------|-----|---|
| J1491 | Battery Storage | Indianapolis Power & Light Company | Marion | IN | NRIS | 200 | IPL EW Stout North Yard 138 kV Substation |
| J1517 | Battery Storage | Duke Energy Indiana, LLC | Vermillion | IN | NRIS | 40 | Hillsdale North 230 kV |
| J1518 | Solar | Duke Energy Indiana, LLC | Vermillion | IN | NRIS | 185 | Hillsdale North 230 kV |

| Project | Fuel Type | Transmission Owner | County | State | Service Requested | MW | Point of Interconnection |
|---------|-----------|--|-------------|-------|-------------------|-----|---|
| J1519 | Solar | Ameren Missouri | Bollinger | MO | NRIS | 200 | St. Francois to Lutesville 345 kV |
| J1563 | Solar | Duke Energy Indiana, LLC | Montgomery | IN | NRIS | 200 | Wabash River - Whitesville 230kV line |
| J1565 | Solar | Duke Energy Indiana, LLC | Lawrence | IN | NRIS | 200 | Bedford - Columbus 345kV line (Line #34517) |
| J1578 | Solar | Duke Energy Indiana, LLC | Johnson | IN | NRIS | 200 | Columbus -Greenwood Clark Twp 230kV line (Circuit ID 23019) |
| J1579 | Solar | Ameren Illinois | Edwards | IL | NRIS | 200 | Albion-Crossville 138kV Line |
| J1585 | Solar | Ameren Missouri | Moniteau | MO | NRIS | 200 | Apache Tap - Barnett 161kV line |
| J1591 | Solar | Duke Energy Indiana, LLC | Clay | IN | NRIS | 150 | Staunton 138kV |
| J1593 | Solar | Duke Energy Indiana, LLC | Rush | IN | NRIS | 200 | Greensboro-Gwynneville 345kV |
| J1600 | Solar | Big Rivers Electric Corporation | Meade | KY | NRIS | 40 | Flaherty Tap to Custer 69kV |
| J1604 | Solar | Henderson Municipal Power & Light | Henderson | KY | NRIS | 50 | HMPL Substation #7 69kV |
| J1610 | Solar | City Water, Light, and Power | Sangamon | IL | NRIS | 100 | Auburn North to Chatham Main 138kV |
| J1616 | Solar | Duke Energy Indiana, LLC | Knox | IN | NRIS | 200 | Amo to Edwardsport 345KV |
| J1619 | Solar | Big Rivers Electric Corporation | Henderson | KY | NRIS | 160 | Reid Switchyard 161kV |
| J1624 | Solar | Duke Energy Indiana, LLC | Bartholomew | IN | NRIS | 100 | Columbus Denois Cr - Columbus 345 230 kV Transmission Line |
| J1625 | Solar | Duke Energy Indiana, LLC | Tipton | IN | NRIS | 150 | Kokomo - Tipton 230kV Transmission line |
| J1626 | Solar | Ameren Illinois | Fayette | IL | NRIS | 150 | Ramsey East 138kV bus |
| J1632 | Solar | Big Rivers Electric Corporation | Caldwell | KY | NRIS | 200 | Caldwell County - Barkley 161kV |
| J1636 | Solar | Ameren Missouri | Pike | MO | NRIS | 44 | Peno Creek Substation 161kV |
| J1637 | Solar | Duke Energy Indiana, LLC | Knox | IN | NRIS | 150 | Wheatland Substation 345kV |
| J1638 | Solar | Big Rivers Electric Corporation | Hancock | KY | NRIS | 150 | Skillman Substation 161kV |
| J1641 | Solar | Hoosier Energy REC Inc | Greene | IN | NRIS | 150 | Worthington Substation 138kV |
| J1642 | Hybrid | Southern Indiana Gas & Electric Company d/b/a Vectren Energy Delivery of Indiana, Inc. | Spencer | IN | NRIS | 200 | North East (Castle) - Culley 138kV |
| J1646 | Solar | Northern Indiana Public Service Company | Newton | IN | NRIS | 150 | Morrison Ditch 138kV |

| Project | Fuel Type | Transmission Owner | County | State | Service Requested | MW | Point of Interconnection |
|---------|-----------------|--|-----------|-------|-------------------|-------|--|
| J1649 | Solar | Big Rivers Electric Corporation | McCracken | KY | NRIS | 60 | McCracken County to Shell 69kV |
| J1651 | Solar | Ameren Illinois | Logan | IL | NRIS | 149.5 | Howlett 138 kV Substation |
| J1652 | Solar | Ameren Illinois | Champaign | IL | NRIS | 116 | Sidney 138kV |
| J1653 | Solar | Ameren Illinois | Tazewell | IL | NRIS | 150 | San Jose Rail 138kV |
| J1655 | Battery Storage | Ameren Illinois | Jefferson | IL | | 50 | West Mt Vernon - Xenia 345kV Line (J1241) |
| J1656 | Hybrid | Ameren Illinois | Vermilion | IL | NRIS | 412 | Sydney to Bunsonville 345kV Line |
| J1676 | Wind | Ameren Illinois | McLean | IL | NRIS | 300 | Brokaw - Clinton 345 kV line |
| J1677 | Solar | Ameren Illinois | Macon | IL | NRIS | 180 | Leghorn 345 kV |
| J1678 | Battery Storage | Duke Energy Indiana, LLC | Miami | IN | NRIS | 74.7 | Deedsville 345 kV |
| J1679 | Solar | Ameren Illinois | Clay | IL | NRIS | 125 | Xenia - West Mt Vernon 345 kV |
| J1680 | Solar | Duke Energy Indiana, LLC | Cass | IN | NRIS | 100 | 345 kV Walton Substation |
| J1681 | Solar | Ameren Missouri | Maries | MO | NRIS | 200 | Bland to Franks 345kV line |
| J1684 | Solar | Northern Indiana Public Service Company | Starke | IN | NRIS | 200 | ROLLIN SCHAFER -BURR OAK 345KV LINE |
| J1687 | Solar | Hoosier Energy REC Inc | Decatur | IN | NRIS | 160 | Decatur Switching Station 161kv |
| J1691 | Solar | Hoosier Energy REC, Inc. | Sullivan | IN | NRIS | 200 | Merom 345kV Substation |
| J1695 | Battery Storage | Ameren Illinois | Perry | IL | NRIS | 50 | Aster 138kV Substation (Rebuild of North Coulterville 138kV) |
| J1696 | Solar | Big Rivers Electric Corporation | Henderson | KY | NRIS | 150 | Reid 161kV |
| J1697 | Solar | Duke Energy Indiana, LLC | Jackson | IN | NRIS | 200 | Bedford - Seymour 138kV line (Line#13829) |
| J1699 | Solar | Hoosier Energy REC Inc | Shelby | IN | NRIS | 43 | HE Lewis Creek 69 kV |
| J1701 | Wind | Ameren Illinois | McDonough | IL | NRIS | 200 | Macomb to Ipava 138kV line |
| J1703 | Solar | Big Rivers Electric Corporation | Webster | KY | NRIS | 74 | Reid to Hopkins County 161kV |
| J1704 | Battery Storage | Duke Energy Indiana, LLC | Shelby | IN | NRIS | 50 | Gwynneville 345kV Substation |
| J1707 | Solar | Southern Indiana Gas & Electric Company d/b/a Vectren Energy Delivery of Indiana, Inc. | Dubois | IN | NRIS | 72 | DUFF 345KV |
| J1712 | Solar | Ameren Illinois | Perry | IL | NRIS | 300 | North Coulterville - COMM 345kV |
| J1713 | Wind | Ameren Transmission Company of Illinois | Macon | IL | NRIS | 147.2 | Faraday (138 kV) |

| Project | Fuel Type | Transmission Owner | County | State | Service Requested | MW | Point of Interconnection |
|---------|-----------|--|------------|-------|-------------------|--------|--|
| J1714 | Solar | Ameren Illinois | Fayette | IL | NRIS | 100 | Ramsey East 138kV Substation |
| J1721 | Solar | Duke Energy Indiana, LLC | Vigo | IN | NRIS | 175.12 | Vigo-Worthington 138kV |
| J1724 | Solar | Northern Indiana Public Service Company | LaPorte | IN | NRIS | 150 | LNG - STILLWELL 138kV line |
| J1725 | Wind | Ameren Illinois | Tazewell | IL | NRIS | 100 | San Jose Rail Splitter 138kV (G515) |
| J1726 | Solar | Northern Indiana Public Service Company | Pulaski | IN | NRIS | 200 | Reynolds - Burr 345kV |
| J1736 | Solar | Southern Indiana Gas & Electric Company d/b/a Vectren Energy Delivery of Indiana, Inc. | Dubois | IN | | 100 | Duff 138kV |
| J1737 | Solar | Duke Energy Indiana, LLC | Rush | IN | NRIS | 210 | Gwynville 345 kV |
| J1743 | Solar | Duke Energy Indiana, LLC | Miami | IN | NRIS | 292.9 | Deedsville 345 kV Substation |
| J1744 | Solar | Ameren Illinois | Cumberland | IL | NRIS | 149.5 | Hutsonville - Neoga 138 kV |
| J1755 | Wind | Ameren Illinois | Bureau | IL | NRIS | 147.2 | Bureau County 138 kV |
| J1756 | Hybrid | Indianapolis Power & Light Company | Shelby | IN | NRIS | 309 | Gwynneville to Sunnyside 345kV |
| J1765 | Solar | Duke Energy Indiana, LLC | Tipton | IN | NRIS | 93.2 | Tipton West Substation 230kV |
| J1770 | Wind | Ameren Illinois | Vermilion | IL | ERIS | 150 | Hoopston 138kV |
| J1772 | Solar | Northern Indiana Public Service Company | White | IN | NRIS | 200 | Reynolds 345KV |
| J1774 | Wind | Duke Energy Indiana, LLC | Warren | IN | | 50 | Cayuga 345kV |
| J1777 | Solar | Ameren Illinois | Perry | IL | NRIS | 100 | Aster 138kV Substation |
| J1780 | Solar | Duke Energy Indiana, LLC | Montgomery | IN | NRIS | 200 | Linden Tap - Crawfordsville 138kV Line |
| J1782 | Solar | Duke Energy Indiana, LLC | Montgomery | IN | NRIS | 150 | WABASH RIVER GEN. STA. TO WHITESVILLE SOUTH SUB 230kV |
| J1783 | Solar | Duke Energy Indiana, LLC | Montgomery | IN | NRIS | 150 | WABASH RIVER GEN. STA. TO WHITESVILLE SOUTH SUB 230 kV |
| J1784 | Solar | Duke Energy Indiana, LLC | Henry | IN | NRIS | 39 | New Castle to Hagerstown 69 kV |
| J1785 | Solar | Northern Indiana Public Service Company | LaPorte | IN | NRIS | 100 | Maple 69 kV |
| J1786 | Solar | Hoosier Energy REC Inc | Sullivan | IN | NRIS | 200 | Merom 345kV Substation |

| Project | Fuel Type | Transmission Owner | County | State | Service Requested | MW | Point of Interconnection |
|---------|-----------------|--|------------|-------|-------------------|-------|---|
| J1802 | Solar | Northern Indiana Public Service Company | Marshall | IN | NRIS | 150 | Burr Oak 138kV |
| J1805 | Battery Storage | Northern Indiana Public Service Company | LaPorte | IN | NRIS | 0 | Maple 69 kV |
| J1806 | Battery Storage | Duke Energy Indiana, LLC | Henry | IN | | 30 | Greensboro Substation 345kV |
| J1810 | Hybrid | Northern Indiana Public Service Company | White | IN | NRIS | 60 | Reynolds 345kV to Burr Oaks 345kV |
| J1815 | Solar | Duke Energy Indiana, LLC | Montgomery | IN | NRIS | 180 | Linden Junction - Crawfordsville 138 kV |
| J1829 | Solar | Duke Energy Indiana, LLC | Shelby | IN | NRIS | 180 | DEI's Columbus to Clark Twp. 230 kV (one of the two 230 kV circuits going from Columbus to Five Point |
| J1830 | Hybrid | Ameren Illinois | Pulaski | IL | NRIS | 200 | Kelso - Joppa (Massac) 345 kV line |
| J1831 | Wind | Ameren Illinois | Menard | IL | NRIS | 200 | Shockey 138kV |
| J1835 | Wind | Southern Indiana Gas & Electric Company d/b/a Vectren Energy Delivery of Indiana, Inc. | Spencer | IN | NRIS | 200 | Culley to Grandview 138 KV line tap |
| J1836 | Solar | Ameren Missouri | Callaway | MO | NRIS | 300 | Callaway Plant-345 kV |
| J1839 | Gas | Ameren Illinois | Macon | IL | NRIS | 340.3 | Decatur ADM North 138 kV |
| J1840 | Solar | Ameren Illinois | De Witt | IL | NRIS | 250 | Clinton to Goose Creek-4545 345kV line |



1.2. Total Network Upgrades

The cost allocation of Network Upgrades for the projects in the DPP 2020 Central Phase 1 reflects responsibilities for mitigating system impacts. The total cost of Network Upgrades is listed in **Error! Reference source not found.** below. The costs for Network Upgrades are planning-level estimates and subject to revision in the facility studies. Details pertaining to the cost allocation has been detailed in Appendix A – Cost Allocation Summary (CEII).

Table 3: Total Cost of Network Upgrade for DPP 2020 Central Phase 1 Projects

| Project Number | DPP Phase I | | | | | | | | | | | Payment in DPP Phase I | |
|----------------|----------------------------|-----------|---------------|-----------------|----------------------------|---------------------------------|----------------------------|---------------|-----------------------------|-----------------------|--------------------------------------|------------------------|-----------------------|
| | ERIS Network Upgrades (\$) | | | | NRIS Network Upgrades (\$) | Interconnection Facilities (\$) | | | Shared Network Updates (\$) | Total Cost of NU (\$) | 10% of Total Cost of Phase I NU (\$) | M2 (\$) | M3 =10% of NU-M2 (\$) |
| | Thermal | Stability | Short Circuit | Affected System | Deliverability | TO Network Upgrades | TO - Owned Direct Assigned | TO Self Fund? | | | | | |
| J1491 | \$259,094,412 | TBD | TBD | TBD | \$0 | \$2,300,000 | \$0 | No | \$0 | \$261,394,412 | \$26,139,441 | \$800,000 | \$25,339,441 |
| J1517 | \$93,998,273 | TBD | TBD | TBD | \$5,003,056 | \$7,000,000 | \$0 | No | \$0 | \$106,001,328 | \$10,600,133 | \$160,000 | \$10,440,133 |
| J1518 | \$2,038,409 | TBD | TBD | TBD | \$23,123,060 | \$0 | \$0 | N/A | \$0 | \$25,161,469 | \$2,516,147 | \$740,000 | \$1,776,147 |
| J1519 | \$0 | TBD | TBD | TBD | \$7,220 | \$12,000,000 | \$1,500,000 | Yes | \$0 | \$12,007,220 | \$1,200,722 | \$800,000 | \$400,722 |
| J1563 | \$110,110,125 | TBD | TBD | TBD | \$6,504,840 | \$17,000,000 | \$0 | No | \$0 | \$133,614,965 | \$13,361,497 | \$800,000 | \$12,561,497 |
| J1565 | \$0 | TBD | TBD | TBD | \$83,485 | \$20,000,000 | \$0 | No | \$0 | \$20,083,485 | \$2,008,349 | \$800,000 | \$1,208,349 |
| J1578 | \$7,433,851 | TBD | TBD | TBD | \$0 | \$17,000,000 | \$0 | No | \$0 | \$24,433,851 | \$2,443,385 | \$800,000 | \$1,643,385 |
| J1579 | \$0 | TBD | TBD | TBD | \$92,303 | \$8,000,000 | \$1,200,000 | Yes | \$0 | \$8,092,303 | \$809,230 | \$800,000 | \$9,230 |
| J1585 | \$8,500,000 | TBD | TBD | TBD | \$0 | \$8,000,000 | \$1,200,000 | Yes | \$7,689,822 | \$24,189,822 | \$2,418,982 | \$800,000 | \$1,618,982 |
| J1591 | \$1,414,168 | TBD | TBD | TBD | \$386,187 | \$8,000,000 | \$0 | No | \$0 | \$9,800,355 | \$980,035 | \$600,000 | \$380,035 |
| J1593 | \$31,927,390 | TBD | TBD | TBD | \$3,601,097 | \$20,000,000 | \$0 | No | \$0 | \$55,528,487 | \$5,552,849 | \$800,000 | \$4,752,849 |
| J1600 | \$0 | TBD | TBD | TBD | \$0 | \$13,000,000 | \$0 | No | \$0 | \$13,000,000 | \$1,300,000 | \$160,000 | \$1,140,000 |
| J1604 | \$418,666 | TBD | TBD | TBD | \$0 | \$444,960 | \$0 | No | \$0 | \$863,626 | \$86,363 | \$200,000 | \$0 |
| J1610 | \$4,470,949 | TBD | TBD | TBD | \$4,661 | \$0 | \$1,780,807 | Yes | \$0 | \$4,475,610 | \$447,561 | \$400,000 | \$47,561 |
| J1616 | \$0 | TBD | TBD | TBD | \$18,754,877 | \$20,000,000 | \$0 | No | \$0 | \$38,754,877 | \$3,875,488 | \$800,000 | \$3,075,488 |
| J1619 | \$1,425,666 | TBD | TBD | TBD | \$939,421 | \$3,259,219 | \$0 | No | \$0 | \$5,624,306 | \$562,431 | \$640,000 | \$0 |
| J1624 | \$0 | TBD | TBD | TBD | \$0 | \$17,000,000 | \$0 | No | \$0 | \$17,000,000 | \$1,700,000 | \$400,000 | \$1,300,000 |

| Project Number | DPP Phase I | | | | | | | | | | | Payment in DPP Phase I | |
|----------------|----------------------------|-----------|---------------|-----------------|----------------------------|---------------------------------|----------------------------|---------------|-----------------------------|-----------------------|--------------------------------------|------------------------|-----------------------|
| | ERIS Network Upgrades (\$) | | | | NRIS Network Upgrades (\$) | Interconnection Facilities (\$) | | | Shared Network Updates (\$) | Total Cost of NU (\$) | 10% of Total Cost of Phase I NU (\$) | M2 (\$) | M3 =10% of NU-M2 (\$) |
| | Thermal | Stability | Short Circuit | Affected System | Deliverability | TO Network Upgrades | TO - Owned Direct Assigned | TO Self Fund? | | | | | |
| J1625 | \$32,346,462 | TBD | TBD | TBD | \$11,006,307 | \$17,000,000 | \$0 | No | \$9,611,180 | \$69,963,950 | \$6,996,395 | \$600,000 | \$6,396,395 |
| J1626 | \$7,113,721 | TBD | TBD | TBD | \$298,695 | \$0 | \$800,000 | Yes | \$0 | \$7,412,416 | \$741,242 | \$600,000 | \$141,242 |
| J1632 | \$58,611,145 | TBD | TBD | TBD | \$68,214,699 | \$13,000,000 | \$0 | No | \$0 | \$139,825,845 | \$13,982,584 | \$800,000 | \$13,182,584 |
| J1636 | \$0 | TBD | TBD | TBD | \$0 | \$0 | \$800,000 | Yes | \$0 | \$0 | \$0 | \$600,000 | \$0 |
| J1637 | \$0 | TBD | TBD | TBD | \$10,930,972 | \$10,000,000 | \$0 | No | \$0 | \$20,930,972 | \$2,093,097 | \$600,000 | \$1,493,097 |
| J1638 | \$0 | TBD | TBD | TBD | \$72,392 | \$5,000,000 | \$0 | No | \$0 | \$5,072,392 | \$507,239 | \$600,000 | \$0 |
| J1641 | \$0 | TBD | TBD | TBD | \$12,375,392 | \$8,600,000 | \$0 | No | \$0 | \$20,975,392 | \$2,097,539 | \$600,000 | \$1,497,539 |
| J1642 | \$21,050,184 | TBD | TBD | TBD | \$327,433 | \$11,167,966 | \$0 | No | \$0 | \$32,545,583 | \$3,254,558 | \$800,000 | \$2,454,558 |
| J1646 | \$780,295 | TBD | TBD | TBD | \$4,769,808 | \$3,600,000 | \$0 | No | \$0 | \$9,150,103 | \$915,010 | \$600,000 | \$315,010 |
| J1649 | \$0 | TBD | TBD | TBD | \$0 | \$13,000,000 | \$0 | No | \$0 | \$13,000,000 | \$1,300,000 | \$240,000 | \$1,060,000 |
| J1651 | \$10,772,793 | TBD | TBD | TBD | \$6,674,412 | \$800,000 | \$1,200,000 | Yes | \$0 | \$18,247,205 | \$1,824,720 | \$800,000 | \$1,024,720 |
| J1652 | \$1,731,392 | TBD | TBD | TBD | \$15,491,504 | \$0 | \$800,000 | Yes | \$0 | \$17,222,896 | \$1,722,290 | \$800,000 | \$922,290 |
| J1653 | \$8,755,699 | TBD | TBD | TBD | \$33,052,950 | \$0 | \$800,000 | Yes | \$0 | \$41,808,650 | \$4,180,865 | \$600,000 | \$3,580,865 |
| J1655 | \$12,089,318 | TBD | TBD | TBD | \$2,666 | \$0 | \$50,000 | Yes | \$0 | \$12,091,984 | \$1,209,198 | \$200,000 | \$1,009,198 |
| J1656 | \$224,328,500 | TBD | TBD | TBD | \$75,759,610 | \$12,000,000 | \$1,500,000 | Yes | \$0 | \$312,088,110 | \$31,208,811 | \$1,980,000 | \$29,228,811 |
| J1676 | \$108,112,379 | TBD | TBD | TBD | \$9,107,879 | \$12,000,000 | \$1,500,000 | Yes | \$0 | \$129,220,258 | \$12,922,026 | \$1,200,000 | \$11,722,026 |
| J1677 | \$5,900,520 | TBD | TBD | TBD | \$6,582,089 | \$2,500,000 | \$1,500,000 | Yes | \$0 | \$14,982,609 | \$1,498,261 | \$720,000 | \$778,261 |
| J1678 | \$4,765,629 | TBD | TBD | TBD | \$1,587,180 | \$5,000,000 | \$0 | No | \$0 | \$11,352,809 | \$1,135,281 | \$298,800 | \$836,481 |
| J1679 | \$9,906,851 | TBD | TBD | TBD | \$6,877 | \$12,000,000 | \$1,500,000 | Yes | \$0 | \$21,913,727 | \$2,191,373 | \$500,000 | \$1,691,373 |
| J1680 | \$0 | TBD | TBD | TBD | \$2,189,329 | \$18,000,000 | \$0 | No | \$0 | \$20,189,329 | \$2,018,933 | \$400,000 | \$1,618,933 |
| J1681 | \$0 | TBD | TBD | TBD | \$7,263 | \$12,000,000 | \$1,500,000 | Yes | \$0 | \$12,007,263 | \$1,200,726 | \$800,000 | \$400,726 |
| J1684 | \$0 | TBD | TBD | TBD | \$0 | \$23,700,000 | \$0 | No | \$0 | \$23,700,000 | \$2,370,000 | \$800,000 | \$1,570,000 |
| J1687 | \$10,000,000 | TBD | TBD | TBD | \$0 | \$9,300,000 | \$0 | No | \$0 | \$19,300,000 | \$1,930,000 | \$800,000 | \$1,130,000 |
| J1691 | \$0 | TBD | TBD | TBD | \$14,079,206 | \$2,350,000 | \$0 | No | \$7,123,740 | \$23,552,946 | \$2,355,295 | \$800,000 | \$1,555,295 |
| J1695 | \$5,972,719 | TBD | TBD | TBD | \$2,316 | \$0 | \$800,000 | Yes | \$0 | \$5,975,035 | \$597,504 | \$200,000 | \$397,504 |

| Project Number | DPP Phase I | | | | | | | | | | | Payment in DPP Phase I | |
|----------------|----------------------------|-----------|---------------|-----------------|----------------------------|---------------------------------|----------------------------|---------------|-----------------------------|-----------------------|--------------------------------------|------------------------|-----------------------|
| | ERIS Network Upgrades (\$) | | | | NRIS Network Upgrades (\$) | Interconnection Facilities (\$) | | | Shared Network Updates (\$) | Total Cost of NU (\$) | 10% of Total Cost of Phase I NU (\$) | M2 (\$) | M3 =10% of NU-M2 (\$) |
| | Thermal | Stability | Short Circuit | Affected System | Deliverability | TO Network Upgrades | TO - Owned Direct Assigned | TO Self Fund? | | | | | |
| J1696 | \$1,341,933 | TBD | TBD | TBD | \$881,101 | \$5,000,000 | \$0 | No | \$0 | \$7,223,034 | \$722,303 | \$600,000 | \$122,303 |
| J1697 | \$10,000,000 | TBD | TBD | TBD | \$87,610 | \$15,000,000 | \$0 | No | \$0 | \$25,087,610 | \$2,508,761 | \$800,000 | \$1,708,761 |
| J1699 | \$8,764,690 | TBD | TBD | TBD | \$0 | \$7,100,000 | \$0 | No | \$0 | \$15,864,690 | \$1,586,469 | \$200,000 | \$1,386,469 |
| J1701 | \$28,683,412 | TBD | TBD | TBD | \$70,887,408 | \$8,000,000 | \$1,200,000 | Yes | \$0 | \$107,570,819 | \$10,757,082 | \$800,000 | \$9,957,082 |
| J1703 | \$24,945,590 | TBD | TBD | TBD | \$19,184,230 | \$13,000,000 | \$0 | No | \$0 | \$57,129,820 | \$5,712,982 | \$400,000 | \$5,312,982 |
| J1704 | \$23,032,350 | TBD | TBD | TBD | \$967,868 | \$20,000,000 | \$0 | No | \$0 | \$44,000,218 | \$4,400,022 | \$200,000 | \$4,200,022 |
| J1707 | \$0 | TBD | TBD | TBD | \$47,716 | \$5,000,000 | \$0 | No | \$0 | \$5,047,716 | \$504,772 | \$288,000 | \$216,772 |
| J1712 | \$5,124,029 | TBD | TBD | TBD | \$13,839 | \$12,000,000 | \$1,500,000 | Yes | \$0 | \$17,137,868 | \$1,713,787 | \$1,200,000 | \$513,787 |
| J1713 | \$40,573,552 | TBD | TBD | TBD | \$4,742,796 | \$0 | \$800,000 | Yes | \$0 | \$45,316,349 | \$4,531,635 | \$600,000 | \$3,931,635 |
| J1714 | \$4,886,220 | TBD | TBD | TBD | \$198,956 | \$0 | \$50,000 | Yes | \$0 | \$5,085,177 | \$508,518 | \$400,000 | \$108,518 |
| J1721 | \$0 | TBD | TBD | TBD | \$7,027,087 | \$15,000,000 | \$0 | No | \$0 | \$22,027,087 | \$2,202,709 | \$700,480 | \$1,502,229 |
| J1724 | \$0 | TBD | TBD | TBD | \$0 | \$14,600,000 | \$0 | No | \$0 | \$14,600,000 | \$1,460,000 | \$600,000 | \$860,000 |
| J1725 | \$17,349,997 | TBD | TBD | TBD | \$22,036,081 | \$0 | \$50,000 | Yes | \$0 | \$39,386,078 | \$3,938,608 | \$400,000 | \$3,538,608 |
| J1726 | \$0 | TBD | TBD | TBD | \$0 | \$23,700,000 | \$0 | No | \$0 | \$23,700,000 | \$2,370,000 | \$800,000 | \$1,570,000 |
| J1736 | \$0 | TBD | TBD | TBD | \$58,383 | \$0 | \$0 | No | \$0 | \$58,383 | \$5,838 | \$400,000 | \$0 |
| J1737 | \$3,729,401 | TBD | TBD | TBD | \$4,069,357 | \$20,000,000 | \$0 | No | \$0 | \$27,798,758 | \$2,779,876 | \$840,000 | \$1,939,876 |
| J1743 | \$0 | TBD | TBD | TBD | \$6,223,491 | \$5,000,000 | \$0 | No | \$0 | \$11,223,491 | \$1,122,349 | \$1,171,600 | \$0 |
| J1744 | \$3,205,495 | TBD | TBD | TBD | \$388,542 | \$8,000,000 | \$1,200,000 | Yes | \$0 | \$11,594,037 | \$1,159,404 | \$598,000 | \$561,404 |
| J1755 | \$19,634,572 | TBD | TBD | TBD | \$795,626 | \$800,000 | \$1,200,000 | Yes | \$0 | \$21,230,198 | \$2,123,020 | \$600,000 | \$1,523,020 |
| J1756 | \$188,290,797 | TBD | TBD | TBD | \$5,987,461 | \$18,500,000 | \$0 | No | \$0 | \$212,778,258 | \$21,277,826 | \$1,996,000 | \$19,281,826 |
| J1765 | \$20,274,856 | TBD | TBD | TBD | \$7,151,405 | \$10,000,000 | \$0 | No | \$0 | \$37,426,261 | \$3,742,626 | \$600,000 | \$3,142,626 |
| J1770 | \$47,886,750 | TBD | TBD | TBD | \$0 | \$0 | \$800,000 | Yes | \$0 | \$47,886,750 | \$4,788,675 | \$600,000 | \$4,188,675 |
| J1772 | \$0 | TBD | TBD | TBD | \$0 | \$0 | \$0 | N/A | \$0 | \$0 | \$0 | \$800,000 | \$0 |
| J1774 | \$0 | TBD | TBD | TBD | \$11,190,258 | \$0 | \$0 | No | \$0 | \$11,190,258 | \$1,119,026 | \$200,000 | \$919,026 |
| J1777 | \$93,458 | TBD | TBD | TBD | \$4,632 | \$800,000 | \$1,200,000 | Yes | \$0 | \$898,090 | \$89,809 | \$400,000 | \$0 |

| Project Number | DPP Phase I | | | | | | | | | | | Payment in DPP Phase I | |
|----------------|----------------------------|-----------|---------------|-----------------|----------------------------|---------------------------------|----------------------------|---------------|-----------------------------|-----------------------|--------------------------------------|------------------------|-----------------------|
| | ERIS Network Upgrades (\$) | | | | NRIS Network Upgrades (\$) | Interconnection Facilities (\$) | | | Shared Network Updates (\$) | Total Cost of NU (\$) | 10% of Total Cost of Phase I NU (\$) | M2 (\$) | M3 =10% of NU-M2 (\$) |
| | Thermal | Stability | Short Circuit | Affected System | Deliverability | TO Network Upgrades | TO - Owned Direct Assigned | TO Self Fund? | | | | | |
| J1780 | \$88,896,650 | TBD | TBD | TBD | \$5,855,713 | \$15,000,000 | \$0 | No | \$0 | \$109,752,363 | \$10,975,236 | \$800,000 | \$10,175,236 |
| J1782 | \$81,232,855 | TBD | TBD | TBD | \$4,957,002 | \$17,000,000 | \$0 | No | \$0 | \$103,189,857 | \$10,318,986 | \$600,000 | \$9,718,986 |
| J1783 | \$81,232,855 | TBD | TBD | TBD | \$4,957,002 | \$17,000,000 | \$0 | No | \$0 | \$103,189,857 | \$10,318,986 | \$600,000 | \$9,718,986 |
| J1784 | \$20,000,000 | TBD | TBD | TBD | \$0 | \$9,000,000 | \$0 | No | \$0 | \$29,000,000 | \$2,900,000 | \$156,000 | \$2,744,000 |
| J1785 | \$0 | TBD | TBD | TBD | \$0 | \$3,000,000 | \$0 | No | \$0 | \$3,000,000 | \$300,000 | \$400,000 | \$0 |
| J1786 | \$0 | TBD | TBD | TBD | \$14,079,206 | \$2,350,000 | \$0 | No | \$7,123,740 | \$23,552,946 | \$2,355,295 | \$800,000 | \$1,555,295 |
| J1802 | \$0 | TBD | TBD | TBD | \$0 | \$3,600,000 | \$0 | No | \$0 | \$3,600,000 | \$360,000 | \$600,000 | \$0 |
| J1805 | \$691,450 | TBD | TBD | TBD | \$0 | \$0 | \$0 | N/A | \$0 | \$691,450 | \$69,145 | \$0 | \$69,145 |
| J1806 | \$17,893,232 | TBD | TBD | TBD | \$374,216 | \$0 | \$0 | N/A | \$0 | \$18,267,448 | \$1,826,745 | \$120,000 | \$1,706,745 |
| J1810 | \$4,261,192 | TBD | TBD | TBD | \$0 | \$0 | \$0 | N/A | \$0 | \$4,261,192 | \$426,119 | \$240,000 | \$186,119 |
| J1815 | \$81,303,350 | TBD | TBD | TBD | \$0 | \$15,000,000 | \$0 | No | \$0 | \$96,303,350 | \$9,630,335 | \$720,000 | \$8,910,335 |
| J1829 | \$5,566,149 | TBD | TBD | TBD | \$0 | \$17,000,000 | \$0 | No | \$0 | \$22,566,149 | \$2,256,615 | \$1,000,000 | \$1,256,615 |
| J1830 | \$14,682,373 | TBD | TBD | TBD | \$0 | \$12,000,000 | \$1,500,000 | Yes | \$0 | \$26,682,373 | \$2,668,237 | \$800,000 | \$1,868,237 |
| J1831 | \$67,061,370 | TBD | TBD | TBD | \$6,902,880 | \$800,000 | \$1,200,000 | Yes | \$0 | \$74,764,250 | \$7,476,425 | \$800,000 | \$6,676,425 |
| J1835 | \$0 | TBD | TBD | TBD | \$0 | \$12,000,000 | \$0 | No | \$0 | \$12,000,000 | \$1,200,000 | \$800,000 | \$400,000 |
| J1836 | \$0 | TBD | TBD | TBD | \$11,466 | \$1,000,000 | \$1,500,000 | Yes | \$0 | \$1,011,466 | \$101,147 | \$1,200,000 | \$0 |
| J1839 | \$10,537,268 | TBD | TBD | TBD | \$10,087,233 | \$1,500,000 | \$1,200,000 | Yes | \$0 | \$22,124,501 | \$2,212,450 | \$1,361,200 | \$851,250 |
| J1840 | \$7,687,121 | TBD | TBD | TBD | \$11,028,309 | \$12,000,000 | \$1,500,000 | Yes | \$0 | \$30,715,430 | \$3,071,543 | \$1,425,000 | \$1,646,543 |

Analyses performed demonstrate that transmission facilities are required to reliably interconnect this group of generators to the transmission system. ERS and NRS Network Upgrades required for full interconnection service detailed in **Error! Reference source not found.**

Due to the timing of DPP 2020 Central Phase 1, there is a discrepancy with the DPP-2020 South Phase 3 report. MISO is aware of additional Network Upgrades that will impact Central projects once Central completes Phase 2. Please refer to the DPP 2020 South Phase 3 System Impact Study for additional information.

Table 4: ERS & NRS Upgrades Required for Interconnection Service

| Network Upgrade | Type | TO | NU Cost Estimate (\$) | Projects impacted |
|--|-----------|--------|-----------------------|--|
| 132-39 Reconductor | ERS | IPL | \$ 5,000,000 | J1491 |
| 2nd Mason-Quiver Line | NRS | AMIL | \$ 19,000,000 | J1653, J1725, |
| 2nd Overton 345/161 kV XFMR; J1490-Montgomery 3 parallel lines | ERS | AMMO | \$ - | J1498, J1590, J1655, J1695, J1754, |
| 2nd San Jose Rail-Towerline Line | NRS | AMIL | \$ 37,000,000 | J1651, J1651, J1653, J1653, J1725, J1725, J1831, J1831, |
| 345kV NU Projects | ERS | AMIL | \$ - | J1770 |
| 48154 J1815 POI to LINDNT | ERS | DEI | \$ 9,000,000 | J1780, J1815, |
| A.E. Staley to Laf Ind S. - Recon | ERS | DEI | \$ 1,000,000 | J1780, J1815, |
| AEP Facility Limit. No NIPSCO Upgrades. | NRS | NIPS | \$ - | J1497, J1502, J1508, J1510, J1512, J1513, J1567, J1573, J1596, J1615, J1629, J1684, J1706, J1716, J1719, J1720, J1724, J1732, J1735, J1740, J1745, J1746, J1750, J1751, J1752, J1773, J1778, J1779, J1785, J1793, J1803, J1814, J1817, J1824, J1843, |
| AEP/PJM Howe-Sturgis | NRS | NIPS | \$ - | J1550 |
| Albion S J1422 Rating Update | NRS | AMIL | \$ - | J1579 |
| Albion TR Upgrade | NRS | AMIL | \$ - | J1579 |
| AMO Relaying | NRS | DEI | \$ - | J1616, J1637, |
| Bloomington 345-138 sub SUM_R1.idv | NRS | DEI | \$ 42,000,000 | J1641, J1691, J1721, J1786, |
| Bunsonville-Eugene 345 kV 2nd Line | ERS (LPC) | Ameren | \$ 30,000,000 | J1491, J1492, J1517, J1586, J1635, J1639, J1642, J1655, J1656, J1659, J1660, J1665, J1676, J1678, J1695, J1701, J1704, J1713, J1725, J1755, J1756, J1770, J1805, J1806, J1810, J1831 |
| Bunsonville-J1656 345 kV 2nd Line | ERS (LPC) | Ameren | \$ 20,000,000 | J1491, J1492, J1517, J1586, J1635, J1639, J1642, J1655, J1656, J1659, J1660, J1665, J1676, J1678, J1695, J1701, J1704, J1713, J1725, J1755, J1756, J1770, J1805, J1806, J1810, J1831, J1517, J1656, J1676, J1770 |
| Cane-Mason City 138 kV rebuild to 1200A | ERS (LPC) | Ameren | \$ 11,900,000 | J1610, J1651, J1653, J1725, J1831 |
| Car Jt to Tipton | ERS | DEI | \$ 35,250,000 | J1625, J1765, |

| Network Upgrade | Type | TO | NU Cost Estimate (\$) | Projects impacted |
|---|------------|---------|-----------------------|--|
| Case W- J1771 Rating Update | NRIS | AMIL | \$ - | J1519, J1585, J1610, J1626, J1655, J1679, J1681, J1695, J1712, J1714, J1744, J1777, J1836, |
| Cay_CT to Cayuga Uprate and 2nd Line | NRIS | DEI | \$ 3,500,000 | J1591, J1626, J1641, J1652, J1691, J1713, J1714, J1721, J1744, J1786, J1840, J1774, |
| Caysub to Eugene Parallel Lines | ERIS | AEP/DEI | \$ 72,000,000 | J1491,J1517,J1642,J1656,J1676,J1704,J1756,J1770,J1806, |
| Cayuga Bank 10 | ERIS | DEI | \$ 12,000,000 | J1517 |
| Cayuga Bank 9 | ERIS | DEI | \$ 12,000,000 | J1517 |
| Cayuga Plant - Hillsdale North | ERIS | DEI | \$ 50,000,000 | J1517 |
| Cayuga Sub to Cayuga 2nd Line | ERIS | DEI | \$ 34,666,667 | J1491,J1517,J1642,J1656,J1676,J1704,J1756,J1770,J1806, |
| Cayuga Sub to Cayuga 3rd Line | ERIS | DEI | \$ 34,666,667 | J1517,J1656,J1770, |
| Cayuga to Nucor Parallel Line and Uprate | ERIS | DEI | \$ 119,000,000 | J1491,J1517,J1656,J1704,J1756,J1770,J1806, |
| Cayuga_Nucor_3rdLine.id v | NRIS | DEI | \$ 112,000,000 | J1517, J1518, J1646, J1652, J1656, J1676, J1677, J1713, J1780, J1839, J1840, J1774, |
| Century Aluminum RAS | NRIS | HE | \$ - | J1642, J1642, J1736, J1736, |
| Chrys 3 to Kokomo | ERIS | DEI | \$ 9,000,000 | J1491,J1704,J1756,J1806,J1491,J1704,J1756,J1806,J1563,J1625,J1765,J1782,J1783,J1563,J1625,J1765,J1782,J1783, |
| CHRY1 TO CHRY2 | ERIS | DEI | \$ 6,000,000 | J1563,J1625,J1765, |
| CHRY1 TO CHRY3 | ERIS | DEI | \$ 1,000,000 | J1563,J1625,J1765,J1782,J1783, |
| Construct 23 mile Weedman-N Champaign 138 kV line | ERIS (LPC) | Ameren | \$ 48,000,000 | J1517, J1676, J1713, J1831, J1517, J1676, J1713, J1831, J1676, J1676, J1676, J1517, J1676, J1713, J1831, J1491 |
| Construct 2nd 29 mile Kansas-Arland 345 kV line | ERIS (LPC) | Ameren | \$ 73,000,000 | J1491, J1492, J1517, J1586, J1635, J1639, J1642, J1655, J1656, J1659, J1660, J1665, J1676, J1678, J1695, J1701, J1704, J1713, J1725, J1755, J1756, J1770, J1805, J1806, J1810, J1831, J1491, J1492, J1517, J1586, J1635, J1639, J1642, J1655, J1656, J1659, J1660, J1665, J1676, J1678, J1695, J1701, J1704, J1713, J1725, J1755, J1756, J1770, J1805, J1806, J1810, J1831, J1713, J1491, J1492, J1494, J1495, J1496, J1508, J1512, J1517, J1528, J1572, J1575, J1586, J1613, J1635, J1639, J1642, J1655, J1659, J1660, J1665, J1676, J1678, J1701, J1704, J1713, J1725, J1733, J1755, J1756, J1769, J1773, J1781, J1804, J1806, J1810, J1817, J1826, J1830, J1831 |
| Construct 2nd 3.5 mile Coffeen N-Redhawk 345 kV Line | ERIS (LPC) | Ameren | \$ 18,500,000 | J1610, J1626, J1646, J1651, J1652, J1653, J1656, J1676, J1677, J1713, J1714, J1725, J1744, J1770, J1831, J1839, J1840 |
| Construct 2nd 31.5 mi 3000 A Callaway-Bland 345 kV line | ERIS (LPC) | Ameren | \$ 69,375,000 | J1491, J1517, J1521, J1572, J1575, J1590, J1594, J1613, J1621, J1642, J1655, J1695, J1704, J1754, J1756, J1769, J1806, J1826, J1830, J1521, J1523, J1572, J1575, J1590, J1594, J1613, J1621, J1642, J1655, J1695, J1701, J1704, J1723, J1754, J1756, J1769, J1819, J1821, J1826, J1830, J1491, J1517, J1521, J1572, J1575, J1590, J1594, J1613, J1621, J1642, J1655, J1695, J1704, J1754, |

| Network Upgrade | Type | TO | NU Cost Estimate (\$) | Projects impacted |
|--|------------|-----------|-----------------------|---|
| | | | | J1756, J1769, J1806, J1826, J1830, J1491, J1492, J1494, J1495, J1496, J1498, J1517, J1521, J1523, J1528, J1572, J1575, J1586, J1590, J1594, J1613, J1621, J1635, J1639, J1642, J1655, J1659, J1660, J1665, J1678, J1695, J1701, J1704, J1723, J1733, J1754, J1756, J1769, J1804, J1806, J1810, J1819, J1821, J1826, J1830 |
| Construct 2nd 32.5 mile Arland-Faraday 345 kV line | ERIS (LPC) | Ameren | \$ 81,000,000 | J1491, J1492, J1517, J1586, J1635, J1639, J1642, J1655, J1656, J1659, J1660, J1665, J1676, J1678, J1695, J1701, J1704, J1713, J1725, J1755, J1756, J1770, J1805, J1806, J1810, J1831, J1491, J1492, J1517, J1586, J1635, J1639, J1642, J1655, J1656, J1659, J1660, J1665, J1676, J1678, J1695, J1701, J1704, J1713, J1725, J1755, J1756, J1770, J1805, J1806, J1810, J1831, J1713, J1713, J1831, J1831, J1655, J1676, J1701, J1713, J1725, J1831, J1491, J1492, J1494, J1495, J1496, J1508, J1512, J1517, J1528, J1572, J1575, J1586, J1613, J1635, J1639, J1642, J1655, J1659, J1660, J1665, J1676, J1678, J1701, J1704, J1713, J1725, J1733, J1755, J1756, J1769, J1773, J1781, J1804, J1806, J1810, J1817, J1826 |
| Crawfordsville to Lake Holiday Jct | ERIS | DEI | \$ 25,000,000 | J1780, J1815, |
| Docket to Gillet 138 kV to 1200A | ERIS | AMIL | \$ 6,800,000 | J1831 |
| DPP2020-BREC-1 | ERIS | BREC/TV A | \$ 23,150,000 | J1604, J1619, J1632, J1696, J1703, |
| DPP2020-BREC-2 | ERIS | BREC | \$ 9,981,000 | J1632, J1703, |
| DPP2020-BREC-3 | ERIS | BREC | \$ 8,940,000 | J1632, |
| DPP2020-BREC-4 | ERIS | BREC | \$ 10,681,000 | J1632, |
| DPP2020-BREC-5 | ERIS | BREC | \$ - | J1649, |
| DPP2020-BREC-6 | ERIS | BREC | \$ - | J1649, |
| DPP2020-BREC-7 | ERIS | BREC | \$ 16,930,000 | J1632, |
| DPP2020-BREC-8 | ERIS | BREC | \$ 17,061,000 | J1703, |
| DPP2020-BREC-9 | ERIS | BREC | \$ - | J1600, |
| Dresser to Sugar Creek | ERIS | DEI | \$ 4,200,000 | J1491, J1517, J1642, J1704, J1756, J1806, |
| Dresser-Fairbanks Uprate (2018) | NRIS | DEI | \$ - | J1565, J1579, J1616, J1619, J1637, J1638, J1641, J1642, J1691, J1696, J1697, J1703, J1707, J1736, J1786, |
| Enterprise South Jct to Lebanon Enterprise | ERIS | DEI | \$ 4,500,000 | J1563, J1782, J1783, |
| Fall Creek- Noblesville Rebuild pt 1 | NRIS | DEI | \$ 5,800,000 | J1517, J1518, J1563, J1616, J1625, J1637, J1652, J1656, J1765, J1782, J1783, J1774, |
| Fall Creek- Noblesville Rebuild pt 2 | NRIS | DEI | \$ 70,000,000 | J1517, J1518, J1563, J1616, J1625, J1637, J1652, J1656, J1765, J1782, J1783, J1774, |
| Fountaintown Jct | ERIS | DEI | \$ 13,000,000 | J1756 |
| FVPTS1 to MCOMFT Reconductor | ERIS | DEI | \$ 9,225,000 | J1593, J1737, J1756, J1806, |
| Gen Foods to Laf S.E. - Recon | ERIS | DEI | \$ 3,000,000 | J1780, J1815, |

| Network Upgrade | Type | TO | NU Cost Estimate (\$) | Projects impacted |
|--|------------|--------|-----------------------|--|
| Gillett - Shockey 138 kV to 1200A | ERIS (LPC) | Ameren | \$ 6,375,000 | J1701, J1725, J1831 |
| Goose Creek- Rising 345 kV 2nd Line | ERIS (LPC) | Ameren | \$ 50,000,000 | J1491, J1491, J1492, J1492, J1494, J1494, J1495, J1495, J1496, J1496, J1508, J1508, J1512, J1512, J1517, J1517, J1528, J1528, J1572, J1572, J1575, J1575, J1586, J1586, J1613, J1613, J1635, J1635, J1639, J1639, J1642, J1642, J1655, J1655, J1659, J1659, J1660, J1660, J1665, J1665, J1676, J1676, J1678, J1678, J1701, J1701, J1704, J1704, J1713, J1713, J1725, J1725, J1733, J1733, J1755, J1755, J1756, J1756, J1769, J1769, J1773, J1773, J1781, J1781, J1804, J1804, J1806, J1806, J1810, J1810, J1817, J1817, J1826, J1826, J1830, J1830, J1831, J1831 |
| Grand Tower-Wittenberg 138 kV line rating update | NRIS | Ameren | \$ - | J1695, J1777, |
| Grandview sub switch upgrade New rating of 102MVA. | NRIS | SIGE | \$ 200,000 | J1642 |
| Greensboro to Greenfield | ERIS | DEI | \$ 35,000,000 | J1593,J1756,J1806, |
| Greensboro to New Castle | ERIS | DEI | \$ 500,000 | J1593,J1806, |
| H.E. Waldon Jct to Prescott | ERIS | DEI | \$ 16,000,000 | J1699,J1756, |
| H.E. Waldon to St. Paul | ERIS | DEI | \$ 20,000,000 | J1756,J1699, |
| H.H. DTRS to Greensburg | ERIS | HE/DEI | \$ 10,000,000 | J1687 |
| Haggerstown-J1784 POI 69150 rebuild with 954 ACSR | ERIS | DEI | \$ 20,000,000 | J1784 |
| Hamilton TR Upgrade | NRIS | AMIL | \$ 10,000,000 | J1734 |
| Hastpk to Greenfield Reconductor | ERIS | DEI | \$ 2,925,000 | J1593,J1756,J1806, |
| Havana- Havana S Rating Update | NRIS | AMIL | \$ - | J1651, J1653, J1725, J1831, |
| Havana S-Cane Line Rebuild | NRIS | AMIL | \$ 8,000,000 | J1651, J1653, J1725, J1831, |
| HE Washington Jct to Greenburg Washington St. | ERIS | DEI | \$ 2,500,000 | J1756 |
| Hillsdale to Montezuma | ERIS | DEI | \$ 6,000,000 | J1780,J1815, |
| Install 2nd Faraday 345/138 kV Transformer | ERIS (LPC) | Ameren | \$ 9,000,000 | J1491, J1517, J1642, J1676, J1701, J1713, J1725, J1831 |
| J1180-Sullivan Rating Update/ AEP AFS | NRIS | AMIL | \$ - | J1519, J1585, J1610, J1626, J1651, J1652, J1655, J1676, J1677, J1679, J1681, J1695, J1712, J1713, J1714, J1744, J1777, J1831, J1836, J1839, J1840, |
| J1352 Montgomery Line Rebuild | NRIS | AMMO | \$ 8,000,000 | J1494, J1495, J1496, J1497, J1498, J1502, J1503, J1504, J1508, J1510, J1512, J1513, J1520, J1521, J1529, J1534, J1566, J1567, J1572, J1573, J1575, J1581, J1582, J1588, J1594, J1596, J1597, J1605, J1611, J1613, J1615, J1620, J1621, J1629, J1653, J1657, J1701, J1706, J1708, J1716, J1719, J1720, J1725, J1730, J1732, J1733, J1734, J1735, J1740, J1745, J1746, J1750, J1751, J1752, J1754, J1755, J1769, J1773, J1778, J1779, |

| Network Upgrade | Type | TO | NU Cost Estimate (\$) | Projects impacted |
|---|------------|--------|-----------------------|--|
| | | | | J1781, J1793, J1803, J1808, J1814, J1817, J1824, J1826, J1843, |
| J1563 to Wabash River | ERIS | DEI | \$ 138,000,000 | J1563,J1782,J1783, |
| J1578 POI to Clark Township | ERIS | DEI | \$ 13,000,000 | J1578,J1829, |
| J1585 - Barnet - 161 Rebuild to 1200A | ERIS (LPC) | Ameren | \$ 8,500,000 | J1585 |
| J1701 - Ipava - 138 kV rebuild 1200A | ERIS (LPC) | Ameren | \$ 6,375,000 | J1701 |
| J1701 Ipava Rebuild | NRIS | AMIL | \$ 13,000,000 | J1701, J1734, |
| J1701-Macomb Rating Update | ERIS | AMIL | \$ - | J1701 |
| J1771-J1180 Rating Update | NRIS | AMIL | \$ - | J1519, J1585, J1610, J1626, J1655, J1679, J1681, J1695, J1712, J1714, J1744, J1777, J1836, |
| J1780 POI to Crawfordsville | ERIS | DEI | \$ 21,000,000 | J1780,J1815, |
| J1782 to Whitesville | ERIS | DEI | \$ 36,400,000 | J1517,J1518,J1563,J1591,J1782,J1783, |
| Jacksonville IP Terminal Upgrade- MISO Project ID 23149 | ERIS | AMIL | \$ - | J1610 |
| JH1453 - Havana 138 kV - Rebuild to 1600A | ERIS (LPC) | Ameren | \$ 10,200,000 | J1610, J1651, J1653, J1725, J1831 |
| Kinmundy-Louisville Rebuild | NRIS | AMMO | \$ - | J1626, J1714, |
| Kok Chrysler South to Greentown Maple St | ERIS | DEI | \$ 20,000,000 | J1563, J1625, J1765, J1782, J1783 |
| Kokomo Delco to Kok Highland Park | ERIS | DEI | \$ 8,600,000 | J1563,J1625,J1765,J1782,J1783, |
| Laf AE Stealey to General Foods Jct | ERIS | DEI | \$ 3,000,000 | J1780,J1815, |
| Lafayette Gen to South Jct | ERIS | DEI | \$ 1,200,000 | J1780,J1815, |
| Lafayette S. to Fairfield Reconnector | ERIS | DEI | \$ 5,000,000 | J1780,J1815, |
| Lafayette S. to Shadeland | ERIS | DEI | \$ 10,000,000 | J1780,J1815, |
| Lafayette SE to Tipmont WEA | ERIS | DEI | \$ 11,000,000 | J1780,J1815, |
| Lake Holiday Jct to Park Co. Marshall sub | ERIS | DEI | \$ 9,000,000 | J1780,J1815, |
| Lebanon Interprise to Lebanon | ERIS | DEI | \$ 3,250,000 | J1563,J1782,J1783, |
| Louisville S- Jasper Rating Update | NRIS | AMIL | \$ - | J1655, J1679, |
| L RTP MISO ID 23417 | NRIS | NIPS | \$ - | J1646, |
| L RTP Tranche 1- Hipple to Leesburg | ERIS | NIPS | \$ - | J1802 |
| L RTP-16 | NRIS | NIPS | \$ - | J1646, |
| Macomb NE - Hornsby Line Rebuild | NRIS | AMIL | \$ 20,000,000 | J1734 |
| Macomb W-Monument Rebuild | NRIS | AMIL | \$ 70,000,000 | J1701, J1734, |
| Mason-San Jose Rail 138 kV line rebuild to 2000 A.idv | NRIS | AMIL | \$ 3,000,000 | J1653, J1725, |

| Network Upgrade | Type | TO | NU Cost Estimate (\$) | Projects impacted |
|--|------------|----------|-----------------------|---|
| Mason-San Jose Rail Line Rebuild | NRIS | AMIL | \$ 3,000,000 | J1651, J1831, |
| MISO ID 17825 | NRIS | AMIL | \$ - | J1579 |
| MISO ID 22796 | NRIS | AMIL | \$ - | J1734 |
| MISO ID 23478 | NRIS | AMIL | \$ - | J1610, J1701, J1734, J1831, |
| Mittal - Bureau 138 kV to 1200A | ERIS (LPC) | Ameren | \$ 12,962,500 | J1755 |
| Mohawk to HASTPK Reconductor | ERIS | DEI | \$ 5,300,000 | J1704,J1737, |
| Montezuma to Rockville | ERIS | DEI | \$ 16,000,000 | J1780,J1815, |
| NIPS 34501 Stillwell to Dumont | ERIS | AEP/NIPS | \$ 9,800,000 | J1492,J1586,J1635,J1639,J1659,J1660,J1665, |
| NIPS 34519 St John to Crete | ERIS | NIPS/CE | \$ 900,000 | J1492,J1586,J1635,J1678,J1805,J1810, |
| NRIS BREC 2020-1 | NRIS | BREC | \$ 16,000,000 | J1632, J1703, |
| NRIS BREC 2020-2 | NRIS | BREC | \$ 22,000,000 | J1632, J1703, |
| NRIS BREC 2020-3 | NRIS | BREC | \$ 12,500,000 | J1632, J1703, |
| NRIS BREC 2020-4 | NRIS | BREC | \$ 21,500,000 | J1632, J1703, |
| NRIS BREC 2020-5 | NRIS | BREC | \$ 15,000,000 | J1632 |
| NRIS BREC 2020-6 | NRIS | BREC | \$ 2,000,000 | J1619, J1696, J1703, |
| NRIS DPP-2020-DEI-MEROM_FAIRBANKS_U PRATE_CONDUCTOR | NRIS | HE/DEI | \$ 3,000,000 | J1565, J1579, J1616, J1619, J1637, J1638, J1641, J1642, J1691, J1696, J1697, J1703, J1707, J1736, J1786, |
| Nucor to Whitestown Parallel Line and Rebuild | ERIS | DEI | \$ 198,000,000 | J1491,J1704,J1756,J1806,J1491, |
| NW-MarionCounty-Reinforcement + Relay Update | ERIS | DEI/IPL | \$ 64,200,000 | J1491 |
| Park Co to Rockville | ERIS | DEI | \$ 16,000,000 | J1780,J1815, |
| Pike Jct to Enterprise South Jct | ERIS | DEI | \$ 9,950,000 | J1563,J1782,J1783, |
| Pike Jct to Thorntown | ERIS | DEI | \$ 30,000 | J1563,J1782,J1783, |
| Prescott New Bank.idv | NRIS | DEI | \$ 15,000,000 | J1593, J1704, J1737, J1756, J1806, |
| Putnam-Mittal 138kV to 1200A | ERIS (LPC) | Ameren | \$ 1,000,000 | J1755 |
| Quiver - Mason 138 kV to 2000A | ERIS | AMIL | \$ 6,800,000 | J1725 |
| RAS | NRIS | DEI | \$ - | J1616 |
| Rebuild 0.25 miles of Grand Tower-Wittenberg 138 kV line to 1600 A | ERIS (LPC) | Ameren | \$ 500,000 | J1695, J1712, J1777, J1830 |
| Rebuild 10 miles of Yvonne-Taylorville S 138 kV line to 2000 A | ERIS (LPC) | Ameren | \$ 8,500,000 | J1701, J1831 |
| Rebuild 10.25 miles of N Nashville-Ashley 138 kV line to 1200 A | ERIS (LPC) | Ameren | \$ 8,712,500 | J1655, J1679 |
| Rebuild 11 mile J1840-Leghorn 345 kV line to 3000 A | ERIS (LPC) | Ameren | \$ 22,000,000 | J1491, J1492, J1508, J1512, J1517, J1521, J1572, J1575, J1586, J1594, J1613, J1621, J1635, J1639, J1642, J1655, J1659, J1660, |

| Network Upgrade | Type | TO | NU Cost Estimate (\$) | Projects impacted |
|---|------------|--------|-----------------------|--|
| | | | | J1665, J1676, J1678, J1701, J1704, J1713, J1725, J1754, J1755, J1756, J1769, J1773, J1781, J1806, J1810, J1817, J1826, J1831 |
| Rebuild 13.5 miles of El Paso tap to Minonk tap section of McLean-Rutland 138 kV line to 1600 A | ERIS (LPC) | Ameren | \$ 11,475,000 | J1676, J1677, J1839, J1840 |
| Rebuild 16.5 mile Rantoul-Rising 138 kV line to 1600 A | ERIS (LPC) | Ameren | \$ 14,000,000 | J1517, J1676, J1713, J1831, J1517, J1676, J1713, J1831, J1676, J1676, J1517, J1676, J1713, J1831 |
| Rebuild 17 mile Rezzy-Moro 138 kV line to 2000 A | ERIS (LPC) | Ameren | \$ 14,000,000 | J1610, J1626, J1651, J1652, J1655, J1676, J1677, J1679, J1713, J1714, J1744, J1770, J1831, J1839, J1840 |
| Rebuild 2.25 mile J1266-Salem W 138 kV line to 1600 A | ERIS (LPC) | Ameren | \$ 2,000,000 | J1626, J1655, J1679, J1714, J1744 |
| Rebuild 23 miles of Scarlet-Montgomery 345 kV line to 3000 A; Upgrade Montgomery terminal equipment | ERIS (LPC) | Ameren | \$ 27,600,000 | J1491, J1492, J1494, J1495, J1496, J1498, J1517, J1521, J1523, J1528, J1572, J1575, J1586, J1590, J1594, J1613, J1621, J1635, J1639, J1642, J1655, J1659, J1660, J1665, J1678, J1695, J1701, J1704, J1723, J1733, J1754, J1756, J1769, J1804, J1806, J1810, J1819, J1821, J1826, J1830 |
| Rebuild 3.5 miles of Decatur JCT to E. Main St. section of N. Decatur-E. Main St. 138 kV line to 2000 A | ERIS (LPC) | Ameren | \$ 2,975,000 | J1676, J1725, J1831 |
| Rebuild 4 mile Cottage Hills to Laclede S tap section of Wood River-Cottage Hills 138 kV line to 2000 A | ERIS (LPC) | Ameren | \$ 3,500,000 | J1626, J1713, J1714 |
| Rebuild 4 miles of J1232 POI-Mattoon W 138 kV line to 2000 A | ERIS (LPC) | Ameren | \$ 3,400,000 | J1676, J1713, J1831 |
| Rebuild 4.5 miles of J1232 POI-Arland 138 kV line to 2000 A | ERIS (LPC) | Ameren | \$ 3,825,000 | J1676, J1713, J1831 |
| Rebuild 5 mile J1840-Goose Creek 345 kV line to 3000 A | ERIS (LPC) | Ameren | \$ 10,000,000 | J1491, J1492, J1508, J1512, J1517, J1521, J1572, J1575, J1586, J1594, J1613, J1621, J1635, J1639, J1642, J1655, J1659, J1660, J1665, J1676, J1678, J1701, J1704, J1713, J1725, J1754, J1755, J1756, J1769, J1773, J1781, J1806, J1810, J1817, J1826, J1831 |
| Rebuild 5 miles of Latham-Docket 138 kV line to 2000 A | ERIS (LPC) | Ameren | \$ 4,000,000 | J1701, J1725, J1831 |
| Rebuild 6 miles of Labadie-Gray Summit-1 345 kV line to 3000 A | ERIS (LPC) | Ameren | \$ 12,000,000 | J1491, J1498, J1517, J1521, J1572, J1575, J1590, J1594, J1613, J1621, J1642, J1655, J1695, J1704, J1723, J1754, J1756, J1806, J1830 |
| Rebuild 6 miles of Labadie-Gray Summit-2 345 kV line to 3000 A | ERIS (LPC) | Ameren | \$ 12,000,000 | J1491, J1498, J1517, J1521, J1572, J1575, J1590, J1594, J1613, J1621, J1642, J1655, J1695, J1704, J1723, J1754, J1756, J1806, J1830 |

| Network Upgrade | Type | TO | NU Cost Estimate (\$) | Projects impacted |
|---|------------|---------|-----------------------|--|
| Rebuild 6.5 miles of Austin-Yvonne 138 kV line to 2000 A | ERIS (LPC) | Ameren | \$ 5,525,000 | J1701, J1831 |
| Rebuild 9.5 miles of N Nashville to Okawville section of Barrel-N Nashville 138 kV line to 1200 A; (1) bus conductor upgrade at Okawville to 1200 A | ERIS (LPC) | Ameren | \$ 8,075,000 | J1655, J1679, J1712 |
| Rebuild ADM N-Mt. Zion 7.5 mile 138 kV line to 2000 A | ERIS (LPC) | Ameren | \$ 6,000,000 | J1491, J1517, J1642, J1676, J1701, J1713, J1725, J1831 |
| Rebuild Rezzy to Litchfield tap 138 kV line section to 2000 A | ERIS (LPC) | Ameren | \$ 4,000,000 | J1610, J1626, J1651, J1652, J1676, J1677, J1713, J1714, J1744, J1831, J1839, J1840 |
| Rebuild Rising-Bondville 138 kV line to 2000 A | ERIS (LPC) | Ameren | \$ 2,762,500 | J1676 |
| Rebuild Shockey-Dirksen 138 kV line to 1200 A | ERIS (LPC) | Ameren | \$ 11,900,000 | J1831 |
| Rebuild Whitestown Hortonville | NRIS | 620/208 | \$ 21,000,000 | J1517, J1518, J1616, J1637, J1652, J1656, J1774, |
| Replace 2 345 kV switches at Labadie to 3000 A | ERIS (LPC) | Ameren | \$ 500,000 | J1491, J1517, J1521, J1572, J1575, J1590, J1594, J1613, J1621, J1642, J1655, J1695, J1704, J1754, J1756, J1806, J1826, J1830 |
| Replace 69 kV 600 A switch with 1200 A 69 kV switch | ERIS (LPC) | Ameren | \$ 55,000 | J1734 |
| Replace Sioux wave trap with 3000 A wave trap | ERIS (LPC) | Ameren | \$ 200,000 | J1491, J1492, J1517, J1521, J1572, J1575, J1586, J1590, J1594, J1613, J1621, J1635, J1639, J1642, J1655, J1659, J1660, J1665, J1678, J1695, J1704, J1754, J1756, J1805, J1806, J1810, J1830 |
| Replace Sioux wave trap with 3000 A wave trap; upgrade 0.01 mi of Sioux-Belleau 345 kV line to 3000 A | ERIS (LPC) | Ameren | \$ 500,000 | J1491, J1517, J1521, J1572, J1575, J1590, J1594, J1613, J1621, J1642, J1655, J1695, J1704, J1754, J1756, J1769, J1806, J1826, J1830 |
| Re-tap (2) 138 kV CTs for 2000 A capability at N Decatur 27th St. | ERIS (LPC) | Ameren | \$ 250,000 | J1652, J1656, J1676, J1677, J1713, J1770, J1839, J1840 |
| Ruby - Sidney - 345kV 3000A | ERIS | AMIL | \$ 3,000,000 | J1656, J1770, |
| Seymour Bank 1 | ERIS | DEI | \$ 10,000,000 | J1697 |
| Spencer Creek to J1352 Line Rebuild | NRIS | AMMO | \$ 52,000,000 | J1494, J1495, J1496, J1497, J1498, J1502, J1503, J1504, J1508, J1510, J1512, J1513, J1520, J1521, J1529, J1534, J1566, J1567, J1572, J1573, J1575, J1581, J1582, J1588, J1594, J1596, J1597, J1605, J1611, J1613, J1615, J1620, J1621, J1629, J1653, J1657, J1701, J1706, J1708, J1716, J1719, J1720, J1725, J1730, J1732, J1733, J1734, J1735, J1740, J1745, J1746, J1750, J1751, J1752, J1754, J1755, J1769, J1773, J1778, J1779, J1781, J1793, J1803, J1808, J1814, J1817, J1824, J1826, J1843, |
| Sugar Creek - Kansas 345 kV 2nd Line | ERIS (LPC) | Ameren | \$ 90,500,000 | J1491, J1492, J1517, J1586, J1635, J1639, J1642, J1655, J1656, J1659, J1660, J1665, |

| Network Upgrade | Type | TO | NU Cost Estimate (\$) | Projects impacted |
|---|------------|--------|-----------------------|--|
| | | | | J1676, J1678, J1695, J1701, J1704, J1713, J1725, J1755, J1756, J1770, J1805, J1806, J1810, J1831, J1491, J1492, J1517, J1586, J1635, J1639, J1642, J1655, J1656, J1659, J1660, J1665, J1676, J1678, J1695, J1701, J1704, J1713, J1725, J1755, J1756, J1770, J1805, J1806, J1810, J1831, J1642, J1704, J1756, J1830 |
| Sugar Creek to Cay CT Conductor Upgrade | NRIS | DEI | \$ 3,000,000 | J1591, J1626, J1641, J1652, J1691, J1713, J1714, J1721, J1744, J1786, J1840, |
| Thorntown Substation | ERIS | DEI | \$ 12,000,000 | J1563, J1782, J1783, |
| Tipmont Jct to Linden Jct | ERIS | DEI | \$ 22,000,000 | J1780, J1815, |
| Tipmont Jct to Tipmont WEA | ERIS | DEI | \$ 12,000,000 | J1780, J1815, |
| Upgrade 10 miles of Lawrenceville-Vincennes 138 kV line (Ameren end) line to 2000 A | ERIS (LPC) | Ameren | \$ 8,500,000 | J1642, J1655 |
| Upgrade Casey W 345 kV Wave Trap | NRIS | AMIL | \$ 200,000 | J1519, J1610, J1626, J1651, J1655, J1676, J1677, J1679, J1681, J1695, J1712, J1713, J1714, J1744, J1777, J1831, J1836, J1839, J1840, |
| Walton Transformer Replacement | NRIS | DEI | \$ 10,000,000 | J1678, J1680, J1743, |
| Whitesville to Thornton Reconductor | ERIS | DEI | \$ 38,000,000 | J1517, J1518, J1563, J1591, J1782, J1783, |
| Whitesville to Whitesville South | ERIS | DEI | \$ 10,000,000 | J1563, J1782, J1783, |

Note:

- 1) Details pertaining to upgrades, costs, and the execution plan for interconnection of the generating facility at the POI will be documented in the Facility Study for Interconnecting Generator.
- 2) Facilities that have been included as base case assumptions and the level of interconnection service that would be conditional upon these facilities being in service will be documented in the GIA (Generator Interconnection Agreement) for each respective GI request successfully achieving GIA execution.
- 3) A detailed summary of the estimated cost of Network Upgrades on a per project basis can be found in Appendix B – Network Upgrade Table Per Project (CEII).

2. FERC Order 827 Compliance Review

The Final Rule of FERC Order 827 “Reactive Power Requirements for Non-Synchronous Generation”, which was issued June 16, 2016, states that “Under this Final Rule, newly interconnecting non-synchronous generators that have not yet executed a Facilities Study Agreement as of the effective date of this Final Rule will be required to provide dynamic reactive power within the range of 0.95 leading to 0.95 lagging at the high-side of the generator substation.” As such, this Final Rule applies to all wind and solar projects included in the DPP 2020 Central study.

In this study, the power factor at the high-side of the generator substation for each inverter-based project was calculated and reviewed. The study method is to set Qgen of each study project at its Qmax, solve the case, then record the P and Q injection on the high side of the generator substation to calculate the lagging power factor (injecting VAR to the system). The same process is then repeated by setting Qgen at Qmin to calculate the leading power factor (absorbing VAR from the system).

The results show that all projects meet the requirement to maintain 0.95 leading power factor, however, 55

projects do not meet the requirement to provide reactive power capability corresponding to 0.95 lagging power factor, as highlighted in red below in **Error! Reference source not found..** Additional reactive support will be needed for these projects to meet the FERC requirement on reactive power capability prior to the completion of their GIA.

Table 5: FERC Order 827 Review Results

| Project | Pmax (MW) | Reactive Power Capability (MVAR) | Modeled VAR Compensation (MVAR) | VAR Injection | | | VAR Absorption | | | Meet FERC Order 827 Requirement? | Add'l VAR Needed (MVAR) |
|---------|-----------|----------------------------------|---------------------------------|---------------|----------|-----------|----------------|----------|-----------|----------------------------------|-------------------------|
| | | | | P (MW) | Q (MVAR) | P.F. (pu) | P (MW) | Q (MVAR) | P.F. (pu) | | |
| J1491 | 200.0 | ±65.00 | 0 | 197.0 | 11.5 | 0.9983 | 195.3 | -147.4 | -0.7982 | No | 53.3 |
| J1517 | 45.0 | ±21.80 | 0 | 44.7 | 19.6 | 0.9159 | 44.7 | -24.3 | -0.8783 | Yes | N/A |
| J1518 | 219.4 | ±106.30 | 0 | 214.2 | 75.5 | 0.9432 | 212.7 | -145.7 | -0.8250 | Yes | N/A |
| J1519 | 203.3 | ±104.28 | 0 | 198.0 | 49.9 | 0.9697 | 192.2 | -221.5 | -0.6553 | No | 15.2 |
| J1563 | 204.0 | ±66.88 | 0 | 199.2 | 8.3 | 0.9991 | 196.1 | -164.3 | -0.7665 | No | 57.2 |
| J1565 | 204.0 | ±66.88 | 0 | 199.5 | 13.5 | 0.9977 | 197.1 | -149.4 | -0.7969 | No | 52.1 |
| J1578 | 204.0 | ±66.88 | 0 | 199.4 | 12.9 | 0.9979 | 196.8 | -151.0 | -0.7934 | No | 52.7 |
| J1579 | 204.0 | ±66.88 | 0 | 199.5 | 14.9 | 0.9972 | 197.3 | -145.9 | -0.8039 | No | 50.7 |
| J1585 | 204.0 | ±66.88 | 0 | 199.3 | 12.9 | 0.9979 | 196.7 | -151.1 | -0.7932 | No | 52.6 |
| J1591 | 91.2 | ±25.00 | 28 | 150.0 | 57.4 | 0.9339 | 180.3 | -92.8 | -0.8893 | Yes | N/A |
| J1591 | 91.2 | ±25.00 | 28 | 150.0 | 57.4 | 0.9339 | 180.3 | -92.8 | -0.8893 | Yes | N/A |
| J1593 | 100.0 | ±48.43 | 0 | 197.0 | 62.1 | 0.9537 | 195.6 | -152.0 | -0.7896 | No | 2.6 |
| J1593 | 100.0 | ±48.43 | 0 | 197.0 | 62.1 | 0.9537 | 195.6 | -152.0 | -0.7896 | No | 2.6 |
| J1600 | 40.8 | ±13.45 | 0 | 40.0 | 9.8 | 0.9714 | 40.3 | -17.8 | -0.9147 | No | 3.4 |
| J1604 | 51.1 | ±16.87 | 0 | 50.0 | 10.0 | 0.9806 | 50.4 | -25.4 | 0.8933 | No | 6.4 |
| J1610 | 102.1 | ±33.70 | 0 | 100.0 | 15.7 | 0.9879 | 99.9 | -57.5 | -0.8666 | No | 17.2 |
| J1616 | 203.3 | ±104.28 | 0 | 198.0 | 50.8 | 0.9686 | 192.4 | -219.0 | -0.6600 | No | 14.3 |
| J1619 | 68.4 | ±26.30 | 52 | 187.3 | 76.8 | 0.9252 | 186.8 | -91.2 | -0.8986 | Yes | N/A |
| J1619 | 121.6 | ±26.30 | 52 | 187.3 | 76.8 | 0.9252 | 186.8 | -91.2 | -0.8986 | Yes | N/A |
| J1624 | 101.4 | ±53.25 | 0 | 99.8 | 31.7 | 0.9530 | 98.9 | -88.3 | -0.7460 | No | 1.1 |
| J1625 | 152.4 | ±84.72 | 0 | 149.4 | 46.9 | 0.9541 | 146.9 | -157.9 | -0.6813 | No | 2.2 |
| J1626 | 152.4 | ±84.72 | 0 | 149.6 | 49.5 | 0.9495 | 147.5 | -148.2 | -0.7054 | Yes | N/A |
| J1632 | 117.8 | ±33.00 | 64 | 232.5 | 88.2 | 0.9349 | 231.6 | -128.5 | -0.8744 | Yes | N/A |
| J1632 | 117.8 | ±33.00 | 64 | 232.5 | 88.2 | 0.9349 | 231.6 | -128.5 | -0.8744 | Yes | N/A |
| J1636 | 52.0 | ±17.00 | 7 | 51.5 | 17.5 | 0.9469 | 51.4 | -26.0 | -0.8922 | Yes | N/A |
| J1637 | 91.2 | ±25.00 | 56 | 180.3 | 82.6 | 0.9091 | 179.8 | -91.6 | -0.8910 | Yes | N/A |
| J1637 | 91.2 | ±25.00 | 56 | 180.3 | 82.6 | 0.9091 | 179.8 | -91.6 | -0.8910 | Yes | N/A |
| J1638 | 91.2 | ±25.00 | 28 | 150.0 | 54.5 | 0.9398 | 179.6 | -95.9 | -0.8820 | Yes | N/A |
| J1638 | 91.2 | ±25.00 | 28 | 150.0 | 54.5 | 0.9398 | 179.6 | -95.9 | -0.8820 | Yes | N/A |
| J1641 | 91.2 | ±25.00 | 42 | 180.2 | 59.6 | 0.9495 | 179.5 | -95.9 | -0.8821 | Yes | N/A |
| J1641 | 91.2 | ±25.00 | 42 | 180.2 | 59.6 | 0.9495 | 179.5 | -95.9 | -0.8821 | Yes | N/A |

| Project | Pmax (MW) | Reactive Power Capability (MVAR) | Modeled VAR Compensation (MVAR) | VAR Injection | | | VAR Absorption | | | Meet FERC Order 827 Requirement? | Add'l VAR Needed (MVAR) |
|---------|-----------|----------------------------------|---------------------------------|---------------|----------|-----------|----------------|----------|-----------|----------------------------------|-------------------------|
| | | | | P (MW) | Q (MVAR) | P.F. (pu) | P (MW) | Q (MVAR) | P.F. (pu) | | |
| J1642 | 209.0 | ±68.69 | 0 | 200.0 | 97.4 | 0.8991 | 304.3 | -209.8 | -0.8233 | Yes | N/A |
| J1642 | 104.5 | ±34.35 | 0 | 200.0 | 97.4 | 0.8991 | 304.3 | -209.8 | -0.8233 | Yes | N/A |
| J1646 | 152.1 | ±67.00 | 0 | 149.7 | 39.8 | 0.9664 | 148.8 | -105.0 | -0.8170 | No | 19.3 |
| J1649 | 61.3 | ±20.16 | 0 | 60.0 | 12.6 | 0.9787 | 60.5 | -29.6 | -0.8982 | No | 7.1 |
| J1651 | 149.5 | ±49.10 | 92 | 146.4 | 120.8 | 0.7714 | 144.7 | -103.9 | -0.8122 | Yes | N/A |
| J1652 | 134.9 | ±44.96 | 0 | 116.0 | 29.0 | 0.9701 | 132.9 | -71.5 | -0.8807 | No | 9.1 |
| J1653 | 172.2 | ±57.40 | 0 | 150.0 | 27.4 | 0.9837 | 168.5 | -110.5 | -0.8362 | No | 21.9 |
| J1655 | 54.5 | ±18.15 | 0 | 50.0 | 15.2 | 0.9569 | 54.2 | -21.9 | -0.9271 | No | 1.3 |
| J1656 | 112.0 | -39.74 / 53.28 | 28 | 412.0 | 110.3 | 0.9660 | 409.6 | -283.0 | -0.8227 | No | 25.1 |
| J1656 | 100.0 | ±32.87 | 28 | 412.0 | 110.3 | 0.9660 | 409.6 | -283.0 | -0.8227 | No | 25.1 |
| J1656 | 106.4 | -37.75 / 50.62 | 28 | 412.0 | 110.3 | 0.9660 | 409.6 | -283.0 | -0.8227 | No | 25.1 |
| J1656 | 103.5 | ±34.00 | 28 | 412.0 | 110.3 | 0.9660 | 409.6 | -283.0 | -0.8227 | No | 25.1 |
| J1676 | 151.2 | ±73.22 | 30 | 294.9 | 129.0 | 0.9162 | 287.7 | -292.3 | -0.7014 | Yes | N/A |
| J1676 | 151.2 | ±73.22 | 30 | 294.9 | 129.0 | 0.9162 | 287.7 | -292.3 | -0.7014 | Yes | N/A |
| J1677 | 183.0 | ±137.28 | 0 | 178.8 | 120.5 | 0.8292 | 176.7 | -169.5 | -0.7216 | Yes | N/A |
| J1678 | 40.5 | ±14.29 | 0 | 74.7 | 20.4 | 0.9645 | 76.0 | -34.6 | -0.9099 | No | 4.1 |
| J1678 | 36.0 | ±12.70 | 0 | 74.7 | 20.4 | 0.9645 | 76.0 | -34.6 | -0.9099 | No | 4.1 |
| J1679 | 126.7 | ±95.04 | 0 | 124.4 | 74.3 | 0.8587 | 121.9 | -151.3 | -0.6276 | Yes | N/A |
| J1680 | 102.8 | ±77.10 | 0 | 101.1 | 56.6 | 0.8728 | 99.7 | -116.8 | -0.6492 | Yes | N/A |
| J1681 | 100.0 | ±48.43 | 0 | 197.2 | 73.6 | 0.9368 | 196.1 | -136.8 | -0.8200 | Yes | N/A |
| J1681 | 100.0 | ±48.43 | 0 | 197.2 | 73.6 | 0.9368 | 196.1 | -136.8 | -0.8200 | Yes | N/A |
| J1684 | 201.0 | ±85.60 | 0 | 196.2 | 24.5 | 0.9923 | 188.1 | -261.1 | -0.5845 | No | 53.0 |
| J1687 | 186.6 | ±62.20 | 0 | 160.0 | 32.2 | 0.9803 | 182.3 | -120.1 | -0.8349 | No | 20.4 |
| J1691 | 203.0 | ±149.32 | 0 | 199.5 | 101.0 | 0.8922 | 198.8 | -210.0 | -0.6875 | Yes | N/A |
| J1695 | 53.8 | ±16.40 | 0 | 50.0 | 8.1 | 0.9873 | 53.2 | -28.3 | -0.8832 | No | 8.4 |
| J1696 | 152.1 | ±67.00 | 0 | 149.3 | 40.4 | 0.9653 | 147.9 | -111.6 | 0.7981 | No | 8.7 |
| J1697 | 204.0 | ±66.88 | 0 | 199.4 | 13.8 | 0.9976 | 196.9 | -149.8 | -0.7959 | No | 51.7 |
| J1701 | 100.1 | ±33.35 | 0 | 196.4 | 24.2 | 0.9925 | 194.8 | -128.5 | -0.8347 | No | 40.3 |
| J1701 | 100.1 | ±33.35 | 0 | 196.4 | 24.2 | 0.9925 | 194.8 | -128.5 | -0.8347 | No | 40.3 |
| J1703 | 91.2 | ±24.70 | 24 | 74.0 | 35.5 | 0.9017 | 89.4 | -58.3 | -0.8377 | Yes | N/A |
| J1704 | 53.8 | ±16.40 | 0 | 50.0 | 7.4 | 0.9892 | 53.2 | -29.9 | -0.8722 | No | 9.0 |
| J1707 | 73.4 | ±31.30 | 0 | 72.3 | 32.2 | 0.9133 | 72.2 | -31.9 | -0.9145 | Yes | N/A |
| J1712 | 150.7 | ±78.66 | 0 | 297.5 | 89.7 | 0.9574 | 294.9 | -269.4 | -0.7383 | No | 8.1 |
| J1712 | 150.7 | ±78.66 | 0 | 297.5 | 89.7 | 0.9574 | 294.9 | -269.4 | -0.7383 | No | 8.1 |
| J1713 | 151.5 | ±73.38 | 0 | 146.7 | 38.5 | 0.9673 | 143.1 | -138.7 | -0.7181 | No | 9.8 |
| J1714 | 104.7 | ±32.90 | 0 | 100.0 | 13.8 | 0.9906 | 102.9 | -60.7 | -0.8613 | No | 19.1 |

| Project | Pmax (MW) | Reactive Power Capability (MVAR) | Modeled VAR Compensation (MVAR) | VAR Injection | | | VAR Absorption | | | Meet FERC Order 827 Requirement? | Add'l VAR Needed (MVAR) |
|---------|-----------|----------------------------------|---------------------------------|---------------|----------|-----------|----------------|----------|-----------|----------------------------------|-------------------------|
| | | | | P (MW) | Q (MVAR) | P.F. (pu) | P (MW) | Q (MVAR) | P.F. (pu) | | |
| J1721 | 100.8 | ±75.60 | 0 | 174.8 | 84.2 | 0.9010 | 173.9 | -197.9 | -0.6601 | Yes | N/A |
| J1721 | 77.8 | ±58.32 | 0 | 174.8 | 84.2 | 0.9010 | 173.9 | -197.9 | -0.6601 | Yes | N/A |
| J1724 | 172.2 | ±57.40 | 0 | 150.0 | 27.2 | 0.9840 | 168.2 | -113.8 | -0.8283 | No | 32.1 |
| J1725 | 100.8 | ±69.36 | 0 | 97.0 | 55.2 | 0.8691 | 94.3 | -102.8 | -0.6758 | Yes | N/A |
| J1726 | 207.8 | ±88.00 | 0 | 200.0 | 44.2 | 0.9765 | 200.4 | -167.6 | -0.7670 | No | 34.9 |
| J1736 | 101.6 | ±52.14 | 0 | 99.7 | 40.5 | 0.9264 | 99.0 | -70.1 | -0.8162 | Yes | N/A |
| J1737 | 212.5 | ±87.30 | 0 | 208.0 | 57.6 | 0.9638 | 206.6 | -127.7 | -0.8506 | No | 10.8 |
| J1743 | 148.5 | ±52.41 | 0 | 292.9 | 97.7 | 0.9486 | 296.3 | -131.0 | -0.9145 | Yes | N/A |
| J1743 | 153.0 | ±54.00 | 0 | 292.9 | 97.7 | 0.9486 | 296.3 | -131.0 | -0.9145 | Yes | N/A |
| J1744 | 153.0 | ±53.92 | 22 | 149.9 | 64.4 | 0.9188 | 149.2 | -74.2 | -0.8954 | Yes | N/A |
| J1755 | 151.5 | ±73.33 | 0 | 147.2 | 46.3 | 0.9539 | 145.4 | -116.0 | -0.7816 | No | 2.1 |
| J1765 | 96.9 | ±40.04 | 20 | 95.9 | 46.0 | 0.9018 | 95.6 | -60.5 | -0.8452 | Yes | N/A |
| J1770 | 150.0 | ±49.30 | 0 | 147.1 | 31.2 | 0.9782 | 146.4 | -75.0 | -0.8901 | No | 17.1 |
| J1772 | 203.3 | ±104.14 | 0 | 199.5 | 78.6 | 0.9304 | 197.9 | -145.2 | -0.8063 | No | 0.3 |
| J1777 | 104.7 | ±34.41 | 0 | 100.0 | 7.0 | 0.9976 | 101.6 | -83.6 | -0.7724 | No | 25.9 |
| J1780 | 200.0 | ±65.74 | 0 | 198.1 | 58.7 | 0.9588 | 198.0 | -73.5 | -0.9375 | No | 6.4 |
| J1782 | 75.0 | ±24.65 | 0 | 147.5 | -16.6 | 0.9937 | 144.8 | -184.2 | -0.6180 | No | 65.1 |
| J1782 | 75.0 | ±24.65 | 0 | 147.5 | -16.6 | 0.9937 | 144.8 | -184.2 | -0.6180 | No | 65.1 |
| J1783 | 75.0 | ±24.65 | 0 | 147.5 | -16.6 | 0.9937 | 144.8 | -184.2 | -0.6180 | No | 65.1 |
| J1783 | 75.0 | ±24.65 | 0 | 147.5 | -16.6 | 0.9937 | 144.8 | -184.2 | -0.6180 | No | 65.1 |
| J1784 | 39.0 | ±12.82 | 0 | 37.9 | -8.9 | 0.9734 | 37.1 | -49.4 | -0.6008 | No | 21.4 |
| J1785 | 102.4 | ±49.25 | 12 | 100.0 | 40.4 | 0.9272 | 31.9 | -120.2 | -0.2566 | Yes | N/A |
| J1786 | 203.0 | ±149.32 | 0 | 199.5 | 101.6 | 0.8911 | 198.8 | -209.2 | -0.6888 | Yes | N/A |
| J1802 | 151.2 | ±72.65 | 0 | 147.3 | 44.5 | 0.9572 | 144.7 | -126.1 | -0.7539 | No | 13.7 |
| J1805 | 25.4 | ±11.80 | 12 | 25.3 | 23.6 | 0.7316 | 25.3 | -12.9 | 0.8907 | Yes | N/A |
| J1806 | 30.0 | ±13.02 | | 29.9 | 13.2 | 0.9145 | 29.9 | -12.3 | -0.9247 | Yes | N/A |
| J1810 | 60.0 | ±26.00 | 34 | 59.6 | 59.2 | 0.7094 | 59.6 | -26.5 | -0.9136 | Yes | N/A |
| J1815 | 181.4 | ±60.79 | 25 | 179.4 | 53.2 | 0.9587 | 178.7 | -106.5 | -0.8591 | No | 5.7 |
| J1829 | 180.0 | ±69.40 | 0 | 175.8 | 37.1 | 0.9784 | 174.0 | -119.1 | -0.8252 | No | 20.6 |
| J1830 | 206.0 | ±16.72 | 0 | 200.0 | 9.8 | 0.9988 | 394.0 | -301.5 | -0.7941 | No | 55.9 |
| J1830 | 203.5 | ±33.44 | 0 | 200.0 | 9.8 | 0.9988 | 394.0 | -301.5 | -0.7941 | No | 55.9 |
| J1831 | 202.8 | ±98.40 | 0 | 197.7 | 31.3 | 0.9877 | 189.4 | -279.1 | -0.5615 | No | 33.7 |
| J1835 | 200.0 | ±66.00 | 0 | 195.3 | 5.6 | 0.9996 | 191.8 | -172.7 | -0.7431 | No | 58.6 |
| J1836 | 153.5 | ±54.10 | 0 | 300.0 | 44.3 | 0.9893 | 299.1 | -199.8 | -0.8315 | No | 54.3 |
| J1836 | 153.5 | ±54.10 | 0 | 300.0 | 44.3 | 0.9893 | 299.1 | -199.8 | -0.8315 | No | 54.3 |

| Project | Pmax (MW) | Reactive Power Capability (MVAR) | Modeled VAR Compensation (MVAR) | VAR Injection | | | VAR Absorbion | | | Meet FERC Order 827 Requireme nt? | Add'l VAR Needed (MVAR) |
|---------|--------------|---|---------------------------------------|---------------|-------------|--------------|---------------|-------------|-----------|--|----------------------------------|
| | | | | P (MW) | Q (MVAR) | P.F. (pu) | P (MW) | Q (MVAR) | P.F. (pu) | | |
| J1839 | 325.0 | ±200.00 | | 322.5 | 149.0 | 0.9079 | 321.6 | -271.7 | -0.7638 | Yes | N/A |
| J1840 | 254.0 | ±167.20 | 0 | 246.4 | 80.4 | 0.9506 | 232.6 | -420.4 | -0.4841 | No | 0.6 |

3. Model Development and Study Assumptions

3.1 Base Case Models

The origin of the DPP 2020 Central Phase 1 models is the MTEP20 models. Since DPP 2019 Central Phase 3 was not completed at the time this study was being performed, all pre-queued projects and associated Network Upgrades from DPP 2019 Central Phase 2 were included with the Bench Cases. The Study Cases contain all the interconnection requests in DPP 2020 Central Phase 1 in addition to all the facilities in the Bench Cases.

- Bench Cases
 - DPP20-2025SH90-Phase 1-Bench_Central_Final_v1
 - DPP20-2025SUM-Phase 1-Bench_Central_Final_v1
- Study Cases
 - DPP20-2025SH90-Phase 1-Study_Charging_Central_Final_v1
 - DPP20-2025SH90-Phase 1-Study_Discharging_Central_Final_v1
 - DPP20-2025SUM-Phase 1-Study_Discharging_Central_Final_v1
 - DPP20-2025SUM-Phase 1-Study_NIPSCO LPC Charging_Final_v1

3.2 Monitored Elements

Under NERC category P0 conditions (system intact) branches were monitored for loading above the normal rating (PSS®E Rating A), and for NERC category P1-P7 conditions branches were monitored for emergency rating (PSS®E Rating B). Voltage limits were specified for system intact and contingent conditions as per applicable Transmission Owner Planning Criteria.

3.3 Contingencies

The following contingencies were considered in the steady state analysis:

- 1) NERC Category P0 (system intact -- no contingencies)
- 2) NERC Category P1 contingencies
 - a. Single element outages, at buses with a nominal voltage of 68 kV and above
 - b. Multiple element NERC Category P1 contingencies
- 3) NERC Category P2-P7 contingencies
- 4) For all the contingencies and post-disturbance analyses, cases were solved with transformer tap adjustment enabled, area interchange adjustment disabled, phase shifter adjustment disabled (fixed) and switched shunt adjustment enabled.

3.4 Study Methodology

Non-linear (AC) contingency analysis was performed on the benchmark and study cases, and the incremental impact of the DPP 2020 Central generating facilities was evaluated by comparing the steady state performance of the transmission system in the Bench and Study Cases. Analyses used PSS®E version 34.6.1 and TARA version 2202_2.

3.5 Performance Criteria

A branch is considered a thermal constraint if the following conditions are met:

- 1) The generator has a larger than twenty percent (20%) sensitivity factor on the overloaded facilities under post-contingent condition (see NERC TPL) or five percent (5%) sensitivity factor under system-intact condition, or
- 2) The overloaded facility or the overload-causing contingency is at generator's outlet, or
- 3) The megawatt impact due to the generator is greater than or equal to twenty percent (20%) of the applicable rating (normal or emergency) of the overloaded facility, or
- 4) For any other constrained facility, where none of the Study Generators meet one of the above criteria, however, the cumulative MW impact of the group of study generators is greater than twenty percent (20%) of the rating of the facility, then only those study generators whose individual MW impact is greater than five percent (5%) of the rating of the facility and has DF greater than five percent (5%) will be responsible for mitigating the cumulative MW impact constraint, or
- 5) Impacts on Affected Systems would be classified as injection constraints based on the Affected Systems' criteria, or
- 6) Any other applicable Transmission Owner Local Planning Criteria are met.

A bus is considered a voltage constraint if both of the following conditions are met:

- 1) The bus voltage is outside of the applicable normal or emergency limits for the post change case, and
- 2) The change in bus voltage is greater than 0.01 per unit

All generators must mitigate thermal injection constraints and voltage constraints in order to obtain any type of Interconnection Service. Further, all generators requesting NRIS must mitigate constraints found by using the Deliverability algorithm to meet the system performance criteria for NERC category P1 events, if DFAX due to the study generator is equal to or greater than 5%.

4. Voltage Analysis

The voltage analysis for DPP 2020 Central Phase 1 did not identify any valid voltage constraints.

5. Thermal Analysis

The thermal analysis results for DPP 2020 Central Phase 1 show 55 generator projects causing constraints. The details pertaining to the thermal analysis can be found in Appendix C – MISO ERS Analysis (CEII).

6. Deliverability Analysis

Generator interconnection projects must pass Generator Deliverability Study to be granted NRIS. If the generator is deemed not fully deliverable, the customer can choose either to change the project to an Energy Resource project, reduce their NR service request amount during decision point, or to proceed with the system upgrades that will make the generator fully deliverable. Generator Deliverability Study ensures that the Network Resources, on an aggregate basis, can meet the MISO aggregate load requirements during system peak condition without getting bottled up. The wind and solar generators are tested at 100% of their maximum output level which then can be used to meet Resource Adequacy obligations, under Module E, of the MISO Transmission and Energy Market Tariff (TEMT).

The MISO Generator Deliverability Study whitepaper describing the algorithm can be found in BPM 015 – Generation Interconnection, Appendix C.

6.1 Determining the MW Restriction

If one facility is overloaded based on the assessed "severe yet credible dispatch" scenario described in the study methodology, and the generator under study has a DF greater than 5%, part or all its output it is not deliverable. The restricted MW is calculated as following:

$$(MW \text{ restricted}) = \frac{\text{worst loading} - MW \text{ rating}}{(\text{generator sensitivity factor})}$$

If the result is larger than the maximum output of the generator, 100% of this generator's output is not deliverable.

6.2 Deliverability Study Results

The limiting constraints (monitored facilities – contingency facility pairs) seen in the deliverability analysis for the 2024 Summer case are summarized in Appendix D – MISO Deliverability Analysis (CEII). If a project is not determined to be fully deliverable as a result of the NRIS study, upgrades may be required to attain higher deliverable levels. The NRIS amount evaluated reflects the amount at the generator terminal (reviewed by the interconnection customer during the model review period).

Table 6: Deliverability Results (NRIS)

| Project # | NR Requested (MW) | Maximum Deliverable Amount (MW) |
|-----------|-------------------|---------------------------------|
| J1491 | 200 | 200 |
| J1517 | 40 | 0 |
| J1518 | 185 | 0 |
| J1519 | 200 | 0 |
| J1563 | 200 | 138.36 |
| J1565 | 200 | 127.35 |
| J1578 | 200 | 200 |
| J1579 | 200 | 0 |
| J1585 | 200 | 0 |
| J1591 | 150 | 0 |
| J1593 | 200 | 100.08 |
| J1600 | 40 | 40 |
| J1604 | 50 | 50 |
| J1610 | 100 | 0 |
| J1616 | 200 | 0 |
| J1619 | 160 | 69.1 |
| J1624 | 100 | 100 |
| J1625 | 150 | 103.77 |
| J1626 | 150 | 0 |
| J1632 | 200 | 125.82 |
| J1636 | 44 | 44 |
| J1637 | 150 | 0 |
| J1638 | 150 | 64.78 |
| J1641 | 150 | 0 |

| Project # | NR Requested (MW) | Maximum Deliverable Amount (MW) |
|-----------|-------------------|---------------------------------|
| J1642 | 200 | 0 |
| J1646 | 150 | 0 |
| J1649 | 60 | 60 |
| J1651 | 149.5 | 99.06 |
| J1652 | 116 | 0 |
| J1653 | 150 | 48.78 |
| J1655 | 50 | 0 |
| J1656 | 412 | 0 |
| J1676 | 300 | 0 |
| J1677 | 180 | 0 |
| J1678 | 74.7 | 66.83 |
| J1679 | 125 | 0 |
| J1680 | 100 | 89.46 |
| J1681 | 200 | 0 |
| J1684 | 200 | 148.21 |
| J1687 | 160 | 160 |
| J1691 | 200 | 0 |
| J1695 | 50 | 0 |
| J1696 | 150 | 64.78 |
| J1697 | 200 | 127.35 |
| J1699 | 43 | 43 |
| J1701 | 200 | 0 |
| J1703 | 74 | 28.64 |
| J1704 | 50 | 25.02 |
| J1707 | 72 | 31.09 |
| J1712 | 300 | 0 |
| J1713 | 147.2 | 0 |
| J1714 | 100 | 0 |
| J1721 | 175.12 | 0 |
| J1724 | 150 | 111.16 |
| J1725 | 100 | 32.52 |
| J1726 | 200 | 200 |
| J1736 | 100 | 0 |
| J1737 | 210 | 105.09 |
| J1743 | 292.9 | 262.03 |

| Project # | NR Requested (MW) | Maximum Deliverable Amount (MW) |
|-----------|-------------------|---------------------------------|
| J1744 | 149.5 | 0 |
| J1755 | 147.2 | 117.06 |
| J1756 | 309 | 154.62 |
| J1765 | 93.2 | 64.48 |
| J1770 | 0 | 0 |
| J1772 | 200 | 200 |
| J1774 | 50 | 0 |
| J1777 | 100 | 0 |
| J1780 | 200 | 0 |
| J1782 | 150 | 103.78 |
| J1783 | 150 | 103.78 |
| J1784 | 39 | 39 |
| J1785 | 100 | 74.11 |
| J1786 | 200 | 0 |
| J1802 | 150 | 150 |
| J1805 | 0 | 0 |
| J1806 | 1.6 | 0 |
| J1810 | 60 | 60 |
| J1815 | 180 | 180 |
| J1829 | 180 | 180 |
| J1830 | 200 | 200 |
| J1831 | 200 | 0 |
| J1835 | 200 | 200 |
| J1836 | 300 | 0 |
| J1839 | 340.3 | 0 |
| J1840 | 250 | 0 |

7. Shared Network Upgrades Analysis

Shared Network Upgrade (SNU) Analysis, which tests for Network Upgrades driven by higher queued interconnection projects, was performed for this System Impact Study.

The maximum MW impacts and SNU cost allocations appear in Table 7.

Table 7: Shared Network Upgrade Cost Allocation

| Network Upgrades | Project Study Cycle | Projects sharing cost | MW Contribution | Total NU Cost (\$) | Cost Responsibility (\$) |
|---|---------------------|-----------------------|-----------------|--------------------|--------------------------|
| Belle Tap-Meta Tap 138 kV Line Rebuild Central 2019 | DPP-2019-3 | J1488 | 3.72 | \$14,000,000 | \$2,103,393 |
| | DPP-2019-3 | J1490 | 7.44 | | \$4,206,785 |
| | DPP-2020-1 | J1585 | 13.60 | | \$7,689,822 |
| Parallel 08NEWLON - 08KOK HP line Central 2019 | DPP-2019-3 | J1378 | 26.84 | \$24,000,000 | \$10,717,245 |
| | DPP-2019-3 | J1482 | 9.20 | | \$3,671,575 |
| | DPP-2020-1 | J1625 | 24.07 | | \$9,611,180 |
| Fairbanks - Dresser 345kV new line Central 2018 | DPP-2018-APR | J1027 | 7.5 | \$6,000,000 | \$309,130 |
| | DPP-2018-APR | J1028 | 7.53 | | \$310,366 |
| | DPP-2018-APR | J1074 | 10.06 | | \$414,646 |
| | DPP-2018-APR | J1189 | 10.06 | | \$414,646 |
| | DPP-2020-1 | J1691 | 55.21 | | \$2,275,606 |
| | DPP-2020-1 | J1786 | 55.21 | | \$2,275,606 |

8. Cost Allocation

The cost allocation of Network Upgrades (NU) for the study group reflects responsibilities for mitigating system impacts based on Interconnection Customer-elected level of NRIS as of the draft System Impact Study report date.

8.1 Cost Assumptions for Network Upgrades

The cost estimate for each NU identified in the System Impact Study is provided by the corresponding Transmission Owner.

8.2 Cost Allocation Methodology

The costs of NU for a set of generation projects (one or more sub-groups or entire group with identified NU) are allocated based on the MW impact from each project on the constrained facilities in the Study Case.

Cost Allocation Methodology for Thermal Constraints

1. With all study group generation projects dispatched in the Study Case, all thermal constraints are identified.
2. Distribution factor from each project on each constraint is obtained.
3. For each thermal constraint, the maximum MW contribution (increasing flow) from each project is then calculated in the Post Case without any Network Upgrades.
4. For each thermal constraint, the cost estimates for one or a subset of NU are provided by the corresponding Transmission Owner.
5. The cost of each NU is allocated based on the pro rata share of the MW contribution from each project on the constraints mitigated or partly mitigated by this NU. The methodology to determine



the cost allocation of one NU is:

$$\text{Project A Cost Portion of NU} = \frac{\text{Max(Proj. A MW contribution on constraint)}}{\sum_i \text{Max(Proj. i MW contrution on constraint)}}$$

6. The total NU costs for each project are calculated if more than one NU is required.



Appendix A – Cost Allocation Summary (CEII)

Appendix B – Network Upgrade Table Per Project (CEII)

Appendix C – MISO ERIS Analysis (CEII)

Appendix D – MISO Deliverability Analysis (CEII)

Appendix E- Ameren System LPC

Appendix F- LPC Results