#### FILED July 1, 2021 INDIANA UTILITY REGULATORY COMMISSION

I&M Exhibit: \_\_\_\_\_

Cause No. 45576

#### INDIANA MICHIGAN POWER COMPANY

#### PRE-FILED VERIFIED DIRECT TESTIMONY

OF

JASON A. CASH

#### Content

I.	Introduction of Witness	1
II.	Purpose of Testimony	3
III.	Depreciation Study Overview	4
IV.	Study Methods and Procedures	
	Advanced Metering Infrastructure	
V.	Study Results	18

#### Page 1 of 20

#### DIRECT TESTIMONY OF JASON A. CASH ON BEHALF OF INDIANA MICHIGAN POWER COMPANY

#### I. Introduction of Witness

1	Q1.	Please state your name and business address.
2		My name is Jason A. Cash and my business address is 1 Riverside Plaza,
3		Columbus, OH 43215.
4	Q2.	By whom are you employed and in what capacity?
5		I am employed by American Electric Power Service Corporation (AEPSC) as an
6		Accounting Senior Manager in Corporate Accounting. AEPSC supplies
7		engineering, accounting, planning, advisory, and other services to the
8		subsidiaries of the American Electric Power (AEP) system, one of which is
9		Indiana Michigan Power Company (I&M or the Company).
10	Q3.	What are your responsibilities as an Accounting Senior Manager?
11		My responsibilities include providing the AEP and affiliated companies with
12		accounting support for regulatory filings, including the preparation of

- depreciation studies and testimony. I also monitor regulatory proceedings and
   legislation for accounting implications and assist in determining the appropriate
   regulatory accounting treatment.
- Q4. Briefly describe your educational background and professional
   experience.
- 18I graduated with a Bachelor of Science degree with a major in accounting from19The Ohio State University in 2000. In 2000, I joined AEPSC and have held

several positions within the Accounting organization, including general ledger 1 accounting and financial reporting for Ohio Power Company and AEPSC. 2 From 2008 through 2013, I worked in AEPSC's Transmission Accounting 3 4 department where I was promoted to Supervisor of Transmission Accounting in 2013. From 2014 through 2019, I worked in AEPSC's Accounting Policy & 5 Research department as a Staff Accountant and was later promoted to Senior 6 7 Staff Accountant in 2019. In 2019, I was promoted to my current position of 8 Accounting Senior Manager.

#### 9 Q5. Have you previously testified before any regulatory commissions?

Yes. I have prepared depreciation studies and testified before the Indiana Utility 10 Regulatory Commission (IURC or Commission) in Cause Nos. 44967 and 11 45235. I have also prepared depreciation studies or testified before the 12 13 Oklahoma Corporation Commission, the Louisiana Public Service Commission, 14 the Public Utility Commission of Texas, the Public Utilities Commission of Ohio, the Virginia State Corporation Commission, the Arkansas Public Service 15 Commission, the Public Service Commission of West Virginia, the Michigan 16 17 Public Service Commission, the Public Service Commission of Kentucky, the 18 Tennessee Regulatory Authority, and the Federal Energy Regulatory Commission. 19

Q6. Have you had any formal training relating to depreciation and utility
 accounting?

Yes. I am a member of the Society of Depreciation Professionals (SDP) and
was a former at-large director for the SDP. I have completed training courses
offered by the SDP, which include Depreciation Fundamentals, Life and Net
Salvage Analysis, and Analyzing the Life of Real World Property.

These training classes included topics such as introduction to plant and
 depreciation accounting, data requirements and collection, depreciation models,
 life cycle analysis, current regulatory issues, actuarial life analysis, net salvage
 analysis, and simulation life analysis.

### II. Purpose of Testimony

5	Q7.	What is the purpose of your testimony?
6		The purpose of my testimony is to recommend revised depreciation accrual
7		rates for I&M's electric plant in service based on a depreciation study for I&M's
8		electric utility plant in service at December 31, 2020 (as adjusted, see below).
9		Schedules I and II in the Depreciation Study Report (included as Attachment
10		JAC-1) detail the results of the study. The depreciation rates determined by the
11		study are intended to provide recovery of invested capital, cost of removal, and
12		credit for salvage over the expected life of the property.

13	Q8.	Are you sponsoring any attachments?
14		Yes, I am sponsoring the following attachments:
15		Attachment JAC-1: Depreciation Study Report.
16		Attachment JAC-2: Brandenburg Industrial Service Company's
17		conceptual dismantling study performed for the Rockport Plant.
18		Attachment JAC-3: Sargent and Lundy's conceptual dismantling studies
19		performed for the Company's hydroelectric (or hydraulic) facilities.
20	Q9.	Are you sponsoring any workpapers?

21 Yes, I am sponsoring the following workpapers:

7	Q11.	Please summarize your testimony.
6		Yes.
5		or under your direction and supervision?
4	Q10.	Were the attachments and workpapers that you sponsor prepared by you
3		WP-JAC-3: Figure JAC-1 of Direct Testimony
2		WP-JAC-2: I&M Meter Depreciation Calculation
1		WP-JAC-1: Depreciation Study Workpapers

- 8 The depreciation study I prepared supports revisions to the depreciation rates 9 and accruals previously approved by the Commission, resulting in an annual 10 depreciation expense increase of \$10,500,192 on a Total Company basis. The 11 primary driver of this increase is investment at the Cook Nuclear Plant.
- 12 My study includes expected production plant investment through the Test Year to properly match depreciation rates with plant in service when rates become 13 14 effective in 2022. It also reflects (i) reasonable assumptions for salvage and dismantlement, (ii) a consolidated "whole plant" approach for the Rockport units 15 that has the effect of reducing the depreciation rates associated with certain 16 investments at that plant, and (iii) the same approach to Account 370 (Meters) 17 18 that was approved by the Commission in I&M's last rate case. The revised depreciation rates are reasonable and should be approved. 19

#### **III. Depreciation Study Overview**

#### 20 Q12. What is the basis for I&M's current depreciation rates?

I&M's current depreciation rates are based on a Commission Order received in
 Cause No. 45235 where the Commission approved the Company's current

steam production, nuclear production, hydroelectric production, other
 production, transmission, distribution and general plant depreciation rates.

Q13. How do the depreciation rates and annual accruals as a result of your
 study compare with I&M's current rates and accruals?

*Figure JAC-1* compares the rates and accruals of I&M with those of the study.
This comparison is based on expected Total Company depreciable plant
balances for Steam Production Plant prior to December 31, 2022 (before the
end of the Rockport Unit 2 lease), for Nuclear, Hydraulic, and Other Production
Plant at December 31, 2022, and Total Company depreciable plant balances for
all other functions at December 31, 2020.

#### Figure JAC-1. Composite Depreciation Rates and Accruals

Steam Production Plant - Plant In Service prior to December 31, 2022 Nuclear, Hydraulic and Other Production Plant - Plant In Service at December 31, 2022 Plant In Service at December 31, 2020 (All Other Functions)

	I	Existing		Study	
Functional Plant Group	<u>Rates</u>	Accruals (\$)	Rates	Accruals (\$)	<u>Difference</u> <u>(\$)</u>
Steam Production <sup>1</sup>	8.16%	93,485,397	7.99%	91,491,790	(1,993,607)
Nuclear Production	4.10%	150,259,300	4.52%	165,645,446	15,386,146
Hydraulic Production	2.74%	2,041,834	4.33%	3,223,644	1,181,810
Other Production	5.29%	1,968,059	5.37%	1,999,612	31,553
Transmission	2.48%	41,667,464	2.67%	44,835,980	3,168,516
Distribution	3.48%	89,903,251	3.17%	81,896,932	(8,006,319)
General	3.55%	<u>5,795,047</u>	4.00%	<u>6,527,140</u>	732,093
Total Depreciable Plant	4.12%	<u>385,120,352</u>	4.23%	<u>395,620,544</u>	<u>10,500,192</u>

<sup>&</sup>lt;sup>1</sup> The existing Steam Production accrual amount and rate reflect the annual depreciation for Rockport, based on existing rates, prior to the Rockport Unit 2 lease ending and the owned investment of Rockport Unit 2 being retired from the Company's books. This provides a more accurate representation of the change in annual Rockport depreciation expense, before the end of the Rockport Unit 2 lease. Schedule II of the Depreciation Study Report shows a comparison using Total Company depreciable plant balances for Steam Production Plant at December 31, 2022.

Direct Testimony of Jason Cash

1	Figure JAC-1 shows a comparison of the depreciation accruals before the end
2	of the Rockport Unit 2 Lease, producing a decrease of approximately \$2.0
3	million on a Total Company basis for Steam Production Plant.

#### 4 Q14. What do you recommend with respect to I&M's depreciation accrual rates?

- 5 Based on the results of the study, I am recommending an overall increase in 6 I&M's depreciation accrual rates, to be made effective upon implementation of 7 new base rates.
- For purposes of comparison, applying my recommended I&M Indiana rates to
  total Company depreciable plant in service as of December 31, 2020 (as
  adjusted, as discussed later in my testimony) would produce an increase in
  annual depreciation expense of \$10,500,192. The primary driver of this increase
  is in the Nuclear function, as discussed later in my testimony.

#### **IV. Study Methods and Procedures**

Q15. Please explain the definition of depreciation as used in preparing your 13 14 depreciation study. The definition of depreciation that I used in preparing the study is the same that 15 is used by FERC and the National Association of Regulatory Utility 16 Commissioners: 17 18 Depreciation, as applied to depreciable electric plant, means the loss in service value not restored by current maintenance, incurred in 19 connection with the consumption or prospective retirement of electric 20 plant in the course of service from causes which are known to be in 21 22 current operation and against which the utility is not protected by insurance. 23 24 Among the causes to be given consideration are wear and tear,

decay, action of the elements, inadequacy, obsolescence, changes
 in the art, changes in demand and requirements of public authorities.

- Net salvage value means the salvage value of property retired less
   the cost of removal. Service value means the difference between
   original cost and net salvage value of electric plant.<sup>2</sup>
- Q16. Please explain the methods and procedures you used in preparing your
   depreciation study.

8 The methods and procedures are fully described in Attachment JAC-1, the 9 Depreciation Study Report. In summary, all of the property included in the 10 Depreciation Study Report was considered on a group plan. Under the group 11 plan, depreciation is accrued upon the basis of the original cost of all property 12 included in each depreciable plant group instead of individual items of property.

Upon retirement of any depreciable property, its full cost, less any net salvage realized, is charged to the accumulated provision for depreciation regardless of the age of the particular item retired. Also under this plan, the dollars in each primary plant account are considered as a separate group for depreciation accounting purposes and an annual depreciation rate for each account is determined.

In this study, the plant groups consisted of the individual primary plant accounts
for Production, Transmission, Distribution, and General Plant property. The
depreciation rates were calculated by the Average Remaining Life Method,
which is the same method that was used to calculate I&M's current depreciation
rates. The Average Remaining Life method recovers the original cost of the
plant (adjusted for net salvage) less accumulated depreciation over the average
remaining life of the plant.

26 For Production Plant, the generating unit retirement dates and the interim 27 retirement history for the individual plant accounts were used to determine the

<sup>&</sup>lt;sup>2</sup> 18 C.F.R. pt. 101 ("Definitions" ¶¶ 12, 19, 37).

average service lives and the remaining lives of the plants. The average service
 lives for the Company's Transmission, Distribution, and General Plant were
 determined using statistical procedures similar to those used in the insurance
 industry in studies of human mortality. The historical retirement experience of
 property groups was studied, and retirement characteristics of the property were
 described using the lowa-type retirement dispersion curves.

- Net salvage for each property group was determined based on actual historical
  experience for Production, Transmission, Distribution, and General Plant
  accounts. In addition, Production plant included terminal retirement net salvage
  amounts for Steam and Hydraulic Production Plant.
- 11To determine terminal net salvage for Steam and Hydraulic Production Plant,12my depreciation study used the conceptual dismantling cost estimates that are13reflected in I&M's current depreciation rates. For I&M's Rockport Plant, the14estimate was prepared by Brandenburg Industrial Service Company15(Brandenburg). For I&M's hydraulic production plants, the estimates were16prepared by Sargent & Lundy (S&L). Both Brandenburg and S&L are17independent engineering firms.
- Q17. Do you consider the dismantling studies used in your depreciation study
   to be reliable and of a type generally relied upon by persons such as
   yourself during the course of studying depreciation rates?
- 21 Yes.

# Q18. Do the previous estimates prepared by Brandenburg and S&L remain as reliable sources for the purposes of calculating terminal net salvage for the Company's Rockport and hydraulic plants?

Yes. Because major additions, such as the selective catalytic reduction system
(SCR) that was installed on Rockport Unit 2, are included with these previous

1		estimates, they continue to provide reasonable bases for calculating the terminal
2		net salvage on each plant.
3		A copy of the Brandenburg dismantling study is included with my testimony as
4		Attachment JAC-2. A copy of the S&L dismantling studies are included with my
5		testimony as Attachment JAC-3.
6		The recommended depreciation rates include the estimated final removal cost
7		and expected terminal net salvage amounts specific to each of the Company's
8		steam and hydraulic generating stations at their estimated retirement dates.
9	Q19.	Do the estimates prepared by Brandenburg and S&L include amounts for
10		contingencies that may occur during the projects?
11		Brandenburg's estimate for the Rockport Plant does not contain an amount for
12		contingency. However, the S&L estimates for the Company's Hydro facilities
13		each contain an estimated amount for contingency.
14	Q20.	Are the contingency costs included with S&L's demolition cost estimates
15		reasonable and appropriate?
16		Yes. An amount for contingency is "intended to cover unknowns," and is
17		included in the estimates because "experience teaches that almost every
18		complex project, such as demolition of a generation station, ends up with
19		unknowns." <sup>3</sup>
20		Contingencies included in the demolition cost estimates are necessary to
21		account for the unknowns anticipated to occur during these complex projects.

<sup>&</sup>lt;sup>3</sup> Re *PSI Energy, Inc.*, Cause No. 42359, p. 67, 2004 WL 1493966 (IURC May 18, 2004).

1	Q21.	Has the IURC previously accepted S&L's use of a contingency factor in the
2		preparation of conceptual demolition cost estimates for I&M?
3		Yes. On page 105 of its Order in Cause No. 44075, the Commission accepted
4		S&L's use of a contingency factor and stated: "We find the contingencies used
5		in I&M's demolition estimates to be reasonable and similar to the factors we
6		approved in Cause No. 43526."
7		In its Cause No 45235 Order, the Commission also stated:
8 9 10 11 12		The Commission has previously recognized the inclusion of a contingency factor in demolition studies for purposes of computing final terminal salvage. As Mr. Cash testified, the Commission accepted the inclusion of contingencies in Cause No. 44075. 44075 Order, p. 105.
13 14 15 16 17		In the 44075 Order, the Commission cited the Order in Northern Indiana Pub. Serv. Co., Cause No. 43526, p. 54,2010 WL 3444546, 284 P.U.R. 4th 369 (IURC August 25,2010), wherein the Commission approved the inclusion of contingency in the calculation of depreciation.
18 19 20 21 22		We find Mr. D. Garrett and Mr. Rutter, without saying so, are asking the Commission to disregard our prior acceptance of contingency in I&M's demolition estimates without showing us why this change is warranted. The Commission accepts Petitioner's proposed contingency factor. <sup>4</sup>
23	Q22.	Please explain how you determined terminal net salvage as of the
24		retirement year.
25		Brandenburg provided terminal net salvage amounts, excluding any asbestos,
26		ash pond, or landfill-type removal costs, stated at a 2018 price level. For the
27		purposes of developing depreciation rates, I needed the terminal net salvage
28		amount at the time of the unit retirement. Thus, I applied a 2.20% inflation rate

factor to the net salvage amounts provided by the Brandenburg study to 1 determine the terminal net salvage amount at Rockport Unit 1's retirement year. 2 Similarly, the S&L study provided terminal net salvage amounts stated at a 2015 3 4 price level. To estimate the cost at each unit's retirement date, I applied the same 2.20% inflation rate factor to the net salvage amounts provided by the 5 S&L study in order to determine the terminal net salvage amount for each 6 hydraulic plant at the plant's retirement year. The terminal net salvage amounts 7 8 after inflation were used in the calculation of net salvage percentages in the depreciation study. 9

#### 10 **Q23.** What is the source of the inflation rate used for this purpose?

The 2.20% inflation rate was taken from the *Livingston Survey*, a December 18,
2020 publication of the research department of the Federal Reserve Bank of
Philadelphia. The *Livingston Survey* provides a long-term inflation outlook
projecting an inflation rate for a ten-year period.

# Q24. Has the Company applied an inflation rate or escalation factor to its final demolition estimates in previous depreciation studies that have been filed with this Commission?

Yes. The Company has consistently applied an inflation rate or escalation factor to its generation plant demolition estimates in prior depreciation studies filed with the Commission. Additionally, the Company has consistently used the *Livingston Survey* as its source for obtaining the long-term inflation rate used in its depreciation studies.

1	Q25.	Has the IURC accepted the Company's application of an escalation factor
2		to develop a terminal net salvage amount to be used for the purpose of
3		calculating depreciation rates?
4		Yes. In Cause No. 44075, the Commission considered the Company's
5		application of a 2.5% escalation factor to the Company's demolition estimates
6		for Steam Production Plant and made the following conclusions (on page 105 of
7		its Order) before ultimately accepting the Company's proposed depreciation
8		rates in that Cause:
9 10 11		Therefore, we find that inflation should be factored into dismantlement cost estimates and reject the OUCC's proposal to restate costs of removal at present value.
12		
13 14		We therefore reject Mr. Selecky's proposal to modify the depreciation rates using lower estimates of future inflation.
15		
16		The Commission accepted I&M's depreciation rates in Cause No. 44555 and
17		Cause No. 44967, both of which included inflating I&M's final demolition costs to
18		a future level.
19		In Cause No. 45235, the Commission once again agreed with the Company's
20		application of an inflation factor to its final demolition cost estimates. On page 33
21		of its final order in Cause No. 45235, the Commission stated "The Commission
22		finds the inclusion of the escalation factor at issue was appropriate based upon
23		Mr. Cash's rebuttal testimony."
24	Q26.	Did the depreciation study exclude the cost to remove asbestos and to
25		cover ash ponds and landfills?
26		Yes. The costs to remove asbestos and to cover ash ponds and landfills are
27		included in the Company's ARO accounting. The depreciation and accretion on

20

21

22

these AROs are incorporated into the cost of providing service, which is
 discussed in more detail by Company witness Ross.

# Q27. Were there any changes in the depreciation parameters for I&M's plant in service since the depreciation study presented in Cause No. 45235 that you would like to discuss?

- Yes. In addition to the Company's electric utility plant in service and
  accumulated depreciation on the books at December 31, 2020, the depreciation
  study includes an adjustment for the 2021-2022 forecast additions to plant in
  service at Rockport, Cook, and the Company's hydraulic and solar generating
  stations to reflect a forward-looking test period for the Company's steam,
  nuclear, hydraulic and other production plant investment.
- 12 The depreciation study also includes a calculation to estimate a corresponding 13 adjustment to accumulated depreciation for all of production plant that reflects 14 an additional two years of depreciation accrued through 2022. The adjustments 15 made to original cost and accumulated depreciation are as follows:
- Rockport Plant Original cost \$33.3 million; accumulated depreciation
   \$186.4 million.
- Cook Plant Original cost \$217.0 million; accumulated depreciation
   \$290.5 million.
  - Hydraulic Production Plant Original cost \$19.1 million; accumulated depreciation \$3.0 million.
  - Other Production Plant Accumulated depreciation \$3.9 million
- The total forecast additions for production plant included in the depreciation
   study total approximately \$269.4 million, including \$217.0 million of forecasted
   additions for the Cook Plant related to the Life Cycle Management (LCM)
   project. Company witness Lies discusses capital investment at Cook.

1

2

3

4

The forecast additions to Rockport, Cook, and the Company's hydraulic and solar generating station plant balances and accumulated depreciation were included with the depreciation study because production plant uses finite end-oflife dates in the depreciation study to calculate depreciation rates.

- In comparison, transmission, distribution and general plant use an average
  service life and average remaining life to calculate depreciation rates in the
  depreciation study. Including the forecast additions and accumulated
  depreciation will ensure that accurate depreciation rates are established for
  each generating station when rates become effective in 2022.
- Establishing depreciation rates in this manner better supports the full depreciation of such assets and better aligns customer rates with the remaining service life of each generating station while reducing the extent to which the costs will need to be reflected in rates after the assets are no longer in service.

# Q28. Were there any changes in the depreciation parameters for I&M's Rockport Plant since the depreciation study presented in Cause No. 45235?

- Yes. In this depreciation study, all of the Company's investment in Rockport Unit
   1 and certain leasehold improvements made at Rockport Unit 2 are presented
   together as the Rockport Plant and depreciation rates were calculated for each
   utility account used by the Rockport Plant.
- The certain leasehold improvements at Rockport Unit 2 include the Company's share of the owned non-severable leasehold improvements made to the unit, including the dry sorbent injection system (DSI) installed in 2015 and the SCR installed in 2021.
- Q29. Why was the change made to calculate depreciation rates for the Rockport
   Plant as a whole versus calculating them separately for Rockport Units 1 &

## 2 as presented in previous depreciation studies filed with this Commission?

The change was made primarily to summarize all of the investment made at the Rockport Plant, including the SCR, DSI and actived carbon injection (ACI) investments made on each Rockport Unit, and calculate an individual depreciation rate for each utility account used by the Rockport Plant through 2028.

8 Summarizing the depreciation rates by each utility account establishes 9 depreciation of the existing Rockport Plant through 2028, or the remaining life of 10 Rockport Unit 1, considers the lease ending for Rockport Unit 2 in December 11 2022, and also incorporates the remaining net book value associated with the 12 certain leasehold improvements of Rockport Unit 2 at December 2022.

The depreciation rates approved in Cause No. 45235 established depreciation rates for the investment in Rockport Unit 2 through 2028 for the Unit 2 SCR, through 2025 for the Unit 2 DSI, and through 2022 for the other investment at Unit 2. The proposed depreciation rates in this case depreciate the remaining net book value of all Rockport Plant investment at December 31, 2022 through 2028.

**Advanced Metering Infrastructure** 

## Q30. Please explain the methodology you used to establish a depreciation rate for Account 370.

The Company has decided to transition to AMI meters across its service territory over four years, or 2021 through 2024. This requires the Company to retire the meters currently installed over the same time period. As a result, a depreciation rate was calculated in the current depreciation study to reflect the retirement of the meters that are currently installed and the installation of new AMI meters. 1The depreciation rate calculation for Account 370 uses the currently approved2depreciation rate through 2021, the expected retirement of the current meters by3year, and the projected costs to install AMI Meters by year. Please see WP-4JAC-2 for the depreciation rate calculation of Account 370.

5 Using updated investment and timing information from the Company's plans to 6 implement AMI Meters, the Company is proposing a depreciation rate in this 7 case of 10.08% as compared to the 9.27% depreciation rate approved in Cause 8 No. 45235.

9 Q31. Did you calculate a depreciation rate for Account 370 in the same manner
 10 as you did for the depreciation rate that was calculated and approved for
 11 the same account in Cause No. 45235?

- 12 Yes. The calculation of the depreciation rate for Account 370 was performed in
- 13 exactly the same manner that was calculated and approved in Cause No.
- 14 45235. I merely updated the information in the calculation to reflect the
- 15 Company's currently expected investment and timeframe to implement the new
- 16 meters across its service territory. As a result, a slight change to the approved
- 17 depreciation rate for Account 370 is being proposed in this case which
- 18 represents the change in meter technology from AMR to AMI type meters.
- Q32. Over what time period does the Company calculate depreciation rates for
   Account 370 to reflect the installation of AMI meters?
- The depreciation rates that were calculated for Account 370 are based on a 15 year estimated useful life for AMI meters after the meters are installed.

1	Q33.	Is recovery of the remaining value of property, plant and equipment that
2		has been retired a normal utility ratemaking practice?
3		Yes. Recovery of the remaining value of a generating station or Transmission,
4		Distribution and General property is normal utility ratemaking practice and this
5		practice follows FERC Electric Plant Instruction No. 10 "Additions and
6		Retirements of Electric Plant", paragraph (2), which states:
7 8 9 10		<i>"(2) When a retirement unit is retired from electric plant, with or without replacement, the book cost thereof shall be credited to the electric plant account in which it is included, determined in the manner set forth in paragraph D, below.</i>
11 12 13		If the retirement is of a depreciable class, the book cost of the unit retired and credited to electric plant shall be charged to the accumulated provision for depreciation applicable to such property."
14	Q34.	Could the Company have requested a depreciation rate for meters using
15		the current meter plant balances and the retirement history of Account
16		370?
17		Yes. However, instead of proposing two separate rates for meters, one
18		depreciation rate for the current AMR meter investment through 2024 and one
19		depreciation rate for its AMI meter investment over a 15 year expected useful
20		life, the Company is proposing a single depreciation rate for Account 370 that
21		reflects the change in technology that will occur while also depreciating its
22		current investment of AMR meters over the life of the AMI meters.

#### V. Study Results

1	Q35.	Please explain the results of your study for Steam Production Plant.
2		As shown in Figure JAC-1, a decrease of approximately \$2.0 million is expected
3		for Steam Production Plant on a Total Company basis. This is mainly due to
4		depreciating the expected remaining balance of Rockport Unit 2 through 2028.

#### 5 Q36. Please explain the results of your study for Nuclear Production Plant.

6 The composite rate for Nuclear Production Plant increased from 4.10% to 4.52%
7 mainly due to a \$146.9 million increase in the depreciable plant in service
8 balance since the 2018 depreciation study. The increase in depreciable nuclear
9 plant in service since 2018 is mostly due to the LCM Project, which is discussed
10 in detail by Company witness Lies.

#### 11 Q37. Please explain the results of your study for Hydraulic Production Plant.

- 12 The composite rate for Hydraulic Production Plant increased from 2.74% to 13 4.33% due to a \$17.4 million increase in the depreciable plant in service balance 14 since the 2018 depreciation study.
- 15 Q38. Please explain the results of your study for Other Production Plant.
- 16 The composite depreciation rate for Other Production Plant increased slightly 17 from 5.29% to 5.37% due to a \$0.3 million increase in the depreciable plant in 18 service balance since the 2018 depreciation study.
- 19 Q39. Please explain the results of your study for Transmission Plant.

The depreciation rate for Transmission Plant increased from 2.48% to 2.67%
due to increases in the net salvage ratio for three accounts (Accounts 353, 354,

and 355) and decreases in the average service life for four accounts (Accounts
 352, 353, 355 and 358).

- The depreciation rate increase was partially offset by an increase in the average service lives for three accounts (Accounts 354, 356 and 357) and decreases in the net salvage ratio for three accounts (Accounts 352, 356 and 358).
- As shown on Schedule III of the depreciation study report, the Iowa Curves
  selected are the same as those approved in Cause No. 45235, with the
  exception of accounts 352 and 358. The Actuarial analysis performed for
  Account 352 indicated that a better fitting curve should be selected for the
  account and conservative judgment was used for the curve and life selected for
  account 358.

#### 12 **Q40.** Please explain the results of your study for Distribution Plant.

The depreciation rate for Distribution Plant decreased from 3.48% to 3.17% due to increases in the average service life for eight accounts (Accounts 364, 365, 366, 367, 368, 369, 371, and 373) and a decrease in the net salvage ratio for Account 370.

- 17 The decrease was offset by increases in the net salvage ratio for seven 18 accounts (Accounts 361, 362, 364, 365, 368, 369 and 373), decreases in the 19 average service life of two accounts (Accounts 361 and 362), and updating the 20 depreciation rate that was calculated for Account 370.
- As shown on Schedule III of the depreciation study report, the Iowa Curves selected are the same as those approved in Cause No. 45235, with the exception of accounts 361,362 and 367 where the Actuarial analysis performed for each account indicated a better fitting curve should be used.

1	Q41.	Please explain the results of your study for General Plant.
2		The depreciation rate for General Plant increased from 3.55% to 4.00% due to
3		increases in the net salvage ratio for three accounts (Accounts 390, 391, and
4		397) and a decrease in the average service life of Account 390. A better fitting
5		L1.0 Iowa Curve was selected during the Actuarial analysis for Account 390,
6		resulting in a lower average service life.
7	Q42.	Does this conclude your pre-filed verified direct testimony?

8 Yes.

9

#### VERIFICATION

I, Jason A. Cash, Accounting Senior Manager in Corporate Accounting of American Electric Power Service Corporation, affirm under penalties of perjury that the foregoing representations are true and correct to the best of my knowledge, information, and belief.

Date: 6/20

0-0 000

Jason A. Cash

### **INDIANA MICHIGAN POWER COMPANY**

## **DEPRECIATION STUDY REPORT**

OF

### **ELECTRIC PLANT IN SERVICE**

AT DECEMBER 31, 2020

#### **DEPRECIATION STUDY REPORT**

#### **Table of Contents**

SUBJECT	PAGE
I. Introduction	 3
II. Discussion of Methods and Procedures Used In The Study	 5
III. Net Salvage	 16
IV. Calculation of Depreciation Requirement	 20
V. Study Results	 20
SCHEDULE I – Explanation of Column Headings	 23
SCHEDULE I – Calculation of Depreciation Rates by the Remaining Life Method	 24
SCHEDULE II – Compare Depreciation Rates Using Current and Study Rates	 28
SCHEDULE III – Comparison of Mortality Characteristics	 32
SCHEDULE IV – Estimated Generation Plant Retirement Dates	 33

#### I. INTRODUCTION

This report presents the results of a depreciation study of Indiana Michigan Power Company's (I&M) depreciable electric utility plant in service at December 31, 2020 adjusted to include 2021-2022 forecasted additions to production plant. The study was preformed by Jason A. Cash, Accounting Senior Manager at American Electric Power Service Corporation (AEPSC). The purpose of the depreciation study was to develop appropriate annual depreciation accrual rates for each of the primary plant accounts that comprise the functional groups for which I&M computes its annual depreciation expense.

The recommended depreciation rates are based on the Average Remaining Life Method of computing depreciation. Further explanation of this method is contained in Section II of this report.

The definition of depreciation used in this Study is the same as that used by the Federal Energy Regulatory Commission (FERC) and the National Association of Regulatory Utility Commissioners:

"Depreciation, as applied to depreciable electric plant, means the loss in service value not restored by current maintenance, incurred in connection with the consumption or prospective retirement of electric plant in the course of service from causes which are known to be in current operation and against which the utility is not protected by insurance. Among the causes to be given consideration are wear and tear, decay, action of the elements, inadequacy, obsolescence, changes in the art, changes in demand and requirements of public authorities."

"Service value means the difference between original cost and the

net salvage value (net salvage value means the salvage value of the property retired less the cost of removal) of the electric plant." (FERC <u>Accounting and Reporting Requirements for Public Utilities and Licensees</u>, ¶15.001.)

SCHEDULE I of this report shows the recommended depreciation accrual rates by primary plant accounts and composited to functional plant classifications. SCHEDULE II compares depreciation expense using existing rates approved by the Commission and rates recommended by the depreciation study. SCHEDULE III shows a comparison of the current and existing mortality characteristics that were used to compute the recommended depreciation rates for Transmission, Distribution and General Plant functions. SCHEDULE IV lists I&M's generating stations and includes the year installed (in service) and the estimated retirement year. A simple comparison of I&M's current rates and accruals and the study rates and accruals is shown below on Figure JAC-1. Figure JAC-1 is based on expected Total Company depreciable plant balances for Steam Production Plant prior to December 31, 2022 (before the end of the Rockport Unit 2 lease), for Nuclear, Hydraulic, and Other Production Plant at December 31, 2022; and Total Company depreciable plant balances for all other functions at December 31, 2020:

#### Figure JAC-1

Steam Production Plant - Plant In Service prior to December 31, 2022 Nuclear, Hydraulic and Other Production Plant - Plant In Service at December 31, 2022 Plant In Service at December 31, 2020 (All Other Functions)

	Existing			Study	
Functional Plant Group	<u>Rates</u>	Accruals (\$)	<u>Rates</u>	Accruals (\$)	<u>Difference</u> ( <u>\$)</u>
Steam Production (1)	8.16%	93,485,397	7.99%	91,491,790	(1,993,607)
Nuclear Production	4.10%	150,259,300	4.52%	165,645,446	15,386,146
Hydraulic Production	2.74%	2,041,834	4.33%	3,223,644	1,181,810
Other Production	5.29%	1,968,059	5.37%	1,999,612	31,553
Transmission	2.48%	41,667,464	2.67%	44,835,980	3,168,516
Distribution	3.48%	89,903,251	3.17%	81,896,932	(8,006,319)
General	3.55%	<u>5,795,047</u>	4.00%	<u>6,527,140</u>	<u>732,093</u>
Total Depreciable Plant	4.12%	<u>385,120,352</u>	4.23%	<u>395,620,544</u>	10.500.192

**Note:** The existing Steam Production accrual amount and rate reflect the annual depreciation for Rockport, based on existing rates, prior to the Rockport Unit 2 lease ending and the owned investment of Rockport Unit 2 being retired from the Company's books. This provides a more accurate representation of the change in annual Rockport depreciation expense, before the end of the Rockport Unit 2 lease. Schedule II of the Depreciation Study Report shows a comparison using Total Company depreciable plant balances for Steam Production Plant at December 31, 2022.

Figure JAC-1 shows a comparison of the depreciation accruals before the end of

the Rockport Unit 2 Lease, producing a decrease of approximately \$2.0 million on a

Total Company basis for Steam Production Plant and an overall Total Company

increase of \$10,500,192.

#### II. DISCUSSION OF METHODS AND PROCEDURES USED IN THE STUDY

#### 1. <u>Group Method</u>

All of the depreciable property included in this report was considered on a group plan. Under the group plan, depreciation expense is accrued upon the basis of the original cost of all property included in each depreciable plant account. Upon retirement of any depreciable property, its full cost, less any net salvage realized,

is charged to the accrued depreciation reserve regardless of the age of the particular item retired. Also, under this plan, the dollars in each primary plant account are considered as a separate group for depreciation accounting purposes and an annual depreciation rate for each account is determined. The annual accruals by primary account were then summed, to arrive at the total accrual for each functional group. The total accrual divided by the original cost yields the functional group accrual rate.

#### 2. Annual Depreciation Rates Using the Average Remaining Life Method

I&M's current depreciation rates are based on the Average Remaining Life Method. The Average Remaining Life Method recovers the original cost of the plant, adjusted for net salvage, less accumulated depreciation, over the average remaining life of the plant. By this method, the annual depreciation rate for each account is determined on the following basis:

Annual Depreciation Expense =

(Orig. Cost x Net Salvage Ratio) - Accumulated Depreciation Average Remaining Life

Annual Depreciation = <u>Annual Depreciation Expense</u> Rate Original Cost

#### 3. <u>Methods of Life Analysis</u>

Depending upon the type of property and the nature of the data available from the property accounting records, one of three life analyses was used to arrive at the historically realized mortality characteristics and service lives of the depreciable plant investments. These methods are identified and described as follows:

#### Life Span Analysis

The life span analysis was employed for Production Plant. I&M's investment in production plant includes steam, nuclear, hydraulic and solar generating plants. The life-span method of analysis is particularly suited to specific location property, such as a generating plant, where all of the surviving investments are likely to be retired in total at a future date.

The key elements in the life span analysis are the age of the surviving investments, the projected retirement date of the facility and the expected interim retirements. Interim retirements are those that are expected to occur between the date of the depreciation study and the expected final retirement date of the generating plant. Examples of interim retirements include fans, pumps, motors, a set of boiler tubes, a turbine rotor, etc. The interim retirement history for each primary production plant account was analyzed and the results of those analyses were used to project future interim retirements.

The age of the surviving investments was obtained from I&M's property accounting records. The retirement dates used in the life-span analysis for Steam Production Plant (Rockport) have not been updated from the retirement dates that were presented in Cause No. 45235. This depreciation study recommends summarizing the investment made at the Rockport Plant, including the SCR, DSI and ACI investments made on each Rockport Unit, and calculate an individual depreciation rate for each utility account used by the Rockport Plant through 2028. For Nuclear and Hydraulic Production plants, the retirement dates are based on the Nuclear Regulatory Commission (NRC) and FERC license expiration dates for the plants, except for the Constantine hydraulic plant where I&M is in the process of filing for 30 year license extension with FERC. For Other Production Plant, the 20 year life for the Company's four solar facilities was based on I&M's expected

useful life for the facilities as approved by the Commission in the order in Cause No. 44511.

A discussion of the life analyses for Steam, Nuclear, Hydraulic and Other Production (solar) Plant follows:

#### Steam Production Plant

I&M's depreciable investment in Steam Production Plant is for the Rockport Generation plant. The Rockport Plant is located on the Ohio River near Rockport Indiana and consists of two generating units. Rockport Unit 2 is a leased unit and the depreciable property that is included in this report for Unit 2 consists of equipment items that are owned by I&M at the leased unit.

The Rockport generating units and their capacities are as follows (also shown on SCHEDULE IV – Estimated Generation Plant Retirement Dates):

Plant	Unit	Rating	Commercial Operating Date
Rockport	1	1,300 MW	1984
Rockport	2	1,300 MW	1989

I&M continues to evaluate each of the Rockport generating units and estimated the following retirement dates for each of the units:

<u>Plant</u>	<u>Unit</u>	Retirement Date
Rockport	1	2028
Rockport	2	2022

The estimated retirement date for Rockport Unit 1 is 2028 and is the same retirement date that was proposed for Rockport Unit 1 in Cause No. 45235. The estimated retirement date for certain leasehold improvements made at Rockport Unit 2 is 2022 and is based on the expiration date of the lease. As previously mentioned, this depreciation study recommends summarizing the investment made at the Rockport Plant and calculating an individual depreciation rate for each utility account used by the Rockport Plant through 2028.

#### Nuclear Production Plant

I&M's depreciable investment in nuclear production plant is the Cook plant that is located on Lake Michigan at Bridgman, Michigan. The Cook generating units and their capacities are as follows:

<u>Plant</u>	<u>Unit</u>	Rating	Commercial Operating Date
Cook	1	1,020 MW	1975
Cook	2	1,090 MW	1978

In 2005, the NRC granted I&M a 20 year license extension to Cook Plant which established the currently approved estimated retirement dates of 2034 for Unit 1 and 2037 for Unit 2.

In 2013, the Company received Commission approval in Cause No. 44812 to complete a number of capital additions to the Cook Plant under a Life Cycle Management (LCM) project. The LCM project is intended to allow the Cook Plant to continue to operate during the 20 year license extension that was granted in 2005. Cook Plant's increase in depreciable plant in service of \$146.9 million since the last depreciation study (with adjusted December 31, 2018 plant in service balances) was mostly due to capital additions related to the LCM project.

#### Hydraulic Production Plant

I&M's investment in Hydraulic Production Plant includes Berrien Springs, Buchanan, Constantine, Elkhart, Mottville and Twin Branch plants. The plants have a number of generating units that were placed into commercial operation over the period from 1904 through 1923. All the plants are located on the St. Joseph River in either the state of Indiana or Michigan.

The generating plants and their capacities are as follows:

<u>Plant</u>	<u>Capacity</u>	First Unit's Commercial <u>Operating Date</u>	FERC License <u>Expiration</u>
Berrien Springs	7.2 MW	1908	*
Buchanan	4.1 MW	1919	2036
Constantine	1.2 MW	1921	2053
Elkhart	3.4 MW	1913	2030
Mottville	1.7 MW	1923	2033
Twin Branch	4.8 MW	1904	2036

\* Not FERC licensed. The retirement date was estimated to be the same date as Buchanan and Twin Branch which is 2036.

I&M is in the process of filing with FERC to relicense the Constantine Plant and continue operating the plant for at least an additional 30 year period.

#### Other Production Plant

I&M's depreciable investment in Other Production Plant at December 2016 is for the Deer Creek, Olive, Twin Branch and Watervliet Solar Plants. The Deer Creek Solar Plant is located just south of Marion, Indiana and is generating up to 2.5 megawatts of electricity. The Olive Solar Plant is located in New Carlisle, Indiana and is generating up to 5.0 megawatts of electricity. The Twin Branch Solar Plant is located in Mishawaka, Indiana and is generating up to 2.6 megawatts of electricity. The Watervliet Solar Plant is located in Watervliet, MI and is generating up to 4.6 megawatts of electricity.

The generating plants and their capacities are as follows:

<u>Plant</u>	<u>Capacity</u>	Commercial Operating Date
Deer Creek	2.5 MW	2015
Olive	5.0 MW	2016
Twin Branch	2.6 MW	2016
Watervliet	4.6 MW	2016

#### Actuarial Analysis - Transmission, Distribution and General Plant

This method of analyzing past experience represents the application to industrial property of statistical procedures developed in the life insurance field for investigating human mortality. It is distinguished from other methods of life estimation by the requirement that it is necessary to know the age of the property at the time of its retirement and the age of survivors, or plant remaining in service; that is, the installation date must be known for each particular retirement and for each particular survivor.

The application of this method involves the statistical procedure known as

the "annual rate method" of analysis. This procedure relates the retirements during each age interval to the exposures at the beginning of that interval, the ratio of these being the annual retirement ratio. Subtracting each retirement ratio from unity yields a sequence of annual survival ratios from which a survivor curve can be determined. This is accomplished by the consecutive multiplication of the survivor ratios. The length of this curve depends primarily upon the age of the oldest property. Normally, if the period of years from the inception of the account to the time of the study is short in relation to the expected maximum life of the property, an incomplete or stub survivor curve results.

While there are a number of acceptable methods of smoothing and extending this stub survivor curve in order to compute the area under it from which the average life is determined, the well-known Iowa Type Curve Method was used in this study.

By this procedure, instead of mathematically smoothing and projecting the stub survivor curve to determine the average life of the group, it was assumed that the stub curve would have the same mortality characteristics as the type curve selected. The selection of the appropriate type curve and average life is accomplished by plotting the stub curve, superimposing on it Iowa curves of the various types and average lives drawn to the same scale, and then determining which Iowa type curve and average life best matches the stub. The Actuarial Method of Life Analysis was used for the following accounts:

- 352.0 Transmission Structures & Improvements
- 353.0 Transmission Station Equipment
- 358.0 Underground Conductor and Devices
- 361.0 Distribution Structures & Improvements
- 362.0 Distribution Station Equipment
- 367.0 Underground Conductor
- 390.0 General Structures & Improvements

The result of the actuarial analysis for the above accounts is detailed in the depreciation study work papers.

#### Simulated Plant Record Analysis – Transmission Plant

The "Simulated Plant Record" (SPR) method designates a class of statistical techniques that provide an estimate of the age distribution, mortality dispersion and average service life of property accounts whose recorded history provides no indication of the age of the property units when retired from service. For each such account, the available property records usually reveal only the annual gross additions, annual retirements and balances with no indication of the age of either plant retirements or annual plant balances. For the accounts using this methodology, the "Balances method" of analysis was used.

The SPR Balances Method is a trial and error procedure that attempts to duplicate the annual balance of a plant account by distributing the actual annual gross additions over time according to an assumed mortality distribution. Specifically, the dollars remaining in service at any date are estimated by multiplying each year's additions by the successive proportion surviving at each age as given by the assumed survivor characteristics. For a given year, the balance indicated is the accumulation of survivors from all vintages and this is compared with the actual book balance. This process is repeated for different survivor curves and average life combinations until a pattern is discovered which produces a series of "simulated balances" most nearly equaling the actual balances shown in a company's books.

This determination is based on the distribution producing the minimum sum of squared differences between the simulated balance and the actual balances over a test period of years.

The iterative nature of the simulated methods makes them ideally suited for computerized analysis. For each analysis of a given property account, the computer program provides a single page summary containing the results of each analysis indicating the "best fit" based on criteria selected by the user.

The results of the analysis using the Balance Method is shown in the depreciation study work papers. The analysis also shows the value of the Index of Variation of the difference that is calculated according to the Balances Method where a lower value for the Index of Variation indicates better agreement with the actual data.

The SPR Method of Life Analysis was utilized for the following accounts:

- 354.0 Transmission Towers & Fixtures
- 355.0 Transmission Poles & Fixtures
- 356.0 Transmission OH Conductor & Devices
- 357.0 Transmission Underground Conduit
- 364.0 Distribution Poles, Towers & Fixtures
- 365.0 Distribution Overhead Conductor & Devices
- 366.0 Distribution Underground Conduit
- 368.0 Distribution Line Transformers
- 369.0 Distribution Services
- 371.0 Distribution Installations on Customers' Premises
- 373.0 Distribution Street Lighting and Signal Systems

## Vintage Year Accounting - General Equipment

In 1998, the Company began using a vintage year accounting method for general plant accounts 391 to 398 in accordance with Federal Energy Regulatory Commission Accounting Release Number 15 (AR-15). This accounting method requires amortization of vintage groups of property over their useful lives. AR-15 also requires that property be retired when it meets its average service life.

As a result, my recommendation for these accounts is that the current useful life approved by the Commission be retained and used to continue depreciation of the account balances.

## 4. Final Selection of Average Life and Curve Type

The final selection of average life and curve type for each depreciable plant account analyzed by the Actuarial and SPR Methods was primarily based on the results of the mortality analyses of past retirement history.

## III. <u>NET SALVAGE</u>

## 1. Net Salvage - Steam Production Plant

The net salvage analysis for steam production plant included a review of the Company's experienced functional interim retirement, salvage and removal history for the period 1954-2020. This interim salvage analysis calculated life to date salvage, removal and net salvage percentages as compared to original cost retirements.

While this type of analysis was used to determine the net salvage applicable to interim retirements for steam production plant, the most significant net salvage amount for generating plants occurs at the end of their life. Therefore, to assist in establishing total net salvage applicable to I&M's steam generating plant, I&M contracted Brandenburg Industrial Service Company (Brandenburg) to update the conceptual demolition cost estimate for the Rockport Plant that was included in I&M's last depreciation study and incorporated in I&M's current depreciation rates. The updated Brandenburg cost estimate to demolish the Rockport Plant is based on current (2018) price levels which were inflated to the retirement date of Rockport Unit 1 (2028) in the depreciation study. The estimate of demolition costs was included in the net salvage ratios for Steam Production Plant. Brandenburg's demolition costs incorporated in the depreciation study totals do not include Asset Retirement Obligation (ARO) amounts associated with the removal of asbestos or any cost associated with the final disposition of Rockport landfills and ash ponds since accretion and depreciation associated with these AROs is included separately in I&M's cost of service.

## 2. <u>Net Salvage - Nuclear Production Plant</u>

The net salvage analysis for nuclear production plant included a review of the Company's experienced functional interim retirement, salvage and removal history for the period 1995-2020. Prior to June 2007, I&M maintained salvage and removal costs at the functional plant level, rather than by primary plant accounts. To determine gross salvage, gross removal and net salvage percentages for individual plant accounts, original cost retirements, salvage and removal were detailed by account for the period 1995 through 2020. Total functional salvage and removal were allocated to individual plant accounts using original cost retirements for the period 1995 to 2007 and were listed as directly charged for 2008 through 2020. The gross salvage and cost of removal percentages were calculated for the twenty-six year time period (1995 to 2020) for each account. The salvage and removal percentages for each account were then netted to determine a net salvage percentage for each account.

Costs associated with the final retirement of I&M's Cook nuclear plant are included in the Company's nuclear decommissioning and ARO accounting and are not included in the depreciation study.

## 3. Net Salvage - Hydraulic Production Plant

The net salvage analysis for hydraulic production plant included a review of the Company's experienced functional interim retirement, salvage and removal history for the period 2001-2020. This interim salvage analysis calculates annual interim salvage, removal and net salvage percentages as compared to original cost retirements.

As with the depreciation study that was performed for Cause Nos. Cause Nos. 44967 and 45235, I&M relied on the same conceptual terminal demolition cost estimates that were provided by Sargent & Lundy (S&L) for each of the

Company's hydraulic plants in that Cause. Since the S&L cost estimates to demolish the hydraulic plants are based on 2015 price levels, the S&L cost estimates were inflated to each plant's estimated retirement date in the depreciation study. I&M's current depreciation study uses the interim net salvage analysis mentioned above plus the S&L conceptual terminal demolition cost estimates to determine the total net salvage amount to include in the depreciation rate calculation for each of the Company's Hydraulic Production Plants.

## 4. Net Salvage - Other Production Plant

As with the depreciation study that was performed for Cause Nos. 44967 and 45235, the net salvage analysis for other production plant included an estimated cost for demolition at each site and an estimated cost to recycle the number of panels located at each site.

## 5. Net Salvage – Transmission, Distribution and General Plant

The net salvage percentages used in this report for Transmission, Distribution and General Plant are expressed as a percent of original cost and are based on the Company's experience combined with the judgment of the analyst. Prior to June 2007, I&M maintained salvage and removal costs at the functional plant level, rather than by primary plant accounts. To determine gross salvage, gross removal and net salvage percentages for individual plant accounts, original cost retirements, salvage and removal were detailed by account for the period 1995 through 2020. Total functional salvage and removal were allocated to individual plant accounts using original cost retirements for the period 1995 to 2007 and were listed as directly charged for 2008 through 2020. The gross salvage and cost of removal percentages were calculated for the twenty-six year time period (1995 to 2020) for each account. The salvage and removal percentages for each account were then netted to determine a net salvage percentage for each account.

The net salvage percentages were converted to net salvage ratios (1 minus the net salvage percentage) which appear in Column IV on SCHEDULE I. The net salvage percentages were used to determine the total amount to be recovered through depreciation. The same net salvage percentages were also reflected in the determination of the calculated depreciation requirement, which was used to allocate accumulated depreciation at the functional group to the accounts comprising each group.

## 6. <u>Net Salvage – Ratios</u>

The net salvage ratios shown in Column IV on SCHEDULE I of this report may be explained as follows:

- a. Where the ratio is shown as unity (1.00), it was assumed that the net salvage in that particular account would be zero.
- Where the ratio is less than unity, it was assumed that the salvage exceeded the removal costs. For example, if the net salvage were 20%, the net salvage ratio would be expressed as .80.
- c. Where the ratio is greater than unity, it was assumed that the salvage was less than the cost of removal. For example, if the net salvage were minus 5%, the net salvage ratio would be expressed as 1.05.

## IV. CALCULATION OF DEPRECIATION REQUIREMENT

The accumulated depreciation by functional group was allocated to individual plant accounts based on the calculation of a depreciation requirement (theoretical reserve) for each plant account using the average service life, curve type and net salvage amount recommended in this study.

## V. <u>STUDY RESULTS</u>

Production, Transmission, Distribution and General plant results are discussed below. In addition, Transmission, Distribution and General Plant average service life, retirement dispersion pattern and net salvage percentages used to calculate each primary plant account depreciation rate are shown on SCHEDULE III. The mortality characteristics and net salvage values for the current rates are also shown. Changes to the mortality characteristics follow trends shown by historical retirement experience. Gross salvage and gross cost of removal percentages were largely based on the history of each account.

## Steam Production Plant

As shown in Figure JAC-1, a decrease of approximately \$2.0 million is expected for Steam Production Plant is expected on a Total Company basis. This is mainly due to depreciating the expected remaining balance of Rockport Unit 2 through 2028.

## Nuclear Production Plant

The composite rate for Nuclear Production Plant increased from 4.10% to 4.52% mainly due to a \$146.9 million increase in the depreciable plant in service

balance since the 2018 depreciation study. The increase in depreciable nuclear plant in service since 2018 is mostly due to I&M's LCM program which was detailed in the Company's 2013 order in Cause No. 44812. The LCM program is intended to perform work necessary to allow the Cook Units 1 and 2 to reach the end of their renewed license period in 2034 (Unit 1) and 2037 (Unit 2).

## Hydraulic Production Plant

The composite rate for Hydraulic Production Plant increased from 2.74% to 4.33% due a \$17.4 million increase in the depreciable plant in service balance since the 2018 depreciation study.

## Other Production Plant

The composite depreciation rate for Other Production Plant increased slightly from 5.29% to 5.37% due to a \$0.3 million increase in the depreciable plant in service balance since the 2018 depreciation study.

## Transmission Plant

The depreciation rate for Transmission Plant increased from 2.48% to 2.67% due to increases in the net salvage ratio for three accounts (Accounts 353, 354, and 355) and decreases in the average service life for four accounts (Accounts 352, 353, 355 and 358). The depreciation rate increase was partially offset by an increase in the average service lives for three accounts (Accounts 354, 356 and 357) and decreases in the net salvage ratio for three accounts (Accounts 352, 356 and 358). As shown on Schedule III of the depreciation study report, the Iowa Curves selected are the same as those approved in Cause No. 45235, with the exception of accounts 352 and 358. The Actuarial analysis performed for Account 352 indicated that a better fitting curve should be selected

for the account and conservative judgment was used for the curve and life selected for account 358.

## **Distribution Plant**

The depreciation rate for Distribution Plant decreased from 3.48% to 3.17% due to increases in the average service life for eight accounts (Accounts 364, 365, 366, 367, 368, 369, 371, and 373) and a decrease in the net salvage ratio for Account 370. The decrease was offset by increases in the net salvage ratio for seven accounts (Accounts 361, 362, 364, 365, 368, 369 and 373), decreases in the average service life of two accounts (Accounts 361 and 362), and updating the depreciation rate that was calculated for Account 370. As shown on Schedule III of the depreciation study report, the Iowa Curves selected are the same as those approved in Cause No. 45235, with the exception of accounts 361,362 and 367 where the Actuarial analysis performed for each account indicated a better fitting curve should be used.

## General Plant

The depreciation rate for General Plant increased from 3.55% to 4.00% due to increases in the net salvage ratio for three accounts (Accounts 390, 391, and 397) and a decrease in the average service life of Account 390. A better fitting L1.0 lowa Curve was selected during the Actuarial analysis for Account 390, resulting in a lower average service life.

## **SCHEDULE I – EXPLANATION OF COLUMN HEADINGS**

SCHEDULE I shows the determination of the recommended annual depreciation accrual rate by primary plant accounts by the straight line remaining life method. An explanation of the schedule follows:

Column I	-	Account number.
Column II	-	Account title.
Column III	-	Original Cost at December 31, 2016, adjusted to include 2017 projected additions
Column IV	-	Net Salvage Ratio.
Column V	-	Total to be Recovered (Column III) * (Column IV).
Column VI	-	Calculated Depreciation Requirement.
Column VII	-	Allocated Accumulated Depreciation – I&M's accumulated depreciation (adjusted book reserve) spread to each account on the basis of the Calculated Depreciation Requirement shown in Column VI.
Column VIII	-	Remaining to be Recovered (Column V - Column VII).
Column IX	-	Average Remaining Life.
Column X	-	Recommended Annual Accrual Amount.
Column XI	-	Recommended Annual Accrual Percent or Depreciation Rate (Column X/Column III).

	ACCOUNT	ORIGINAL COST	NET SALVG RATIO	TOTAL TO BE RECOVERED	DEPRECIATION	ALLOCATED ACCUMULATE D DEPRECIATION	REMAINING TO BE RECOVERED	AVG REMAIN LIFE	RECOMMEN ANNUAL ACC	
NO.	TITLE							-	AMOUNT	%
(I)	(II)	(III)	(IV)	(V)	(VI)	(VII)	(VIII)	(IX)	(X)	(XI)
STEAM	PRODUCTION PLANT									
<u>Rockp</u>	ort									
311.0	Structures & Improvements	103,081,792	1.02	105,143,428	90,063,864	53,340,105	51,803,323	5.47	9,470,443	9.19%
312.0	Boiler Plant Equipment	646,499,630	1.02	659,429,623	531,021,903	314,496,432	344,933,191	5.39	63,995,026	9.90%
314.0	Turbogenerator Units	110,198,824	1.02	112,402,800	92,010,973	54,493,275	57,909,525	5.35	10,824,210	9.82%
315.0	Accessory Electrical Equipment	60,038,956	1.02	61,239,735	53,196,660	31,505,593	29,734,142	5.44	5,465,835	9.10%
316.0	Miscellaneous Power Plant Equip.	<u>17,952,020</u>	1.02	18,311,060	15,204,150	<u>9,004,621</u>	<u>9,306,439</u>	5.36	<u>1,736,276</u>	9.67%
	Total Rockport	937,771,222	1.02	<u>956,526,646</u>	781,497,550	462,840,025	493,686,620	5.40	<u>91,491,790</u>	9.76%
Total Ste	eam Production Plant	937,771,222	1.02	<u>956,526,646</u>	781,497,550	462,840,025	493,686,620	5.40	<u>91,491,790</u>	9.76%
NUCLE	AR PRODUCTION PLANT									
Cook U	Unit 1									
321.0	Structures & Improvements	86,734,372	1.01	87,601,716	67,751,167	52,347,711	35,254,005	11.28	3,125,355	3.60%
322.0	Reactor Plant Equipment	782,729,686	1.03	806,211,577	503,156,645	388,762,289	417,449,288	10.95	38,123,223	4.87%
323.0	Turbogenerator Units	312,897,355	1.03	322,284,276	187,150,479	144,601,188	177,683,088	10.45	17,003,166	5.43%
324.0	Accessory Electrical Equipment	137,248,173	1.00	137,248,173	91,626,880	70,795,200	66,452,973	11.13	5,970,618	4.35%
325.0	Miscellaneous Power Plant Equip.	36,218,603	1.00	36,218,603	22,654,736	17,504,106	18,714,497	10.97	<u>1,705,971</u>	4.71%
	Total Cook Unit 1	<u>1,355,828,189</u>	1.02	<u>1,389,564,344</u>	872,339,907	<u>674,010,494</u>	715,553,850	10.85	<u>65,928,332</u>	4.86%
<u>Cook</u>										
321.0	Structures & Improvements	378,680,285	1.02	386,253,891	249,249,636	192,581,892	193,671,999	14.15	13,687,067	3.61%
322.0	Reactor Plant Equipment	1,053,868,998	1.03	1,085,485,068	600,707,437	464,134,580	621,350,488	13.62	45,620,447	4.33%
323.0	Turbogenerator Units	425,843,325	1.04	442,877,058		166,645,297	276,231,761	12.83	21,530,145	5.06%
324.0	Accessory Electrical Equipment	200,678,427	1.00	200,678,427	106,821,127	82,534,984	118,143,443	13.91	8,493,418	4.23%
325.0	Miscellaneous Power Plant Equip.	248,016,731	1.00	248,016,731	137,376,467	106,143,465	141,873,266	13.66	10,386,037	4.19%
	Total Cook Unit 2	2,307,087,766	1.02	2,363,311,175	1,309,835,794	1,012,040,218	1,351,270,957	13.55	<u>99,717,114</u>	4.32%
Total Nu	clear Production Plant	<u>3,662,915,955</u>	1.02	<u>3,752,875,519</u>	2,182,175,701	<u>1,686,050,712</u>	<u>2,066,824,807</u>	12.48	<u>165,645,446</u>	4.52%
HYDRA	ULIC PRODUCTION PLANT									
Berrie	n Springs									
331.0	Structures & Improvements	696,548	1.04	724,410	423,273	341,708	382,702	13.34	28,688	4.12%
332.0	Reservoirs, Dams & Waterways	6,320,266	1.04	6,573,077	4,453,917	3,595,649	2,977,428	13.40	222,196	3.52%
333.0	Waterwheels, Turbines & Generators	8,386,954	1.04	8,722,432	5,477,687	4,422,138	4,300,294	13.21	325,533	3.88%
334.0	Accessory Electrical Equip.	1,417,718	1.04	1,474,427	966,929	780,602	693,825	13.04	53,207	3.75%
335.0	Misc. Power Plant Equip.	<u>929,404</u>	1.04	966,580	575,405	464,525	502,055	13.29	<u>37,777</u>	4.06%
	Total Berrien Springs	17,750,890	1.04	18,460,926	11,897,211	9,604,622	8,856,304	13.27	667,402	3.76%
Bucha	nan									
331.0	Structures & Improvements	660,195	1.05	693,205	406,287	327,996	365,209	13.34	27,377	4.15%
332.0	Reservoirs, Dams & Waterways	5,154,683	1.05	5,412,417	3,825,496	3,088,324	2,324,093	13.40	173,440	3.36%
333.0	Waterwheels, Turbines & Generators	1,414,445	1.05	1,485,167	1,076,004	868,658	616,509	13.21	46,670	3.30%
334.0	Accessory Electrical Equip.	1,108,771	1.05	1,164,210	808,427	652,643	511,567	13.04	39,231	3.54%
335.0	Misc. Power Plant Equip.	<u>311,833</u>	1.05	327,425	192,788	155,638	171,787	13.29	12,926	4.15%
	Total Buchanan	8,649,927	1.05	9,082,423	6,309,002	5,093,259	3,989,164	13.31	299,643	3.46%

NO.	ACCOUNT TITLE	ORIGINAL COST	NET SALVG RATIO	TOTAL TO BE RECOVERED	CALCULATED DEPRECIATION REQUIREMENT	ALLOCATED ACCUMULATE D DEPRECIATION	REMAINING TO BE RECOVERED	AVG REMAIN LIFE	RECOMMEN ANNUAL ACC AMOUNT	
(I)	(II)	(III)	(IV)	(V)	(VI)	(VII)	(VIII)	(IX)	(X)	(XI)
Elkhaı	<u>-t</u>									
331.0	Structures & Improvements	1,632,902	1.03	1,681,889	1,183,377	955,341	726,548	7.42	97,918	6.00%
332.0	Reservoirs, Dams & Waterways	11,027,557	1.03	11,358,384	7,468,137	6,029,029	5,329,355	7.45	715,350	6.49%
333.0	Waterwheels, Turbines & Generators	875,459	1.03	901,723	699,106	564,389	337,334	7.35	45,896	5.24%
334.0	Accessory Electrical Equip.	766,670	1.03	789,670	607,967	490,812	298,858	7.27	41,108	5.36%
335.0	Misc. Power Plant Equip.	342,337	1.03	352,607	207,932	167,864	184,743	7.39	<u>24,999</u>	7.30%
	Total Elkhart	14,644,925	1.03	15,084,273	10,166,519	8,207,435	6,876,838	7.43	925,270	6.32%
Twin I	Branch									
331.0	Structures & Improvements	1,428,784	1.05	1,500,223	757,013	611,137	889,086	13.34	66,648	4.66%
332.0	Reservoirs, Dams & Waterways	8,416,861	1.05	8,837,704	5,373,324	4,337,886	4,499,818	13.40	335,807	3.99%
333.0	Waterwheels, Turbines & Generators	9,909,128	1.05	10,404,584	5,960,786	4,812,145	5,592,439	13.21	423,349	4.27%
334.0	Accessory Electrical Equip.	2,876,083	1.05	3,019,887	1,784,149	1,440,344	1,579,543	13.04	121,131	4.21%
335.0	Misc. Power Plant Equip.	1,005,606	1.05	1,055,886	474,832	<u>383,332</u>	672,554	13.29	<u>50,606</u>	5.03%
	Total Twin Branch	23,636,462	1.05	24,818,285	14,350,104	11,584,844	13,233,441	13.27	997,541	4.22%
Consta	intine									
331.0	Structures & Improvements	470,900	1.17	550,953	243,136	196,284	354,669	29.66	11,958	2.54%
332.0	Reservoirs, Dams & Waterways	1,653,789	1.17	1,934,933	898,583	725,426	1,209,507	29.99	40,330	2.44%
333.0	Waterwheels, Turbines & Generators	993,032	1.17	1,161,847	582,783	470,481	691,366	29.01	23,832	2.409
334.0	Accessory Electrical Equip.	671,796	1.17	786,001	257,651	208,002	577,999	28.18	20,511	3.05%
335.0	Misc. Power Plant Equip.	475,641	1.17	556,500	155,263	125,344	431,156	29.43	<u>14,650</u>	3.08%
	Total Constantine	4,265,158	1.17	4,990,235	2,137,416	1,725,537	3,264,698	29.34	111,281	2.61%
Mottvi	lle									
331.0	Structures & Improvements	797,060	1.04	828,942	550,003	444,018	384,924	10.40	37,012	4.64%
332.0	Reservoirs, Dams & Waterways	2,312,828	1.04	2,405,341	1,759,748	1,420,645	984,696	10.44	94,320	4.08%
333.0	Waterwheels, Turbines & Generators	639,576	1.04	665,159	507,583	409,772	255,387	10.32	24,747	3.87%
334.0	Accessory Electrical Equip.	772,571	1.04	803,474	549,415	443,543	359,931	10.22	35,218	4.56%
335.0	Misc. Power Plant Equip.	409,136	1.04	425,501	240,706	194,322	231,179	10.37	22,293	5.45%
336.0	Roads, Railroads & Bridges	<u>902</u>	1.04	<u>938</u>	<u>796</u>	<u>643</u>	<u>295</u>	10.38	<u>28</u>	3.15%
	Total Mottville	4,932,073	1.04	<u>5,129,356</u>	3,608,251	<u>2,912,943</u>	2,216,413	10.38	213,618	4.33%
Crews	Service Center									
331.0	Structures & Improvements	417,303	1.05	438,168	291,864	235,622	202,546	29.66	6,829	1.64%
335.0	Misc. Power Plant Equip.	126,865	1.05	133,208	89,929	72,600	60,608	29.43	2,059	1.62%
	Total Crew Service Center	544,168	1.05	571,376	381,793	308,222	263,154	29.61	<u>8,888</u>	1.63%
otal Ha	draulic Production Plant	74,423,603	1.05	78,136,874	48,850,296	39,436,861	38,700,012	12.01	3,223,644	4.33%

	٦	

IN										
	ACCOUNT	ORIGINAL COST	NET SALVG RATIO	TOTAL TO BE RECOVERED	CALCULATED DEPRECIATION REQUIREMENT	ALLOCATED ACCUMULATE D DEPRECIATION	REMAINING TO BE RECOVERED	AVG REMAIN LIFE	RECOMMEN ANNUAL ACC	RUAL
NO.	TITLE				an b				AMOUNT	%
(I)	(II)	(III)	(IV)	(V)	(VI)	(VII)	(VIII)	(IX)	(X)	(XI)
OTHER	PRODUCTION PLANT									
Deer C	Creek Solar Facility									
344.0	Generators	5,668,204	1.03	5,838,250	2,189,344	2,027,991	3,810,259	12.50	304,821	5.38%
345.0	Accessory Electric Equip.	720,502	1.03	742,117	162,301	150,340	591,777	12.50	47,342	6.57%
346.0	Misc. Power Plant Equip.	10,893	1.03	11,220	1,659	1,537	9,683	12.50	775	7.11%
	Total Deer Creek Solar Facility	<u>6,399,599</u>		6,591,587	2,353,304	<u>2,179,868</u>	4,411,719	12.50	352,938	5.51%
Olive S	Solar Facility									
341.0	Structures & Improvements	376,687	1.03	387,988	126,096	116,803	271,185	13.50	20,088	5.33%
344.0	Generators	11,184,837	1.03	11,520,382	3,744,124	3,468,187	8,052,195	13.50	596,459	5.33%
345.0	Accessory Electric Equip.	269,062	1.03	277,134	90,069	83,431	193,703	13.50	14,348	5.33%
346.0	Misc. Power Plant Equip.	215,250	1.03	221,708	72,055	66,745	154,963	13.50	<u>11,479</u>	5.33%
	Total Olive Solar Facility	12,045,836	1.03	12,407,211	4,032,344	3,735,166	8,672,045	13.50	642,374	5.33%
<u>Twin I</u>	Branch Solar Facility									
344.0	Generators	6,955,324	1.04	7,233,537	2,350,900	<u>2,177,641</u>	<u>5,055,896</u>	13.50	374,511	5.38%
Water	vliet Facility									
341.0	Structures & Improvements	358,237	1.03	368,984	119,920	111,082	257,902	13.50	19,104	5.33%
344.0	Generators	11,107,366	1.03	11,440,587	3,718,191	3,444,164	7,996,423	13.50	592,328	5.33%
346.0	Misc. Power Plant Equip.	343,931	1.03	354,249	<u>114,883</u>	106,416	247,833	13.50	<u>18,358</u>	5.34%
	Total Watervliet Facility	11,809,534	1.03	12,163,820	3,952,994	3,661,662	8,502,158	13.50	629,789	5.33%
Total Ot	her Production Plant	37,210,293	1.03	<u>38,396,155</u>	<u>12,689,542</u>	<u>11,754,335</u>	<u>26,641,818</u>	13.32	<u>1,999,612</u>	5.37%
Total Pr	oduction Plant	<u>4,712,321,073</u>	1.02	<u>4,825,935,194</u>	<u>3,025,213,089</u>	<u>2,200,081,933</u>	<u>2,625,853,257</u>	10.01	262,360,492	5.57%
TRANS	MISSION PLANT									
350.1	Land Rights	62,292,873	1.00	62,292,873	23,350,156	17,804,684	44,488,189	40.64	1,094,690	1.76%
352.0	Structures & Improvements	52,265,232	1.10	57,491,755	7,849,551	5,985,346	51,506,409	56.13	917,627	1.76%
353.0	Station Equipment	826,489,176	1.10	909,138,094	213,734,540	162,974,326	746,163,768	33.66	22,167,670	2.68%
354.0	Towers & Fixtures	230,452,983	1.39	320,329,646	191,173,868	145,771,629	174,558,017	26.61	6,559,865	2.85%
355.0	Poles & Fixtures	208,136,265	1.64	341,343,475	44,409,633	33,862,706	307,480,769	43.49	7,070,149	3.40%
356.0	OH Conductor & Devices	294,558,395	1.35	397,653,833	159,649,845	121,734,305	275,919,528	40.10	6,880,786	2.34%
357.0	Underground Conduit	2,241,687	1.00	2,241,687	1,117,374	852,007	1,389,680	27.59	50,369	2.25%
358.0	Underground Conductor	4,522,363	1.13	5,110,270	1,464,317	1,116,554	3,993,716	42.81	93,289	2.06%
359.0	Roads and Trails	<u>91,159</u>	1.00	<u>91,159</u>	25,925	<u>19,768</u>	<u>71,391</u>	46.51	<u>1,535</u>	1.68%
Total Tr	ransmission Plant	<u>1,681,050,133</u>	1.25	2,095,692,792	<u>642,775,209</u>	490,121,325	<u>1,605,571,467</u>	35.81	<u>44,835,980</u>	2.67%

ACCOUNT	ORIGINAL COST	NET SALVG RATIO	TOTAL TO BE RECOVERED	DEPRECIATION	D		AVG REMAIN LIFE	RECOMMEN ANNUAL ACC	
TITLE	-						-	AMOUNT	%
(II)	(III)	(IV)	(V)	(VI)	(VII)	(VIII)	(IX)	(X)	(XI)
BUTION PLANT - IN									
Land Rights	10,926,039	1.00	10,926,039	2,388,029	2,947,585	7,978,454	50.61	157,646	1.44%
Structures & Improvements	32,691,043	1.25	40,863,804	3,686,322	3,066,234	37,797,570	58.94	641,289	1.96%
-	379,401,090	1.12	424,929,221	51,766,238	34,619,804	390,309,417	40.16	9,718,860	2.56%
	5,606,730	1.00	5,606,730	4,242,655	3,747,078	1,859,652	3.65	509,494	9.09%
Poles, Towers, & Fixtures	252,111,755	1.87	471,448,982	83,961,086	112,061,327	359,387,655	33.33	10,782,708	4.28%
Overhead Conductor & Devices	399,931,378	1.16	463,920,398	74,997,865	90,991,491	372,928,907	32.63	11,429,020	2.86%
						122.114.288		2,401,933	1.66%
e									1.96%
-									3.42%
									2.65%
									10.08%
									4.90%
Street Lighting & Signal Sys.	<u>18,113,668</u>	1.18	<u>21,374,128</u>		<u>12,452,701</u>		13.12	<u>679,987</u>	3.75%
	2.081.061.734	1.20	2.506.777.846	496.702.687		1.931.814.347	29.57	65.338.424	3.14%
	1,001,001,701	120	<u></u>	<u></u>	<u>er (p dd (15)</u>	<u>1001011011</u>	20101	<u></u>	
SUTION PLANT - MI									
Land Rights	6,056,743	1.00	6,056,743	1,371,435	1,692,786	4,363,957	50.61	87,389	1.44%
Structures & Improvements	4,510,462	1.25	5,638,078	650,345	540,949	5,097,129	58.94	88,480	1.96%
Station Equipment	96,403,578	1.12	107,972,007	15,863,769	10,609,243	97,362,764	40.16	2,469,505	2.56%
Storage Battery Equipment	0	1.00	0	0	0	0	0.00	0	9.09%
Poles, Towers, & Fixtures	80,503,822	1.87	150,542,147	32,451,643	43,312,615	107,229,532	33.33	3,443,113	4.28%
Overhead Conductor & Devices	139,323,640	1.16	161,615,422	24,893,815	30,202,531	131,412,891	32.63	3,981,515	2.86%
Underground Conduit	12,573,950	1.00	12,573,950	2,780,271	2,977,885	9,596,065	50.84	208,457	1.66%
Underground Conductor	37,852,912	1.00	37,852,912	14,814,525	13,307,161	24,545,751	42.40	741,401	1.96%
Line Transformers	52,380,639	1.08	56,571,090	16,556,427	22,569,130	34,001,960	19.24	1,791,873	3.42%
Services	33,052,679	1.24	40,985,322	11,709,296	14,282,261	26,703,061	33.12	875,696	2.65%
Meters	22,239,359	1.20	26,687,231	5,776,094	5,776,094	20,911,137	(3)	2,241,727	10.08%
Installations on Custs. Prem.	8,344,653	1.23	10,263,923	3,593,958	6,412,292	3,851,631	11.64	408,541	4.90%
Street Lighting & Signal Sys.	5,882,009	1.18	6,940,771	1,682,554	2,149,078	4,791,693	13.12	220,811	3.75%
stribution Plant - MI	499,124,446	1.25	623,699,596	132,144,132	153,832,025	469,867,571	28.38	<u>16,558,508</u>	3.32%
stribution Plant	2,580,186,180	1.21	<u>3,130,477,442</u>	<u>628,846,819</u>	728,795,524	<u>2,401,681,918</u>	29.33	<u>81,896,932</u>	3.17%
AL PLANT									
Structures & Improvements	61,646,560	1.05	64,728,888	13,985,046	9,451,468	55,277,420	35.28	1,566,820	2.54%
Office Furniture & Equipment	5,869,860	0.97	5,693,764	2,427,416	1,640,513	4,053,251	12.62	321,177	5.47%
Stores Equipment	996,539	1.00	996,539	285,967	193,264	803,275	9.98	80,488	8.08%
Tools Shop & Garage Equipment	16,780,302	1.00	16,780,302	7,424,999	5,018,013	11,762,289	8.92	1,318,642	7.86%
Laboratory Equipment	240,988	0.99	238,578	114,920	77,666	160,912	10.37	15,517	6.44%
Power Operated Equipment	543,715	1.00	543,715	355,674	240,374	303,341	8.65	35,068	6.45%
Communication Equipment	66,159,303	1.01	66,820,896	18,584,595	12,559,966	54,260,930	19.49	2,784,040	4.21%
Miscellaneous Equipment	10,826,054	0.92	<u>9,959,970</u>	4,036,340	2,727,867	7,232,103	17.84	405,387	3.74%
neral Plant	<u>163,063,321</u>	1.02	165,762,652	47,214,957	<u>31,909,131</u>	<u>133,853,521</u>	20.51	<u>6,527,140</u>	4.00%
Total Depreciable Plant	<u>9,136,620,707</u>	1.12	<u>10,217,868,080</u>	<u>4,344,050,074</u>	<u>3,450,907,913</u>	<u>6,766,960,163</u>	17.10	<u>395,620,544</u>	4.33%
	TITLE (II) SUTION PLANT - IN Land Rights Structures & Improvements Station Equipment Poles, Towers, & Fixtures Overhead Conductor & Devices Underground Conduit Underground Conduit Underground Conductor Line Transformers Services Meters (3) Installations on Custs. Prem. Street Lighting & Signal Sys. stribution Plant - IN SUTION PLANT - MI Land Rights Structures & Improvements Station Equipment Storage Battery Equipment Poles, Towers, & Fixtures Overhead Conductor & Devices Underground Conduit Underground Conduit Underground Conduit Underground Conductor Line Transformers Services Meters Installations on Custs. Prem. Street Lighting & Signal Sys. stribution Plant - MI stribution Plant - MI stribution Plant J AL PLANT Structures & Improvements Office Furniture & Equipment Tools Shop & Garage Equipment Laboratory Equipment Power Operated Equipment Communication Equipment Miscellaneous Equipment Meters Installatione Structures (Conters) Structures & Improvements Office Furniture & Equipment Stores Equipment Power Operated Equipment Communication Equipment And PLANT	ACCOUNTCOSTTITLE (II)(III)BUTION PLANT - IN	ACCOUNTORIGINAL COSTSALVG RATIOTITLE (II)(III)(IV)SUTON PLANT - IN(III)(IV)SUTION PLANT - IN32,691,0431.25Station Equipment379,401,0901.12Storage Battery Equipment5,606,7301.00Poles, Towers, & Fixtures252,111,7551.87Overhead Conductor & Devices399,931,3781.16Underground Conductor255,708,9781.00Line Transformers318,204,3241.08Services166,556,1471.24Meters (3)76,493,4471.20Installations on Custs. Prem.20,81,061,7341.20Installations on Custs. Prem.20,81,061,7341.20Street Lighting & Signal Sys.18,113,6681.18Land Rights6,056,7431.00Structures & Improvements4,510,4621.25Station Equipment96,033,8221.87Overhead Conductor & Devices139,323,6401.16Underground Conduit12,573,9501.00Line Transformers52,306,3391.08Services33,052,6791.24Meters22,239,3591.20Istallations on Custs. Prem.8,344,6531.25Stribution Plant - MI499,124,4461.25Meters22,239,3591.20Istallations on Custs. Prem.8,344,6531.23Street Lighting & Signal Sys.5.882,0091.18Aribution Plant - MI499,124,4461.25Aributio	ACCOUNT         ORIGINAL TTLE (II)         SALVG COST         TOTAL TO BE RATIO         RECOVERED           IIII         (III)         (IV)         (V)           SUTION PLANT - IN         IIIIII         IIII         (IV)         (V)           Structures & Improvements         32,691,043         1.25         40,863,804           Station Equipment         5,606,730         1.00         5,606,730           Storage Battery Equipment         5,606,730         1.00         14,482,340           Underground Conduit         144,882,340         1.01         144,882,340           Underground Conductor         255,708,978         1.00         255,708,978           Line Transformers         318,204,324         1.08         343,660,670           Services         166,556,147         1.20         91,792,136           Installations on Custs. Prem.         20,434,795         1.23         25,134,798           Structures & Improvements         4,510,462         1.25         5,638,078           Station Equipment         96,403,578         1.12         107,972,007           Structures & Improvements         4,510,462         1.25         5,638,078           Station Equipment         96,403,578         1.12         107,972,007 <td>ACCOUNT         ORIGINAL COST         SALVG RATIO         TOTAL TO BE REQUIREMENT           ITILE (II)         (III)         (IV)         (V)         (V)           STUCTON PLANT - IN         U         (V)         (V)         (V)           Structures &amp; Improvements         32,691,043         1.25         40,863,804         3,686,322           Structures &amp; Improvements         32,691,043         1.25         40,863,804         3,686,322           Storage Battery Equipment         5,606,730         1.00         5,606,730         4,242,655           Poles, Towers, &amp; Fixtures         252,111,755         1.87         471,448,982         83,361,086           Overhead Conductor &amp; Devices         39,9913,178         1.00         255,708,978         48,263,147           Line Transformers         318,204,324         1.00         14,488,240         21,257,149           Underground Conductor         255,708,978         1.00         255,708,978         48,263,147           Line Transformers         318,204,324         1.20         91,792,136         40,800,844           Installations on Custs. Prem.         20,434,975         1.23         25,147,978         756,030           Structures &amp; Improvements         4,510,462         1.25         5,638,078</td> <td>NET         CALCULATE         ACCUMULATE           TITLE         COST         SALVO         TOTAL TO BE         DERECIATION         D           III         (II)         (III)         (IV)         (V)         (VI)         (VI)           SUTON PLANT - IN         IIII         IIII         100         100         10.926.039         1.23         40.863.804         3.586.22         3.066.238           Station Equipment         37.901.090         1.12         424.929.221         51.766.238         34.619.804           Storage Battery Equipment         5.067.730         1.00         55.067.30         4.71.448.92         83.961.086         112.001.377           Poles, Towers, &amp; Fixtures         325.11.755         1.87         471.448.92         83.961.086         112.001.377           Underground Conductor         255.708.978         1.00         24.859.203.87         74.973.85           Vorthaid Conductor &amp; Devices         106.55.147         1.21         20.570.8978         48.263.147         43.352.417           Vartures &amp; Informers         318.204.324         1.08         2.374.738         7.50.590         13.489.903           Storage Battery Equipment         0.00         0         0         0         0         0</td> <td>NET         CACCULATED         ACCUMUATE ALCULATED         ACCUMUATE ALC</td> <td>NET         CACCULATED         ACCUNULLAT         ACC         AVG           ACCOUNT         NATIO         TOTAL TOP         D<td>NET         CALCULTED         ACCUMILATE         NUM         RECOVERED         INFERICUTERED         CALCULATE         NUM         RECOVERED         INFE           ACCOUNT         TILE         00         070         V0         V0         V1D         V1D         000         000         000         000           ACCOUNT         000         00         00         00         000</td></td>	ACCOUNT         ORIGINAL COST         SALVG RATIO         TOTAL TO BE REQUIREMENT           ITILE (II)         (III)         (IV)         (V)         (V)           STUCTON PLANT - IN         U         (V)         (V)         (V)           Structures & Improvements         32,691,043         1.25         40,863,804         3,686,322           Structures & Improvements         32,691,043         1.25         40,863,804         3,686,322           Storage Battery Equipment         5,606,730         1.00         5,606,730         4,242,655           Poles, Towers, & Fixtures         252,111,755         1.87         471,448,982         83,361,086           Overhead Conductor & Devices         39,9913,178         1.00         255,708,978         48,263,147           Line Transformers         318,204,324         1.00         14,488,240         21,257,149           Underground Conductor         255,708,978         1.00         255,708,978         48,263,147           Line Transformers         318,204,324         1.20         91,792,136         40,800,844           Installations on Custs. Prem.         20,434,975         1.23         25,147,978         756,030           Structures & Improvements         4,510,462         1.25         5,638,078	NET         CALCULATE         ACCUMULATE           TITLE         COST         SALVO         TOTAL TO BE         DERECIATION         D           III         (II)         (III)         (IV)         (V)         (VI)         (VI)           SUTON PLANT - IN         IIII         IIII         100         100         10.926.039         1.23         40.863.804         3.586.22         3.066.238           Station Equipment         37.901.090         1.12         424.929.221         51.766.238         34.619.804           Storage Battery Equipment         5.067.730         1.00         55.067.30         4.71.448.92         83.961.086         112.001.377           Poles, Towers, & Fixtures         325.11.755         1.87         471.448.92         83.961.086         112.001.377           Underground Conductor         255.708.978         1.00         24.859.203.87         74.973.85           Vorthaid Conductor & Devices         106.55.147         1.21         20.570.8978         48.263.147         43.352.417           Vartures & Informers         318.204.324         1.08         2.374.738         7.50.590         13.489.903           Storage Battery Equipment         0.00         0         0         0         0         0	NET         CACCULATED         ACCUMUATE ALCULATED         ACCUMUATE ALC	NET         CACCULATED         ACCUNULLAT         ACC         AVG           ACCOUNT         NATIO         TOTAL TOP         D <td>NET         CALCULTED         ACCUMILATE         NUM         RECOVERED         INFERICUTERED         CALCULATE         NUM         RECOVERED         INFE           ACCOUNT         TILE         00         070         V0         V0         V1D         V1D         000         000         000         000           ACCOUNT         000         00         00         00         000</td>	NET         CALCULTED         ACCUMILATE         NUM         RECOVERED         INFERICUTERED         CALCULATE         NUM         RECOVERED         INFE           ACCOUNT         TILE         00         070         V0         V0         V1D         V1D         000         000         000         000           ACCOUNT         000         00         00         00         000

#### Notes:

(1) Production Plant original cost includes 2021-22 forecasted plant additions totaling \$269,468,143. A corresponding adjustment was made to Production Plant accumulated depreciation that includes an additional two years of depreciation using the expected plant balances at 12/31/2022.

(2) Rockport depreciation rates are calculated using a 2028 retirement date.

(3) The depreciation rate for Distribution Account 370, Meters, was calculated to include AMI Meter deployment set to begin in 2021 along with the expected retirement of the current meters. The depreciation rate that was calculated is based on a 15 year service life of the AMI Meters to be installed.

#### INDIANA MICHIGAN POWER COMPANY ANNUAL DEPRECIATION RATES AND ACCRIALS BY THE REMAINING LIFE METHOD SCHEDULE II - COMPARE DEPRECIATION EXPENSE USING CURRENT AND STUDY RATES BASED ON DEPRECIABLE PLANT IN SERVICE AT DECEMBER 31, 2020 (1)

IN			CURRENT				
			INDIANA				
			APPROVED	ANNUAL	STUDY	STUDY	DIFFERENCE
	ACCOUNT	ORIGINAL COST	RATE	ACCRUAL	RATE	ACCRUAL	(DECREASE)
NO.	TITLE	(2)	(4)	(5)	(6)		(9)
(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)
STEAM	PRODUCTION PLANT						
Rockp	ort						
311.0	Structures & Improvements	103,081,792	6.96%	7,174,493	9.19%	9,470,443	2,295,950
312.0	Boiler Plant Equipment	646,499,630	7.22%	46,677,273	9.90%	63,995,026	17,317,753
314.0	Turbogenerator Units	110,198,824	7.58%	8,353,071	9.82%	10,824,210	2,471,139
315.0	Accessory Electrical Equipment	60,038,956	6.92%	4,154,696	9.10%	5,465,835	1,311,139
316.0	Miscellaneous Power Plant Equipment	17,952,020	7.40%	1,328,449	9.67%	1,736,276	407,827
	Total Rockport	937,771,222	7.22%	67,687,982	9.76%	<u>91,491,790</u>	23,803,808
Total St	eam Production Plant	937,771,222	7.22%	67,687,982	9.76%	<u>91,491,790</u>	23,803,808
	AR PRODUCTION PLANT						
NUCLE	AR PRODUCTION PLANT						
Cook		0.4 80					aac 1
321.0	Structures & Improvements	86,734,372	3.34%	2,896,928	3.60%	3,125,355	228,427
322.0 323.0	Reactor Plant Equipment Turbogenerator Units	782,729,686 312,897,355	4.35% 5.16%	34,048,741 16,145,504	4.87% 5.43%	38,123,223 17,003,166	4,074,482 857,662
323.0	Accessory Electrical Equipment	137,248,173	3.92%	5,380,128	4.35%	5,970,618	590,490
325.0	Miscellaneous Power Plant Equipment	36,218,603	4.55%	1,647,946	4.71%	1,705,971	58,025
		<u></u>		<u></u>			
	Total Cook Unit 1	1,355,828,189	4.43%	60,119,247	4.86%	65,928,332	5,809,085
Cook							
321.0	Structures & Improvements	378,680,285	3.28%	12,420,713	3.61%	13,687,067	1,266,354
322.0	Reactor Plant Equipment	1,053,868,998	3.82%	40,257,796	4.33%	45,620,447	5,362,651
323.0	Turbogenerator Units	425,843,325	4.81%	20,483,064	5.06%	21,530,145	1,047,081
324.0 325.0	Accessory Electrical Equipment Miscellaneous Power Plant Equipment	200,678,427 248,016,731	3.69% 3.86%	7,405,034 9,573,446	4.23% 4.19%	8,493,418 10,386,037	1,088,384 <u>812,591</u>
325.0	wiscenateous rower riant Equipment	248,010,731	3.80%	9,575,440	4.1970	10,380,037	812,391
	Total Cook Unit 2	2,307,087,766	3.91%	90,140,053	4.32%	99,717,114	9,577,061
Total Nu	clear Production Plant	3,662,915,955	4.10%	150,259,300	4.52%	<u>165,645,446</u>	<u>15,386,146</u>
HYDRA	ULIC PRODUCTION PLANT						
Berrie	n Springs						
331.0	Structures & Improvements	696,548	3.12%	21,732	4.12%	28,688	6,956
332.0	Reservoirs, Dams & Waterways	6,320,266	2.34%	147,894	3.52%	222,196	74,302
333.0	Waterwheels, Turbines & Generators	8,386,954	2.82%	236,512	3.88%	325,533	89,021
334.0	Accessory Electrical Equip.	1,417,718	2.59%	36,719	3.75%	53,207	16,488
335.0	Misc. Power Plant Equip.	<u>929,404</u>	3.06%	28,440	4.06%	<u>37,777</u>	<u>9,337</u>
	Total Berrien Springs	17,750,890	2.66%	471,297	3.76%	667,402	196,105
Bucha	nan						
331.0	Structures & Improvements	660,195	3.23%	21,324	4.15%	27,377	6,053
332.0	Reservoirs, Dams & Waterways	5,154,683	2.29%	118,042	3.36%	173,440	55,398
333.0	Waterwheels, Turbines & Generators	1,414,445	2.19%	30,976	3.30%	46,670	15,694
334.0	Accessory Electrical Equip.	1,108,771	2.47%	27,387	3.54%	39,231	11,844
335.0	Misc. Power Plant Equip.	311,833	3.22%	10,041	4.15%	12,926	2,885
	Total Buchanan	8,649,927	2.40%	<u>207,770</u>	3.46%	299,643	91,873

#### INDIANA MICHIGAN POWER COMPANY ANNUAL DEPRECIATION RATES AND ACCRUALS BY THE REMAINING LIFE METHOD SCHEDULE II - COMPARE DEPRECIATION EXPENSE USING CURRENT AND STUDY RATES BASED ON DEPRECIABLE PLANT IN SERVICE AT DECEMBER 31, 2020 (1)

IN			CURRENT				
			INDIANA				
		ODICIDIAL COST	APPROVED	ANNUAL	STUDY	STUDY	DIFFER
	ACCOUNT	ORIGINAL COST	RATE	ACCRUAL	RATE	ACCRUAL	(DECRE
NO.	TITLE		(1)	(7)	(0)		(0)
(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)
Elkhar	r <u>t</u>						
331.0	Structures & Improvements	1,632,902	3.14%	51,273	6.00%	97,918	
332.0	Reservoirs, Dams & Waterways	11,027,557	3.64%	401,403	6.49%	715,350	3
333.0	Waterwheels, Turbines & Generators	875,459	2.40%	21,011	5.24%	45,896	
334.0	Accessory Electrical Equip.	766,670	2.37%	18,170	5.36%	41,108	
335.0	Misc. Power Plant Equip.	342,337	4.48%	15,337	7.30%	24,999	
	Total Elkhart	14,644,925	3.46%	507,194	6.32%	925,270	4
<u>Twin I</u>	Branch						
331.0	Structures & Improvements	1,428,784	2.89%	41,292	4.66%	66,648	
332.0	Reservoirs, Dams & Waterways	8,416,861	2.31%	194,429	3.99%	335,807	1
333.0	Waterwheels, Turbines & Generators	9,909,128	2.59%	256,646	4.27%	423,349	1
334.0	Accessory Electrical Equip.	2,876,083	2.44%	70,176	4.21%	121,131	
335.0	Misc. Power Plant Equip.	1,005,606	3.46%	34,794	5.03%	50,606	
	Total Twin Branch	23,636,462	2.53%	597,337	4.22%	997,541	4
Consta	antine						
331.0	Structures & Improvements	470,900	2.36%	11,113	2.54%	11,958	
332.0	Reservoirs, Dams & Waterways	1,653,789	2.26%	37,376	2.44%	40,330	
333.0	Waterwheels, Turbines & Generators	993,032	2.20%	21,847	2.40%	23,832	
334.0	Accessory Electrical Equip.	671,796	2.82%	18,945	3.05%	20,511	
335.0	Misc. Power Plant Equip.	475,641	2.99%	14,222	3.08%	14,650	
	Total Constantine	4,265,158	2.43%	103,503	2.61%	<u>111,281</u>	
Mottvi	ille						
331.0	Structures & Improvements	797,060	3.38%	26,941	4.64%	37,012	
332.0	Reservoirs, Dams & Waterways	2,312,828	2.72%	62,909	4.08%	94,320	
333.0	Waterwheels, Turbines & Generators	639,576	2.45%	15,670	3.87%	24,747	
334.0	Accessory Electrical Equip.	772,571	3.21%	24,800	4.56%	35,218	
335.0	Misc. Power Plant Equip.	409,136	4.32%	17,675	5.45%	22,293	
336.0	Roads, Railroads & Bridges	<u>902</u>	1.62%	<u>15</u>	3.15%	<u>28</u>	
	Total Mottville	4,932,073	3.00%	148,010	4.33%	213,618	!
Crew S	Service Center						
331.0	Structures & Improvements	417,303	1.24%	5,175	1.64%	6,829	
335.0	Misc. Power Plant Equip.	126,865	1.22%	<u>1,548</u>	1.62%	2,059	
	Total Crew Service Center	544,168	1.24%	6,723	1.63%	8,888	

#### INDIANA MICHIGAN POWER COMPANY ANNUAL DEPRECIATION RATES AND ACCRIALS BY THE REMAINING LIFE METHOD SCHEDULE II - COMPARE DEPRECIATION EXPENSE USING CURRENT AND STUDY RATES BASED ON DEPRECIABLE PLANT IN SERVICE AT DECEMBER 31, 2020 (1)

IN							
114			CURRENT				
			INDIANA				
			APPROVED	ANNUAL	STUDY	STUDY	DIFFERENCE
	ACCOUNT	ORIGINAL COST	RATE	ACCRUAL	RATE	ACCRUAL	(DECREASE)
NO.	TITLE						
(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)
OTHER	PRODUCTION PLANT						
Deer (	Creek Solar Facility						
344.0	Generators	5,668,204	5.29%	299,848	5.38%	304,821	4,973
345.0	Accessory Electric Equip.	720,502	5.35%	38,547	6.57%	47,342	8,795
346.0	Misc. Power Plant Equip.	10,893	6.12%	<u>667</u>	7.11%	<u>775</u>	<u>108</u>
	Total Deer Creek Solar Facility	<u>6,399,599</u>	5.30%	339,062	5.51%	352,938	13,876
Olive	Solar Facility						
341.0	Structures & Improvements	376,687	5.31%	20,002	5.33%	20,088	86
344.0	Generators	11,184,837	5.31%	593,915	5.33%	596,459	2,544
345.0	Accessory Electric Equip.	269,062	5.31%	14,287	5.33%	14,348	61
346.0	Misc. Power Plant Equip.	215,250	5.31%	11,430	5.33%	11,479	49
	Total Olive Solar Facility	12,045,836	5.31%	639,634	5.33%	642,374	<u>2,740</u>
	Branch Solar Facility						
344.0	Generators	<u>6,955,324</u>	5.31%	369,328	5.38%	374,511	<u>5,183</u>
Water	vliet Facility						
341.0	Structures & Improvements	358,237	5.25%	18,807	5.33%	19,104	297
344.0	Generators	11,107,366	5.25%	583,137	5.33%	592,328	9,191
346.0	Misc. Power Plant Equip.	343,931	5.26%	18,091	5.34%	18,358	267
	Total Watervliet Facility	11,809,534	5.25%	620,035	5.33%	629,789	9,754
Total Ot	ther Production Plant	37,210,293	5.29%	<u>1,968,059</u>	5.37%	<u>1,999,612</u>	31,553
Total Pr	oduction Plant	4,712,321,073	4.71%	221,957,175	5.57%	262,360,492	40,403,317
TRANS	MISSION PLANT						
350.1	Land Rights	62,292,873	1.66%	1,034,062	1.76%	1,094,690	60,628
352.0	Structures & Improvements	52,265,232	1.77%	925,095	1.76%	917,627	(7,468)
353.0	Station Equipment	826,489,176	2.43%	20,083,687	2.68%	22,167,670	2,083,983
354.0	Towers & Fixtures	230,452,983	2.57%	5,922,642	2.85%	6,559,865	637,223
355.0	Poles & Fixtures	208,136,265	3.19%	6,639,547	3.40%	7,070,149	430,602
356.0	OH Conductor & Devices	294,558,395	2.35%	6,922,122	2.34%	6,880,786	(41,336)
357.0	Underground Conduit	2,241,687	2.30%	51,559	2.25%	50,369	(1,190)
358.0	Underground Conductor	4,522,363	1.93%	87,282	2.06%	93,289	6,007
359.0	Roads and Trails	<u>91,159</u>	1.61%	<u>1,468</u>	1.68%	<u>1,535</u>	<u>67</u>
Total Tr	ansmission Plant	<u>1,681,050,133</u>	2.48%	41,667,464	2.67%	44,835,980	3,168,516

## INDIANA MICHIGAN POWER COMPANY ANNUAL DEPRECIATION RATES AND ACCRUALS BY THE REMAINING LIFE METHOD SCHEDULE II - COMPARE DEPRECIATION EXPENSE USING CURRENT AND STUDY RATES BASED ON DEPRECIABLE PLANT IN SERVICE AT DECEMBER 31, 2020 (1)

IN							
			CURRENT				
			INDIANA				
		ORIGINAL COST	APPROVED RATE	ANNUAL ACCRUAL	STUDY RATE	STUDY ACCRUAL	DIFFERENCE (DECREASE)
NO	ACCOUNT TITLE	ORIGINAL COST	KAIL	ACCRUAL	KAIE	ACCRUAL	(DECKEASE)
NO. (1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)
(1)	(2)	(3)	(4)	(3)	(0)	())	(8)
DISTRI	BUTION PLANT - IN						
360.1	Land Rights	10,926,039	1.42%	155,150	1.44%	157,646	2,496
361.0	Structures & Improvements	32,691,043	1.42%	513,249	1.96%	641,289	128,040
362.0	Station Equipment	379,401,090	2.17%	8,233,004	2.56%	9,718,860	1,485,856
363.0	Storage Battery Equipment	5,606,730	8.33%	467,041	9.09%	509,494	42,453
364.0	Poles, Towers, & Fixtures	252,111,755	4.95%	12,479,532	4.28%	10,782,708	(1,696,824)
365.0	Overhead Conductor & Devices	399,931,378	3.11%	12,437,866	2.86%	11,429,020	(1,008,846)
366.0	Underground Conduit	144,882,340	1.79%	2,593,394	1.66%	2,401,933	(191,461)
367.0	Underground Conductor	255,708,978	1.94%	4,960,754	1.96%	5,008,409	47,655
368.0	Line Transformers	318,204,324	4.92%	15,655,653	3.42%	10,885,354	(4,770,299)
369.0	Services	166,556,147	2.97%	4,946,718	2.65%	4,412,730	(533,988)
370.0	Meters (3)	76,493,447	9.27%	7,090,943	10.08%	7,710,539	619,596
371.0	Installations on Custs. Prem.	20,434,795	6.99%	1,428,392	4.90%	1,000,455	(427,937)
373.0	Street Lighting & Signal Sys.	18,113,668	5.05%	914,740	3.75%	679,987	(234,753)
575.0	Succe Eighting & Signal Sys.	10,115,000	5.0570	<u>714,740</u>	5.1570	017,781	(234(133)
Total Di	stribution Plant - IN	2,081,061,734	3.45%	71,876,436	3.14%	65,338,424	(6,538,012)
DISTRI	BUTION PLANT - MI						
360.1	Land Rights	6,056,743	1.42%	86,006	1.44%	87,389	1,383
361.0	Structures & Improvements	4,510,462	1.57%	70,814	1.96%	88,480	17,666
362.0	Station Equipment	96,403,578	2.17%	2,091,958	2.56%	2,469,505	377,547
363.0	Storage Battery Equipment	0	8.33%	0	9.09%	0	0
364.0	Poles, Towers, & Fixtures	80,503,822	4.95%	3,984,939	4.28%	3,443,113	(541,826)
365.0	Overhead Conductor & Devices	139,323,640	3.11%	4,332,965	2.86%	3,981,515	(351,450)
366.0	Underground Conduit	12,573,950	1.79%	225,074	1.66%	208,457	(16,617)
367.0	Underground Conductor	37,852,912	1.94%	734,346	1.96%	741,401	7,055
368.0	Line Transformers	52,380,639	4.92%	2,577,127	3.42%	1,791,873	(785,254)
369.0	Services	33,052,679	2.97%	981,665	2.65%	875,696	(105,969)
370.0	Meters	22,239,359	9.27%	2,061,589	10.08%	2,241,727	180,138
371.0	Installations on Custs. Prem.	8,344,653	6.99%	583,291	4.90%	408,541	(174,750)
373.0	Street Lighting & Signal Sys.	5,882,009	5.05%	297,041	3.75%	220,811	(76,230)
Total Di	stribution Plant - MI	499,124,446	3.61%	<u>18,026,815</u>	3.32%	16,558,508	(1,468,307)
Total Di	stribution Plant	2,580,186,180	3.48%	<u>89,903,251</u>	3.17%	81,896,932	(8,006,319)
GENER	AL PLANT						
390.0	Structures & Improvements	61,646,560	2.08%	1,282,248	2.54%	1,566,820	284,572
391.0	Office Furniture & Equipment	5,869,860	4.79%	281,166	5.47%	321,177	40,011
393.0	Stores Equipment	996,539	7.35%	73,246	8.08%	80,488	7,242
394.0	Tools Shop & Garage Equipment	16,780,302	6.99%	1,172,943	7.86%	1,318,642	145,699
395.0	Laboratory Equipment	240,988	5.41%	13,037	6.44%	15,517	2,480
396.0	Power Operated Equipment	543,715	4.81%	26,153	6.45%	35,068	8,915
397.0	Communication Equipment	66,159,303	3.91%	2,586,829	4.21%	2,784,040	197,211
398.0	Miscellaneous Equipment	10,826,054	3.32%	359,425	3.74%	405,387	45,962
Total Ge	eneral Plant	<u>163.063.321</u>	3.55%	<u>5.795.047</u>	4.00%	6.527,140	732,093
	Total Depreciable Plant	<u>9,136,620,707</u>	3.93%	359,322,937	4.33%	<u>395,620,544</u>	36,297,607

Notes:

 (1) Production Plant original cost includes 2021-22 forecasted plant additions totaling \$269,468,143. A corresponding adjustment was made to Production Plant accumulated depreciation that includes an additional two years of depreciation using the expected plant balances at 12/31/2022.
 (2) Rockport depreciation rates are calculated using a 2028 retirement date.
 (3) The depreciation rate for Distribution Account 370, Meters, was calculated to include AMI Meter deployment set to begin in 2021 along with the expected retirement of the current meters. The depreciation rate that was calculated is based on a 15 year service life of the AMI Meters to be installed.

## INDIANA MICHIGAN POWER COMPANY SCHEDULE III - COMPARISON OF MORTALITY CHARACTERISTICS DEPRECIATION STUDY AS OF DECEMBER 31, 2020

	(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)	(10)	(11)
	Existing Rates						Study Ra	ates			
		Average		U	Cost of	Net	Average		,	Cost of	Net
		Service	Iowa	Salvage	Removal	Salvage	-		Salvage	Removal	Salvage
		Life	Curve	Factor	Factor	Factor	Life	Curve	Factor	Factor	Factor
		(Years)					(Years)				
TRANS	SMISSION PLANT										
350.1	Rights of Way	65	R5.0	0%	0%	0%	65	R5.0	0%	0%	0%
352.0	Structures & Improvements	70	L2.0	0%	18%	-18%	65	L1.5	0%	10%	-10%
353.0	Station Equipment	45	L1.0	16%	21%	-5%	44	L1.0	15%	25%	-10%
354.0	Towers & Fixtures	64	R5.0	4%	41%	-37%	66	R5.0	2%	41%	-39%
355.0	Poles & Fixtures	51	L0.5	5%	64%	-59%	50	L0.5	3%	67%	-64%
356.0	OH Cond. & Devices	66	R4.0	13%	53%	-40%	67	R4.0	8%	43%	-35%
357.0	Underground Conduit	50	L5.0	0%	0%	0%	55	R5.0	0%	0%	0%
358.0	Underground Conductor and Devices	65	L2.5	1%	19%	-18%	60	L1.5	0%	13%	-13%
359.0	Roads and Trails	65	R5.0	0%	0%	0%	65	R5.0	0%	0%	0%
DISTR	IBUTION PLANT										
360.1	Rights of Way	65	R5.0	0%	0%	0%	65	R5.0	0%	0%	0%
361.0	Structures & Improvements	71	R2.0	2%	14%	-12%	65	R1.5	1%	26%	-25%
362.0	Station Equipment	49	L0.0	13%	19%	-6%	46	L0.5	10%	22%	-12%
363.0	Storage Battery Equipment	15	SQ	0%	0%	0%	15	SQ	0%	0%	0%
364.0	Poles, Towers, & Fixtures	35	L0.0	19%	100%	-81%	41	L0.0	17%	104%	-87%
365.0	Overhead Conductor & Devices	35	L0.0	20%	33%	-13%	39	L0.0	18%	34%	-16%
366.0	Underground Conduit	56	R2.0	0%	0%	0%	60	R2.0	0%	0%	0%
367.0	Underground Conductor	52	R1.0	0%	0%	0%	54	R2.0	0%	0%	0%
368.0	Line Transformers	21	R0.5	18%	24%	-6%	27	R0.5	16%	24%	-8%
369.0	Services	40	R0.5	4%	26%	-22%	44	R0.5	4%	28%	-24%
370.0	Meters	15	SQ	10%	32%	-22%	15	SQ	9%	29%	-20%
371.0	Installations on Custs. Prem.	14	L0.0	3%	26%	-23%	17	L0.0	3%	26%	-23%
373.0	Street Lighting & Signal Sys.	19	R0.5	8%	22%	-14%	22	R0.5	6%	24%	-18%
<u>GENEI</u>	RAL PLANT										
390.0	Structures & Improvements	51	L0.5	11%	13%	-2%	45	L1.0	6%	11%	-5%
391.0	Office Furniture & Equipment	22	SQ	7%	3%	4%	22	SQ	6%	3%	3%
393.0	Stores Equipment	14	SQ	0%	0%	0%	14	SQ	0%	0%	0%
394.0	Tools Shop & Garage Equipment	16	SQ	1%	1%	0%	16	SQ	1%	1%	0%
395.0	Laboratory Equipment	20	SQ	2%	1%	1%	20	SQ	2%	1%	1%
396.0	Power Operated Equipment	25	SQ	2%	2%	0%	25	SQ	2%	2%	0%
397.0	Communication Equipment	27	SQ	6%	6%	0%	27	SQ	6%	7%	-1%
398.0	Miscellaneous Equipment	30	SQ	25%	17%	8%	30	SQ	25%	17%	8%

Plant	Capacity (MW)	Fuel	Year Installed	Estimated Year Retired	Life Span (Years)
Steam Production Plant					
<i>Rockport</i> Unit 1 Unit 2 - leased unit (a)	1,300 1,300	Coal Coal	1984 1989	2028 2028	44 39
Nuclear Production Plant					
Cook Unit 1 Unit 2	1,020 1,090	Nuclear Nuclear	1975 1978	2034 2037	59 59
Hydraulic Production Plant (b)					
Berrien Springs	7.2	Hydro	1908	2036	128
Buchanan	4.1	Hydro	1919	2036	117
Constantine	1.2	Hydro	1921	2053	132
Elkhart	3.4	Hydro	1913	2030	117
Mottville	1.7	Hydro	1923	2033	110
Twin Branch	4.8	Hydro	1904	2036	132
Other Production Plant					
Deer Creek Solar Facility	2.5	Solar	2015	2035	20
Olive Solar Facility	5.0	Solar	2016	2036	20
Twin Branch Solar Facility	2.6	Solar	2016	2036	20
Watervliet Solar Facility	4.6	Solar	2016	2036	20

#### INDIANA MICHIGAN POWER COMPANY SCHEDULE IV - ESTIMATED GENERATION PLANT RETIREMENT DATES DEPRECIATION STUDY AS OF DECEMBER 31, 2020

#### NOTES:

(a) Although the Rockport Unit 2 lease is set to expire at the end of 2022, the life span for the associated owned equipment at Rockport Unit 2 is based on a 2028 retirement date.

(b) The estimated retirement year for the Company's Hydraulic Production Plants assumes that the plants will be retired at their end of their current FERC license year except for Constantine Plant where the Company is in the process of filing for a 30 year license extension. Berrien Springs is not FERC licensed and the Berrien Springs retirement year was assumed to be the same year as Buchanan and Twin Branch Plants which is 2036.

Indiana Michigan Power Company Attachment JAC-2 Witness: Cash Page 1 of 13

# **Brandenburg**.



# **Rockport Power Plant**

Rockport, IN September 27, 2018

**Conceptual Dismantlement Cost** 

## American Electric Power Company Rockport Plant ROCKPORT, IN

## **Dismantling Information**

September 27, 2018

## ROCKPORT AEP POWER PLANT CONCEPTUAL DEMOLITION PLAN

#### **DEFINITIONS:**

#### **Concrete Debris**

Concrete stacks, cooling towers, turbine pedestals, and elevated floor slabs (estimated 66,200 cubic yards)

#### **Construction / Demolition Debris**

Any solid waste resulting from the construction, remodeling, repair, or demolition of structures. Such wastes may include, but not limited to;

roof material/drywall/ceiling tiles/fiberglass (estimated 16,342 yards)

#### Contractor

The individual, partnership or corporation with which AEP Company enters into a contract to perform all of the work described in the Specification.

#### Contract

A purchase order placed by Purchaser and accepted by Contractor, together with this Specification and all other documents referred to in such purchase order, or a formal contract executed by Purchaser and Contractor, together with this Specification and all other documents referred to in such formal contract.

#### Engineer

The Engineer or his authorized representative designated by AEP Company to be assigned to this contract.

## **Fill Material**

Material to be used to bring area to grade.

#### Greases

Any used or unused greases or waste containing grease.

## **Hazardous Waste**

Hazardous waste as defined in 40 CFR 261.3 or as defined in any applicable state regulation.

## HAZMATs

Any hazardous, toxic or regulated substance controlled under RCRA, CERCLA or any other Federal, State, or Local law, statute, regulation or ordinance pertaining to the handling, transportation, or disposal of any controlled substance.

#### SDS

Safety Data Sheet.

## Non-Ferrous Scrap (estimated 1,836,829 lbs)

All non-ferrous scrap such as copper or brass

## Oils (estimated 15,000 gallons)

Any used or unused hydraulic, lubrication, rolling, waste or other such oil or oily waste.

## OSHA

Occupational Safety and Health Act and amendments thereto.

## PCBs

Polychlorinated By-phenols (plant personnel verified that there are no PCB's present at the site).

## **Process Materials**

Any raw materials, blended raw materials, recyclable process generated dusts (such as flue dust), fly ash, ash slurry and etc.

## SCR Unit

Selective Catalytic Reduction Unit

## Scrap Ferrous (estimated 132,374 tons)

All ferrous scrap designated by the Engineer to be suitable for melting at a steel processing plant.

## **Structural Removal**

As in the Specification, shall mean all work of every nature described herein, implied herein, or necessary to complete the work described or implied herein, with the exception of Asbestos Abatement.

## **AEP Company**

American Electric Power Company

## American Electric Power Company Rockport Plant ROCKPORT, IN

## Information Sheets

## **Dismantling Information**

September 27, 2018

## **ROCKPORT PLANT**

## 1. GENERAL SCOPE OF WORK

- 1.1. The work to be performed under the terms of this specification shall consist of the dismantling and removal of all facilities, machinery, equipment, all associated structures, foundations, debris, asbestos containing materials, hazardous substances and hazardous waste as directed by the Engineer. Upon completion each dismantling site shall be left in a neat, clean, safe condition.
- 1.2. Work under this specification shall be performed in accordance with the terms and conditions of the Contract, entered into between AEP Company and the Contractor, and in accordance with all EPA, OSHA, Federal, State, County, and Local laws, statutes, ordinances, and regulations.
- 1.3. The Contractor shall perform all utility disconnection and/or relocation work which is necessary to complete the proposed dismantling and removal work, without disrupting active utilities.
- 1.4. The Contractor shall perform all excavation, back-filling, construction and closure work which is necessary to complete the proposed dismantling work.
- 1.5. The Contractor shall provide all labor, materials, equipment, services and pay all necessary taxes, in addition to securing all required permits, to perform the dismantling.
- 1.6. The Contractor is responsible to clean up and dispose of any and all materials which are generated as a result of a spill caused by the Contractor, or which are generated as a result of the improper handling of any materials by the Contractor. This includes all RACM, Hazardous Substances, Hazardous Waste, Special wastes, Non-process Debris, Demolition Debris, and combustible materials.
- 1.7. The switchyard(s) shall remain intact following the razing efforts.
- 2. FACILITY DISMANTLEMENT AND RELATED WORK
  - 2.1. Perform the environment abatement of the following:
    - 2.1.1. Vacuum, transport and dispose of dust accumulations inside area of Unit 1 and 2 Boiler
    - 2.1.2. HAZMAT sweep of structures, tanks and pipe in Unit 1 and 2 Boiler area
    - 2.1.3. Remove Units 1 and 2 fluorescent light bulbs, PCB ballast, mercury vapor light, HID vapor lights and mercury containing instruments.

- 2.1.4. Remove office, storage and maintenance building fluorescent light bulbs, PCB ballast, mercury vapor light, HID vapor lights and mercury containing instruments.
- 2.2. Perform the building dismantling, equipment removal, concrete removal to surrounding grade elevation of the following.
  - 2.2.1. Unit 1 boiler building, turbine generator building, precipitators, SCR unit, office and maintenance building, coal conveyor.
  - 2.2.2. Unit 2 boiler building, turbine generator building, precipitators, office and maintenance building, coal conveyor.
  - 2.2.3. Concrete stack for Unit 1 and 2
  - 2.2.4. Unit 1 water-cooling tower structure, adjacent pump structures, adjacent condensate water tank to surround grade elevation. Fill the pits and trenches to surround grade elevation.
  - 2.2.5. Unit 2 water-cooling tower structure, adjacent pump structures, adjacent condensate water tank to surround grade elevation. Fill the pits and trenches to surround grade elevation.
  - 2.2.6. The ammonia storage building and chemical manufacturing building structure and ammonia storage tank structures.
  - 2.2.7. The multiple single story maintenance, storage and office buildings located throughout the site.
  - 2.2.8. The condensate storage tanks
  - 2.2.9. Pre-Treatment Building
  - 2.2.10. Service Building
  - 2.2.11. Fly Ash Silos
  - 2.2.12. The coal barge unloading station(s), the coal crusher house, car dumper building, coal conveyors, and coal transfer stations.
  - 2.2.13. Brandenburg shall remove the existing site asphalt and concrete parking lots, roadways, and sidewalks.
  - 2.2.14. The concrete dock river cells shall have the sheet piling, and the concrete cap removed.
  - 2.2.15. The Clearwater Pond filled in with existing berm material and crushed concrete from the demolition efforts.

## 3. WORK BY CONTRACTOR

The Contractor Shall:

- 3.1. Furnish all supervision, labor, materials, tools, supplies and equipment necessary to perform the work, including dismantling and removal of all the facilities, equipment, structures, etc. noted herein with the exception of specific structures which are designated in this Specification to remain.
- 3.2. Furnish on the site, during the performance of the work, an experienced supervisor who shall be duly authorized to represent and act for the Contractor in all matters pertaining to the work covered by this Specification.
- 3.3. Provide all written instructions, orders, and other communications delivered to the Contractor's construction office shall be considered as having been delivered to the Contractor himself.
- 3.4. Develop detailed written demolition plans for each area to be dismantled, and submit them to the Engineer for his review prior to the start of work in an area. Such plans shall include, but limited to:

- 3.4.1. A detailed and complete schedule for the performance of the work.
- 3.4.2. A survey of each area, identifying all materials to be disposed of other than scrap and equipment.
- 3.4.3. Identification and protection of demolition areas.
- 3.4.4. Termination and/or relocation of utilities.
- 3.4.5. Handling and disposal of hazardous wastes and materials.
- 3.4.6. Handling and disposal of oils and greases.
- 3.4.7. Handling and disposal of non-hazardous debris and materials.
- 3.4.8. Fire prevention and protection.
- 3.4.9. Handling and storage locations for ferrous and non-ferrous scrap.
- 3.4.10. Method of demolition and/or equipment removal.
- 3.4.11. Clean-out, breaking open, and filling of basements, pits, and tunnels.
- 3.4.12. Final grading and restoration of demolition site.
- 3.5. Clear each site of existing equipment, structures, and material designated to be removed. Each site will be left in a neat, clean, safe condition in conformity with all applicable Federal, State, or Local laws, statutes and/or regulations, including but not limited to CAA, OSHA, RCRA, SARA, TSCA, and/or CERCLA. The finished condition of each site will be approved by the Engineer.
- 3.6. Remove all structures down to final grade except where otherwise noted. Final grade will generally be the adjacent grade surrounding the facility to be removed. The removal of concrete & debris and grading will be done concurrent with the demolition work. As one area is cleared of structures, the required concrete removal work in that area will be done simultaneously with the demolition of structures in the next area of work. If the Contractor breaches the provisions of this section AEP Company reserves the right, in AEP Company's sole opinion, to stop the Contractor from doing further demolition until the concrete and debris removal is current.
- 3.7. Perform all material removal work in accordance with all applicable Federal, State, and/or Local rules, regulations and/or ordinances, which is necessary to complete the proposed removal work.
- 3.8. Perform all utility, telecommunications and telemetering disconnection and/or relocation work which is necessary to complete the proposed removal work.
- 3.9. Prior to beginning demolition of any facility, Contractor shall ascertain that no live utilities remain in the facility and identify and locate all underground utilities. It shall be the Contractor's exclusive responsibility to determine that all utility systems in each area remain isolated from active utility systems.
- 3.10. Perform all excavation, back–filling, construction and closure work which is necessary to complete the proposed dismantling and removal work.
- 3.11. Remove all debris generated as a result of the proposed removal work.
- 3.12. Break the floors of all pits, trenches and depressions sufficiently to provide drainage and to prevent the accumulation of water within the underground structure.
- 3.13. Tunnel and basement roof structures which do not support structures designated to remain and which are located less than 3 feet below finish grade elevation will be broken in. Said tunnel excavations will be filled with fill materials approved by the Site Engineer up to finish grade elevation.
- 3.14. Properly drain and capture all contents of pipelines prior to dismantling any pipelines.
- 3.15. Empty and shovel clean all pits, sumps, basements, and depressions to the satisfaction of the Engineer.

Areas will be inspected by the Site Engineer prior to filling. Any pits, sumps, basements or depressions in contact with a hazardous waste or PCB shall be decontaminated in accordance with any applicable Federal and/or State rules and/or regulations.

- 3.16. Back-fill all pits, sumps, and depressions up to existing grade. Each site shall be rough graded and left in a neat, clean, safe condition. Contractor will use fill material approved by the Engineer. The final six inches of fill shall be other select fill material approved by the Engineer.
- 3.17. Furnish all fill material in accordance with the Specification. If the work activity generates more fill material than needed, the Contractor shall pay for the transportation and disposal off site. If the work activity is fill negative, the Contractor shall pay for the purchase and transportation of required fill to the site. Such purchased material shall be approved by the Site Engineer.
- 3.18. Furnish portable sanitary facilities and drinking water for Contractor's personnel in areas of removal.
- 3.19. Furnish electric power and temporary lighting in those areas of removal where active utilities are not available.
- 3.20. Provide adequate protective barriers for open pits, holes and depressions, as a result of the equipment removal work, until they are properly backfilled. Temporary barricades shall conform to all applicable Federal, State and Local, rules and regulations or standards including, but not limited to OSHA.
- 3.21. Remove above ground utility support systems such as poles, structural steel towers or guy wires which have been designated to be removed by the Engineer.
- 3.22. Remove and scrap all tanks, including supporting steel and concrete structures. Prior to removal work Contractor shall remove the contents of each tank, drain each tank and otherwise purge each tank in accordance with all applicable rules or regulations to render them safe for removal. Notify Engineer of any potentially contaminated soils. Remove of these tanks shall conform to all applicable Federal, State, and Local laws, statutes, regulations or ordinances.
- 3.23. Secure the approval of local Fire Department for the Fire Prevention Plan. Contractor shall meet with representatives of the Fire Department prior to commencement of work on each facility. Prior to the commencement of removal work, Contractor shall inspect all fire hydrants in the work area and shall notify the Engineer of those that are not in good operating condition.
- 3.24. Provide fire extinguishers and fire hoses as required to immediately control any fires resulting from the work. Implement all fire prevention measures as directed by the Fire Department. Measures required by Fire Department may include, but will not be limited to, the maintenance of pressurized fire hoses at each removal site.
- 3.25. Attend a safety meeting with AEP Company's representatives prior to starting work in each facility or designed area.
- 3.26. Furnish all temporary or permanent supports or protective devices which are necessary to preserve active pipes, electrical lines or other structures which AEP Company designates to remain in place.
- 3.27. Abide by AEP Company Contractor Safety Responsibilities, AEP Company Energy Control-Lockout and Tryout Rules, as well as all Federal, State, and Local regulations.
- 3.28. Secure the Engineer's approval prior to using any railroad track or mobile crane movements to or from the dismantling site.
- 3.29. Schedule rail movements, order all railroad cars and be solely responsible for demurrage charges resulting from the Contractor's operations.
- 3.30. Where Contractor removes railroad track, the Contractor shall remove all wooden and concrete ties, and load and transport them to an approved disposal site approved by the Engineer. Contractor shall be responsible for

the cost of all removal, loading, transportation, and disposal of such material.

- 3.31. Subsequent to the removal efforts, Brandenburg shall place six (6) inches of topsoil and hydro seed the work area.
- 3.32. HAZARDOUS WASTE HANDLING AND DISPOSAL
  - 3.32.1. Contractor shall provide all supervision, labor, consumable materials, tools, equipment, documentation, services and permits required to identify, remove and load any hazardous waste located in, adjacent to or forming a part of the equipment designated for removal. Contractor shall be responsible to perform all in-plant handling of such materials, including, but not limited to removal, loading, and in-plant transportation. Hazardous waste removal work shall include, but is not necessarily limited to, the work described herein.
  - 3.32.2. Contractor is required to secure samples of all materials, which are suspected of being a hazardous waste, located in the areas defined in this Specification. Samples shall be collected in accordance with all applicable regulations. Contractor shall deliver all samples of suspected hazardous waste to the Engineer. AEP Company shall secure required analyses of all such samples.
  - 3.32.3. Prepare a complete written hazardous waste removal plan for each work site that will be submitted to the Engineer for his review prior to the start of work in an area.
  - 3.32.4. Contractor shall provide all respirators, protective clothing and equipment required to protect all personnel associated with the handling or removal of any Hazardous Wastes. All said respirators, protective clothing and equipment shall conform to all applicable rules, regulations and standards, including but not limited to OSHA.
  - 3.32.5. Employ only competent persons, trained, knowledgeable and qualified in the techniques of handling and disposal of hazardous wastes and subsequent cleaning of contaminated areas. Employees who perform hazardous waste removal work shall possess current, valid licenses as required by any government agency having jurisdiction over the work. Perform all hazardous waste removal in strict accordance with all applicable Federal, State and Local laws, statutes, ordinances and regulations. Contractor shall provide timely and accurate notification in accordance with all Federal, State and Local laws, statutes, regulations and ordinances.
  - 3.32.6. Contractor shall post all appropriate warning signs at each work area, as is required by applicable regulations.
  - 3.32.7. Maintain complete and accurate records of all removal activities in accordance with all Federal, State, and Local laws, statutes, regulations and ordinances. Contractor shall submit copies of all such records to AEP Company on a weekly basis.
  - 3.32.8. Perform personal monitoring as necessary to assure the safety of all persons associated with the removal of hazardous wastes and as required by Federal, State, and Local laws, statutes, regulations and ordinances. If so required, Contractor shall perform environmental air monitoring in the area of each location where hazardous waste removal work is performed. Environmental air monitoring shall comply with applicable Federal, State, and Local laws, statutes, regulations and ordinances.
  - 3.32.9. AEP Company shall be responsible for disposal, the method of disposal and the disposal site for all identified hazardous waste except asbestos waste. Contractor shall load all such wastes into trucks or containers provided by AEP Company.
- 3.33. CONSTRUCTION / DEMOLITION WASTE

- 3.33.1. Contractor is required to perform the work described herein in a manner that will separate <sup>9</sup> of <sup>13</sup> construction / demolition waste from ferrous scrap, combustible waste, non-ferrous scrap, ferrous scrap, process demolition waste, oils and greases, hazardous wastes, and all other materials.
- 3.33.2. Contractor shall identify all quantities of construction / demolition waste to the Engineer. The Engineer shall positively identify all such materials as being construction / demolition waste.
- 3.33.3. For all materials which have been positively identified by the Engineer as construction / demolition waste, Contractor shall use such materials as clean fill in locations approved for filling by the Engineer.
- 3.33.4. Contractor shall be responsible to perform all in-plant handling of such materials, including, but not limited to, screening, separation, from other materials, loading, crushing and transportation.
- 3.33.5. Contractor shall be responsible for any costs that are incurred as a result of his handling construction / demolition waste, including, but not limited to, sampling, analysis, permit applications, loading, on and off-site transportation, and disposal at an approved disposal site.

## 3.34. OILS

- 3.34.1. Contractor is required to secure samples of all oils and oily wastes located in the areas defined in this Specification. Samples shall be collected in accordance with all applicable regulations.
- 3.34.2. AEP Company shall secure analyses required by the applicable regulations, or by the disposal facility, of all such samples, including, but not limited to, analysis for PCB contamination.
- 3.34.3. For all oils which have been positively identified as being free of PCB contamination (i.e. less than 50 ppm), Contractor shall be responsible to perform all handling of such materials, including, but not limited to, removal, clean up, loading and transportation.
- 3.34.4. Contractor shall be responsible to pay for fees to dispose of all oils and oily waste in accordance with all applicable regulations. The Engineer shall approve all methods of disposal and disposal sites for all oils and oily waste.

### 3.35. GREASES

- 3.35.1. Contractor is required to secure samples of all greases and wastes containing grease located in the areas defined in this Specification. Samples shall be collected in accordance with all applicable regulations.
- 3.35.2. AEP Company shall secure analyses required by the applicable regulations, or by the disposal facility, of all such samples.
- 3.35.3. Contractor shall be responsible to perform all handling of such materials, including, but not limited to, removal, clean up, loading, and transportation.
- 3.35.4. AEP Company shall be responsible for the disposal of all special and hazardous greases and waste containing greases in accordance with all applicable regulations.

### 3.36. PROCESS MATERIALS

- 3.36.1. Contractor is required to perform the work described herein in a manner that will separate process demolition debris from ferrous scrap, combustible debris, non-ferrous scrap, construction / demolition waste, oils and greases, hazardous wastes, and all other materials.
- 3.36.2. Prior to the start of demolition in an area, Contractor shall identify all quantities of process materials to the Engineer. The Engineer shall positively identify all such materials as being process materials.

## 3.37. PCBs AND EQUIPMENT CONTAINING PCBs

- 3.37.1. Prior to dismantling, Contractor shall conduct a survey of each dismantling area to locate and identify any electrical or hydraulic equipment which has not been clearly identified as being free of PCB contamination and, therefore, may contain PCBs. Contractor shall provide the Engineer with the location and description of any surveyed equipment which may contain PCBs. Where so directed by AEP Company, Contractor shall provide AEP Company with a sample of the oil contained in the piece of equipment. AEP Company will secure analysis and provide Contractor with the written results.
- 3.37.2. Prior to dismantling the facility, the Contractor shall remove, intact each piece of PCB contaminated equipment. Contractor shall transport said PCB equipment to AEP Company's designated PCB storage facility. Contractor shall schedule and coordinate said deliveries with the Engineer. Alternatively, at the direction of the Engineer, Contractor shall load PCB equipment onto vehicles provided by AEP Company. Contractor shall schedule and coordinate said loading with the Engineer. Contractor shall schedule and coordinate the pumping and removal of PCB dielectric fluid from transformers prior to loading when so directed by the Engineer.
- 3.37.3. AEP Company shall be responsible for the disposal of all PCB equipment and fluids.

## 3.38. PIPING SYSTEMS

- 3.38.1. Prior to the commencement of dismantling work, Contractor shall identify, plan and perform all piping shut offs, disconnections, and relocation work necessary to complete the work specified in a safe, orderly manner.
- 3.38.2. Piping shall be purged (where necessary) and shall be removed to a point of origin as designated by the Engineer.
- 3.38.3. Contractor shall submit plans, procedures and working drawings showing design details for all piping work to the Engineer for review. Contractor shall secure the Engineer's review of all designs, plans and procedures prior to the commencement of work. The correctness of the design shall remain the Contractors responsibility.
- 3.38.4. Contractor shall provide all supervision, labor, materials, tools and equipment necessary to complete all piping work required for the work as specified herein. Contractor shall be responsible for the identification of all piping construction, disconnection and relocation work, which will be required to complete all work specified herein.
- 3.38.5. Contractor shall perform all piping construction, disconnection and relocation work using methods which will not interrupt AEP Company's ongoing operations.
- 3.38.6. Secure the Engineer's permission prior to any utility outage. In the absence of the Engineer's approval of Contractor's proposed outage, Contractor shall perform the proposed work on live pressurized lines.

### 3.39. ELECTRICAL SYSTEMS

- 3.39.1. Prior to the commencement of dismantling work, Contractor shall identify, plan and perform all electrical shut offs, disconnections, and relocation work necessary to complete the work specified in a safe and orderly manner.
- 3.39.2. Conduit, cable, wireways, and buss shall be removed to a point of origin as designated by the Engineer.
- 3.39.3. Contractor shall submit plans, procedures and working drawings showing design details for all electrical and related work to the Engineer for review. Contractor shall secure the Engineer's review of all designs prior to the commencement of work. The correctness of design shall remain the

Contractor's responsibility.

- 3.39.4. Contractor shall provide all supervision, labor, materials, tools and equipment necessary to complete all electrical, telecommunication and telemetering work required for the dismantling work specified herein. Contractor shall be responsible for the identification of all electrical, telecommunication and telemetering construction, disconnection and relocation work which will be required to complete all work specified herein.
- 3.39.5. Contractor shall perform all electrical construction, disconnection and relocation work using methods which will not interrupt AEP Company's ongoing operations.
- 3.39.6. Contractor shall secure the Engineer's permission prior to any utility outage. In the absence of the Engineer's approval of Contractor's proposed outage, Contractor shall perform the proposed work on live energized lines.
- 4. WORK BY PURCHASER:

AEP Company Shall:

- 4.1. Provide Safety Data Sheets (SDS) in accordance with OSHA "Right to Know" regulations for each substance listed under said regulations.
- 4.2. Provide, where available, utility services such as 460 Volt, 3 phase, 60 Hz power, 250 Volt DC current, potable water, oxygen, compressed air, or natural gas, which are deemed available by AEP Company. Contractor may, at his own expense and approval of the Engineer, make necessary connections provided there is no interruption to normal production operations. AEP Company assumes no responsibility or liability for loss of, or damage to, the equipment or materials of the Contractor or his subcontractors. Contractor will pay charges that may be assessed. The assessment of charges and/or the availability of utilities may change through the course of the contract as determined.
- 4.3. Provide existing railroad tracks, railroad tracks sidings, and roadways on plant site, if available, for Contractor's use when and where the Engineer may designate. Contractor shall keep traffic lanes free of congestion so as to avoid interference with normal plant operations.
- 4.4. Provide one copy of all available drawings necessary for the completion of the work specified. These drawings are to be used by the Contractor for reference only in the performance of the work. Said drawings are not to be construed as a complete description of the Scope of Work, nor as fully depicting existing conditions. Additional copies may be purchased by Contractor through the Purchaser.
- 4.5. Approve the selection of all subcontractors before they will be allowed to enter the job site and perform work. Subcontractors are subject to all applicable terms and conditions contained herein.
- 4.6. Provide written releases for the demolition of each specific area or facility as identified in the Schedule of Values. Demolition shall not commence without the receipt of said release.
- 4.7. Assign to Contractor ownership of each facility to be dismantled. The assignment shall include:
  - 4.7.1. All ferrous and non-ferrous scrap resulting from the dismantling work
  - 4.7.2. All ferrous and non-ferrous scrap located within each dismantling area as identified by Engineer during the site visitation.
  - 4.7.3. Spare parts and/or spare equipment.
  - 4.7.4. All railroad track designated for removal.
  - 4.7.5. All vehicles and mobile equipment located within each dismantling area as identified in the Specification.

4.8. AEP Company will maintain ownership of all real estate

#### 5. Asbestos

5.1. This conceptual estimate does not include the cost for the removal or disposal of asbestos containing materials.

## 6. Landfill

- 6.1. This conceptual cost estimate does not include the cost for the closure or capping of any landfill(s), if present.
- 7. Clearwater Pond
  - 7.1. This conceptual estimate includes backfilling the Clearwater pond on the south side of the west wastewater pond from EL. 375' up to surrounding grade elevation with berm material currently surrounding there existing pond as well as crushed concrete material from the demolition efforts.
- 8. Ash Pond / Fly Ash Pond
  - 8.1. This conceptual cost estimate does not include the cost for any water filtering, discharge, or capping of any pond(s), if present.
- 9. Resale Equipment Value
  - 9.1. Brandenburg does not believe that any equipment holds a resale value greater than the anticipated scrap value of said equipment; therefore, no resale of equipment has been included.

### 10. Pricing

Description	Cost
General Conditions	\$184,500.00
Environmental	\$450,000.00
Unit 1 and 2 Demolition	\$7,090,775.00
Stack	\$475,000.00
Cooling Towers	\$1,200,000.00
River Cells	\$5,300,000.00
Flowable Fill	\$990,000.00
Clearwater Pond	\$717,000.00
Total	\$16,407,275.00

Total Cost = \$38,717,775.00

Scrap Revenue = (\$22,310,500.00)

## Volumes

Demolition Material	Volume
Concrete	66,200 yards
Demolition Debris	16,342 yards
Scrap Ferrous Steel	132,374 tons
Scrap Non-ferrous Steel	1,836,829 lbs
Oils/Greases	15,000 gallons
Clearwater Pond Backfill	81,700 yards



## Berrien Springs Hydroelectric Plant CONCEPTUAL DEMOLITION COST ESTIMATE

Prepared for: Indiana Michigan Power Company (Owner) and American Electric Power Service Corporation

> Project No. 13465-000 February 12, 2016 Revision 0



55 East Monroe Street Chicago, IL 60603-5780 USA





February 12, 2016

American Electric Power Service Corporation Conceptual Demolition Cost Estimate

**Issue Summary Page** 

Revision Number	Date	Purpose	Prepared By	Reviewed By	Approved By	Pages Affected
A	01/28/16	Comments	R. C. Kinsinger	A.D. Chapin D. F. Franczak	M. N. Ozan	All
0	02/12/16	Use	R. C. Kinsinger Rkinninger 4C	A.D. Chapin AChapin D. F. Franczak S.F. Franczak	T. J. Meehan Ymm	All

Page IS-1

\\Snl6c\data6\AEPFossil\Rockport\_Tanners Creek CDCEU 2015\6.0 Evaluations-Reports\6.06 Studies\Berrien Springs\Berrien Springs Hydro\_Conceptual Demolition Cost Estimate\_No 33705\_Rev 0.doc



**Section** 

Indiana Michigan Power Company Attachment JAC-3 Witness; Cash Berrien Springs Hydroelectric Plant<sup>age 3 of 205</sup> Indiana Michigan Power Company American Electric Power Service Corporation Conceptual Demolition Cost Estimate February 12, 2016

## TABLE OF CONTENTS

Sargent & Lundy

1	INTRODUCTION	1
2	COST ESTIMATE SUMMARY	1
3	TECHNICAL BASIS	4
4	COMMERICAL BASIS	6
4.1	General Information	6
4.2	Quantities/Material Cost	6
4.3	Construction Labor Wages	6
4.4	Scrap Value	7
4.5	Indirect Costs	8
4.6	Escalation	8
4.7	Contingency	8
4.8	Assumptions	8
5	REFERENCES	9

<u>EXHIBIT</u>	DESCRIPTION
1	Conceptual Cost Estimate Summary
2	Conceptual Demolition Cost Estimate No. 33705B
3	Asbestos Removal Conceptual Cost Estimate No. 33737B
4	Retirement Option 1-3 Demolition Scope and Sequence

TOC-1



Indiana Michigan Power Company Attachment JAC-3 Witness; Cash Berrien Springs Hydroelectric Plant Indiana Michigan Power Company American Electric Power Service Corporation Conceptual Demolition Cost Estimate February 12, 2016

# 1.0 INTRODUCTION

The Berrien Springs Hydroelectric Plant located in the City of Berrien Springs, Michigan is owned and operated by Indiana Michigan Power Company (I&M), a subsidiary of American Electric Power (AEP). The plant consists of two (2) earthen dams separated by a concrete spillway, rollway section and powerhouse. The powerhouse and adjacent penstock sections are located between the left embankment and the rollway sections. Each of the two (2) open flume penstock sections feed six (6) Flygt generating units which were installed in 1995 with a total capacity rating of 7,200 kW. The two (2) original generating units located in the powerhouse were abandoned in place and the other two (2) of the four (4) units were removed. Trash racks and a log boom are located upstream of the penstock sections. The control room for the hydroelectric components is located in the powerhouse.

AEP recently contracted S&L to prepare conceptual demolition cost estimates considering three (3) retirement options defined as follows: (1) Option 1, Non-Power Operation, (2) Option 2, Partial Removal of the Dam Structures, and (3) Option 3, Complete Removal of the Dam and Powerhouse. Also, in addition S&L was requested to prepare a separate Asbestos Removal Conceptual Cost Estimate.

The objective of the conceptual demolition cost estimates is to determine the gross demolition costs for Berrien Springs Hydroelectric Plant (including gross salvage credits and any other benefits), in support of documenting a component of future AEP book depreciation rates to be approved by the I&M's state commissions and potential future inclusion in submittal of a rate case to the state commissions, and other potential uses. The cost estimate considers the demolition/dismantlement methodology which complies with current OSHA rules and regulations.

## 2.0 COST ESTIMATE SUMMARY

Conceptual Demolition Cost Estimate No. 33705B, dated February 12, 2016, was prepared and is included as Exhibit 2. This cost estimate was prepared for retirement option 3, but includes accounts allowing the determination of cost estimates for retirement options 1 and 2 as well. A summary of the conceptual demolition cost estimates for all three (3) retirement options is provided in Exhibit 1 and detailed in the following tables.



The cost estimate is structured into a code of accounts as identified in Table 2-1.

Account Number	Description
10, 21	Demolition Costs (including steel, equipment & piping scrap value)
18	Scrap Value Costs
91	Other Direct & Construction Indirect Costs
93	Indirect Costs
94	Contingency Costs
96	Escalation Costs

 Table 2-1

 Cost Estimate Code of Accounts

The results of the cost estimate for retirement option 3 are provided in Table 2-2 below.

# Table 2-2Cost Estimate Results SummaryRetirement Option 3

Description	Total Cost	
Demolition Cost	\$9,416,995	
Scrap Value	(\$226,765)	
Direct Cost Subtotal	\$9,190,231	
Indirect Cost	\$942,000	
Contingency Cost	\$2,106,000	
Escalation Cost	\$0	
Total Project Cost	\$12,238,230	



The results of the cost estimate for retirement option 1 are provided in Table 2-3 below.

Description	Total Cost	
Demolition Cost	\$177,529	
Scrap Value	(\$113,105)	
Direct Cost Subtotal	\$64,424	
Indirect Cost	\$6,000	
Contingency Cost	\$53,600	
Escalation Cost	\$0	
Total Project Cost	\$124,024	


# Table 2-3Cost Estimate Results SummaryRetirement Option 1

The results of the cost estimate for retirement option 2 are provided in Table 2-4 below.

# Table 2-4 Cost Estimate Results Summary Retirement Option 2

Description	Total Cost	
Demolition Cost	\$6,189,535	
Scrap Value	(\$186,641)	
Direct Cost Subtotal	\$6,002,895	
Indirect Cost	\$615,000	
Contingency Cost	\$1,389,400	
Escalation Cost	\$0	
Total Project Cost	\$8,007,295	

Page 3 of 9 \\Snl6c\data6\AEPFossi\\Rockport\_Tanners Creek CDCEU 2015\6.0 Evaluations-Reports\6.06 Studies\Berrien Springs\Berrien Springs Hydro\_Conceptual Demolition Cost Estimate\_No 33705\_Rev 0.doc





Indiana Michigan Power Company American Electric Power Service Corporation **Conceptual Demolition Cost Estimate** February 12, 2016

Asbestos Removal Conceptual Cost Estimate No. 33737B, dated February 12, 2016, was prepared and is included as Exhibit 3. The total estimated cost for asbestos removal prior to plant dismantlement is \$5,100. Quantities were derived from drawings and past experience. The cost of asbestos removal is excluded from the total conceptual demolition cost estimates for each retirement option detailed in the tables above.

#### 3.0 **TECHNICAL BASIS**

The scope of dismantlement is based on three (3) retirement options, as requested by AEP, as follows:

Retirement Option 1, Non-Power Operation: This scenario would consider leaving intact all of the existing water-impounding structures and the powerhouse. Only the electric generating units and their auxiliary equipment would be removed so as to preclude the generation of electricity by the former hydroelectric plant. In addition, the spillway would be modified as required in order to pass river flows and maintain the impoundment's water surface elevation at the current conditions.

Retirement Option 2, Partial Removal of the Dam Structures: This scenario would consider demolition and removal of certain elements of the hydroelectric site in order to drain the existing impoundment and create a natural river channel through the dam site. This would generally include removal of the generating units and powerhouse and possibly but not inclusively demolition and removal of substantial portions of concrete spillway structures. This option would address the removal and stabilization of any sediments that have accumulated at the upstream end of the dam and the stabilization of the newly exposed reservoir/riverbanks.

Retirement Option 3, Complete Removal of the Dam and Powerhouse: This scenario would consider complete removal of the electric generating components and powerhouse and complete removal of the dam. Similar to option 2, this option would address the removal and stabilization of any sediments that have accumulated at the upstream end of the dam and the stabilization of the newly exposed reservoir/riverbanks.

The scope of dismantlement for each retirement option, as interpreted from the definitions above, are identified on marked plant drawings included as Exhibit 4. The scope of dismantlement and the sequence of demolition for each retirement option are defined on these sketches.



Berrien Springs Hydroelectric Plant Indiana Michigan Power Company American Electric Power Service Corporation **Conceptual Demolition Cost Estimate** February 12, 2016

Retirement options 2 and 3 include the same demolition work as retirement option 1, removal of the generating unit components from the powerhouse. The powerhouse is not removed in retirement option 1, but is removed in retirement option 3. For retirement option 2 the powerhouse may or may not be removed, depending on if removal of portions of the dam can restore river flow to natural flow without removing the powerhouse (refer to Exhibit 4).

For each of the retirement options the scope of sediment removal is based on the quantity that would be disturbed from the demolition work itself and not complete removal of all sediment potentially disturbed by the partial or complete removal of the dam. The subcontractor costs included in retirement options 2 and 3 are for lime stabilization of the sediment and removal of the sediment and other wastes (such as timber) to the waste disposal site. These costs do not apply to retirement option 1 since only generating unit components in the powerhouse are removed and this material has scrap value.

Retirement options 2 and 3 include the stabilization of newly exposed riverbanks, which include the dam area and areas upstream of the dam. The extent of stabilization for retirement option 3 may be slightly more than retirement option 2, since the entire dam is being removed in retirement option 3.

The following are excluded from the scope of the conceptual demolition cost estimates:

- ➤ Asbestos removal (separate cost estimate prepared).
- > The conceptual demolition cost estimate includes the cost to remove the one (1) main power transformer located in the switchyard, but not the cost to remove the switchyard itself (and remaining components in the switchyard).
- > The existing fish ladder will remain in place.
- > Evaluation of the effect of the complete removal of the series of dams on the river watershed.
- > Evaluation of the effect of the removal of any one dam, on either the upstream or downstream side dam and reservoir, after removal of the dam.
- > Potential social or environmental impact of the draining of the reservoirs and the impact on property values or other community impact.
- > The conceptual demolition cost estimate excludes any costs related to performing surveys to quantify the amount of sediment and chemical testing of the sediment. The quantity of sediment to be removed was estimated for retirement options 2 and 3 and the cost to remove the sediment is included in the conceptual demolition cost estimate. As stated above, the scope of sediment removal is based on the quantity that would be disturbed from the demolition work itself and not complete removal of the sediment potentially disturbed by the partial or complete removal of the dam.

Page 5 of 9



Indiana Michigan Power Company Attachment JAC-3 Witness; Cash Berrien Springs Hydroelectric Plant Indiana Michigan Power Company American Electric Power Service Corporation Conceptual Demolition Cost Estimate February 12, 2016

The scope of the demolition cost estimate was reaffirmed during a review of the facility by two S&L employees in conjunction with a representative from Bradenburg Industrial Service Co. and AEP corporate and plant personnel. The facility review was held on Wednesday December 16, 2015.

# 4.0 COMMERCIAL BASIS

## 4.1 General Information

The Conceptual Demolition Cost Estimates prepared for the Berrien Springs Hydroelectric Plant is a conceptual estimate of the cost to dismantle the powerhouse and dam in accordance with the scope defined for each of the three (3) retirement options. Costs were calculated for (1) demolition of existing plant structures and equipment and associated site restoration costs, (2) scrap value of steel, copper and stainless steel, as applicable, (3) associated indirect costs, and (4) contingency.

All units used in the cost estimate are U.S. Standard and all costs are in US Dollars (4<sup>th</sup> Quarter 2015 levels). A three (3) year demolition schedule is anticipated for retirement option 3 including asbestos removal (to be performed prior to start of demolition work). The schedule takes into consideration environmental permitting, asbestos removal which includes mapping out all asbestos contamination throughout the powerhouse and associated abatement, followed by total plant demolition and site restoration. The schedule for the other two (2) retirement options would be correspondingly less.

# 4.2 Quantities/Material Cost

Quantities of pieces of equipment and/or bulk material commodities used in the cost estimates were intended to be reasonable and representative of projects of this type. Material quantities were estimated from the hydroelectric plant drawings and data provided by AEP, and the information obtained from Plant personnel during the facility review.

## 4.3 Construction Labor Wages

Craft labor rates (Craft Hourly Rate) for the cost estimate were calculated as Union Labor rates for South Bend, Indiana, based on 2015, R. S. Means "Labor Rates for the Construction Industry". The craft rates were incorporated into work crews appropriate for the activities by adding allowances for small tools, construction equipment, insurance, and site overheads to arrive at crew hourly rates detailed in the cost estimate. A 1.10 regional labor productivity multiplier was included based on Compass International Global Construction Yearbook, 2015 Edition, for union work in Indiana. National Maintenance

Page 6 of 9



February 12, 2016

Agreement Rates (typically negotiated by AEP) do not apply as this work is assumed to be performed as a lump sum contract.

# 4.3.1 Labor Work Schedule and Incentives

The estimate assumed a 5x8 work week. No per diem or other labor incentives are included.

# 4.3.2 Construction Indirects

Allowances were included in the cost estimate as direct costs as noted for the following:

- > Freight: Material and scrap freight included in the material and scrap costs.
- Additional Crane Allowance: None included. Cost of cranes and construction machinery are included in the labor wage rates.
- > Mobilization and Demobilization: Included in labor wage rates.
- Scaffolding: Included in labor wage rates.
- > Consumables: Included in material and labor costs.
- > Per Diem Costs: Excluded from the estimate.
- > Contractor's General and Administrative Costs and Profit: Included in the labor wage rates.

## 4.4 Scrap Value

The value of scrap was determined by a 3 month average (November and December 2015 and January 2016) using Zone 4 (USA Midwest) of the "Scrap Metals Market Watch" (<u>www.americanrecycler.com</u>).

Since the values obtained are delivered pieces, 25% of the values obtained were deducted to pay for separation, preparation and shipping to the mills. This resulted in realized prices of:

- ➤ Mixed Steel Value @ \$118/Ton
- ➤ Copper Value @ \$3,180/Ton
- ➤ Stainless Steel @ \$675/Ton
- <u>Note:</u> 1 Ton = 2,000 Lbs

All steel is considered to be mixed steel unless otherwise noted.

Page 7 of 9



Indiana Michigan Power Company Attachment JAC-3 Witness; Cash Berrien Springs Hydroelectric Plant Indiana Michigan Power Company American Electric Power Service Corporation Conceptual Demolition Cost Estimate February 12, 2016

## 4.5 Indirect Costs

Allowances were included in the cost estimate as indirect costs as noted for the following:

- > Engineering, Procurement and Project Services: None included.
- Construction Management Support: None included.
- Owners Cost: Included as 10.0% of the total direct cost. Owners Costs include owner project engineering, administration and construction management, permits and fees, legal expenses, taxes, removal of chemicals, etc.

### 4.6 Escalation

No allowance for escalation was included in the cost estimate. All costs are determined in 4<sup>th</sup> Quarter

2015 levels.

## 4.7 Contingency

Allowances were included in the cost estimate as contingency as noted for the following:

- Scrap Value: Included as 15.0% reduction in the salvage value resulting in a total net reduction in the salvage value. The contingency assumes a potential drop in salvage value thus increasing the project cost. Scrap costs are very volatile but by taking a 3-month average some of the effect of volatility is reduced. However there are other variables that affect scrap pricing such as the quantity and processing fees. The contingency applied is based on the estimators confidence in scrap pricing used in the demolition cost estimate.
- ➤ Material: Included as 20.0% of the total material cost.
- ▶ Labor: Included as 20.0% of the total labor cost.
- ➤ Indirect: Included as 20.0% of the total indirect cost.
- Subcontractor: Included as 20.0% of the total subcontractor cost.

### 4.8 Assumptions

The following assumptions apply to the cost estimates.

- The cost estimate for each retirement option is based on the scope and the demolition sequences defined on the sketches provided in Exhibit 4.
- > All chemicals will be removed by the Owner prior to demolition, from the facilities to be demolished.



Berrien Springs Hydroelectric Plant Indiana Michigan Power Company American Electric Power Service Corporation Conceptual Demolition Cost Estimate February 12, 2016

- All electrical equipment and wiring is de-energized prior to start of dismantlement, except for that required for remote operation of the spillway gates after demolition is completed for retirement option 1.
- > No extraordinary environmental costs for demolition have been included.
- Handling, on-site and off-site disposal of hazardous materials would be performed in compliance with methods approved by Owner.
- > The window glazing in the powerhouse may be asbestos contaminated and an allowance for removal and disposal is included in the asbestos removal cost estimate. There is no building or pipe insulation in the facility and consequently no insulation related asbestos contamination.
- Switchyards within the plant boundaries are not part of the scope, neither are access roads to these facilities. Fences and gates needed to protect the switchyard will be left in place.
- All demolished materials are considered debris, except for organic combustibles and non-embedded metals which have scrap value.
- The basis for salvage estimating is for scrap value only. No resale of equipment or material is included.
- Sediment removed due to demolition work is treated with lime and hauled offsite to an approved waste disposal facility.

# 5.0 REFERENCES

- 5.1 Berrien Springs Plant Drawings: One-Line Diagrams, No. 12-12001-2, 10/30/07 and No. W-1000, Revision 17.
- **5.2** Spaulding Consultants, LLC, Supporting Technical Information Document, Berrien Springs Hydroelectric Project, November, 2007.

Sargent & Lundy



Indiana Michigan Power Company Attachment JAC-3 Witness; Cash Berrien Springs Hydroelectric Plant Indiana Michigan Power Company American Electric Power Service Corporation Conceptual Demolition Cost Estimate February 12, 2016

# EXHIBIT 1 Berrien Springs Hydroelectric Plant Conceptual Demolition Cost Estimate Summary

\\Snl6c\data6\AEPFossil\Rockport\_Tanners Creek CDCEU 2015\6.0 Evaluations-Reports\6.06 Studies\Berrien Springs\Berrien Springs Hydro\_Conceptual Demolition Cost Estimate\_No 33705\_Rev 0.doc

	Reti	rement Option 1	Retirement Option 2	Retirement Option 3
Demolition Cost	\$	177,529	\$ 6,189,535	\$ 9,416,995
Scrap Value	\$	(113,105)	\$ (186,641)	\$ (226,765)
Direct Cost Subtotal	\$	64,424	\$ 6,002,895	\$ 9,190,231
Indirect Cost	\$	6,000	\$ 615,000	\$ 942,000
Contingency Cost	\$	53,600	\$ 1,389,400	\$ 2,106,000
Escalation Cost	\$	-	\$ -	\$ -
Total Demolition Cost	\$	124,024	\$ 8,007,295	\$ 12,238,230



Indiana Michigan Power Company Attachment JAC-3 Witness; Cash Berrien Springs Hydroelectric Plant Indiana Michigan Power Company American Electric Power Service Corporation Conceptual Demolition Cost Estimate February 12, 2016

# EXHIBIT 2 Berrien Springs Hydroelectric Plant Conceptual Demolition Cost Estimate No. 33705B

\\Snl6c\data6\AEPFossil\Rockport\_Tanners Creek CDCEU 2015\6.0 Evaluations-Reports\6.06 Studies\Berrien Springs\Berrien Springs Hydro\_Conceptual Demolition Cost Estimate\_No 33705\_Rev 0.doc

Indiana Michigan Power Company Attachment JAC-3 Witness; Cash Page 16 of 205

Client	AEP
Estimator	RCK
Labor rate table	15INSOU
Project No.	13465-000
Station Name	BERRIEN SPRINGS
Unit	ALL
Estimate Date	02/12/2016
<b>Reviewed By</b>	ADC
Approved By	MNO
Estimate No.	33705B
Estimate Class	Conceptual
Cost index	INSOU

Estimate No.: 33705B Project No.: 13465-000 Estimate Date: 02/12/2016 Prep/Rev/App: RCK/ADC/MNO

Area	Description	Subcontract Cost	Scrap Value	Material Cost	Man Hours	Labor Cost	Total Cost
ACCOUNT A	DEMOLITION ACCOUNT A		(113,105)	27,930	1,746	149,599	64,424
ACCOUNT B	DEMOLITION ACCOUNT B	782,260	(73,536)	2,644,808	33,942	2,584,938	5,938,471
ACCOUNT C	DEMOLITION ACCOUNT C	1,456,400	(40,124)	2,863	19,762	1,768,197	3,187,336
	TOTAL DIRECT	2,238,660	(226,765)	2,675,601	55,450	4,502,734	9,190,231

### **Estimate Totals**

Description	Amount	Totals	Hours
Direct Costs:			
Labor	4,502,734		55,450
Material	2,675,601		
Subcontract	2,238,660		
Scrap Value	(226,765)		
-	9,190,230	9,190,230	
Other Direct & Construction			
Indirect Costs:			
91-1 Scaffolding			
91-2 Cost Due To OT 5-10's			
91-3 Cost Due To OT 6-10's			
91-4 Per Diem			
91-5 Consumables			
91-8 Freight on Material			
91-9 Freight on Process Equip			
91-10 Sales Tax			
91-11 Contractors G&A			
91-12 Contractors Profit			
		9,190,230	
Indirect Costs:			
93-1 Engineering Services			
93-2 CM Support			
93-3 Start-Up/Commissioning			
93-4 Start-Up/Spare Parts 93-5 Excess Liability Insur.			
93-6 Sales Tax On Indirects			
93-7 Owners Cost	942,000		
93-8 EPC Fee	342,000		
	942,000	10,132,230	
Contingency:			
94-1 Contingency on Material	535,000		
94-2 Contingency on Labor	901,000		
94-3 Contingency on Sub.	448,000		
94-6 Contingency on Scrap	34,000		
94-5 Contingency on Indirect	188,000		
-	2,106,000	12,238,230	
Escalation:			
96-1 Escalation on Material			
96-2 Escalation on Labor			
96-3 Escalation on Subcontract			
96-4 Escalation on Scrap			
96-5 Escalation on Indirects			
		12,238,230	

Area	Group	Phase	Description	Notes	Quantity	Man Hours	Crew Rate	Labor Cost	Material Cost	Subcontract Cost	Scrap Value	Total Cost
ACCOUNT A			DEMOLITION ACCOUNT A									
	10.00.00		WHOLE PLANT DEMOLITION									
		10.31.00	MECHANICAL EQUIPMENT									
			DEMO .6 MW FLYGT GENERATOR	12 GENERATORS AT 9500# EA	57.00 TN	564	85.53 /MH	48,269		-		48,269
			DEMO FLYGT TURBINE AND GEARS DEMO HOIZONTAL CAMELBACK GENERATOR	12 GENERATORS AT 14000# EA 2 GENERATORS AT 14000# EA	84.00 TN 14.00 TN	832 139	85.53 /MH 85.53 /MH	71,134 11,856		-		71,134 11,856
			TURBINE ROOM 5 TON GANTRY CRANE	2 GENERATORS AT 14000# EA	5.00 TN	50	121.33 /MH	6,006		-		6,006
			MECHANICAL EQUIPMENT		0.00 11	1,584	121.00	137,265			-	137,265
			WHOLE PLANT DEMOLITION			1,584		137,265				137,265
	18.00.00		SCRAP VALUE									
	18.00.00	18.10.00	MIXED STEEL									
		18.10.00	MIXED STEEL MIXED STEEL	.6 MW FLYGT GENERATOR, 12 @5,225# EA	-31.00 TN		79.62 /MH				(3,660)	(3,660
			MIXED STEEL MIXED STEEL	DEMO FLYGT TURBINE AND GEARS	-84.00 TN		79.62 /MH 79.62 /MH			-	(9,919)	(9,919
			MIXED STEEL	DEMO HOIZONTAL CAMELBACK	-8.40 TN		79.62 /MH				(992)	(992)
			Initial office	GENERATOR, 2 @ 4.2 TN EA	0.10 11		10.02 /1011				(002)	(002
			MIXED STEEL	TURBINE ROOM 5 TON GANTRY CRANE	-5.00 TN		79.62 /MH			-	(590)	(590
			MIXED STEEL								(15,161)	(15,161)
		18.30.00	COPPER									
		10.30.00	COPPER	126 MW FLYGT GENERATOR 12@ 4,275	-25.60 TN		79.62 /MH		-	-	(81,408)	(81,408)
				LB EA								
			COPPER	DEMO HOIZONTAL CAMELBACK GENERATOR, 2 @ 2.6 TN EA	-5.20 TN		79.62 /MH		-	-	(16,536)	(16,536)
			COPPER								(97,944)	(97,944)
			SCRAP VALUE								(113,105)	(113,105)
	22.00.00		CONCRETE									
	22.00.00	22.13.00	Concrete									
		22.13.00	FLOWABLE FILL, 1500 PSI	FILL PENSTOCKS TO PREVENT BYPASS	294.00 CY	162	76.27 /MH	12,334	27,930		-	40,264
			Concrete	FLOW		162		12,334	27,930		-	40,264
			CONCRETE			162		12,334	27,930			40,264
			ACCOUNT A DEMOLITION ACCOUNT A			1,746		149,599	27,930		(113,105)	64,424
CCOUNT B												
CCOUNT B			DEMOLITION ACCOUNT P									
	10.00.00		DEMOLITION ACCOUNT B									
	10.00.00		WHOLE PLANT DEMOLITION									
	10.00.00	10.22.00	WHOLE PLANT DEMOLITION CONCRETE									
	10.00.00	10.22.00	WHOLE PLANT DEMOLITION	TAINTER GATE - TOP PORTION: WEIR,	2,197.00 CY	2,719	89.94 /MH	244,552				244,552
	10.00.00	10.22.00	WHOLE PLANT DEMOLITION CONCRETE EQUIPMENT/ BUILDING FOUNDATION	ENDWALL, GATE WALLS & HEAD WALL		, -						
	10.00.00	10.22.00	WHOLE PLANT DEMOLITION CONCRETE EQUIPMENT/ BUILDING FOUNDATION EQUIPMENT/ BUILDING FOUNDATION		2,197.00 CY 697.00 CY	863	89.94 /MH 89.94 /MH	77,584		-		77,584
	10.00.00	10.22.00	WHOLE PLANT DEMOLITION CONCRETE EQUIPMENT/ BUILDING FOUNDATION	ENDWALL, GATE WALLS & HEAD WALL		, -				-		77,584
	10.00.00	10.22.00	WHOLE PLANT DEMOLITION CONCRETE EQUIPMENT/ BUILDING FOUNDATION EQUIPMENT/ BUILDING FOUNDATION CONCRETE STEEL	ENDWALL, GATE WALLS & HEAD WALL GRAVITY DAM - TOP PORTION OF DAM	697.00 CY	863 3,582	89.94 <i>I</i> MH	<u>77,584</u> 322,137		-		77,584 322,137
	10.00.00		WHOLE PLANT DEMOLITION CONCRETE EQUIPMENT/ BUILDING FOUNDATION EQUIPMENT/ BUILDING FOUNDATION CONCRETE STEEL STRUCTURAL AND GIRT STEEL	ENDWALL, GATE WALLS & HEAD WALL GRAVITY DAM - TOP PORTION OF DAM TAINTER GATES STRUCTURE AND WALKWAY		863		77,584		-		77,584 322,137
	10.00.00		WHOLE PLANT DEMOLITION CONCRETE EQUIPMENT/ BUILDING FOUNDATION EQUIPMENT/ BUILDING FOUNDATION CONCRETE STEEL	ENDWALL, GATE WALLS & HEAD WALL GRAVITY DAM - TOP PORTION OF DAM TAINTER GATES STRUCTURE AND WALKWAY GRAVITY DAM TOP PORTION OF DAM:	697.00 CY	863 3,582	89.94 <i>I</i> MH	<u>77,584</u> 322,137		-	- - -	77,584 322,137 3,996
	10.00.00		WHOLE PLANT DEMOLITION CONCRETE EQUIPMENT/ BUILDING FOUNDATION EQUIPMENT/ BUILDING FOUNDATION CONCRETE STEEL STRUCTURAL AND GIRT STEEL	ENDWALL, GATE WALLS & HEAD WALL GRAVITY DAM - TOP PORTION OF DAM TAINTER GATES STRUCTURE AND WALKWAY	697.00 CY 44.90 TN	863 3,582 50	89.94 /MH 79.62 /MH	77,584 322,137 3,996		-	- - - -	77,584 322,137 3,996 3,156
	10.00.00	10.23.00	WHOLE PLANT DEMOLITION CONCRETE EQUIPMENT/ BUILDING FOUNDATION EQUIPMENT/ BUILDING FOUNDATION CONCRETE STEEL STRUCTURAL AND GIRT STEEL STRUCTURAL AND GIRT STEEL STEEL	ENDWALL, GATE WALLS & HEAD WALL GRAVITY DAM - TOP PORTION OF DAM TAINTER GATES STRUCTURE AND WALKWAY GRAVITY DAM TOP PORTION OF DAM:	697.00 CY 44.90 TN	863 3,582 50 40	89.94 /MH 79.62 /MH	77,584 322,137 3,996 3,159		-	- - - -	77,58- 322,137 3,990 3,159
	10.00.00		WHOLE PLANT DEMOLITION CONCRETE EQUIPMENT/ BUILDING FOUNDATION EQUIPMENT/ BUILDING FOUNDATION CONCRETE STEEL STRUCTURAL AND GIRT STEEL STEEL MECHANICAL EQUIPMENT	ENDWALL, GATE WALLS & HEAD WALL GRAVITY DAM - TOP PORTION OF DAM TAINTER GATES STRUCTURE AND WALKWAY GRAVITY DAM TOP PORTION OF DAM:	697.00 CY 44.90 TN 35.50 TN	863 3,582 50 40 <b>90</b>	89.94 /MH 79.62 /MH 79.62 /MH	77,584 322,137 3,996 3,159 7,155		-	- - - -	77.58 322,13 3,99 3,15 7,15
	10.00.00	10.23.00	WHOLE PLANT DEMOLITION CONCRETE EQUIPMENT/ BUILDING FOUNDATION EQUIPMENT/ BUILDING FOUNDATION CONCRETE STEEL STRUCTURAL AND GIRT STEEL STRUCTURAL AND GIRT STEEL STEEL MECHANICAL EQUIPMENT 80 KW PROPANE ELECTRIC GENERATOR	ENDWALL, GATE WALLS & HEAD WALL GRAVITY DAM - TOP PORTION OF DAM TAINTER GATES STRUCTURE AND WALKWAY GRAVITY DAM TOP PORTION OF DAM: STREEL AND WALKWAY	697.00 CY 44.90 TN 35.50 TN 1.50 TN	863 3,582 50 40 90	89.94 /MH 79.62 /MH 79.62 /MH	77,584 322,137 3,996 3,159 7,155 405		-	- - - -	77,58 322,137 3,990 3,155 7,155
	10.00.00	10.23.00	WHOLE PLANT DEMOLITION CONCRETE EQUIPMENT/ BUILDING FOUNDATION EQUIPMENT/ BUILDING FOUNDATION CONCRETE STEEL STRUCTURAL AND GIRT STEEL STEEL MECHANICAL EQUIPMENT	ENDWALL, GATE WALLS & HEAD WALL GRAVITY DAM - TOP PORTION OF DAM TAINTER GATES STRUCTURE AND WALKWAY GRAVITY DAM TOP PORTION OF DAM:	697.00 CY 44.90 TN 35.50 TN 1.50 TN 20.00 TN	863 3,582 50 40 90 3 45	89.94 /MH 79.62 /MH 79.62 /MH 121.33 /MH	77,584 322,137 3,996 3,159 7,155 405 5,406		-	-	77,584 322,137 3,990 3,155 7,155 400 5,400
	10.00.00	10.23.00	WHOLE PLANT DEMOLITION CONCRETE EQUIPMENT/ BUILDING FOUNDATION EQUIPMENT/ BUILDING FOUNDATION CONCRETE STEEL STRUCTURAL AND GIRT STEEL STRUCTURAL AND GIRT STEEL STEEL MECHANICAL EQUIPMENT 80 KW PROPANE ELECTRIC GENERATOR BAR RACKS	ENDWALL, GATE WALLS & HEAD WALL GRAVITY DAM - TOP PORTION OF DAM TAINTER GATES STRUCTURE AND WALKWAY GRAVITY DAM TOP PORTION OF DAM: STREEL AND WALKWAY	697.00 CY 44.90 TN 35.50 TN 1.50 TN	863 3,582 50 40 90	89.94 /MH 79.62 /MH 79.62 /MH 121.33 /MH 121.33 /MH	77,584 322,137 3,996 3,159 7,155 405		-	-	77,584 322,137 3,996 3,156 7,155 400 5,400 8,106
	10.00.00	10.23.00	WHOLE PLANT DEMOLITION CONCRETE EQUIPMENT/ BUILDING FOUNDATION EQUIPMENT/ BUILDING FOUNDATION CONCRETE STEEL STRUCTURAL AND GIRT STEEL STRUCTURAL AND GIRT STEEL STRUCTURAL AND GIRT STEEL STEEL MECHANICAL EQUIPMENT 80 KW PROPANE ELECTRIC GENERATOR BAR RACKS TAINTER GATES	ENDWALL, GATE WALLS & HEAD WALL GRAVITY DAM - TOP PORTION OF DAM TAINTER GATES STRUCTURE AND WALKWAY GRAVITY DAM TOP PORTION OF DAM: STREEL AND WALKWAY 4 AT 5 TONS EACH 6 AT 5 TONS EACH	697.00 CY 44.90 TN 35.50 TN 1.50 TN 20.00 TN 30.00 TN	863 3,582 50 40 90 3 45 67	89.94 /MH 79.62 /MH 79.62 /MH 121.33 /MH	77,584 322,137 3,996 3,159 7,155 405 5,406 8,109		-	-	77,584 322,137 3,990 3,155 7,155 400 5,400 8,100 8,100
	10.00.00	10.23.00	WHOLE PLANT DEMOLITION COCRETE EQUIPMENT/ BUILDING FOUNDATION COURPMENT/ BUILDING FOUNDATION CONCRETE STEL STRUCTURAL AND GIRT STEEL STRUCTURAL AND GIRT STEEL STRUCTURAL AND GIRT STEEL STEEL MECHANICAL EQUIPMENT 80 KW PROPANE ELECTRIC GENERATOR BAR RACKS TAINTER GATES STOP LOGS MECHANICAL EQUIPMENT	ENDWALL, GATE WALLS & HEAD WALL GRAVITY DAM - TOP PORTION OF DAM TAINTER GATES STRUCTURE AND WALKWAY GRAVITY DAM TOP PORTION OF DAM: STREEL AND WALKWAY 4 AT 5 TONS EACH 6 AT 5 TONS EACH	697.00 CY 44.90 TN 35.50 TN 1.50 TN 20.00 TN 30.00 TN	863 3,582 50 40 90 3 45 67 67	89.94 /MH 79.62 /MH 79.62 /MH 121.33 /MH 121.33 /MH	77,584 322,137 3,996 3,159 7,155 5,406 8,109 8,109		-	-	77,584 322,137 3,996 3,155 7,155 400 8,100 8,100
	10.00.00	10.23.00	WHOLE PLANT DEMOLITION CONCRETE EQUIPMENT/ BUILDING FOUNDATION CONCRETE STEEL STRUCTURAL AND GIRT STEEL STRUCTURAL AND GIRT STEEL STEEL MECHANICAL EQUIPMENT 80 KW PROPANE ELECTRIC GENERATOR BAR RACKS TAINTER GATES STOP LOGS MECHANICAL EQUIPMENT ELECTRICAL EQUIPMENT	ENDWALL, GATE WALLS & HEAD WALL GRAVITY DAM - TOP PORTION OF DAM TAINTER GATES STRUCTURE AND WALKWAY GRAVITY DAM TOP PORTION OF DAM: STREEL AND WALKWAY 4 AT 5 TONS EACH 6 AT 5 TONS EACH 6 AT 5 TONS EACH	697.00 CY 44.90 TN 35.50 TN 1.50 TN 20.00 TN 30.00 TN 30.00 TN	863 3,582 50 40 90 3 45 67 67	89.94 /MH 79.62 /MH 79.62 /MH 121.33 /MH 121.33 /MH 121.33 /MH	77,584 322,137 3,996 3,159 7,155 405 5,406 8,109 8,109 22,029		-	•	77,584 322,137 3,996 3,156 7,155 406 8,106 8,106 8,106 8,106
	10.00.00	10.23.00	WHOLE PLANT DEMOLITION COUCRETE EQUIPMENT/ BUILDING FOUNDATION EQUIPMENT/ BUILDING FOUNDATION CONCRETE STEEL STEEL STRUCTURAL AND GIRT STEEL STRUCTURAL AND GIRT STEEL STEEL MECHANICAL EQUIPMENT 80 KW PROPANE ELECTRIC GENERATOR BAR RACKS TAINTER GATES STOP LOGS MECHANICAL EQUIPMENT ELECTRICAL EQUIPMENT GENERATOR BUS TRANSFORMERS	ENDWALL, GATE WALLS & HEAD WALL GRAVITY DAM - TOP PORTION OF DAM TAINTER GATES STRUCTURE AND WALKWAY GRAVITY DAM TOP PORTION OF DAM: STREEL AND WALKWAY 4 AT 5 TONS EACH 6 AT 5 TONS EACH 6 AT 5 TONS EACH 6 AT 5 TONS EACH 4.16 to 34.5 KV, 6800/9068 KVA (STEEL)	697.00 CY 44.90 TN 35.50 TN 1.50 TN 20.00 TN 30.00 TN	863 3,582 50 40 <b>90</b> 3 45 67 67 182	89.94 /MH 79.62 /MH 79.62 /MH 121.33 /MH 121.33 /MH	77,584 322,137 3,996 3,159 7,155 405 5,406 8,109 8,109 22,029 2,356		-	•	77,584 322,137 3,996 3,159 7,155 5,406 8,109 8,109 22,029 2,356
	10.00.00	10.23.00	WHOLE PLANT DEMOLITION CONCRETE EQUIPMENT/ BUILDING FOUNDATION EQUIPMENT/ BUILDING FOUNDATION CONCRETE STEEL STEEL STRUCTURAL AND GIRT STEEL STRUCTURAL AND GIRT STEEL STEEL MECHANICAL EQUIPMENT BAR RACKS TAINTER GATES STOP LOGS MECHANICAL EQUIPMENT ELECTRICAL EQUIPMENT	ENDWALL, GATE WALLS & HEAD WALL GRAVITY DAM - TOP PORTION OF DAM TAINTER GATES STRUCTURE AND WALKWAY GRAVITY DAM TOP PORTION OF DAM: STREEL AND WALKWAY 4 AT 5 TONS EACH 6 AT 5 TONS EACH 6 AT 5 TONS EACH	697.00 CY 44.90 TN 35.50 TN 1.50 TN 20.00 TN 30.00 TN 30.00 TN	863 3,582 50 40 90 3 45 67 67 182 29	89.94 /MH 79.62 /MH 79.62 /MH 121.33 /MH 121.33 /MH 121.33 /MH 121.33 /MH	77,584 322,137 3,996 3,159 7,155 405 5,406 8,109 8,109 22,029		-	•	77,584 322,137 3,996 3,159 7,155 5,406 8,109 22,029 2,356 1,178
	10.00.00	10.23.00	WHOLE PLANT DEMOLITION COCRETE EQUIPMENT/ BUILDING FOUNDATION EQUIPMENT/ BUILDING FOUNDATION CONCRETE STEEL STRUCTURAL AND GIRT STEEL STRUCTURAL AND GIRT STEEL STRUCTURAL AND GIRT STEEL STRUCTURAL AND GIRT STEEL STEEL MECHANICAL EQUIPMENT 80 KW PROPANE ELECTRIC GENERATOR BAR RACKS TAINTER GATES STOP LOGS MECHANICAL EQUIPMENT ELECTRICAL EQUIPMENT GENERATOR BUS TRANSFORMERS GENERATOR BUS TRANSFORMERS	ENDWALL, GATE WALLS & HEAD WALL GRAVITY DAM - TOP PORTION OF DAM TAINTER GATES STRUCTURE AND WALKWAY GRAVITY DAM TOP PORTION OF DAM: STREEL AND WALKWAY 4 AT 5 TONS EACH 6 AT 5 TONS EACH 6 AT 5 TONS EACH 6 AT 5 TONS EACH 4.16 to 34.5 KV, 6800/9068 KVA (STEEL)	697.00 CY 44.90 TN 35.50 TN 1.50 TN 30.00 TN 30.00 TN 10.00 TN 5.00 TN	863 3,582 50 40 90 3 45 67 67 182 29 15	89.94 /MH 79.62 /MH 79.62 /MH 121.33 /MH 121.33 /MH 121.33 /MH 121.33 /MH 80.14 /MH	77,584 322,137 3,996 3,159 7,155 405 5,406 8,109 8,109 22,029 2,356 1,178		-	· · · ·	77,584 322,137 3,996 3,155 7,155 7,155 400 8,100 8,100 8,100 8,100 22,025 2,356 1,177
	10.00.00	10.23.00 10.31.00 10.41.00	WHOLE PLANT DEMOLITION COCRETE EQUIPMENT/ BUILDING FOUNDATION CONCRETE STEL STRUCTURAL AND GIRT STEEL STRUCTURAL AND GIRT STRUCTURAL AND GIRT STRUCTURAL STRUCTURAL AND GIRT STRUCTURAL AND	ENDWALL, GATE WALLS & HEAD WALL GRAVITY DAM - TOP PORTION OF DAM TAINTER GATES STRUCTURE AND WALKWAY GRAVITY DAM TOP PORTION OF DAM: STREEL AND WALKWAY 4 AT 5 TONS EACH 6 AT 5 TONS EACH 6 AT 5 TONS EACH 6 AT 5 TONS EACH 4.16 to 34.5 KV, 6800/9068 KVA (STEEL)	697.00 CY 44.90 TN 35.50 TN 1.50 TN 30.00 TN 30.00 TN 10.00 TN 5.00 TN	863 3,582 50 40 90 3 45 67 67 182 29 15 15	89.94 /MH 79.62 /MH 79.62 /MH 121.33 /MH 121.33 /MH 121.33 /MH 121.33 /MH 80.14 /MH	77,584 322,137 3,996 3,159 7,155 5,406 8,109 8,109 22,029 2,356 1,178 1,178		-	· · · ·	77,584 322,137 3,996 3,155 7,155 5,400 8,105 8,1
	10.00.00	10.23.00	WHOLE PLANT DEMOLITION CONCRETE EQUIPMENT/ BUILDING FOUNDATION EQUIPMENT/ BUILDING FOUNDATION CONCRETE STEL STEL STRUCTURAL AND GIRT STEEL STRUCTURAL AND GIRT STEEL STELL MECHANICAL EQUIPMENT 80 KW PROPANE ELECTRIC GENERATOR BAR RACKS TAINTER GATES STOP LOGS MECHANICAL EQUIPMENT ELECTRICAL EQUIPMENT GENERATOR BUS TRANSFORMERS GENERATOR BUS TRANSFORMERS MISCELLANEOUS ELECTRICAL EQUIPMENT	ENDWALL, GATE WALLS & HEAD WALL GRAVITY DAM - TOP PORTION OF DAM TAINTER GATES STRUCTURE AND WALKWAY GRAVITY DAM TOP PORTION OF DAM: STREEL AND WALKWAY 4 AT 5 TONS EACH 6 AT 5 TONS EACH 6 AT 5 TONS EACH 6 AT 5 TONS EACH 4.16 to 34.5 KV, 6800/9068 KVA (STEEL)	697.00 CY 44.90 TN 35.50 TN 1.50 TN 30.00 TN 30.00 TN 10.00 TN 5.00 TN	863 3,582 50 40 90 3 45 67 67 182 29 15 15	89.94 /MH 79.62 /MH 79.62 /MH 121.33 /MH 121.33 /MH 121.33 /MH 121.33 /MH 80.14 /MH	77,584 322,137 3,996 3,159 7,155 405 5,406 8,109 22,029 2,356 1,178 1,178 1,178 4,711		-		244,552 77,584 322,137 3,996 3,159 7,155 5,406 8,109 22,029 2,356 1,178 1,178 4,711
	10.00.00	10.23.00 10.31.00 10.41.00	WHOLE PLANT DEMOLITION CONCRETE EQUIPMENT/ BUILDING FOUNDATION CONCRETE STEL STRUCTURAL AND GIRT STEEL STRUCTURAL AND GIRT STRUCTURAL AND GIRT STEEL STRUCTURAL AND GIRT STRUCTURAL AND GI	ENDWALL, GATE WALLS & HEAD WALL GRAVITY DAM - TOP PORTION OF DAM TAINTER GATES STRUCTURE AND WALKWAY GRAVITY DAM TOP PORTION OF DAM: STREEL AND WALKWAY 4 AT 5 TONS EACH 6 AT 5 TONS EACH 6 AT 5 TONS EACH 6 AT 5 TONS EACH 4.16 to 34.5 KV, 6800/9068 KVA (STEEL) 4.16 to 34.5 KV, 6800/9068 KVA (CU)	697.00 CY 44.90 TN 35.50 TN 20.00 TN 30.00 TN 30.00 TN 30.00 TN 5.00 TN	863 3,582 50 40 90 3 3 45 67 67 182 29 15 15 59	89.94 /MH 79.62 /MH 79.62 /MH 121.33 /MH 121.33 /MH 121.33 /MH 121.33 /MH 80.14 /MH 80.14 /MH	77,584 322,137 3,996 3,159 7,155 5,406 8,109 8,109 22,029 2,356 1,178 1,178		-	- - - - - - - - - - - - - - - - - - -	77,584 322,137 3,996 3,155 7,155 405 5,400 8,100 8,100 8,100 8,100 8,100 8,100 8,100 8,101 1,175 1,177 1,177 4,711

	_											
Area	Group	Phase	Description	Notes	Quantity	Man Hours	Crew Rate	Labor Cost	Material Cost	Subcontract Cost	Scrap Value	Total Cost
			WHOLE PLANT DEMOLITION			3,912		356,045			10,000	366,045
	18.00.00		SCRAP VALUE									
		18.10.00	MIXED STEEL									
			MIXED STEEL	80 KW PROPANE ELECTRIC GENERATOR	-1.50 TN		79.62 /MH		-	-	(177)	(177)
			MIXED STEEL	BAR RACKS	-20.00 TN		79.62 /MH		-	-	(2,362)	(2,362)
			MIXED STEEL MIXED STEEL	TAINTER GATES AND WALKWAY STOP LOGS	-44.90 TN -30.00 TN		79.62 /MH 79.62 /MH		-	-	(5,302) (3,542)	(5,302) (3,542)
			MIXED STEEL	GRAVITY DAM TOP PORTION OF DAM:	-35.50 TN		79.62 /MH				(4,192)	(4,192)
				STREEL AND WALKWAY								
			MIXED STEEL	GENERATOR BUS TRANSFORMERS	-10.00 TN		79.62 /MH		-	-	(1,181)	(1,181)
			MIXED STEEL								(16,756)	(16,756)
		18.30.00	COPPER									
		16.30.00	COPPER	CABLE	-10.00 TN		79.62 /MH				(31,800)	(31,800)
			COPPER	MISC. TRANSFORMERS & MOTORS UNIT 1	-6.00 TN		79.62 /MH				(19,080)	(19,080)
			COPPER	GENERATOR BUS TRANSFORMERS	-5.00 TN		79.62 /MH		-	-	(15,900)	(15,900)
			COPPER								(66,780)	(66,780)
			SCRAP VALUE								(83,536)	(83,536)
	21.00.00		CIVIL WORK									
	21.00.00	21.17.00	Earthwork, Excavation									
		21.17.00	FOUNDATION EXCAVATION, COMMON EARTH USING 1 CY	RIVER BED EXCAVATION FOR RIPRAP	100.00 CY	17	88.08 /MH	1,453				1,453
			BACKHOE									.,
			Earthwork, Excavation			17		1,453				1,453
		21.41.00	Erosion and Sedimentation Control									
			RIPRAP, RANDOM BROKEN STONE, MACHINE PLACED	STREAMBED PROTECTION 47770 CY - 5689	42,081.00 CY	18,564	74.10 /MH	1,375,577	1,721,113	-	-	3,096,689
				CY ASSUMING REUSE OF CAUSEWAY STONE								
			RIPRAP, RANDOM BROKEN STONE, MACHINE PLACED	FOR CAUSEWAYS INSTALLATION	5,689.00 CY	2,510	74.10 /MH	185,966	232,680		-	418,647
			RIPRAP, RANDOM BROKEN STONE, MACHINE PLACED	REUSE CAUSEWAY RIP RAP FOR BANK	5,689.00 CY	2,510	74.10 /MH	185,966		-	-	185,966
				PROTECTION								7.050
			RIPRAP, RANDOM BROKEN STONE, MACHINE PLACED Erosion and Sedimentation Control	RIPRAP PROTECTION AT SPILLWAY FLOOR	100.00 CY	44 23,627	74.10 /MH	3,269 1,750,778	4,090	-		7,359 3,708,661
			Erosion and Sedimentation Control			23,027		1,750,776	1,957,005			3,700,001
		21.47.00	LANDSCAPING									
			HYDRO OR AIR SEED & MULCH & FERTILIZER		450.00 AC	6,386	74.64 /MH	476,661	686,925	-	-	1,163,586
			LANDSCAPING			6,386		476,661	686,925			1,163,586
		21.65.00	Soil Remediation									
			REMOVAL OF LOCALIZED SILT AT DAM REMOVAL OF LOCALIZED SILT AT DAM	LIME ADDITIVE FOR DRYING LOAD, MIX AND HAUL LIME AND SEDIMENT	3,556.00 CY 10,667.00 CY		196.64 /MH 196.64 /MH			142,240 640,020	-	142,240 640,020
			REMOVAL OF LOCALIZED SILT AT DAM	MIX 7111+3556	10,007.00 CT		190.04 /WH			640,020	-	640,020
			Soil Remediation							782,260		782,260
			CIVIL WORK			30,030		2,228,893	2,644,808	782,260		5,655,961
			ACCOUNT B DEMOLITION ACCOUNT B			33,942		2,584,938	2,644,808	782,260	(73,536)	5,938,471
ACCOUNT C			DEMOLITION ACCOUNT C									
	10.00.00		WHOLE PLANT DEMOLITION									
		10.22.00	CONCRETE EQUIPMENT/ BUILDING FOUNDATION	TAINTER GATE - BOTTOM PORTION :	4.869.00 CY	6.026	89.94 /MH	541.978				541,978
			EQUIPMENT/ BUILDING FOUNDATION	APRON AND THROAT	4,009.00 C1	0,020	69.94 /WH	541,976		-	-	541,976
			EQUIPMENT/ BUILDING FOUNDATION	GRAVITY DAM - BOTTOM PORTION: APRON	838.00 CY	1,037	89.94 /MH	93,279		-	-	93,279
				AND BASE		700						
			EQUIPMENT/ BUILDING FOUNDATION	EAST AND WEST PENSTOCKS - TOP PORTION	638.00 CY	790	89.94 /MH	71,017		-	-	71,017
			EQUIPMENT/ BUILDING FOUNDATION	EAST AND WEST PENSTOCKS - BOTTOM	4,284.00 CY	5,302	89.94 /MH	476,860			-	476,860
				PORTION: APRON AND BASE								
			EQUIPMENT/ BUILDING FOUNDATION	GENERATOR HOUSE - TOP PORTION :	1,106.00 CY	1,369	89.94 /MH	123,111		-	-	123,111
			EQUIPMENT/ BUILDING FOUNDATION	WALLS GENERATOR HOUSE - BOTTOM PORTION :	1,546.00 CY	1,913	89.94 /MH	172.088				172,088
			Equil metry bolebing roombarion	BASEMENT FLOOR	1,040.00 01	1,913	00.04 AMIT				-	172,000
			CONCRETE			16,437		1,478,333				1,478,333
		10.23.00	STEEL									
			STRUCTURAL AND GIRT STEEL	EAST AND WEST PENSTOCKS - TOP PORTION, STEEL DECK AND BAR RACK	128.00 TN	143	79.62 /MH	11,391		-	-	11,391
				I GITTON, STELL DEGR AND DAR RACK								

Area	Group	Phase	Description	Notes	Quantity	Man Hours	Crew Rate	Labor Cost	Material Cost	Subcontract Cost	Scrap Value	Total Cost
		10.23.00	STEEL									
			STRUCTURAL AND GIRT STEEL	GENERATOR HOUSE	221.00 TN	247	79.62 /MH	19,667		-	-	19,667
			STEEL			390		31,058				31,058
		10.24.00	ARCHITECTURAL									
			GENERATOR HOUSE	68'x93'x70' TALL	442,680.00 CF	1,899	89.81 /MH	170,575		-	-	170,575
			ARCHITECTURAL			1,899		170,575				170,575
		10.31.00	MECHANICAL EQUIPMENT									
			DEMO FLYGT PENSTOCKS	12 GENERATORS AT 11,800# EA	70.80 TN	701	85.53 /MH	59,956		-		59,956
			DEMO CAMELBACK PENSTOCKS	2 GENERATORS AT 15 TN EA	30.00 TN	297	85.53 /MH	25,405		-		25,405
			MECHANICAL EQUIPMENT			998		85,361				85,361
			WHOLE PLANT DEMOLITION			19,724		1,765,327				1,765,327
	18.00.00		SCRAP VALUE									
		18.10.00	MIXED STEEL									
			MIXED STEEL	DEMO FLYGT PENSTOCKS	-70.80 TN		79.62 /MH		-	-	(8,360)	(8,360)
			MIXED STEEL	DEMO CAMELBACK PENSTOCKS	-30.00 TN		79.62 /MH		-	-	(3,542)	(3,542)
			MIXED STEEL	EAST AND WEST PENSTOCKS - TOP	-128.00 TN		79.62 /MH		-	-	(15,114)	(15,114)
				PORTION, STEEL DECK AND BAR RACK								
			MIXED STEEL	GENERATOR HOUSE	-111.00 TN		79.62 /MH		-	-	(13,107)	(13,107)
			MIXED STEEL SCRAP VALUE								(40,124)	(40,124) (40,124)
	21.00.00		CIVIL WORK									
		21.17.00	Earthwork, Excavation									
			FOUNDATION EXCAVATION, COMMON EARTH USING 1 CY BACKHOE		40.00 CY	7	88.08 /MH	581		-	-	581
				(140-100)		7		581				581
			Earthwork, Excavation					581				581
		21.41.00	Erosion and Sedimentation Control									
			RIPRAP, RANDOM BROKEN STONE, MACHINE PLACED	RIP RAP PROTECTION AT RETAINING WALLS (170-100)	70.00 CY	31	74.10 /MH	2,288	2,863	-	-	5,151
			Erosion and Sedimentation Control			31		2,288	2,863			5,151
		21.65.00	Soil Remediation									
			REMOVAL OF LOCALIZED SILT AT DAM	LIME ADDITIVE FOR DRYING	6,620.00 CY		196.64 /MH			264,800	-	264,800
			REMOVAL OF LOCALIZED SILT AT DAM	LOAD, MIX AND HAUL LIME AND SEDIMENT MIX 7111+3556	19,860.00 CY		196.64 /MH			1,191,600	-	1,191,600
			Soil Remediation							1,456,400		1,456,400
			CIVIL WORK			37		2,870	2,863	1,456,400		1,462,133
			ACCOUNT C DEMOLITION ACCOUNT C			19,762		1,768,197	2,863	1,456,400	(40,124)	3,187,336



# EXHIBIT 3 Berrien Springs Hydroelectric Plant Asbestos Removal Conceptual Cost Estimate No. 33737B

\\Snl6c\data6\AEPFossil\Rockport\_Tanners Creek CDCEU 2015\6.0 Evaluations-Reports\6.06 Studies\Berrien Springs\Berrien Springs Hydro\_Conceptual Demolition Cost Estimate\_No 33705\_Rev 0.doc

Indiana Michigan Power Company Attachment JAC-3 Witness; Cash Page 23 of 205

# AEP BERRIEN SPRINGS HYDROELECTRIC PLANT DISMANTLEMENT STUDY - ASBESTOS REMOVAL CONCEPTUAL COST ESTIMATE

Client	AEP
Estimator	RCK
Labor rate table	15INSOU
Project No.	13465-000
Station Name	BERRIEN SPRINGS
Unit	ALL
Estimate Date	02/12/2016
Reviewed By	ADC
Approved By	MNO
Estimate No.	33737B
Estimate Class	Conceptual
Cost index	INSOU

Estimate No.: 33737B Project No.: 13465-000 Estimate Date: 02/12/2016 Prep/Rev/App: RCK/ADC/MNO

#### AEP BERRIEN SPRINGS HYDROELECTRIC PLANT DISMANTLEMENT STUDY - ASBESTOS REMOVAL CONCEPTUAL COST ESTIMATE

Area	Description	Subcontract Cost	Scrap Value	Material Cost	Man Hours	Labor Cost	Total Cost
ASBESTOS	ASBESTOS REMOVAL TOTAL DIRECT	3,800 3,800					3,800 3,800

#### AEP BERRIEN SPRINGS HYDROELECTRIC PLANT DISMANTLEMENT STUDY - ASBESTOS REMOVAL CONCEPTUAL COST ESTIMATE

### **Estimate Totals**

Description	Amount	Totals	Hours
Direct Costs:			
Labor			
Material			
Subcontract	3,800		
Scrap Value			
·	3,800	3,800	
Other Direct & Construction			
Indirect Costs:			
91-1 Scaffolding			
91-2 Cost Due To OT 5-10's			
91-3 Cost Due To OT 6-10's			
91-4 Per Diem			
91-5 Consumables			
91-8 Freight on Material			
91-9 Freight on Process Equip			
91-10 Sales Tax			
91-11 Contractors G&A			
91-12 Contractors Profit			
		3,800	
Indirect Costs:			
93-1 Engineering Services			
93-2 CM Support			
93-3 Start-Up/Commissioning			
93-4 Start-Up/Spare Parts			
93-5 Excess Liability Insur.			
93-6 Sales Tax On Indirects			
93-7 Owners Cost	400		
93-8 EPC Fee			
	400	4,200	
Contingency:			
94-1 Contingency on Material			
94-2 Contingency on Labor			
94-3 Contingency on Sub.	800		
94-6 Contingency on Scrap	100		
94-5 Contingency on Indirect	100	E 400	
	900	5,100	
Escalation:			
96-1 Escalation on Material			
96-2 Escalation on Labor			
96-3 Escalation on Subcontract			
96-4 Escalation on Scrap			
96-5 Escalation on Indirects			
		5,100	
Total		5,100	
		3,100	


#### AEP BERRIEN SPRINGS HYDROELECTRIC PLANT DISMANTLEMENT STUDY - ASBESTOS REMOVAL CONCEPTUAL COST ESTIMATE


Area	Group	Phase	Description	Notes	Quantity	Man Hours	Crew Rate	Labor Cost	Material Cost	Subcontract Cost	Scrap Value	Total Cost
ASBESTOS			ASBESTOS REMOVAL									
	10.00.00		WHOLE PLANT DEMOLITION									
		10.37.00	ASBESTOS REMOVAL									
			ASBESTOS REMOVAL - MISC MATERIALS	WINDOW CAULKING MISC MATERIALS	2.00 CY		121.33 /MH			3,800		3,800
			ASBESTOS REMOVAL							3,800		3,800
			WHOLE PLANT DEMOLITION							3,800		3,800
			ASBESTOS ASBESTOS REMOVAL							3,800		3,800




# EXHIBIT 4 Berrien Springs Hydroelectric Plant Retirement Option 1-3 Demolition Scope and Sequence

\\Snl6c\data6\AEPFossil\Rockport\_Tanners Creek CDCEU 2015\6.0 Evaluations-Reports\6.06 Studies\Berrien Springs\Berrien Springs Hydro\_Conceptual Demolition Cost Estimate\_No 33705\_Rev 0.doc








# BERRIEN SPRINGS HYDRO RETIREMENT DEMO SEQUENCE SKETCHES AND CIVIL QUANTITIES BY: S&L


BERRIAN SPRINGS							
OPTION 2							
QUANTITY	UNIT	REMARKS					
450	ACRE						
47,770	CY	2 ft riprap protection @ D(50)=12"					
100	CY	TO BE REPLACED BY RIPRAP					
100	CY	2 ft riprap protection @ D(50)=12"					
	OPTION 2 QUANTITY 450 47,770 100	OPTION 2 QUANTITY UNIT 450 ACRE 47,770 CY 100 CY					

1				
		OPTION 3		
	ITEM	QUANTITY	UNIT	REMARKS
	GRASS SEEDING	450	ACRE	
	RIPRAP PROTECTION	47,770	CY	2 ft riprap protection @ D(50)=12"
	RIVERBED EXCAVATION FOR RIPRAP	140	CY	TO BE REPLACED BY RIPRAP
	RIPRAP PROTECTION AT RETAINING WALLS	170	CY	2 ft riprap protection @ D(50)=12"


JANUARY 25, 2016 PAGE 4 OF 7

Indiana Michigan Power Company Attachment JAC-3 Witness; Cash Page 31 of 205






JANUARY 25, 2016 Indiana Michigan Power Company Attachment JAC/3 Witness; Cash Page 32 of 205



BERRIEN SPRINGS HYDRO RETIREMENT -00002-11-0N July BY: S&L IEM CONCEPTUAL DEMO ESTIMATE BERRIAN SPRINGS RETIREMENT OPTION 3. CIVIL QUANTITIES IL A KIE CHAPIN POOL ELEVATION 624.4± FIFRAP PRUTECTION (TYP) INTER GATE SECTION 130 GRAVITY DAM SECTION PENSTOCK GENERATOR PENSTOCK HOUSE ELEV 626.01 AT (TYP) 245 PP OPP ARIPRAP = (5×2)+ (2×2)2 RIPAPP RETAINING VRIPRAP = (12) × (245+130) (1/2) = 170 CY VExc = (5×2) × (245+130) (1/27) = 140 CY WALL TO RIVERBED REMAIN IN PLACE. = PLAN = SECTIONA ST. JOSEPH IRIVER N. T. S. WATER ELEVATION 598.9± 5 0 CM 1 2 3 F4 5 6 7 3 IS INCH





# Buchanan Hydroelectric Plant CONCEPTUAL DEMOLITION COST ESTIMATE

Prepared for: Indiana Michigan Power Company (Owner) and American Electric Power Service Corporation

> Project No. 13465-000 February 12, 2016 Revision 0



55 East Monroe Street Chicago, IL 60603-5780 USA





Indiana Michigan Power Company Attachment JAC-3 Witness; Cash Buchanan Hydroelectric Plange 36 of 205 Indiana Michigan Power Company American Electric Power Service Corporation Conceptual Demolition Cost Estimate February 12, 2016

# **Issue Summary Page**

Revision Number	Date	Purpose	Prepared By	Reviewed By	Approved By	Pages Affected
A	01/29/16	Comments	R. C. Kinsinger	A.D. Chapin D. F. Franczak	M. N. Ozan	All
0	02/12/16	Use	R. C. Kinsinger RKinsinger AC	A.D. Chapin AChapin D. F. Franczak	T. J. Meehan	All

Page IS-1

\\Snl6c\data6\AEPFossil\Rockport\_Tanners Creek CDCEU 2015\6.0 Evaluations-Reports\6.06 Studies\Buchanan\Buchanan\Hydro\_Conceptual Demolition Cost Estimate\_No 33706\_Rev 0.doc



**Section** 

Indiana Michigan Power Company Attachment JAC-3 Witness; Cash Buchanan Hydroelectric Plant<sup>Page 37 of 205</sup> Indiana Michigan Power Company American Electric Power Service Corporation Conceptual Demolition Cost Estimate February 12, 2016

## TABLE OF CONTENTS

1	INTRODUCTION	1
2	COST ESTIMATE SUMMARY	1
3	TECHNICAL BASIS	4
4	COMMERICAL BASIS	6
4.1	General Information	6
4.2	Quantities/Material Cost	6
4.3	Construction Labor Wages	6
4.4	Scrap Value	7
4.5	Indirect Costs	8
4.6	Escalation	8
4.7	Contingency	8
4.8	Assumptions	8
5	REFERENCES	9

<u>EXHIBIT</u>	DESCRIPTION
1	Conceptual Cost Estimate Summary
2	Conceptual Demolition Cost Estimate No. 33706B
3	Asbestos Removal Conceptual Cost Estimate No. 33738B
4	Retirement Option 1-3 Demolition Scope and Sequence

TOC-1





Indiana Michigan Power Company Attachment JAC-3 Witness; Cash Buchanan Hydroelectric Plant Indiana Michigan Power Company American Electric Power Service Corporation Conceptual Demolition Cost Estimate February 12, 2016

# 1.0 INTRODUCTION

The Buchanan Hydroelectric Plant located in the City of Buchanan, Michigan is owned and operated by Indiana Michigan Power Company (I&M), a subsidiary of American Electric Power (AEP). The plant consists of (from left to right referenced facing downstream) a short left embankment section, a south abutment training wall, the spillway, the left headrace embankment (which includes the fish ladder), the powerhouse and the terminal headrace abutment. An access bridge spans the upstream end of the headrace and is not considered a water retaining structure. The powerhouse is located downstream of the spillway, at the downstream end of the headrace, and returns flow to the river in a cross channel direction. The powerhouse contains ten (10) operating Leffel Type Z and S turbine generators rated at 0.4 to 0.5 MW each, installed in 1996.

AEP recently contracted S&L to prepare conceptual demolition cost estimates considering three (3) retirement options defined as follows: (1) Option 1, Non-Power Operation, (2) Option 2, Partial Removal of the Dam Structures, and (3) Option 3, Complete Removal of the Dam and Powerhouse. Also, in addition S&L was requested to prepare a separate Asbestos Removal Conceptual Cost Estimate.

The objective of the conceptual demolition cost estimates is to determine the gross demolition costs for Buchanan Hydroelectric Plant (including gross salvage credits and any other benefits), in support of documenting a component of future AEP book depreciation rates to be approved by the I&M's state commissions and potential future inclusion in submittal of a rate case to the state commissions, and other potential uses. The cost estimate considers the demolition/dismantlement methodology which complies with current OSHA rules and regulations.

## 2.0 COST ESTIMATE SUMMARY

Conceptual Demolition Cost Estimate No. 33706B, dated February 12, 2016, was prepared and is included as Exhibit 2. This cost estimate was prepared for retirement option 3, but includes accounts allowing the determination of cost estimates for retirement options 1 and 2 as well. A summary of the conceptual demolition cost estimates for all three (3) retirement options is provided in Exhibit 1 and detailed in the following tables.



The cost estimate is structured into a code of accounts as identified in Table 2-1.

Account Number	Description
10, 21, 22	Demolition Costs (including steel, equipment & piping scrap value)
18	Scrap Value Costs
91	Other Direct & Construction Indirect Costs
93	Indirect Costs
94	Contingency Costs
96	Escalation Costs

 Table 2-1

 Cost Estimate Code of Accounts

The results of the cost estimate for retirement option 3 are provided in Table 2-2 below.

# Table 2-2Cost Estimate Results SummaryRetirement Option 3

Description	Total Cost
Demolition Cost	\$6,045,099
Scrap Value	(\$161,882)
Direct Cost Subtotal	\$5,883,217
Indirect Cost	\$599,000
Contingency Cost	\$1,343,000
Escalation Cost	\$0
Total Project Cost	\$7,825,217



The results of the cost estimate for retirement option 1 are provided in Table 2-3 below.

Description	Total Cost	
Demolition Cost	\$149,377	
Scrap Value	(\$80,344)	
Direct Cost Subtotal	\$69,033	
Indirect Cost	\$7,000	
Contingency Cost	\$42,600	
Escalation Cost	\$0	
Total Project Cost	\$118,633	

# Table 2-3Cost Estimate Results SummaryRetirement Option 1

The results of the cost estimate for retirement option 2 are provided in Table 2-4 below.

# Cost Estimate Results Summary Retirement Option 2

Description	Total Cost	
Demolition Cost	\$4,143,050	
Scrap Value	(\$81,466)	
Direct Cost Subtotal	\$4,061,584	
Indirect Cost	\$414,000	
Contingency Cost	\$918,600	
Escalation Cost	\$0	
Total Project Cost	\$5,394,184	

Page 3 of 9 \\Snl6c\data6\AEPFossil\Rockport\_Tanners Creek CDCEU 2015\6.0 Evaluations-Reports\6.06 Studies\Buchanan\Buchanan Hydro\_Conceptual Demolition Cost Estimate\_No 33706\_Rev 0.doc



Buchanan Hydroelectric Plan Indiana Michigan Power Company American Electric Power Service Corporation Conceptual Demolition Cost Estimate February 12, 2016

Asbestos Removal Conceptual Cost Estimate No. 33738B, dated February 12, 2016, was prepared and is included as Exhibit 3. The total estimated cost for asbestos removal prior to plant dismantlement is \$55,200. Quantities were derived from drawings and past experience. Asbestos removal applies to the powerhouse, thus the removal cost applies to all three (3) retirement options. The cost of asbestos removal is excluded from the total conceptual demolition cost estimates for each retirement option detailed in the tables above.

### 3.0 TECHNICAL BASIS

The scope of dismantlement is based on three (3) retirement options, as requested by AEP, as follows:

<u>Retirement Option 1, Non-Power Operation:</u> This scenario would consider leaving intact all of the existing water-impounding structures and the powerhouse. Only the electric generating units and their auxiliary equipment would be removed so as to preclude the generation of electricity by the former hydroelectric plant. In addition, the spillway would be modified as required in order to pass river flows and maintain the impoundment's water surface elevation at the current conditions.

<u>Retirement Option 2, Partial Removal of the Dam Structures:</u> This scenario would consider demolition and removal of certain elements of the hydroelectric site in order to drain the existing impoundment and create a natural river channel through the dam site. This would generally include removal of the generating units and powerhouse and possibly but not inclusively demolition and removal of substantial portions of concrete spillway structures. This option would address the removal and stabilization of any sediments that have accumulated at the upstream end of the dam and the stabilization of the newly exposed reservoir/riverbanks.

<u>Retirement Option 3, Complete Removal of the Dam and Powerhouse:</u> This scenario would consider complete removal of the electric generating components and powerhouse and complete removal of the dam. Similar to option 2, this option would address the removal and stabilization of any sediments that have accumulated at the upstream end of the dam and the stabilization of the newly exposed reservoir/riverbanks.

The scope of dismantlement for each retirement option, as interpreted from the definitions above, are identified on marked plant drawings included as Exhibit 4. The scope of dismantlement and the sequence of demolition for each retirement option are defined on these sketches.



Buchanan Hydroelectric Plant Indiana Michigan Power Company American Electric Power Service Corporation Conceptual Demolition Cost Estimate February 12, 2016

Retirement options 2 and 3 include the same demolition work as retirement option 1, removal of the generating unit components from the powerhouse. The powerhouse is not removed in retirement option 1, but is removed in retirement option 3. For retirement option 2 the powerhouse may or may not be removed, depending on if removal of portions of the dam can restore river flow to natural flow without removing the powerhouse (refer to Exhibit 4).

For each of the retirement options the scope of sediment removal is based on the quantity that would be disturbed from the demolition work itself and not complete removal of all sediment potentially disturbed by the partial or complete removal of the dam. The subcontractor costs included in retirement options 2 and 3 are for lime stabilization of the sediment and removal of the sediment and other wastes (such as timber) to the waste disposal site. These costs do not apply to retirement option 1 since only generating unit components in the powerhouse are removed and this material has scrap value.

Retirement options 2 and 3 include the stabilization of newly exposed riverbanks, which include the dam area and areas upstream of the dam. The extent of stabilization for retirement option 3 may be slightly more than retirement option 2, since the entire dam is being removed in retirement option 3.

The following are excluded from the scope of the conceptual demolition cost estimates:

- Asbestos removal (separate cost estimate prepared).
- The conceptual demolition cost estimate includes the cost to remove the one (1) main power transformer located in the switchyard, but not the cost to remove the switchyard itself (and remaining components in the switchyard).
- > The existing fish ladder and access bridge will remain in place.
- > Evaluation of the effect of the complete removal of the series of dams on the river watershed.
- Evaluation of the effect of the removal of any one dam, on either the upstream or downstream side dam and reservoir, after removal of the dam.
- Potential social or environmental impact of the draining of the reservoirs and the impact on property values or other community impact.
- The conceptual demolition cost estimate excludes any costs related to performing surveys to quantify the amount of sediment and chemical testing of the sediment. The quantity of sediment to be removed was estimated for retirement options 2 and 3 and the cost to remove the sediment is included in the conceptual demolition cost estimate. As stated above, the scope of sediment removal is based on the quantity that would be disturbed from the demolition work itself and not complete removal of the sediment potentially disturbed by the partial or complete removal of the dam.

Page 5 of 9



Indiana Michigan Power Company Attachment JAC-3 Witness; Cash Buchanan Hydroelectric Plant Indiana Michigan Power Company American Electric Power Service Corporation Conceptual Demolition Cost Estimate February 12, 2016

The scope of the demolition cost estimate was reaffirmed during a review of the facility by two S&L employees in conjunction with a representative from Bradenburg Industrial Service Co. and AEP corporate and plant personnel. The facility review was held on Wednesday December 16, 2015.

#### 4.0 COMMERCIAL BASIS

#### 4.1 General Information

The Conceptual Demolition Cost Estimates prepared for the Buchanan Hydroelectric Plant is a conceptual estimate of the cost to dismantle the powerhouse and dam in accordance with the scope defined for each of the three (3) retirement options. Costs were calculated for (1) demolition of existing plant structures and equipment and associated site restoration costs, (2) scrap value of steel, copper and stainless steel, as applicable, (3) associated indirect costs, and (4) contingency.

All units used in the cost estimate are U.S. Standard and all costs are in US Dollars (4<sup>th</sup> Quarter 2015 levels). A three (3) year demolition schedule is anticipated for retirement option 3 including asbestos removal (to be performed prior to start of demolition work). The schedule takes into consideration environmental permitting, asbestos removal which includes mapping out all asbestos contamination throughout the powerhouse and associated abatement, followed by total plant demolition and site restoration. The schedule for the other two (2) retirement options would be correspondingly less.

#### 4.2 Quantities/Material Cost

Quantities of pieces of equipment and/or bulk material commodities used in the cost estimates were intended to be reasonable and representative of projects of this type. Material quantities were estimated from the hydroelectric plant drawings and data provided by AEP, and the information obtained from Plant personnel during the facility review.

#### 4.3 Construction Labor Wages

Craft labor rates (Craft Hourly Rate) for the cost estimate were calculated as Union Labor rates for South Bend, Indiana, based on 2015, R. S. Means "Labor Rates for the Construction Industry". The craft rates were incorporated into work crews appropriate for the activities by adding allowances for small tools, construction equipment, insurance, and site overheads to arrive at crew hourly rates detailed in the cost estimate. A 1.10 regional labor productivity multiplier was included based on Compass International Global Construction Yearbook, 2015 Edition, for union work in Indiana. National Maintenance

Page 6 of 9



Agreement Rates (typically negotiated by AEP) do not apply as this work is assumed to be performed as a lump sum contract.

#### 4.3.1 Labor Work Schedule and Incentives

The estimate assumed a 5x8 work week. No per diem or other labor incentives are included.

#### 4.3.2 Construction Indirects

Allowances were included in the cost estimate as direct costs as noted for the following:

- Freight: Material and scrap freight included in the material and scrap costs.
- Additional Crane Allowance: None included. Cost of cranes and construction machinery are included in the labor wage rates.
- Mobilization and Demobilization: Included in labor wage rates.
- Scaffolding: Included in labor wage rates.
- Consumables: Included in material and labor costs.
- > Per Diem Costs: Excluded from the estimate.
- Contractor's General and Administrative Costs and Profit: Included in the labor wage rates.

#### 4.4 Scrap Value

The value of scrap was determined by a 3 month average (November and December 2015 and January 2016) using Zone 4 (USA Midwest) of the "Scrap Metals Market Watch" (<u>www.americanrecycler.com</u>).

Since the values obtained are delivered pieces, 25% of the values obtained were deducted to pay for separation, preparation and shipping to the mills. This resulted in realized prices of:

- Mixed Steel Value @ \$118/Ton
- Copper Value @ \$3,180/Ton
- Stainless Steel @ \$675/Ton
- <u>Note:</u> 1 Ton = 2,000 Lbs

All steel is considered to be mixed steel unless otherwise noted.

Page 7 of 9



#### 4.5 Indirect Costs

Allowances were included in the cost estimate as indirect costs as noted for the following:

- > Engineering, Procurement and Project Services: None included.
- Construction Management Support: None included.
- Owners Cost: Included as 10.0% of the total direct cost. Owners Costs include owner project engineering, administration and construction management, permits and fees, legal expenses, taxes, removal of chemicals, etc.

#### 4.6 Escalation

No allowance for escalation was included in the cost estimate. All costs are determined in 4<sup>th</sup> Quarter

2015 levels.

#### 4.7 Contingency

Allowances were included in the cost estimate as contingency as noted for the following:

- Scrap Value: Included as 15.0% reduction in the salvage value resulting in a total net reduction in the salvage value. The contingency assumes a potential drop in salvage value thus increasing the project cost. Scrap costs are very volatile but by taking a 3-month average some of the effect of volatility is reduced. However there are other variables that affect scrap pricing such as the quantity and processing fees. The contingency applied is based on the estimators confidence in scrap pricing used in the demolition cost estimate.
- Material: Included as 20.0% of the total material cost.
- Labor: Included as 20.0% of the total labor cost.
- ▶ Indirect: Included as 20.0% of the total indirect cost.
- Subcontractor: Included as 20.0% of the total subcontractor cost.

#### 4.8 Assumptions

The following assumptions apply to the cost estimates.

- The cost estimate for each retirement option is based on the scope and the demolition sequences defined on the sketches provided in Exhibit 4.
- All chemicals will be removed by the Owner prior to demolition, from the facilities to be demolished.

#### \\Snl6c\data6\AEPFossil\Rockport\_Tanners Creek CDCEU 2015\6.0 Evaluations-Reports\6.06 Studies\Buchanan\Buchanan\Hydro\_Conceptual Demolition Cost Estimate\_No 33706\_Rev 0.doc



Buchanan Hydroelectric Plane<sup>46 of 205</sup> Indiana Michigan Power Company American Electric Power Service Corporation Conceptual Demolition Cost Estimate February 12, 2016

- All electrical equipment and wiring is de-energized prior to start of dismantlement, except for that required for remote operation of the sluice and crest gates after demolition is completed for retirement option 1. There are two (2) sluice gates on the dam and three (3) hydraulically operated crest gates used to regulate the reservoir elevation.
- > No extraordinary environmental costs for demolition have been included.
- Handling, on-site and off-site disposal of hazardous materials would be performed in compliance with methods approved by Owner.
- The window glazing in the powerhouse may be asbestos contaminated and an allowance for removal and disposal is included in the asbestos removal cost estimate. There are twenty (20) control boards mounted on 3' x 9' transite (asbestos) panels and an allowance for removal and disposal is included in the asbestos removal cost estimate. There is no building or pipe insulation in the facility and consequently no insulation related asbestos contamination.
- Switchyards within the plant boundaries are not part of the scope, neither are access roads to these facilities. Fences and gates needed to protect the switchyard will be left in place.
- All demolished materials are considered debris, except for organic combustibles and nonembedded metals which have scrap value.
- The basis for salvage estimating is for scrap value only. No resale of equipment or material is included.
- Sediment removed due to demolition work is treated with lime and hauled offsite to an approved waste disposal facility.

### 5.0 **REFERENCES**

- 5.1 Buchanan Plant Drawings: One-Line Diagrams, No. 1-12001-0 and No. E-1000, Revision 8.
- **5.2** Findlay Engineering, Inc., Supporting Technical Information Document, Buchanan Hydroelectric Project, August, 2005.



Indiana Michigan Power Company Attachment JAC-3 Witness; Cash Buchanan Hydroelectric Plant Indiana Michigan Power Company American Electric Power Service Corporation Conceptual Demolition Cost Estimate February 12, 2016

## EXHIBIT 1 Buchanan Hydroelectric Plant Conceptual Demolition Cost Estimate Summary

\\Snl6c\data6\AEPFossil\Rockport\_Tanners Creek CDCEU 2015\6.0 Evaluations-Reports\6.06 Studies\Buchanan\Buchanan Hydro\_Conceptual Demolition Cost Estimate\_No 33706\_Rev 0.doc



	Retirement Option 1		Retirement Option 2			Retirement Option 3		
Demolition Cost	\$	149,377	\$	4,143,050	\$	6,045,099		
Scrap Value	\$	(80,344)	\$	(81,466)	\$	(161,882)		
Direct Cost Subtotal	\$	69,033	\$	4,061,584	\$	5,883,217		
Indirect Cost	\$	7,000	\$	414,000	\$	599,000		
Contingency Cost	\$	42,600	\$	918,600	\$	1,343,000		
Escalation Cost	\$	-	\$	-	\$	-		
Total Demolition Cost	\$	118,633	\$	5,394,184	\$	7,825,217		



Indiana Michigan Power Company Attachment JAC-3 Witness; Cash Buchanan Hydroelectric Plant Indiana Michigan Power Company American Electric Power Service Corporation Conceptual Demolition Cost Estimate February 12, 2016

## EXHIBIT 2 Buchanan Hydroelectric Plant Conceptual Demolition Cost Estimate No. 33706B

\\Snl6c\data6\AEPFossil\Rockport\_Tanners Creek CDCEU 2015\6.0 Evaluations-Reports\6.06 Studies\Buchanan\Buchanan\Buchanan\Hydro\_Conceptual Demolition Cost Estimate\_No 33706\_Rev 0.doc



Indiana Michigan Power Company Attachment JAC-3 Witness; Cash Page 50 of 205

Client	AEP
Estimator	RCK
Labor rate table	15INSOU
Project No.	13465-000
Station Name	BUCHANAN
Unit	ALL
Estimate Date	02/12/2016
<b>Reviewed By</b>	ADC
Approved By	MNO
Estimate No.	33706B
Estimate Class	Conceptual
Cost index	INSOU

Estimate No.: 33706B Project No.: 13465-000 Estimate Date: 02/12/2016 Prep/Rev/App: RCK/ADC/MNO

Area	Description	Subcontract Cost	Scrap Value	Material Cost	Man Hours	Labor Cost	Total Cost
ACCOUNT A	DEMOLITION ACCOUNT A		(80,344)	27,930	1,404	121,447	69,033
ACCOUNT B	DEMOLITION ACCOUNT B	865,700	(1,122)	1,830,118	17,340	1,297,855	3,992,551
ACCOUNT C	DEMOLITION ACCOUNT C	489,000	(80,416)	(2,945)	15,823	1,415,994	1,821,633
	TOTAL DIRECT	1,354,700	(161,882)	1,855,103	34,568	2,835,296	5,883,218

#### **Estimate Totals**

Direct Costs:			
Labor	2,835,296		34,568
Material	1,855,103		
Subcontract	1,354,700		
Scrap Value	(161,882)		
	5,883,217	5,883,217	
Other Direct & Construction			
Indirect Costs:			
91-1 Scaffolding			
91-2 Cost Due To OT 5-10's			
91-3 Cost Due To OT 6-10's			
91-4 Per Diem			
91-5 Consumables			
91-8 Freight on Material			
91-9 Freight on Process Equip			
91-10 Sales Tax			
91-11 Contractors G&A			
91-12 Contractors Profit			
		5,883,217	
Indirect Costs:			
93-1 Engineering Services			
93-2 CM Support			
93-3 Start-Up/Commissioning			
93-4 Start-Up/Spare Parts			
93-5 Excess Liability Insur. 93-6 Sales Tax On Indirects			
93-7 Owners Cost	599,000		
93-8 EPC Fee	333,000		
	599,000	6,482,217	
Contingency:			
94-1 Contingency on Material	371,000		
94-2 Contingency on Labor	557,000		
94-3 Contingency on Sub.	271,000		
94-6 Contingency on Scrap	24,000		
94-5 Contingency on Indirect	120,000		
	1,343,000	7,825,217	
Escalation:			
96-1 Escalation on Const Equip 96-2 Escalation on Engr Equip			
96-2 Escalation on Endr Eduld 96-1 Escalation on Material			
96-2 Escalation on Labor			
96-3 Escalation on Subcontract			
96-4 Escalation on Process Eq			
96-5 Escalation on Indirects			
		7,825,217	
		7,825,217	
		7,023,217	

										Subcontract		
Area	Group	Phase	Description	Notes	Quantity	Man Hours	Crew Rate	Labor Cost	Material Cost	Cost	Scrap Value	Total Cost
ACCOUNT A	40.00.00		DEMOLITION ACCOUNT A									
	10.00.00	10.31.00	WHOLE PLANT DEMOLITION MECHANICAL EQUIPMENT									
		10.31.00	DEMO .6 MW GENERATOR	10 GENERATORS AT 9500# EA	47.50 TN	470	85.53 /MH	40,225				40.225
			DEMO TURBINE AND GEARS	10 GENERATORS AT 14000# EA	70.00 TN	693	85.53 /MH	59,278		-		59,278
			TURBINE ROOM 8.8 TON OVERHEAD CRANE		8.00 TN	79	121.33 /MH	9,610		-		9,610
			MECHANICAL EQUIPMENT WHOLE PLANT DEMOLITION			1,243		109,113 109,113				<u>109,113</u> 109,113
			WHOLE PLANT DEMOLITION			1,243		109,113				109,113
	18.00.00		SCRAP VALUE									
		18.10.00	MIXED STEEL									
			MIXED STEEL	104 & .5 MW GENERATOR, 10 @5,225#	-26.10 TN		79.62 /MH		-	-	(3,082)	(3,082)
			MIXED STEEL	EA DEMO TURBINE AND GEARS	-70.00 TN		79.62 /MH		-	-	(8,266)	(8,266)
			MIXED STEEL	TURBINE ROOM 8.8 TON OVERHEAD CRANE	-8.00 TN		79.62 /MH		-	-	(945)	(945)
			MIXED STEEL								(12,292)	(12,292)
		18.30.00	COPPER									
		10.00.00	COPPER	10 .4 &.5 MW GENERATOR 10@ 4,275 LB EA	-21.40 TN		79.62 /MH		-	-	(68,052)	(68,052)
			COPPER								(68,052)	(68,052)
			SCRAP VALUE								(80,344)	(80,344)
	22.00.00		CONCRETE									
	22.00.00	22.13.00	Concrete									
			FLOWABLE FILL, 1500 PSI	FILL PENSTOCKS TO PREVENT BYPASS	294.00 CY	162	76.27 /MH	12,334	27,930	-	-	40,264
			Concrete	FLOW		162		12,334	27,930			40,264
			CONCRETE			162		12,334	27,930			40,264
			ACCOUNT A DEMOLITION ACCOUNT A			1,404		121,447	27,930		(80,344)	69,033
ACCOUNT B			DEMOLITION ACCOUNT B									
	10.00.00	40.00.00	WHOLE PLANT DEMOLITION									
		10.22.00	CONCRETE EQUIPMENT/ BUILDING FOUNDATION	SLUICE GATE CREST 16'X6'X7.7'	27.00 CY	33	89.94 /MH	3,005				3,005
			EQUIPMENT/ BUILDING FOUNDATION	RIGHT GATE CREST 137.85X6'X7.7'	236.00 CY	292	89.94 /MH	26,270				26,270
			EQUIPMENT/ BUILDING FOUNDATION	CENTER GATE APRON 127.9X6X3.5	99.00 CY	123	89.94 /MH	11,020		-	-	11,020
			EQUIPMENT/ BUILDING FOUNDATION	LEFT GATE CREST 92.44X6'X7.7	158.00 CY	196	89.94 /MH	17,587		-		17,587
			CONCRETE			644		57,882				57,882
		10.23.00	STEEL									
			STRUCTURAL AND GIRT STEEL	HEADRACE BRIDGE - LEFT IN PLACE	0.00 TN		79.62 /MH			-	-	
		10.31.00	MECHANICAL EQUIPMENT 80 KW PROPANE ELECTRIC GENERATOR		1.50 TN	3	121.33 /MH	405				405
			SLUICE GATES	2 AT 4 TONS EACH	8.00 TN	18	121.33 /MH	2,162		-		2,162
			MECHANICAL EQUIPMENT			21		2,568				2,568
			WHOLE PLANT DEMOLITION			665		60,450				60,450
	18.00.00		SCRAP VALUE									
	10.00.00	18.10.00	MIXED STEEL									
			MIXED STEEL	80 KW PROPANE ELECTRIC GENERATOR	-1.50 TN		79.62 /MH		-	-	(177)	(177)
			MIXED STEEL	SLUICE GATES	-8.00 TN		79.62 /MH		-	-	(945)	(945)
			MIXED STEEL SCRAP VALUE								(1,122)	(1,122)
			SCRAF VALUE								(1,122)	(1,122)
	21.00.00		CIVIL WORK									
		21.17.00	Earthwork, Excavation									
			FOUNDATION EXCAVATION, CLAY USING 1 CY BACKHOE	RIVERBED EXCAVATION FOR RIPRAP	152.00 CY	28	88.08 /MH	2,504		-		2,504 2,504
			Earthwork, Excavation			28		2,504				2,504
		21.41.00	Erosion and Sedimentation Control									
			RIPRAP, RANDOM BROKEN STONE, MACHINE PLACED	FOR CAUSEWAYS	5,156.00 CY	1,684	74.10 /MH	124,789	210,880	-	-	335,670
			RIPRAP, RANDOM BROKEN STONE, MACHINE PLACED RIPRAP, RANDOM BROKEN STONE, MACHINE PLACED	RIPRAP PROTECTION CREDIT FOR REUSE OF CAUSEWAY STONE	38,100.00 CY -5,156.00 CY	12,444	74.10 /MH 74.10 /MH	922,124	1,558,290 (210,880)	-	-	2,480,414 (210,880)
			RIPRAP, RANDOM BROKEN STONE, MACHINE PLACED RIPRAP, RANDOM BROKEN STONE, MACHINE PLACED	RIPRAP PROTECTION AT SPILLWAY FLOOR	-5,156.00 CY 152.00 CY	50	74.10 /MH 74.10 /MH	3,679	(210,880) 6,217	-	-	(210,880) 9,896
			,	SLAB				2,570	-,			2,230

										0.1		
Area	Group	Phase	Description	Notes	Quantity	Man Hours	Crew Rate	Labor Cost	Material Cost	Subcontract Cost	Scrap Value	Total Cost
			Erosion and Sedimentation Control			14,178		1,050,593	1,564,507			2,615,099
		21.47.00	LANDSCAPING									
			HYDRO OR AIR SEED & MULCH & FERTILIZER		174.00 AC	2,469	74.64 /MH	184,309	265,611	-	-	449,920
			LANDSCAPING			2,469		184,309	265,611			449,920
		21.65.00	Soil Remediation									
			REMOVAL OF LOCALIZED SILT AT DAM	LIME ADDITIVE FOR DRYING	3,935.00 CY		196.64 /MH			157,400	-	157,400
			REMOVAL OF LOCALIZED SILT AT DAM	LOAD, MIX AND HAUL LIME AND SEDIMENT MIX (7870+3935)	11,805.00 CY		196.64 /MH			708,300	-	708,300
			Soil Remediation							865,700		865,700
			CIVIL WORK			16,676		1,237,405	1,830,118	865,700		3,933,223
			ACCOUNT B DEMOLITION ACCOUNT B			17,340		1,297,855	1,830,118	865,700	(1,122)	3,992,551
ACCOUNT C			DEMOLITION ACCOUNT C									
	10.00.00		WHOLE PLANT DEMOLITION									
		10.22.00	CONCRETE									
			EQUIPMENT/ BUILDING FOUNDATION EQUIPMENT/ BUILDING FOUNDATION	SLUICE GATE APRON 16'X34'X6' SLUICE GATE THROAT 16'X34'X6'	121.00 CY 121.00 CY	150 150	89.94 /MH 89.94 /MH	13,469 13,469		-	-	13,469 13,469
			EQUIPMENT/ BUILDING FOUNDATION	RIGHT GATE APRON 137.85X34'X6'	1,042.00 CY	1,290	89.94 /MH 89.94 /MH	13,469			-	13,469
			EQUIPMENT/ BUILDING FOUNDATION	RIGHT GATE THROAT 137.85X34'X6'	1,042.00 CY	1,290	89.94 /MH	115,987				115,987
			EQUIPMENT/ BUILDING FOUNDATION	1 CENTER GATE APRON 127.9X30X4.5	640.00 CY	792	89.94 /MH	71,240		-	-	71,240
			EQUIPMENT/ BUILDING FOUNDATION	2 CENTER GATE APRON 127.9X30X4.5	640.00 CY	792	89.94 /MH	71,240		-	-	71,240
			EQUIPMENT/ BUILDING FOUNDATION	CENTER GATE THROAT 127.9X40'X10'	1,895.00 CY	2,345	89.94 /MH	210,936		-	-	210,936
			EQUIPMENT/ BUILDING FOUNDATION	LEFT GATE APRON 92.44X34X6'	698.00 CY	864	89.94 /MH	77,696		-	-	77,696
			EQUIPMENT/ BUILDING FOUNDATION GENERATOR HOUSE	LEFT GATE THROAT 92.44X34X6'	698.00 CY 2,890.00 CY	864 3,577	89.94 /MH 89.94 /MH	77,696 321,691		-	-	77,696 321,691
			CONCRETE		2,090.00 C1	12,113	69.94 /IVIH	1,089,409		-	-	1,089,409
		10.23.00	STEEL									
		10.23.00	STEEL STRUCTURAL AND GIRT STEEL	GENERATOR HOUSE	221.00 TN	247	79.62 /MH	19,667				19,667
			STEEL		221.00	247	10.02	19,667				19,667
		10.24.00	ARCHITECTURAL									
			GENERATOR HOUSE	272.5'X30'X60'TALL	490,500.00 CF	2,104	89.81 /MH	189,001		-	-	189,001
			ARCHITECTURAL			2,104		189,001				189,001
		10.31.00	MECHANICAL EQUIPMENT									
			DEMO PENSTOCKS	10 GENERATORS AT 11,800# EA	59.00 TN	584	85.53 /MH	49,963		-		49,963
			BAR RACKS	10 AT 5 TONS EACH	50.00 TN	111	121.33 /MH	13,514		-		13,514
			STOP LOGS	10 AT 5 TONS EACH	50.00 TN	111	121.33 /MH	13,514		-		13,514
			MECHANICAL EQUIPMENT			807		76,992				76,992
		10.41.00	ELECTRICAL EQUIPMENT GENERATOR BUS TRANSFORMERS	2.4 to 34.5 KV, 2.67 MVA (STEEL)	3.40 TN	10	80.14 /MH	801				801
			GENERATOR BUS TRANSFORMERS	2.4 to 34.5 KV, 2.67 MVA (CU)	1.85 TN	5	80.14 /MH	436				436
			MISCELLANEOUS ELECTRICAL EQUIPMENT		5.00 TN	15	80.14 /MH	1,178		-	-	1,178
			ELECTRICAL EQUIPMENT			30		2,415				2,415
		10.86.00	WASTE									
			WASTE - USER DEFINED	MISC	1.00 LS	0	121.33 /MH	13		-	10,000	10,013
			WASTE WHOLE PLANT DEMOLITION			0 15,301		13 1,377,498			<u>10,000</u> 10,000	10,013 1,387,498
	18.00.00	40.40.00	SCRAP VALUE									
		18.10.00	MIXED STEEL		50.00 TH		70.00 4411				(0.007)	(0.007)
			MIXED STEEL MIXED STEEL	DEMO PENSTOCKS BAR RACKS	-59.00 TN -50.00 TN		79.62 /MH 79.62 /MH		-	-	(6,967) (5,904)	(6,967)
			MIXED STEEL MIXED STEEL	STOP LOGS	-50.00 TN		79.62 /MH 79.62 /MH		-	-	(5,904)	(5,904) (5,904)
			MIXED STEEL	GENERATOR HOUSE	-122.60 TN		79.62 /MH		-		(14,477)	(14,477)
			MIXED STEEL	GENERATOR BUS TRANSFORMERS	-3.40 TN		79.62 /MH		-	-	(401)	(401)
			MIXED STEEL								(33,653)	(33,653)
		18.30.00	COPPER									
			COPPER	CABLE	-10.00 TN		79.62 /MH		-	-	(31,800)	(31,800)
			COPPER COPPER	MISC. TRANSFORMERS & MOTORS UNIT 1 GENERATOR BUS TRANSFORMERS	-6.00 TN -1.85 TN		79.62 /MH 79.62 /MH		-	-	(19,080)	(19,080)
			UUFFEK	GENERATOR BUS TRANSFORMERS	-1.85 IN		79.62 /MH		-	-	(5,883)	(5,883)

Area	Group	Phase	Description	Notes	Quantity	Man Hours	Crew Rate	Labor Cost	Material Cost	Subcontract Cost	Scrap Value	Total Cost
			COPPER								(56,763)	(56,763)
			SCRAP VALUE								(90,416)	(90,416)
	21.00.00		CIVIL WORK									
		21.17.00	Earthwork, Excavation									
			FOUNDATION EXCAVATION, CLAY USING 1 CY BACKHOE	RIVERBED CREDIT EXCAVATION FOR RIPRAP (152-95)	-55.00 CY	-10	88.08 /MH	(906)		-	-	(906)
			Earthwork, Excavation			-10		(906)				(906)
		21.41.00	Erosion and Sedimentation Control									
			RIPRAP, RANDOM BROKEN STONE, MACHINE PLACED	ADDITIONAL CAUSEWAY RIPRAP FOR PHASE 3	1,700.00 CY	555	74.10 /MH	41,145	69,530	-	-	110,675
			RIPRAP, RANDOM BROKEN STONE, MACHINE PLACED	ADDITIONAL CREDIT FOR REUSE OF PHASE 3 CAUSEWAY STONE	-1,700.00 CY		74.10 /MH		(69,530)	-	-	(69,530)
			RIPRAP, RANDOM BROKEN STONE, MACHINE PLACED	RIPRAP PROTECTION AT RETAINING WALLS - CREDIT (152-80)	-72.00 CY	-24	74.10 /MH	(1,743)	(2,945)	-	-	(4,687)
			Erosion and Sedimentation Control			532		39,402	(2,945)			36,457
		21.65.00	Soil Remediation									
			REMOVAL OF LOCALIZED SILT AT DAM	ADDITIONAL LIME ADDITIVE FOR DRYING PHASE 3 (6158-3935)	2,223.00 CY		196.64 /MH			88,920	-	88,920
			REMOVAL OF LOCALIZED SILT AT DAM	ADDITIONAL LOAD, MIX AND HAUL LIME AND SEDIMENT MIX PHASE 3 (18473-11805)	6,668.00 CY		196.64 /MH			400,080	-	400,080
			Soil Remediation							489,000		489,000
			CIVIL WORK			521		38,496	(2,945)	489,000		524,551
			ACCOUNT C DEMOLITION ACCOUNT C			15,823		1,415,994	(2,945)	489,000	(80,416)	1,821,633



Indiana Michigan Power Company Attachment JAC-3 Witness; Cash Buchanan Hydroelectric Plant Indiana Michigan Power Company American Electric Power Service Corporation Conceptual Demolition Cost Estimate February 12, 2016

## EXHIBIT 3 Buchanan Hydroelectric Plant Asbestos Removal Conceptual Cost Estimate No. 33738B

\\Snl6c\data6\AEPFossil\Rockport\_Tanners Creek CDCEU 2015\6.0 Evaluations-Reports\6.06 Studies\Buchanan\Buchanan Hydro\_Conceptual Demolition Cost Estimate\_No 33706\_Rev 0.doc

Indiana Michigan Power Company Attachment JAC-3 Witness; Cash Page 57 of 205

### AEP BUCHANAN HYDROELECTRIC PLANT DISMANTLEMENT STUDY - ASBESTOS REMOVAL CONCEPTUAL COST ESTIMATE

Client	AEP
Estimator	RCK
Labor rate table	15INSOU
Project No.	13465-000
Station Name	BUCHANAN
Unit	ALL
Estimate Date	02/12/2016
Reviewed By	ADC
Approved By	MNO
Estimate No.	33738B
Estimate Class	Conceptual
Cost index	INSOU

Estimate No.: 33738B Project No.: 13465-000 Estimate Date: 02/12/2016 Prep/Rev/App: RCK/ADC/MNO

#### AEP BUCHANAN HYDROELECTRIC PLANT DISMANTLEMENT STUDY - ASBESTOS REMOVAL CONCEPTUAL COST ESTIMATE

Area	Description	Subcontract Cost	Scrap Value	Material Cost	Man Hours	Labor Cost	Total Cost
ASBESTOS	ASBESTOS REMOVAL TOTAL DIRECT	41,800 41,800					41,800 41,800

#### AEP BUCHANAN HYDROELECTRIC PLANT DISMANTLEMENT STUDY - ASBESTOS REMOVAL CONCEPTUAL COST ESTIMATE

#### **Estimate Totals**

Descri	ption Amount	Totals	Hours
Direct Costs:			
Labor			
Material Subcontract	41,800		
Subcontract Scrap Value	41,800		
Scrap value	41,800	41,800	
	41,000	41,000	
Other Direct & Construction			
Indirect Costs:			
91-1 Scaffolding 91-2 Cost Due To OT 5-10's			
91-3 Cost Due To OT 5-10's			
91-4 Per Diem			
91-5 Consumables			
91-8 Freight on Material			
91-9 Freight on Process Equip			
91-10 Sales Tax			
91-11 Contractors G&A			
91-12 Contractors Profit		44.000	
		41,800	
Indirect Costs:			
93-1 Engineering Services			
93-2 CM Support 93-3 Start-Up/Commissioning			
93-4 Start-Up/Spare Parts			
93-5 Excess Liability Insur.			
93-6 Sales Tax On Indirects			
93-7 Owners Cost	4,200		
93-8 EPC Fee	4,200	46,000	
<b>0</b>			
Contingency: 94-1 Contingency on Material			
94-2 Contingency on Labor			
94-3 Contingency on Sub.	8,400		
94-6 Contingency on Scrap			
94-5 Contingency on Indirect	800		
	9,200	55,200	
Escalation:			
96-1 Escalation on Const Equip			
96-2 Escalation on Engr Equip 96-1 Escalation on Material			
96-2 Escalation on Labor			
96-3 Escalation on Subcontract			
96-4 Escalation on Process Eq			
96-5 Escalation on Indirects			
		55,200	
		55,200	
Total		EE 200	
i Oldi		55,200	

#### AEP BUCHANAN HYDROELECTRIC PLANT DISMANTLEMENT STUDY - ASBESTOS REMOVAL CONCEPTUAL COST ESTIMATE


Area	Group	Phase	Description	Notes	Quantity	Man Hours	Crew Rate	Labor Cost	Material Cost	Subcontract Cost	Scrap Value	Total Cost
ASBESTOS	10.00.00	10.37.00	ASBESTOS REMOVAL WHOLE PLANT DEMOLITION ASBESTOS REMOVAL									
			ASBESTOS REMOVAL - MISC MATERIALS ASBESTOS REMOVAL - CONTROL /INSTRUMENT PANELS ASBESTOS REMOVAL	WINDOW CAULKING MISC MATERIALS 20 PANELS 1X3X9' TALL	2.00 CY 20.00 CY		121.33 /MH 121.33 /MH			3,800 38,000 <b>41,800</b>	-	3,800 38,000 <b>41,800</b>
			WHOLE PLANT DEMOLITION ASBESTOS ASBESTOS REMOVAL							<u>41,800</u> 41,800		41,800 41,800



## EXHIBIT 4 Buchanan Hydroelectric Plant Retirement Option 1-3 Demolition Scope and Sequence

\\Snl6c\data6\AEPFossil\Rockport\_Tanners Creek CDCEU 2015\6.0 Evaluations-Reports\6.06 Studies\Buchanan\Buchanan Hydro\_Conceptual Demolition Cost Estimate\_No 33706\_Rev 0.doc


Sargent & Lundy



40

60

100 FEET



PHASE 1

- (1) INSTALL STOPLOGS
- **(2) REMOVE EQUIPMENT**
- ③ REMOVE STOPLOGS


### PHASE 2

**④CONSTRUCT CAUSEWAY (5) DEMO SPILLWAY SECTIONS (6) PLACE RIPRAP PROTECTION ⑦REMOVE CAUSEWAY** 

## PHASE 3


③CONSTRUCT CAUSEWAY

- **9 DEMO SPILLWAY**
- <sup>10</sup> PLACE RIPRAP PROTECTION
- **11 REMOVE CAUSEWAY**
- <sup>12</sup>GROUT DRAFT TUBE





- (1) CONSTRUCT CAUSEWAY
- (2) DEMO POWERHOUSE AND LOG BOOM
- **③ REMOVE CAUSEWAY**
- PHASE 2
- (4) CONSTRUCT CAUSEWAY
- **5 DEMO SPILLWAY SECTIONS**
- <sup>(6)</sup> PLACE RIPRAP PROTECTION AT ABUTMENTS
- **⑦ REMOVE CAUSEWAY**





	BUCHANAN				
OPTION 2					
ITEM	QUANTITY	UNIT	REMARKS		
GRASS SEEDING	174	ACRE			
RIPRAP PROTECTION	38,100	CY	2 ft riprap protection @ D(50)=12"		
RIVERBED EXCAVATION FOR RIPRAP	152	CY	TO BE REPLACED BY RIPRAP		
RIPRAP PROTECTION AT SPILLWAY FLOOR SLAB	152	CY	2 ft riprap protection @ D(50)=12"		


	OPTION 3		
ITEM	QUANTITY	UNIT	REMARKS
GRASS SEEDING	174	ACRE	
RIPRAP PROTECTION	38,100	CY	2 ft riprap protection @ D(50)=12"
BASIN FILL	<del>86,100</del>	CY	
RIPRAP PROTECTION FOR CONCRETE REMOVAL	<del>4,180</del>	CY	2 ft riprap protection @ D(50)=12"
RIVERBED EXCAVATION FOR RIPRAP	95	СҮ	TO BE REPLACED BY RIPRAP
RIPRAP PROTECTION AT RETAINING WALLS	80	СҮ	2 ft riprap protection @ D(50)=12"
	GRASS SEEDING RIPRAP PROTECTION BASIN FILL RIPRAP PROTECTION FOR CONCRETE REMOVAL RIVERBED EXCAVATION FOR RIPRAP	ITEMQUANTITYGRASS SEEDING174RIPRAP PROTECTION38,100BASIN FILL86,100RIPRAP PROTECTION FOR CONCRETE REMOVAL4,180RIVERBED EXCAVATION FOR RIPRAP95	ITEMQUANTITYUNITGRASS SEEDING174ACRERIPRAP PROTECTION38,100CYBASIN FILL86,100CYRIPRAP PROTECTION FOR CONCRETE REMOVAL4,180CYRIVERBED EXCAVATION FOR RIPRAP95CY

JANUARY 25, 2016 PAGE 4 OF 7 Indiana Michigan Power Company Attachment JAC-3 Witness; Cash Page 65 of 205









Indiana Michigan Power Company JANUARY 25, 2014 trachment JAC-3 PAGE 7 OF 7 Witness; Cash Page 68 of 205 CRANE 20T 29'-0" 15'-0" GENERATOR EL.639.3 NORMAL HEADWATER EL.637.7 PII STOPLO FRAI EL.623.83 RACK HEADRACE T EL.619.08 DRAFT TUBE TUNNEL EL.612.23 DIFFUSER SECTION A-A UNITS 1-6 INCL. 10 8 6 4 2 0 CRANE 201 15'-0 14'-0" EL.639.3 NORMAL HEADWATER EL.637.7 RACH HEADRACE EL.623.83 EL.619.08 DRAFT TUBE TUNNEL EL.612.23 DIFFUSE SECTION B-B 0 8 8 4 2 0  $V_{RIPRAP} = (1244^{2}) (110 + 100) \times \frac{1}{27} = 95 \text{ cy}$   $V_{OUT} = (10) (110 + 100) \times \frac{1}{27} = 80 \text{ cy}$ EXHIBIT F SHEET 1 OF 2 INDIANA MICHIGAN POWER COMPANY BUCHANAN HYDROELECTRIC PROJECT NO.2551 MICHIGAN PLAN, ELEVATIONS AND SECTIONS FERC No. 2551-004-1



## Constantine Hydroelectric Plant CONCEPTUAL DEMOLITION COST ESTIMATE

Prepared for: Indiana Michigan Power Company (Owner) and American Electric Power Service Corporation

> Project No. 13465-000 February 12, 2016 Revision 0



55 East Monroe Street Chicago, IL 60603-5780 USA





Constantine Hydroelectric Plane<sup>e 70</sup> of 205 Indiana Michigan Power Company American Electric Power Service Corporation Conceptual Demolition Cost Estimate February 12, 2016

## **Issue Summary Page**

Revision Number	Date	Purpose	Prepared By	Reviewed By	Approved By	Pages Affected
A	01/29/16	Comments	R. C. Kinsinger	A.D. Chapin D. F. Franczak	M. N. Ozan	All
0	02/12/16	Use	R. C. Kinsinger RKinsinger HC	A.D. Chapin Hengin D. F. Franczak S. F. Trazo L	T. J. Meehan	All

\\Snl6c\data6\AEPFossil\Rockport\_Tanners Creek CDCEU 2015\6.0 Evaluations-Reports\6.06 Studies\Constantine\Constantine Hydro\_Conceptual Demolition Cost Estimate\_No 33707\_Rev 0.doc



**Section** 

Indiana Michigan Power Company Attachment JAC-3 Witness; Cash Constantine Hydroelectric Pland Indiana Michigan Power Company American Electric Power Service Corporation Conceptual Demolition Cost Estimate

February 12, 2016

#### TABLE OF CONTENTS

Sargent & Lundy

1	INTRODUCTION	1
2	COST ESTIMATE SUMMARY	1
3	TECHNICAL BASIS	4
4	COMMERICAL BASIS	6
4.1	General Information	6
4.2	Quantities/Material Cost	6
4.3	Construction Labor Wages	6
4.4	Scrap Value	7
4.5	Indirect Costs	8
4.6	Escalation	8
4.7	Contingency	8
4.8	Assumptions	8
5	REFERENCES	9

<u>EXHIBIT</u>	DESCRIPTION
1	Conceptual Cost Estimate Summary
2	Conceptual Demolition Cost Estimate No. 33707B
3	Asbestos Removal Conceptual Cost Estimate No. 33739B
4	Retirement Option 1-3 Demolition Scope and Sequence

TOC-1



Indiana Michigan Power Company Attachment JAC-3 Witness; Cash Constantine Hydroelectric Plant Indiana Michigan Power Company American Electric Power Service Corporation Conceptual Demolition Cost Estimate February 12, 2016

#### 1.0 INTRODUCTION

The Constantine Hydroelectric Plant located in the City of Constantine, Michigan is owned and operated by Indiana Michigan Power Company (I&M), a subsidiary of American Electric Power (AEP). The plant consists of (from left to right referenced facing downstream) a left abutment embankment section, a flashboard regulated spillway, a canal headgate structure, a power canal (headrace) flanked by earth embankments on either side of the canal, the powerhouse and a separate saddle dike on the left bank of the power canal. The powerhouse is located downstream of the spillway, at the downstream end of the headrace, and returns flow to the river. The powerhouse contains four (4) operating S. Morgan Francis turbine generators rated at 0.3 MW each, installed in 1923 or 1924.

AEP recently contracted S&L to prepare conceptual demolition cost estimates considering three (3) retirement options defined as follows: (1) Option 1, Non-Power Operation, (2) Option 2, Partial Removal of the Dam Structures, and (3) Option 3, Complete Removal of the Dam and Powerhouse. Also, in addition S&L was requested to prepare a separate Asbestos Removal Conceptual Cost Estimate.

The objective of the conceptual demolition cost estimates is to determine the gross demolition costs for Constantine Hydroelectric Plant (including gross salvage credits and any other benefits), in support of documenting a component of future AEP book depreciation rates to be approved by the I&M's state commissions and potential future inclusion in submittal of a rate case to the state commissions, and other potential uses. The cost estimate considers the demolition/dismantlement methodology which complies with current OSHA rules and regulations.

#### 2.0 COST ESTIMATE SUMMARY

Conceptual Demolition Cost Estimate No. 33707B, dated February 12, 2016, was prepared and is included as Exhibit 2. This cost estimate was prepared for retirement option 3, but includes accounts allowing the determination of cost estimates for retirement options 1 and 2 as well. A summary of the conceptual demolition cost estimates for all three (3) retirement options is provided in Exhibit 1 and detailed in the following tables.



The cost estimate is structured into a code of accounts as identified in Table 2-1.

Account Number	Description
10, 21, 22	Demolition Costs (including steel, equipment & piping scrap value)
18	Scrap Value Costs
91	Other Direct & Construction Indirect Costs
93	Indirect Costs
94	Contingency Costs
96	Escalation Costs

 Table 2-1

 Cost Estimate Code of Accounts

The results of the cost estimate for retirement option 3 are provided in Table 2-2 below.

# Table 2-2Cost Estimate Results SummaryRetirement Option 3

Description	Total Cost
Demolition Cost	\$3,711,338
Scrap Value	(\$92,058)
Direct Cost Subtotal	\$3,619,279
Indirect Cost	\$371,000
Contingency Cost	\$830,000
Escalation Cost	\$0
Total Project Cost	\$4,820,280



The results of the cost estimate for retirement option 1 are provided in Table 2-3 below.

Description	Total Cost	
Demolition Cost	\$238,539	
Scrap Value	(\$83,035)	
Direct Cost Subtotal	\$174,023	
Indirect Cost	\$17,000	
Contingency Cost	\$67,700	
Escalation Cost	\$0	
Total Project Cost	\$258,723	

# Table 2-3Cost Estimate Results SummaryRetirement Option 1

The results of the cost estimate for retirement option 2 are provided in Table 2-4 below.

# Cost Estimate Results Summary Retirement Option 2

Description	Total Cost
Demolition Cost	\$3,375,501
Scrap Value	(\$83,035)
Direct Cost Subtotal	\$3,292,465
Indirect Cost	\$337,000
Contingency Cost	\$755,000
Escalation Cost	\$0
Total Project Cost	\$4,384,465

Page 3 of 9 \\Snl6c\data6\AEPFossil\Rockport\_Tanners Creek CDCEU 2015\6.0 Evaluations-Reports\6.06 Studies\Constantine\Constantine Hydro\_Conceptual Demolition Cost Estimate\_No 33707\_Rev 0.doc



Constantine Hydroelectric Plant<sup>Page 75 of 205</sup> Indiana Michigan Power Company American Electric Power Service Corporation Conceptual Demolition Cost Estimate February 12, 2016

Asbestos Removal Conceptual Cost Estimate No. 33739B, dated February 12, 2016, was prepared and is included as Exhibit 3. The total estimated cost for asbestos removal prior to plant dismantlement is \$55,200. Quantities were derived from drawings and past experience. Asbestos removal applies to the powerhouse, thus the removal cost applies to all three (3) retirement options. The cost of asbestos removal is excluded from the total conceptual demolition cost estimates for each retirement option detailed in the tables above.

### 3.0 TECHNICAL BASIS

The scope of dismantlement is based on three (3) retirement options, as requested by AEP, as follows:

<u>Retirement Option 1, Non-Power Operation:</u> This scenario would consider leaving intact all of the existing water-impounding structures and the powerhouse. Only the electric generating units and their auxiliary equipment would be removed so as to preclude the generation of electricity by the former hydroelectric plant. In addition, the spillway would be modified as required in order to pass river flows and maintain the impoundment's water surface elevation at the current conditions.

<u>Retirement Option 2, Partial Removal of the Dam Structures:</u> This scenario would consider demolition and removal of certain elements of the hydroelectric site in order to drain the existing impoundment and create a natural river channel through the dam site. This would generally include removal of the generating units and powerhouse and possibly but not inclusively demolition and removal of substantial portions of concrete spillway structures. This option would address the removal and stabilization of any sediments that have accumulated at the upstream end of the dam and the stabilization of the newly exposed reservoir/riverbanks.

<u>Retirement Option 3, Complete Removal of the Dam and Powerhouse:</u> This scenario would consider complete removal of the electric generating components and powerhouse and complete removal of the dam. Similar to option 2, this option would address the removal and stabilization of any sediments that have accumulated at the upstream end of the dam and the stabilization of the newly exposed reservoir/riverbanks.

The scope of dismantlement for each retirement option, as interpreted from the definitions above, are identified on marked plant drawings included as Exhibit 4. The scope of dismantlement and the sequence of demolition for each retirement option are defined on these sketches.

Sargent & Lundy



Constantine Hydroelectric Plant Indiana Michigan Power Company American Electric Power Service Corporation Conceptual Demolition Cost Estimate February 12, 2016

Retirement options 2 and 3 include the same demolition work as retirement option 1, removal of the generating unit components from the powerhouse. The powerhouse is not removed in retirement option 1, but is removed in retirement option 3. For retirement option 2 the powerhouse may or may not be removed, depending on if removal of portions of the dam can restore river flow to natural flow without removing the powerhouse (refer to Exhibit 4).

For each of the retirement options the scope of sediment removal is based on the quantity that would be disturbed from the demolition work itself and not complete removal of all sediment potentially disturbed by the partial or complete removal of the dam. The subcontractor costs included in retirement options 2 and 3 are for lime stabilization of the sediment and removal of the sediment and other wastes (such as timber) to the waste disposal site. These costs do not apply to retirement option 1 since only generating unit components in the powerhouse are removed and this material has scrap value.

Retirement options 2 and 3 include the stabilization of newly exposed riverbanks, which include the dam area and areas upstream of the dam. The extent of stabilization for retirement option 3 may be slightly more than retirement option 2, since the entire dam is being removed in retirement option 3.

The following are excluded from the scope of the conceptual demolition cost estimates:

- Asbestos removal (separate cost estimate prepared).
- The conceptual demolition cost estimate includes the cost to remove the three (3) main power transformers located in the switchyard, but not the cost to remove the switchyard itself (and remaining components in the switchyard).
- > The separate brick storage building near the entrance road will remain in place.
- > Evaluation of the effect of the complete removal of the series of dams on the river watershed.
- Evaluation of the effect of the removal of any one dam, on either the upstream or downstream side dam and reservoir, after removal of the dam.
- Potential social or environmental impact of the draining of the reservoirs and the impact on property values or other community impact.
- The conceptual demolition cost estimate excludes any costs related to performing surveys to quantify the amount of sediment and chemical testing of the sediment. The quantity of sediment to be removed was estimated for retirement options 2 and 3 and the cost to remove the sediment is included in the conceptual demolition cost estimate. As stated above, the scope of sediment removal is based on the quantity that would be disturbed from the demolition work itself and not complete removal of the sediment potentially disturbed by the partial or complete removal of the dam.

Page 5 of 9



Indiana Michigan Power Company Attachment JAC-3 Witness; Cash Constantine Hydroelectric Plant Indiana Michigan Power Company American Electric Power Service Corporation Conceptual Demolition Cost Estimate February 12, 2016

The scope of the demolition cost estimate was reaffirmed during a review of the facility by two S&L employees in conjunction with a representative from Bradenburg Industrial Service Co. and AEP corporate and plant personnel. The facility review was held on Tuesday December 15, 2015.

#### 4.0 COMMERCIAL BASIS

#### 4.1 General Information

The Conceptual Demolition Cost Estimates prepared for the Constantine Hydroelectric Plant is a conceptual estimate of the cost to dismantle the powerhouse and dam in accordance with the scope defined for each of the three (3) retirement options. Costs were calculated for (1) demolition of existing plant structures and equipment and associated site restoration costs, (2) scrap value of steel, copper and stainless steel, as applicable, (3) associated indirect costs, and (4) contingency.

All units used in the cost estimate are U.S. Standard and all costs are in US Dollars (4<sup>th</sup> Quarter 2015 levels). A three (3) year demolition schedule is anticipated for retirement option 3 including asbestos removal (to be performed prior to start of demolition work). The schedule takes into consideration environmental permitting, asbestos removal which includes mapping out all asbestos contamination throughout the powerhouse and associated abatement, followed by total plant demolition and site restoration. The schedule for the other two (2) retirement options would be correspondingly less.

#### 4.2 Quantities/Material Cost

Quantities of pieces of equipment and/or bulk material commodities used in the cost estimates were intended to be reasonable and representative of projects of this type. Material quantities were estimated from the hydroelectric plant drawings and data provided by AEP, and the information obtained from Plant personnel during the facility review.

#### 4.3 Construction Labor Wages

Craft labor rates (Craft Hourly Rate) for the cost estimate were calculated as Union Labor rates for South Bend, Indiana, based on 2015, R. S. Means "Labor Rates for the Construction Industry". The craft rates were incorporated into work crews appropriate for the activities by adding allowances for small tools, construction equipment, insurance, and site overheads to arrive at crew hourly rates detailed in the cost estimate. A 1.10 regional labor productivity multiplier was included based on Compass International Global Construction Yearbook, 2015 Edition, for union work in Indiana. National Maintenance

Page 6 of 9



Constantine Hydroelectric Plant Indiana Michigan Power Company American Electric Power Service Corporation Conceptual Demolition Cost Estimate February 12, 2016

Agreement Rates (typically negotiated by AEP) do not apply as this work is assumed to be performed as a lump sum contract.

#### 4.3.1 Labor Work Schedule and Incentives

The estimate assumed a 5x8 work week. No per diem or other labor incentives are included.

#### 4.3.2 Construction Indirects

Allowances were included in the cost estimate as direct costs as noted for the following:

- Freight: Material and scrap freight included in the material and scrap costs.
- Additional Crane Allowance: None included. Cost of cranes and construction machinery are included in the labor wage rates.
- Mobilization and Demobilization: Included in labor wage rates.
- Scaffolding: Included in labor wage rates.
- Consumables: Included in material and labor costs.
- > Per Diem Costs: Excluded from the estimate.
- Contractor's General and Administrative Costs and Profit: Included in the labor wage rates.

#### 4.4 Scrap Value

The value of scrap was determined by a 3 month average (November and December 2015 and January 2016) using Zone 4 (USA Midwest) of the "Scrap Metals Market Watch" (<u>www.americanrecycler.com</u>).

Since the values obtained are delivered pieces, 25% of the values obtained were deducted to pay for separation, preparation and shipping to the mills. This resulted in realized prices of:

- Mixed Steel Value @ \$118/Ton
- Copper Value @ \$3,180/Ton
- Stainless Steel @ \$675/Ton
- <u>Note:</u> 1 Ton = 2,000 Lbs

All steel is considered to be mixed steel unless otherwise noted.



#### 4.5 Indirect Costs

Allowances were included in the cost estimate as indirect costs as noted for the following:

- > Engineering, Procurement and Project Services: None included.
- Construction Management Support: None included.
- Owners Cost: Included as 10.0% of the total direct cost. Owners Costs include owner project engineering, administration and construction management, permits and fees, legal expenses, taxes, removal of chemicals, etc.

#### 4.6 Escalation

No allowance for escalation was included in the cost estimate. All costs are determined in 4<sup>th</sup> Quarter

2015 levels.

#### 4.7 Contingency

Allowances were included in the cost estimate as contingency as noted for the following:

- Scrap Value: Included as 15.0% reduction in the salvage value resulting in a total net reduction in the salvage value. The contingency assumes a potential drop in salvage value thus increasing the project cost. Scrap costs are very volatile but by taking a 3-month average some of the effect of volatility is reduced. However there are other variables that affect scrap pricing such as the quantity and processing fees. The contingency applied is based on the estimators confidence in scrap pricing used in the demolition cost estimate.
- Material: Included as 20.0% of the total material cost.
- Labor: Included as 20.0% of the total labor cost.
- ▶ Indirect: Included as 20.0% of the total indirect cost.
- Subcontractor: Included as 20.0% of the total subcontractor cost.

#### 4.8 Assumptions

The following assumptions apply to the cost estimates.

- The cost estimate for each retirement option is based on the scope and the demolition sequences defined on the sketches provided in Exhibit 4.
- All chemicals will be removed by the Owner prior to demolition, from the facilities to be demolished.

#### \\Snl6c\data6\AEPFossil\Rockport\_Tanners Creek CDCEU 2015\6.0 Evaluations-Reports\6.06 Studies\Constantine\Constantine Hydro\_Conceptual Demolition Cost Estimate\_No 33707\_Rev 0.doc



Constantine Hydroelectric Plant Indiana Michigan Power Company American Electric Power Service Corporation Conceptual Demolition Cost Estimate February 12, 2016

- All electrical equipment and wiring is de-energized prior to start of dismantlement. There is no reservoir control at this plant, hence electrical power is not required for retirement option 1. The tailwater at Constantine is controlled by the gated spillway structure at Mottville Hydroelectric Plant, approximately seven (7) miles downstream.
- > No extraordinary environmental costs for demolition have been included.
- Handling, on-site and off-site disposal of hazardous materials would be performed in compliance with methods approved by Owner.
- The window glazing in the powerhouse may be asbestos contaminated and an allowance for removal and disposal is included in the asbestos removal cost estimate. There are twenty (20) control boards mounted on 3' x 9' transite (asbestos) panels and an allowance for removal and disposal is included in the asbestos removal cost estimate. There is no building or pipe insulation in the facility and consequently no insulation related asbestos contamination.
- Switchyards within the plant boundaries are not part of the scope, neither are access roads to these facilities. Fences and gates needed to protect the switchyard will be left in place.
- All demolished materials are considered debris, except for organic combustibles and nonembedded metals which have scrap value.
- The basis for salvage estimating is for scrap value only. No resale of equipment or material is included.
- Sediment removed due to demolition work is treated with lime and hauled offsite to an approved waste disposal facility.

## 5.0 **REFERENCES**

- 5.1 Constantine Plant Drawings: One-Line Diagrams, No. 14-12001 and No. E-1000, 12/16/06.
- **5.2** Findlay Engineering, Inc., Supporting Technical Information Document, Constantine Hydroelectric Project, October, 2005.



Indiana Michigan Power Company Attachment JAC-3 Witness; Cash Constantine Hydroelectric Plant Indiana Michigan Power Company American Electric Power Service Corporation Conceptual Demolition Cost Estimate February 12, 2016

## EXHIBIT 1 Constantine Hydroelectric Plant Conceptual Demolition Cost Estimate Summary

\\Snl6c\data6\AEPFossil\Rockport\_Tanners Creek CDCEU 2015\6.0 Evaluations-Reports\6.06 Studies\Constantine\Constantine Hydro\_Conceptual Demolition Cost Estimate\_No 33707\_Rev 0.doc

	F	Retirement Option 1	Retirement Option 2	Retirement Option 3		
Demolition C	Cost \$	238,539	\$ 3,375,501	\$	3,711,338	
Scrap Valu	e \$	(83,035)	\$ (83,035)	\$	(92,058)	
Direct Cost Sub	ototal \$	174,023	\$ 3,292,465	\$	3,619,279	
Indirect Co	st \$	17,000	\$ 337,000	\$	371,000	
Contingency	Cost \$	67,700	\$ 755,000	\$	830,000	
Escalation C	ost \$	-	\$ -	\$	-	
Total Demolitio	n Cost 🖇	258,723	\$ 4,384,465	\$	4,820,280	



Indiana Michigan Power Company Attachment JAC-3 Witness; Cash Constantine Hydroelectric Plant Indiana Michigan Power Company American Electric Power Service Corporation Conceptual Demolition Cost Estimate February 12, 2016

## EXHIBIT 2 Constantine Hydroelectric Plant Conceptual Demolition Cost Estimate No. 33707B

\\Snl6c\data6\AEPFossil\Rockport\_Tanners Creek CDCEU 2015\6.0 Evaluations-Reports\6.06 Studies\Constantine\Constantine Hydro\_Conceptual Demolition Cost Estimate\_No 33707\_Rev 0.doc



Indiana Michigan Power Company Attachment JAC-3 Witness; Cash Page 84 of 205

## AEP CONSTANTINE HYDROELECTRIC PLANT DISMANTLEMENT STUDY CONCEPTUAL COST ESTIMATE

Client	AEP
Estimator	RCK
Labor rate table	15INSOU
Project No.	13465-000
Station Name	CONSTANTINE
Unit	ALL
Estimate Date	02/12/2016
<b>Reviewed By</b>	ADC
Approved By	MNO
Estimate No.	33707B
Estimate Class	Conceptual
Cost index	INSOU

Estimate No.: 33707B Project No.: 13465-000 Estimate Date: 02/12/2016 Prep/Rev/App: RCK/ADC/MNO

#### AEP CONSTANTINE HYDROELECTRIC PLANT DISMANTLEMENT STUDY CONCEPTUAL COST ESTIMATE

Area	Description	Subcontract Cost	Scrap Value	Material Cost	Man Hours	Labor Cost	Total Cost
ACCOUNT A	DEMOLITION ACCOUNT A	18,520	(83,035)	83,209	1,411	155,330	174,023
ACCOUNT B	DEMOLITION ACCOUNT B	523,340		1,485,812	14,749	1,109,290	3,118,442
ACCOUNT C	DEMOLITION ACCOUNT C	(105,880)	(9,023)		4,890	441,717	326,814
	TOTAL DIRECT	435,980	(92,058)	1,569,021	21,050	1,706,337	3,619,279

#### **Estimate Totals**

Description	Amount	Totals	Hours
Direct Costs:			
Labor	1,706,337		21,05
Material	1,569,021		
Subcontract	435,980		
Scrap Value	(92,058)		
·	3,619,280	3,619,280	
Other Direct & Construction			
Indirect Costs:			
91-1 Scaffolding			
91-2 Cost Due To OT 5-10's			
91-3 Cost Due To OT 6-10's			
91-4 Per Diem			
91-5 Consumables			
91-8 Freight on Material			
91-9 Freight on Process Equip			
91-10 Sales Tax			
91-11 Contractors G&A			
91-12 Contractors Profit		0.040.000	
		3,619,280	
Indirect Costs:			
93-1 Engineering Services			
93-2 CM Support			
93-3 Start-Up/Commissioning			
93-4 Start-Up/Spare Parts			
93-5 Excess Liability Insur.			
93-6 Sales Tax On Indirects 93-7 Owners Cost	274 000		
93-8 EPC Fee	371,000		
93-6 EFC Fee	371,000	3,990,280	
Contingency:			
94-1 Contingency on Material	314,000		
94-2 Contingency on Labor	341,000		
94-3 Contingency on Sub.	87,000		
94-6 Contingency on Scrap	14,000		
94-5 Contingency on Indirect	74,000		
	830,000	4,820,280	
Escalation: 96-1 Escalation on Material			
96-1 Escalation on Material 96-2 Escalation on Labor			
96-3 Escalation on Subcontract			
96-3 Escalation on Subcontract 96-4 Escalation on Scrap			
96-5 Escalation on Indirects			
SO-O LOCAIATION ON INUITECIS		4,820,280	
		4,820,280	
Total		4.820.280	
Total		4,820,280	

Area	Group	Phase	Description	Notes	Quantity	Man Hours	Crew Rate	Labor Cost	Material Cost	Subcontract Cost	Scrap Value	Total Cost
COUNT A			DEMOLITION ACCOUNT A									
	10.00.00		WHOLE PLANT DEMOLITION									
		10.31.00	MECHANICAL EQUIPMENT									
			DEMO .3 MW GENERATOR	4 GENERATORS AT 6300# EA	12.60 TN	125	85.53 /MH	10,670		-		10
			DEMO TURBINE AND GEARS	4 TURBINES AT 9300# EA	18.60 TN	184	85.53 /MH	15,751		-		15
			TURBINE ROOM 6.5 TON OVERHEAD CRANE		5.00 TN	50	121.33 /MH	6,006		-		6
			MECHANICAL EQUIPMENT			358		32,428				32,
		10.41.00	ELECTRICAL EQUIPMENT									
			GENERATOR BUS TRANSFORMERS	2.4 to 34.5 KV, 2.67 MVA (STEEL)	8.40 TN	25	80.14 /MH	1,979		-	-	1
			GENERATOR BUS TRANSFORMERS	2.4 to 34.5 KV, 2.67 MVA (CU)	4.40 TN	13	80.14 /MH	1,037		-	-	1
			MISCELLANEOUS ELECTRICAL EQUIPMENT		4.00 TN	12	80.14 /MH	942		-	-	
						49		3,958				3,9
			WHOLE PLANT DEMOLITION			408		36,385				36,
	18.00.00		SCRAP VALUE									
		18.10.00	MIXED STEEL									
			MIXED STEEL	4 GENERATORS AT 6300# EA	-12.60 TN		79.62 /MH		-	-	(1,488)	(1,
			MIXED STEEL	4 TURBINES AT 9300# EA	-18.60 TN		79.62 /MH		-	-	(2,196)	(2,
			MIXED STEEL	TURBINE ROOM 6.5 TON OVERHEAD CRANE	-5.00 TN		79.62 /MH		-	-	(590)	(
			MIXED STEEL MIXED STEEL	80 KW PROPANE ELECTRIC GENERATOR GENERATOR BUS TRANSFORMERS	-1.50 TN -8.40 TN		79.62 /MH 79.62 /MH		-	-	(177)	(
			MIXED STEEL MIXED STEEL	GENERATOR BUS TRANSFORMERS	-8.40 IN		79.62 /MH		-	-	(992) (5,443)	(5,
			MIXED STEEL								(3,443)	(5,
		18.30.00	COPPER									
			COPPER	4 GENERATORS 4 @ 4000 LB EA	-8.00 TN		79.62 /MH		-	-	(25,440)	(25
			COPPER	CABLE	-6.00 TN		79.62 /MH		-	-	(19,080)	(19
			COPPER COPPER	MISC. TRANSFORMERS & MOTORS GENERATOR BUS TRANSFORMERS	-6.00 TN -4.40 TN		79.62 /MH 79.62 /MH		-	-	(19,080)	(19
			COPPER	GENERATOR BUS TRANSFORMERS	-4.40 IN		79.62 /MH		-	-	(13,992) (77,592)	(13
			SCRAP VALUE								(83,035)	(77,
			CONAL TALEE								(00,000)	(00,
	21.00.00		CIVIL WORK									
		21.17.00	EXCAVATION									
			MASS EXCAVATION, COMMON EARTH USING 1.5 CY BACKHOE AND (6) 12 CY DUMP TRUCKS,	DIKE EXCAVATION TO PROVIDE RACEWAY DRAINAGE- MATERIAL PLACED DIRECTLY DOWNSTREAM OF HEADGATES	5,075.00 CY	363	196.64 /MH	71,360		-	-	71
			EXCAVATION	DOWING TREAM OF THEADGATES		363		71,360				71,
		21.41.00	Erosion and Sedimentation Control									
			RIPRAP, RANDOM BROKEN STONE, MACHINE PLACED	RIPRAP PROTECTION AT DIKE MODIFICATION	1,765.00 CY	576	74.10 /MH	42,718	72,189	-	-	114
			Erosion and Sedimentation Control			576		42,718	72,189			114
		21.65.00	Soil Remediation									
			REMOVAL OF LOCALIZED SILT AT HEADGATE	LIME ADDITIVE FOR DRYING	463.00 CY		196.64 /MH			18,520		18
										18,520		18,
			Soil Remediation							18,520		204
			Soil Remediation CIVIL WORK			939		114,078	72,189	10,520		
	22.00.00		CIVIL WORK			939		114,078	72,189	10,520		
	22.00.00	22 13 00	CIVIL WORK CONCRETE			939		114,078	72,189	10,520		
	22.00.00	22.13.00	CIVIL WORK	FILL PENSTOCKS TO PREVENT BYPASS FLOW	116.00 CY	<b>939</b> 64	76.27 /MH	<b>114,078</b> 4,867	<b>72,189</b> 11,020	-		15
	22.00.00	22.13.00	CIVIL WORK CONCRETE Concrete FLOWABLE FILL, 1500 PSI Concrete	FILL PENSTOCKS TO PREVENT BYPASS FLOW	116.00 CY	64	76.27 /MH	4,867	11,020 11, <b>020</b>	-	-	15
	22.00.00	22.13.00	CIVIL WORK CONCRETE Concrete FLOWABLE FILL, 1500 PSI Concrete CONCRETE		116.00 CY	64 64 64	76.27 <i>/</i> MH	4,867	11,020	-	-	15, 15,
	22.00.00	22.13.00	CIVIL WORK CONCRETE Concrete FLOWABLE FILL, 1500 PSI Concrete		116.00 CY	64	76.27 /MH	4,867	11,020 11, <b>020</b>	18,520	(83,035)	15, 15,
COUNT B		22.13.00	CIVIL WORK CONCRETE Concrete FLOWABLE FILL, 1500 PSI Concrete CONCRETE ACCOUNT A DEMOLITION ACCOUNT A DEMOLITION ACCOUNT B		116.00 CY	64 64 64	76.27 <i>I</i> MH	4,867 4,867 4,867	11,020 11,020 11,020	-	(83,035)	15 15
COUNT B	22.00.00		CIVIL WORK CONCRETE Concrete FLOWABLE FILL, 1500 PSI CONCRETE ACCOUNT A DEMOLITION ACCOUNT A DEMOLITION ACCOUNT B WHOLE PLANT DEMOLITION		116.00 CY	64 64 64	76.27 <i>I</i> MH	4,867 4,867 4,867	11,020 11,020 11,020	-	(83,035)	15 15
COUNT B		22.13.00	CIVIL WORK CONCRETE Concrete FLOWABLE FILL, 1500 PSI Concrete CONCRETE ACCOUNT A DEMOLITION ACCOUNT A DEMOLITION ACCOUNT B WHOLE PLANT DEMOLITION CONCRETE	FLOW		64 64 64 1,411		4,867 4,867 4,867 155,330	11,020 11,020 11,020	-	(83,035)	<u>15</u> 15 174,
COUNT B			CIVIL WORK CONCRETE Concrete FLOWABLE FILL, 1500 PSI CONCRETE ACCOUNT A DEMOLITION ACCOUNT A DEMOLITION ACCOUNT B WHOLE PLANT DEMOLITION CONCRETE EQUIPMENT/ BUILDING FOUNDATION		116.00 CY	64 64 64 1,411 829	76.27 /MH	4,867 4,867 4,867 155,330	11,020 11,020 11,020	-	(83,035)	<u>15,</u> 15, 174, 74
COUNT B			CIVIL WORK CONCRETE Concrete FLOWABLE FILL, 1500 PSI Concrete CONCRETE ACCOUNT A DEMOLITION ACCOUNT A DEMOLITION ACCOUNT B WHOLE PLANT DEMOLITION CONCRETE	FLOW		64 64 64 1,411		4,867 4,867 4,867 155,330	11,020 11,020 11,020	-	(83,035)	15 15, 174, 174, 74, 74, 74, 74, 74, 74,

21.17.00 EXCAVATION

Area	Group	Phase	Description	Notes	Quantity	Man Hours	Crew Rate	Labor Cost	Material Cost	Subcontract Cost	Scrap Value	Total Cost
		21.17.00	EXCAVATION MASS EXCAVATION, COMMON EARTH USING 1.5 CY	RIVERBED EXCAVATION FOR RIPRAP	90.00 CY	6	196.64 /MH	1,266		-	-	1,266
			BACKHOE AND (6) 12 CY DUMP TRUCKS, EXCAVATION	PLACEMENT		6		1,266				1,266
		21.41.00	Erosion and Sedimentation Control RIPRAP, RANDOM BROKEN STONE, MACHINE PLACED	NEW STONE REQD IF CAUSEWAY STONE IS	19,773.00 CY	6,458	74.10 /MH	478,561	808,716	-		1,287,276
			RIPRAP, RANDOM BROKEN STONE, MACHINE PLACED RIPRAP, RANDOM BROKEN STONE, MACHINE PLACED	REUSED (24070-4297) FOR CAUSEWAYS RELOCATE CAUSE WAY STONE FOR RIVER	4,297.00 CY 4,297.00 CY	1,403 1,403	74.10 /MH 74.10 /MH	103,999 103,999	175,747	-	:	279,746 103,999
			RIPRAP, RANDOM BROKEN STONE, MACHINE PLACED	BEND PROTECTION RIP RAP PROTECTION AT FLOOR SLABS TO	90.00 CY	29	74.10 /MH	2,178	3,681	-	-	5,859
			RIPRAP, RANDOM BROKEN STONE, MACHINE PLACED	REMAIN IN PLACE RIP RAP PROTECTION AT ABUTMENTS TO REMAIN IN PLACE (240-90)	150.00 CY	49	74.10 /MH	3,630	6,135	-		9,765
			Erosion and Sedimentation Control			9,344		692,368	994,279			1,686,647
		21.47.00	LANDSCAPING HYDRO OR AIR SEED & MULCH & FERTILIZER LANDSCAPING		322.00 AC	4,570 <b>4,570</b>	74.64 /MH	<u>341,078</u> 341,078	491,533 491,533	-	-	832,611 832,611
		21.65.00	Soil Remediation REMOVAL OF LOCALIZED SILT AT DAM	LIME ADDITIVE FOR DRYING	2,000.00 CY		196.64 /MH			80,000		80,000
			REMOVAL OF LOCALIZED SILT AT DAM	LOAD, MIX AND HAUL LIME AND SEDIMENT MIX (4000+2000)	6,000.00 CY		196.64 /MH			360,000		360,000
			REMOVAL OF LOCALIZED SILT AT HEADGATE	LOAD, MIX AND HAUL LIME AND SEDIMENT MIX 926+463	1,389.00 CY		196.64 /MH			83,340		83,340
			Soil Remediation CIVIL WORK			13,920		1,034,711	1,485,812	523,340 523,340		523,340 3,043,863
			ACCOUNT B DEMOLITION ACCOUNT B			14,749		1,109,290	1,485,812	523,340		3,118,442
ACCOUNT C	10.00.00	10.22.00	DEMOLITION ACCOUNT C WHOLE PLANT DEMOLITION CONCRETE									
			EQUIPMENT/ BUILDING FOUNDATION EQUIPMENT/ BUILDING FOUNDATION	SPILLWAY APRON HEADGATE BAYS	579.00 CY 738.00 CY	717 913	89.94 /MH 89.94 /MH	64,450 82,148		-	-	64,450 82,148
			EQUIPMENT/ BUILDING FOUNDATION EQUIPMENT/ BUILDING FOUNDATION	SPILLWAY FOUNDATION POWER HOUSE	358.00 CY 1,270.00 CY	443 1,572	89.94 /MH 89.94 /MH	39,850 141,366		-	-	39,850 141,366
			CONCRETE		1,270.00 01	3,645	00.04 /////	327,813				327,813
		10.23.00	STEEL STRUCTURAL AND GIRT STEEL	GENERATOR HOUSE 140'X58X50'	101.50 TN	113	70.00 4444	0.000				0.000
			STRUCTURAL AND GIRT STEEL STEEL	GENERATOR HOUSE 140'X58X50'	101.50 IN	113	79.62 /MH	9,033 9,033		-		9,033 9,033
		10.24.00	ARCHITECTURAL GENERATOR HOUSE	140X58X50' TALL	203,000.00 CF	871	89.81 /MH	78,221				78,221
			ARCHITECTURAL	HUNDONGO TALL	200,000.00 01	871	00.01 ////1	78,221				78,221
		10.31.00	MECHANICAL EQUIPMENT DEMO PENSTOCKS	4 GENERATORS AT 7,800# EA	15.60 TN	154	85.53 /MH	13,211				13,211
			BAR RACKS	4 AT 5 TONS EACH	20.00 TN	45	121.33 /MH	5,406				5,406
			SLUICE GATES	1 AT 4 TONS EACH	4.00 TN	9	121.33 /MH	1,081		-		1,081
			STOP LOGS MECHANICAL EQUIPMENT	4 AT 5 TONS EACH	20.00 TN	45 <b>252</b>	121.33 /MH	<u>5,406</u> 25,103		-		5,406 25,103
		10.86.00	WASTE									
			WASTE - USER DEFINED WASTE	MISC	1.00 LS		121.33 /MH			-	<u> </u>	10,000 10,000
			WHOLE PLANT DEMOLITION			4,882		440,170			10,000	450,170
	18.00.00	18.10.00	SCRAP VALUE MIXED STEEL									
		10.10.00	MIXED STEEL MIXED STEEL	DEMO PENSTOCKS	-15.60 TN		79.62 /MH		-	-	(1,842)	(1,842)
			MIXED STEEL	BAR RACKS	-20.00 TN		79.62 /MH		-	-	(2,362)	(2,362)
			MIXED STEEL MIXED STEEL	SLUICE GATES STOP LOGS	-4.00 TN -20.00 TN		79.62 /MH 79.62 /MH		-	-	(472) (2,362)	(472) (2,362)
			MIXED STEEL	GENERATOR HOUSE	-101.50 TN		79.62 /MH			-	(11,985)	(11,985)

Area	Group	Phase	Description	Notes	Quantity	Man Hours	Crew Rate	Labor Cost	Material Cost	Subcontract Cost	Scrap Value	Total Cost
			MIXED STEEL								(19,023)	(19,023)
			SCRAP VALUE								(19,023)	(19,023)
	21.00.00	21.17.00	CIVIL WORK EXCAVATION									
			MASS EXCAVATION, COMMON EARTH USING 1.5 CY BACKHOE AND (6) 12 CY DUMP TRUCKS,	RIVERBED EXCAVATION FOR RIPRAP PLACEMENT (200-90)	110.00 CY	8	196.64 /MH	1,547		-	-	1,547
			EXCAVATION			8		1,547				1,547
		21.65.00	Soil Remediation									
			REMOVAL OF LOCALIZED SILT AT DAM	LIME ADDITIVE FOR DRYING CREDIT (1519-2000)	-481.00 CY		196.64 /MH			(19,240)	-	(19,240)
			REMOVAL OF LOCALIZED SILT AT DAM	LOAD, MIX AND HAUL LIME AND SEDIMENT MIX CREDIT (4556-6000))	-1,444.00 CY		196.64 /MH			(86,640)	-	(86,640)
			Soil Remediation							(105,880)		(105,880)
			CIVIL WORK			8		1,547		(105,880)		(104,333)
			ACCOUNT C DEMOLITION ACCOUNT C			4,890		441,717		(105,880)	(9,023)	326,814



Indiana Michigan Power Company Attachment JAC-3 Witness; Cash Constantine Hydroelectric Plant Indiana Michigan Power Company American Electric Power Service Corporation Conceptual Demolition Cost Estimate February 12, 2016

## EXHIBIT 3 Constantine Hydroelectric Plant Asbestos Removal Conceptual Cost Estimate No. 33739B

\\Snl6c\data6\AEPFossil\Rockport\_Tanners Creek CDCEU 2015\6.0 Evaluations-Reports\6.06 Studies\Constantine\Constantine Hydro\_Conceptual Demolition Cost Estimate\_No 33707\_Rev 0.doc

Indiana Michigan Power Company Attachment JAC-3 Witness; Cash Page 91 of 205

## AEP CONSTANTINE HYDROELECTRIC PLANT DISMANTLEMENT STUDY - ASBESTOS REMOVAL CONCEPTUAL COST ESTIMATE

Client	AEP
Estimator	RCK
Labor rate table	15INSOU
Project No.	13465-000
Station Name	CONSTANTINE
Unit	ALL
Estimate Date	02/12/2016
Reviewed By	ADC
Approved By	MNO
Estimate No.	33739B
Estimate Class	Conceptual
Cost index	INSOU

Estimate No.: 33739B Project No.: 13465-000 Estimate Date: 02/12/2016 Prep/Rev/App: RCK/ADC/MNO

#### AEP CONSTANTINE HYDROELECTRIC PLANT DISMANTLEMENT STUDY - ASBESTOS REMOVAL CONCEPTUAL COST ESTIMATE

Area	Description	Subcontract Cost	Scrap Value	Material Cost	Man Hours	Labor Cost	Total Cost
ASBESTOS	ASBESTOS REMOVAL TOTAL DIRECT	41,800 41,800					41,800 41,800

#### AEP CONSTANTINE HYDROELECTRIC PLANT DISMANTLEMENT STUDY - ASBESTOS REMOVAL CONCEPTUAL COST ESTIMATE

#### **Estimate Totals**

Description	Amount	Totals	Hours
Direct Costs:			
Labor			
Material			
Subcontract	41,800		
Scrap Value			
	41,800	41,800	
Other Direct & Construction			
Indirect Costs:			
91-1 Scaffolding			
91-2 Cost Due To OT 5-10's			
91-3 Cost Due To OT 6-10's			
91-4 Per Diem			
91-5 Consumables			
91-8 Freight on Material			
91-9 Freight on Process Equip			
91-10 Sales Tax			
91-11 Contractors G&A			
91-12 Contractors Profit			
		41,800	
Indirect Costs:			
93-1 Engineering Services			
93-2 CM Support			
93-3 Start-Up/Commissioning			
93-4 Start-Up/Spare Parts			
93-5 Excess Liability Insur.			
93-6 Sales Tax On Indirects			
93-7 Owners Cost 93-8 EPC Fee	4,200		
93-8 EPC Fee	4,200	46,000	
Contingency:			
94-1 Contingency on Material			
94-2 Contingency on Labor			
94-3 Contingency on Sub.	8,400		
94-6 Contingency on Scrap			
94-5 Contingency on Indirect	800		
	9,200	55,200	
Escalation: 96-1 Escalation on Material			
96-2 Escalation on Labor			
96-3 Escalation on Subcontract			
96-3 Escalation on Subcontract 96-4 Escalation on Scrap			
96-5 Escalation on Indirects			
30-3 Lacaldion on muncola		55,200	
		55,200	
Total		55,200	

#### AEP CONSTANTINE HYDROELECTRIC PLANT DISMANTLEMENT STUDY - ASBESTOS REMOVAL CONCEPTUAL COST ESTIMATE


Area	Group	Phase	Description	Notes	Quantity	Man Hours	Crew Rate	Labor Cost	Material Cost	Subcontract Cost	Scrap Value	Total Cost
ASBESTOS	10.00.00	10.37.00	ASBESTOS REMOVAL WHOLE PLANT DEMOLITION ASBESTOS REMOVAL									
			ASBESTOS REMOVAL - MISC MATERIALS ASBESTOS REMOVAL - CONTROL /INSTRUMENT PANELS ASBESTOS REMOVAL	WINDOW CAULKING MISC MATERIALS 20 PANELS 1X3X9' TALL	2.00 CY 20.00 CY		121.33 /MH 121.33 /MH			3,800 38,000 41,800	-	3,800 38,000 41,800
			WHOLE PLANT DEMOLITION ASBESTOS ASBESTOS REMOVAL							<u>41,800</u> 41,800		41,800 41,800





Indiana Michigan Power Company Attachment JAC-3 Witness; Cash Constantine Hydroelectric Plant Indiana Michigan Power Company American Electric Power Service Corporation Conceptual Demolition Cost Estimate February 12, 2016

## EXHIBIT 4 Constantine Hydroelectric Plant Retirement Option 1-3 Demolition Scope and Sequence

\\Snl6c\data6\AEPFossil\Rockport\_Tanners Creek CDCEU 2015\6.0 Evaluations-Reports\6.06 Studies\Constantine\Constantine Hydro\_Conceptual Demolition Cost Estimate\_No 33707\_Rev 0.doc







## CONSTANTINE HYDRO RETIREMENT DEMO SEQUENCE SKETCHES & CIVIL QUANTITIES BY: S&L

	CONSTANTINE									
	OPTION 1									
ITEM	QUANTITY	UNIT	REMARKS							
DIKE EXCAVATION	5,075	СҮ	DIKE EXCAVATION TO DRAIN HEADRACE. I HEADGATE							
RIPRAP PROTECTION AT DIKE MODIFICATION	1,765	СҮ	2 ft riprap protection @ D							

C	OPTION 2	
QUANTITY	UNIT	REMARKS
322	ACRE	
24,070	CY	2 ft riprap protection @ D
5,075	СҮ	DIKE EXCAVATION TO DRAIN HEADRA UPSTREAM OF POWERI
1,765	СҮ	2 ft riprap protection @ D
90	СҮ	2 ft riprap protection @ D
90	СҮ	TO BE REPLACED BY R
	QUANTITY 322 24,070 5,075 1,765 90	322     ACRE       24,070     CY       5,075     CY       1,765     CY       90     CY

	C	OPTION 3	
ITEM	QUANTITY	UNIT	REMARKS
GRASS SEEDING	322	ACRE	
RIPRAP PROTECTION AT RIVER BENDS	24,070	CY	2 ft riprap protection @ D
RIVERBED EXCAVATION FOR RIPRAP	200	СҮ	TO BE REPLACED BY RI
RIPRAP PROTECTION AT ABUTMENTS	240	СҮ	2 ft riprap protection @ D
		СҮ	2 ft riprap protection @ D

Note:

Localized miscellaneous silt removal and earthwork as part of dam demolition by Brandenburg

## JANUARY 25, 2016 PAGE 4 OF 8

## PLACE MATERIAL BEHIND

D(50)=12"

D(50)=12"

ACE. PLACE MATERIAL

RHOUSE

D(50)=12"

D(50)=12"


RIPRAP

D(50)=12"


RIPRAP

D(50)=12"

CONSTANTINE HYDRO RETIREMENT DEMO SEQUENCE SKETCHES & CIVIL QUANTITIES BY: S&L



httiana Midnigan Fower Company PAG Ettach prito AC-3 Witness; Cash Page 100 of 205




CONSTANTINE HYDRO RETIREMENT **DEMO SEQUENCE SKETCHES & CIVIL QUANTITIES** 

BY: S&L

VEISPAR = (23,930) ×2×1 = 1,765 CY (+) PLACE S, OTS CY OF OUT DOWNSTREAM HEADGATES DAM & SPILLWAY C 07 FLASHBOARDS -FISH CHUTE THIS DRAWING IS A PART OF THE APPLICATION FOR LICENSE MADE BY THE UNDERSIGNED THIS 12 DAY OF \_\_\_\_\_, 19 22 MICHIGAN POWER COMPANY BY Attuilling president EXHIBIT F SHEET I OF 3 MICHIGAN POWER COMPANY CONSTANTINE HYDRO PROJECT MICHIGAN PROJECT NO. 10661 GENERAL DESIGN DRAWING PLAN AND SECTIONS FERC NO. 10661-1


Indiana Michigan 25wer200mpany PAGttachment JAC-3 Witness; Cash Page 101 of 205





diana Michigan Power Company PAdtachinen 1763 Witness; Cash Page 102 of 205 HEADGATES RIPRAP PROTECTION A PILLW 240 -0 VRIPRAP= (2×5) (240) (=) = 90 CY THIS DRAWING IS A PART OF THE APPLICATION FOR LICENSE MADE BY THE UNDERSIGNED THIS 12 DAY OF \_\_\_\_\_, 19\_82 MICHIGAN POWER COMPANY BY Attuillions p VICE PRESIDENT EXHIBIT F SHEET I OF 3 RUBBLE MICHIGAN POWER COMPANY CONSTANTINE HYDRO PROJECT MICHIGAN PROJECT NO. 10661 GENERAL DESIGN DRAWING PLAN AND SECTIONS FERC NO. 10661-1

#### CONSTANTINE HYDRO RETIREMENT



JANUARY 25, 2016 diana Michigan Rower Company PAttachment JAC-3 Witness; Cash Page 103 of 205 ==105' 1.20 D-A-Z L=90' DAM & SPILLWAY \* FLASHBOARDS = 95 FISH CHUTE Lac  $V_{RIPRAP} = (12) (75+70+105+105+90+95) \frac{1}{27}$ = 240 c7  $V_{CU7} = (2x5) (75+70+105+105+90+95) \frac{1}{22}$ = 200 67 THIS DRAWING IS A PART OF THE APPLICATION FOR LICENSE MADE BY THE UNDERSIGNED THIS 12 DAY OF \_\_\_\_\_, 19\_82 MICHIGAN POWER COMPANY BY Attuillions pr VICE PRESIDENT EXHIBIT F SHEET I OF 3 RUBBLE MICHIGAN POWER COMPANY CONSTANTINE HYDRO PROJECT MICHIGAN PROJECT NO. 10661 GENERAL DESIGN DRAWING PLAN AND SECTIONS FERC NO. 10661-1



## Elkhart Hydroelectric Plant CONCEPTUAL DEMOLITION COST ESTIMATE

Prepared for: Indiana Michigan Power Company (Owner) and American Electric Power Service Corporation

> Project No. 13465-000 February 12, 2016 Revision 0



55 East Monroe Street Chicago, IL 60603-5780 USA





## **Issue Summary Page**

Revision Number	Date	Purpose	Prepared By	Reviewed By	Approved By	Pages Affected
A	02/01/16	Comments	R. C. Kinsinger	A.D. Chapin D. F. Franczak	M. N. Ozan	All
0	02/12/16	Use	R. C. Kinsinger RKinsinger	A.D. Chapin ACHORPM D. F. Franczak X-T. Trazal	T. J. Meehan Ynur	All

Page IS-1

\\Snl6c\data6\AEPFossil\Rockport\_Tanners Creek CDCEU 2015\6.0 Evaluations-Reports\6.06 Studies\Elkhart\Elkhart\Elkhart Hydro\_Conceptual Demolition Cost Estimate\_No 33708\_Rev 0.doc



**Section** 

Indiana Michigan Power Company Attachment JAC-3 Witness; Cash Elkhart Hydroelectric Plant<sup>e 106 of 205</sup> Indiana Michigan Power Company American Electric Power Service Corporation Conceptual Demolition Cost Estimate February 12, 2016

#### TABLE OF CONTENTS

Do	σo
ra	ge

1	INTRODUCTION	1
2	COST ESTIMATE SUMMARY	1
3	TECHNICAL BASIS	4
4	COMMERICAL BASIS	6
4.1	General Information	6
4.2	Quantities/Material Cost	6
4.3	Construction Labor Wages	6
4.4	Scrap Value	7
4.5	Indirect Costs	8
4.6	Escalation	8
4.7	Contingency	8
4.8	Assumptions	8
5	REFERENCES	9

<u>EXHIBIT</u>	DESCRIPTION
1	Conceptual Cost Estimate Summary
2	Conceptual Demolition Cost Estimate No. 33708B
3	Asbestos Removal Conceptual Cost Estimate No. 33740B
4	Retirement Option 1-3 Demolition Scope and Sequence

TOC-1





Indiana Michigan Power Company Attachment JAC-3 Witness; Cash Elkhart Hydroelectric Plant<sup>107 of 205</sup> Indiana Michigan Power Company American Electric Power Service Corporation Conceptual Demolition Cost Estimate February 12, 2016

#### **1.0 INTRODUCTION**

The Elkhart Hydroelectric Plant located in the City of Elkhart, Indiana is owned and operated by Indiana Michigan Power Company (I&M), a subsidiary of American Electric Power (AEP). The plant consists of (from right to left referenced facing downstream) a gated reinforced concrete spillway, an integral intake and powerhouse at the south (left) end of the spillway and concrete retaining walls at both abutments. Between the spillway and powerhouse, there is a concrete gravity cantilevered wall that extends downstream. The spillway is equipped with eleven (11) tainter gates which regulate headwater. The powerhouse consists of the intake and turbine pits followed by the generator room. The powerhouse contains three (3) horizontal shaft operating turbine generators. Unit 1 is rated at 1.44 MW and was installed in 1913 and Units 2 and 3 are rated at 1 MW each and were installed in 1921.

AEP recently contracted S&L to prepare conceptual demolition cost estimates considering three (3) retirement options defined as follows: (1) Option 1, Non-Power Operation, (2) Option 2, Partial Removal of the Dam Structures, and (3) Option 3, Complete Removal of the Dam and Powerhouse. Also, in addition S&L was requested to prepare a separate Asbestos Removal Conceptual Cost Estimate.

The objective of the conceptual demolition cost estimates is to determine the gross demolition costs for Elkhart Hydroelectric Plant (including gross salvage credits and any other benefits), in support of documenting a component of future AEP book depreciation rates to be approved by the I&M's state commissions and potential future inclusion in submittal of a rate case to the state commissions, and other potential uses. The cost estimate considers the demolition/dismantlement methodology which complies with current OSHA rules and regulations.

#### 2.0 COST ESTIMATE SUMMARY

Conceptual Demolition Cost Estimate No. 33708B, dated February 12, 2016, was prepared and is included as Exhibit 2. This cost estimate was prepared for retirement option 3, but includes accounts allowing the determination of cost estimates for retirement options 1 and 2 as well. A summary of the conceptual demolition cost estimates for all three (3) retirement options is provided in Exhibit 1 and detailed in the following tables.



The cost estimate is structured into a code of accounts as identified in Table 2-1.

Account Number	Description
10, 21, 22	Demolition Costs (including steel, equipment & piping scrap value)
18	Scrap Value Costs
91	Other Direct & Construction Indirect Costs
93	Indirect Costs
94	Contingency Costs
96	Escalation Costs

 Table 2-1

 Cost Estimate Code of Accounts

The results of the cost estimate for retirement option 3 are provided in Table 2-2 below.

## Table 2-2Cost Estimate Results SummaryRetirement Option 3

Description	Total Cost	
Demolition Cost	\$7,177,344	
Scrap Value	(\$165,008)	
Direct Cost Subtotal	\$7,012,335	
Indirect Cost	\$718,000	
Contingency Cost	\$1,604,000	
Escalation Cost	\$0	
Total Project Cost	\$9,334,335	



The results of the cost estimate for retirement option 1 are provided in Table 2-3 below.

Description	Total Cost	
Demolition Cost	\$68,721	
Scrap Value	(\$42,715)	
Direct Cost Subtotal	\$26,005	
Indirect Cost	\$2,000	
Contingency Cost	\$20,000	
Escalation Cost	\$0	
Total Project Cost	\$48,005	

# Table 2-3Cost Estimate Results SummaryRetirement Option 1

The results of the cost estimate for retirement option 2 are provided in Table 2-4 below.

# Table 2-4Cost Estimate Results SummaryRetirement Option 2

Description	Total Cost
Demolition Cost	\$5,182,983
Scrap Value	(\$148,382)
Direct Cost Subtotal	\$5,034,600
Indirect Cost	\$515,000
Contingency Cost	\$1,161,900
Escalation Cost	\$0
Total Project Cost	\$6,711,500





Elkhart Hydroelectric Plant Indiana Michigan Power Company American Electric Power Service Corporation Conceptual Demolition Cost Estimate February 12, 2016

Asbestos Removal Conceptual Cost Estimate No. 33740B, dated February 12, 2016, was prepared and is included as Exhibit 3. The total estimated cost for asbestos removal prior to plant dismantlement is \$363,660. Quantities were derived from drawings and past experience. Asbestos removal applies to the powerhouse, thus the removal cost applies to all three (3) retirement options. The cost of asbestos removal is excluded from the total conceptual demolition cost estimates for each retirement option detailed in the tables above.

## 3.0 TECHNICAL BASIS

The scope of dismantlement is based on three (3) retirement options, as requested by AEP, as follows:

<u>Retirement Option 1, Non-Power Operation:</u> This scenario would consider leaving intact all of the existing water-impounding structures and the powerhouse. Only the electric generating units and their auxiliary equipment would be removed so as to preclude the generation of electricity by the former hydroelectric plant. In addition, the spillway would be modified as required in order to pass river flows and maintain the impoundment's water surface elevation at the current conditions.

<u>Retirement Option 2, Partial Removal of the Dam Structures:</u> This scenario would consider demolition and removal of certain elements of the hydroelectric site in order to drain the existing impoundment and create a natural river channel through the dam site. This would generally include removal of the generating units and powerhouse and possibly but not inclusively demolition and removal of substantial portions of concrete spillway structures. This option would address the removal and stabilization of any sediments that have accumulated at the upstream end of the dam and the stabilization of the newly exposed reservoir/riverbanks.

<u>Retirement Option 3, Complete Removal of the Dam and Powerhouse:</u> This scenario would consider complete removal of the electric generating components and powerhouse and complete removal of the dam. Similar to option 2, this option would address the removal and stabilization of any sediments that have accumulated at the upstream end of the dam and the stabilization of the newly exposed reservoir/riverbanks.

The scope of dismantlement for each retirement option, as interpreted from the definitions above, are identified on marked plant drawings included as Exhibit 4. The scope of dismantlement and the sequence of demolition for each retirement option are defined on these sketches.



Elkhart Hydroelectric Plant Indiana Michigan Power Company American Electric Power Service Corporation Conceptual Demolition Cost Estimate February 12, 2016

Retirement options 2 and 3 include the same demolition work as retirement option 1, removal of the generating unit components from the powerhouse. The powerhouse is not removed in retirement option 1, but is removed in retirement option 3. For retirement option 2 the powerhouse may or may not be removed, depending on if removal of portions of the dam can restore river flow to natural flow without removing the powerhouse (refer to Exhibit 4).


For each of the retirement options the scope of sediment removal is based on the quantity that would be disturbed from the demolition work itself and not complete removal of all sediment potentially disturbed by the partial or complete removal of the dam. The subcontractor costs included in retirement options 2 and 3 are for lime stabilization of the sediment and removal of the sediment and other wastes (such as timber) to the waste disposal site. These costs do not apply to retirement option 1 since only generating unit components in the powerhouse are removed and this material has scrap value.

Retirement options 2 and 3 include the stabilization of newly exposed riverbanks, which include the dam area and areas upstream of the dam. The extent of stabilization for retirement option 3 may be slightly more than retirement option 2, since the entire dam is being removed in retirement option 3.

The following are excluded from the scope of the conceptual demolition cost estimates:

- Asbestos removal (separate cost estimate prepared).
- The conceptual demolition cost estimate includes the cost to remove the two (2) main power transformers located in the switchyard, but not the cost to remove the switchyard itself (and remaining components in the switchyard).
- > Evaluation of the effect of the complete removal of the series of dams on the river watershed.
- Evaluation of the effect of the removal of any one dam, on either the upstream or downstream side dam and reservoir, after removal of the dam.
- Potential social or environmental impact of the draining of the reservoirs and the impact on property values or other community impact.
- The conceptual demolition cost estimate excludes any costs related to performing surveys to quantify the amount of sediment and chemical testing of the sediment. The quantity of sediment to be removed was estimated for retirement options 2 and 3 and the cost to remove the sediment is included in the conceptual demolition cost estimate. As stated above, the scope of sediment removal is based on the quantity that would be disturbed from the demolition work itself and not complete removal of the sediment potentially disturbed by the partial or complete removal of the dam.







The scope of the demolition cost estimate was reaffirmed during a review of the facility by two S&L employees in conjunction with a representative from Bradenburg Industrial Service Co. and AEP corporate and plant personnel. The facility review was held on Tuesday December 15, 2015.

# 4.0 COMMERCIAL BASIS

### 4.1 General Information

The Conceptual Demolition Cost Estimates prepared for the Elkhart Hydroelectric Plant is a conceptual estimate of the cost to dismantle the powerhouse and dam in accordance with the scope defined for each of the three (3) retirement options. Costs were calculated for (1) demolition of existing plant structures and equipment and associated site restoration costs, (2) scrap value of steel, copper and stainless steel, as applicable, (3) associated indirect costs, and (4) contingency.

All units used in the cost estimate are U.S. Standard and all costs are in US Dollars (4<sup>th</sup> Quarter 2015 levels). A three (3) year demolition schedule is anticipated for retirement option 3 including asbestos removal (to be performed prior to start of demolition work). The schedule takes into consideration environmental permitting, asbestos removal which includes mapping out all asbestos contamination throughout the powerhouse and associated abatement, followed by total plant demolition and site restoration. The schedule for the other two (2) retirement options would be correspondingly less.

# 4.2 Quantities/Material Cost

Quantities of pieces of equipment and/or bulk material commodities used in the cost estimates were intended to be reasonable and representative of projects of this type. Material quantities were estimated from the hydroelectric plant drawings and data provided by AEP, and the information obtained from Plant personnel during the facility review.

## 4.3 Construction Labor Wages

Craft labor rates (Craft Hourly Rate) for the cost estimate were calculated as Union Labor rates for South Bend, Indiana, based on 2015, R. S. Means "Labor Rates for the Construction Industry". The craft rates were incorporated into work crews appropriate for the activities by adding allowances for small tools, construction equipment, insurance, and site overheads to arrive at crew hourly rates detailed in the cost estimate. A 1.10 regional labor productivity multiplier was included based on Compass International Global Construction Yearbook, 2015 Edition, for union work in Indiana. National Maintenance

Page 6 of 9



Agreement Rates (typically negotiated by AEP) do not apply as this work is assumed to be performed as a lump sum contract.

# 4.3.1 Labor Work Schedule and Incentives

The estimate assumed a 5x8 work week. No per diem or other labor incentives are included.

# 4.3.2 Construction Indirects

Allowances were included in the cost estimate as direct costs as noted for the following:

- Freight: Material and scrap freight included in the material and scrap costs.
- Additional Crane Allowance: None included. Cost of cranes and construction machinery are included in the labor wage rates.
- Mobilization and Demobilization: Included in labor wage rates.
- Scaffolding: Included in labor wage rates.
- > Consumables: Included in material and labor costs.
- > Per Diem Costs: Excluded from the estimate.
- > Contractor's General and Administrative Costs and Profit: Included in the labor wage rates.

## 4.4 Scrap Value

The value of scrap was determined by a 3 month average (November and December 2015 and January 2016) using Zone 4 (USA Midwest) of the "Scrap Metals Market Watch" (<u>www.americanrecycler.com</u>).

Since the values obtained are delivered pieces, 25% of the values obtained were deducted to pay for separation, preparation and shipping to the mills. This resulted in realized prices of:

- Mixed Steel Value @ \$118/Ton
- Copper Value @ \$3,180/Ton
- Stainless Steel @ \$675/Ton
- <u>Note:</u> 1 Ton = 2,000 Lbs

All steel is considered to be mixed steel unless otherwise noted.



# 4.5 Indirect Costs

Allowances were included in the cost estimate as indirect costs as noted for the following:

- > Engineering, Procurement and Project Services: None included.
- Construction Management Support: None included.
- Owners Cost: Included as 10.0% of the total direct cost. Owners Costs include owner project engineering, administration and construction management, permits and fees, legal expenses, taxes, removal of chemicals, etc.

## 4.6 Escalation

No allowance for escalation was included in the cost estimate. All costs are determined in 4<sup>th</sup> Quarter

2015 levels.

## 4.7 Contingency

Allowances were included in the cost estimate as contingency as noted for the following:

- Scrap Value: Included as 15.0% reduction in the salvage value resulting in a total net reduction in the salvage value. The contingency assumes a potential drop in salvage value thus increasing the project cost. Scrap costs are very volatile but by taking a 3-month average some of the effect of volatility is reduced. However there are other variables that affect scrap pricing such as the quantity and processing fees. The contingency applied is based on the estimators confidence in scrap pricing used in the demolition cost estimate.
- Material: Included as 20.0% of the total material cost.
- Labor: Included as 20.0% of the total labor cost.
- ▶ Indirect: Included as 20.0% of the total indirect cost.
- Subcontractor: Included as 20.0% of the total subcontractor cost.

## 4.8 Assumptions

The following assumptions apply to the cost estimates.

- The cost estimate for each retirement option is based on the scope and the demolition sequences defined on the sketches provided in Exhibit 4.
- All chemicals will be removed by the Owner prior to demolition, from the facilities to be demolished.

Page 8 of 9

<sup>\\</sup>Snl6c\data6\AEPFossil\Rockport\_Tanners Creek CDCEU 2015\6.0 Evaluations-Reports\6.06 Studies\Elkhart\Elkhart Hydro\_Conceptual Demolition Cost Estimate\_No 33708\_Rev 0.doc



- All electrical equipment and wiring is de-energized prior to start of dismantlement, except for that required for remote operation of tainter gates No. 10 and 11 after demolition is completed for retirement option 1.
- > No extraordinary environmental costs for demolition have been included.
- Handling, on-site and off-site disposal of hazardous materials would be performed in compliance with methods approved by Owner.
- The window glazing in the powerhouse may be asbestos contaminated and an allowance for removal and disposal is included in the asbestos removal cost estimate. There are nine (9) control boards mounted on 3' x 9' transite (asbestos) panels and eighteen (18) 4kV breakers mounted in cubicles constructed of transite panels. An allowance for removal and disposal of these transite panels is included in the asbestos removal cost estimate. There is no building or pipe insulation in the facility and consequently no insulation related asbestos contamination.
- Switchyards within the plant boundaries are not part of the scope, neither are access roads to these facilities. Fences and gates needed to protect the switchyard will be left in place.
- All demolished materials are considered debris, except for organic combustibles and nonembedded metals which have scrap value.
- The basis for salvage estimating is for scrap value only. No resale of equipment or material is included.
- Sediment removed due to demolition work is treated with lime and hauled offsite to an approved waste disposal facility.

# 5.0 **REFERENCES**

- **5.1** Elkhart Plant Drawings: One-Line Diagrams, No. 5839-1000-35, Revision 35 and No. 13-12000-1, 6/5/98.
- **5.2** American Electric Power, Supporting Technical Information Document, Elkhart Hydroelectric Project, September, 2007.





# EXHIBIT 1 Elkhart Hydroelectric Plant Conceptual Demolition Cost Estimate Summary

\\Snl6c\data6\AEPFossil\Rockport\_Tanners Creek CDCEU 2015\6.0 Evaluations-Reports\6.06 Studies\Elkhart\Elkhart\Elkhart\Hydro\_Conceptual Demolition Cost Estimate\_No 33708\_Rev 0.doc



	Retir	ement Option 1	Retirement Option 2	Retirement Option 3		
Demolition Cost	\$	68,721	\$ 5,182,983	\$	7,177,344	
Scrap Value	\$	(42,715)	\$ (148,382)	\$	(165,008)	
Direct Cost Subtotal	\$	26,005	\$ 5,034,600	\$	7,012,335	
Indirect Cost	\$	2,000	\$ 515,000	\$	718,000	
Contingency Cost	\$	20,000	\$ 1,161,900	\$	1,604,000	
Escalation Cost	\$	-	\$ -	\$	-	
Total Demolition Cost	\$	48,005	\$ 6,711,500	\$	9,334,335	



# EXHIBIT 2 Elkhart Hydroelectric Plant Conceptual Demolition Cost Estimate No. 33708B

\\Snl6c\data6\AEPFossil\Rockport\_Tanners Creek CDCEU 2015\6.0 Evaluations-Reports\6.06 Studies\Elkhart\Elkhart\Elkhart\Hydro\_Conceptual Demolition Cost Estimate\_No 33708\_Rev 0.doc



Indiana Michigan Power Company Attachment JAC-3 Witness; Cash Page 119 of 205

# AEP ELKHART HYDROELECTRIC PLANT DISMANTLEMENT STUDY CONCEPTUAL COST ESTIMATE

Client	AEP
Estimator	RCK
Labor rate table	15INSOU
Project No. Station Name	13465-000 ELKHART
Unit	ALL
Estimate Date	02/12/2016
<b>Reviewed By</b>	ADC
Approved By	MNO
Estimate No.	33708B
Estimate Class	Conceptual
Cost index	INSOU

Estimate No.: 33708B Project No.: 13465-000 Estimate Date: 02/12/2016 Prep/Rev/App: RCK/ADC/MNO

#### AEP ELKHART HYDROELECTRIC PLANT DISMANTLEMENT STUDY CONCEPTUAL COST ESTIMATE

Area	Description	Subcontract Cost	Scrap Value	Material Cost	Man Hours	Labor Cost	Total Cost
ACCOUNT A	DEMOLITION ACCOUNT A		(42,715)		748	68,721	26,005
ACCOUNT B	DEMOLITION ACCOUNT B	663,920	(105,667)	2,073,405	30,143	2,376,937	5,008,595
ACCOUNT C	DEMOLITION ACCOUNT C	617,580	(16,626)	25,644	15,074	1,351,137	1,977,735
	TOTAL DIRECT	1,281,500	(165,009)	2,099,049	45,964	3,796,795	7,012,335

#### **Estimate Totals**

Description	Amount	Totals	Hour
Direct Costs:			
_abor	3,796,795		45,96
Vaterial	2,099,049		
Subcontract	1,281,500		
Scrap Value	(165,009)		
	7,012,335	7,012,335	
Other Direct & Construction			
Indirect Costs:			
91-1 Scaffolding			
91-2 Cost Due To OT 5-10's			
91-3 Cost Due To OT 6-10's			
91-4 Per Diem			
91-5 Consumables			
91-8 Freight on Material			
91-9 Freight on Process Equip			
91-10 Sales Tax			
91-11 Contractors G&A			
91-12 Contractors Profit			
		7,012,335	
ndirect Costs:			
03-1 Engineering Services			
93-2 CM Support			
93-3 Start-Up/Commissioning			
93-4 Start-Up/Spare Parts			
93-5 Excess Liability Insur. 93-6 Sales Tax On Indirects			
93-7 Owners Cost	718,000		
93-8 EPC Fee	710,000		
	718,000	7,730,335	
Contingency:			
94-1 Contingency on Material	420,000		
94-2 Contingency on Labor	759,000		
94-3 Contingency on Sub.	256,000		
94-6 Contingency on Scrap	25,000		
94-5 Contingency on Indirect	144,000		
	1,604,000	9,334,335	
Escalation:			
96-1 Escalation on Material			
96-2 Escalation on Labor			
96-3 Escalation on Subcontract			
96-4 Escalation on Scrap			
96-5 Escalation on Indirects		9,334,335	
		0,000,000	
		9,334,335	
Total		9,334,335	
		3,004,000	

And And And And And And And And And And						•			1.1		Subcontract	0	<b>T</b>
Name         Note: In and model: Note: Section 2011 (Section 2011) (Section 201	Area	Group	Phase	Description	Notes	Quantity	Man Hours	Crew Rate	Labor Cost	Material Cost		Scrap Value	Total Cost
19.100       MCXMMCAL EQUIPMENT INCOME DATABASE OF BENCHMAN DATABASE OF BE	CCOUNT A												
NUMBER OF LANS CONSENSES         CONSENSES<		10.00.00	40.04.00										
END OF ALL DURING CONSISTENCE AND AND ALL DURING AND AND ALL DURING AND AND ALL DURING A			10.31.00			0.00 TN		05 50 441	7 507				
UNDER DECONSTRAINT         LATERSTAND         LATERSTAND <thlaterstand< th="">         LATERSTAND         <thl< td=""><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td>-</td><td></td><td>7,5 12,2</td></thl<></thlaterstand<>											-		7,5 12,2
UNIC FUNCTION         CONSTRUCT         CONSTRUCT <thconstruct< th=""></thconstruct<>											-		3,7
Under Root is "TO INSPECT DAME         OTH ME INFORMATION         0.00000000000000000000000000000000000				DEMO 1.44 MW FRANCIS TURBINE AND GEARS		11.80 TN	130	85.53 /MH	11,103		-		11,
BAR MODB         BAR MODB         ATA TOTM BLCH         SOLD TH         He         SOLD TH         TH         TH         TH         TH         SOLD TH         TH <td></td> <td>-</td> <td></td> <td>17,8</td>											-		17,8
HECHANCAL EQUINANT         748         62,21           110.000         CCAP VALUE         4.02 TH         4.02 TH           110.000         CCAP VALUE         CCAP VALUE         CCAP VALUE           MADE STREE         CCAP VALUE         CCAP VALUE         CCAP VALUE											-		10,8
WINDLE FLAIT EQUIDIN         740         64.21           18.0.00         INSPECTATION         1000000000000000000000000000000000000					4 AT 5 TONS EACH	20.00 TN		121.33 /MH			-		5,
19.500       MIXED STEEL MIXED STEEL M													68, 68,
19.500       MIXED STEEL MIXED STEEL M		40.00.00											
MACD STELL       DEND 14 MW CARCURACY CONTROL 4-00 TH       THE 24 MH		18.00.00	40 40 00										
MICE STEL MICE STEL MODE STEL MOD			18.10.00			0.00 TN		70.00 4411				(045)	
MACE D STELL         DEMO STATEL         DEMO STATEL         4.00 TM         710 2 AM         -         -         -         (172) (102)           MACE D STELL         DEMO STATEL         DEMO STATEL         DEMO STATEL         -											-		()
NMRED STEEL       DEND 144 MU/ FMACED UBLINE AND CHASS       148 DTN COMMEND THE NAME AND COMMEND THE NAME AND COMMEND THE NAME AND THE NAME AND THE NAME AND COMMEND THE NAME AND													(4
COUNT B         MARCE STEEL         DEVOLUTION ACCOUNT A         1000 TH         7.52 AM         -										-	-		(1,3
COUNT B         Decklas         Display for Count Particle Origination         300 Th         Table Add         - <td></td> <td></td> <td></td> <td></td> <td>GEARS</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td>					GEARS								
MAKED STEL INCOME         DAR MACIS         20:00 TN         762.041         -         -         -         2.232 (7.232)           18.3.000         COPPER COPPER         DENO 141 MM CANELBACK COMMENTOR COPPER         3.00 TN         762.041         -				MIXED STEEL		-19.00 TN		79.62 /MH		-	-	(2,244)	(2,3
MAKED STEEL         (12.837)           18.8.00         COPPER CONCERT ENDO 34.8 UNIT CAMELIACK CENERATOR (28.092 × 8 UNIT CAMELIACK CENERATOR EDD 34.8 UNIT CAMELIACK CENERATOR (28.092 × 8 UNIT CAMELIACK										-	-	(4,723)	(4,
11.3.0.0       COPPER COP					BAR RACKS	-20.00 TN		79.62 /MH		-	-	(2,362)	(2,
COPPER DEND 3:44 MW CAMELBACK GENERATOR COPPER         3.80 TN 56.01 N         782 / MH         -         -         (11.445) (23.827)           COPPER COPPER         COPPER         COPPER         COPPER         COPPER         (11.445)         (11.445)           COPPER         COPPER         COPPER         (11.445)         (11.445)         (11.445)         (11.445)           COPPER         COPPER         COPPER         (11.445)         (11.445)         (11.445)         (11.445)           COUNT B         DEMOLITION ACCOUNT A CENTURINA COUNCETE         COUNCETE         (11.445)         (11.445)         (11.445)         (11.445)           10.0.00         DEMOLITION ACCOUNT A CENTURINA COUNCETE         DEMOLITION ACCOUNT A         TANTER CATE : TOP PORTION: WER OUT WILL B ALEO WALL         Aleo WALL         Aleo WALL         (11.445)         (11.445)           10.0.00         STEEL         DEMOLITION ACCOUNT A         TANTER CATE : TOP PORTION: WER OUT WALL B ALEO WALL         8.337         748.044         748.016         -         -           10.0.00         STEEL         TANTER CATE : TOP PORTION: WER WALKWAY         5.00 TN         2.01 MH         2.037         -         -           10.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.				MIXED STEEL								(12,823)	(12,
COPPER         DEMO 2-10 MW CAMELBACK GENERATOR         4.80 TN         7962 AH         - <th< td=""><td></td><td></td><td>18.30.00</td><td>COPPER</td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></th<>			18.30.00	COPPER									
COPPER         CopPER<				COPPER	DEMO 1.44 MW CAMELBACK GENERATOR	-3.60 TN		79.62 /MH			-	(11,448)	(11,
(42,715)           (42,715)				COPPER	DEMO 2-1.0 MW CAMELBACK GENERATOR	-5.80 TN		79.62 /MH		-	-	(18,444)	(18,
ACCOUNT & DEMOLITION ACCOUNT A         748         68,721         (42,715)           COUNT B         DEMOLITION ACCOUNT B         (42,715)         (42,715)           10.2000         DEMOLITION ACCOUNT B         (42,715)         (42,715)           10.2000         CONCRETE         EQUIPMENT BUILDING FOUNDATION         TANTER GATE TOP PORTION WERR GATE WALLS & HEAD WALL         6,720.00 CY         8,317         89.94 /MH         748,016         -         -           10.2000         STEEL         TANTER GATE TOP PORTION WERR GATE WALLS & HEAD WALL         6,720.00 CY         8,317         70.62 /MH         -         -         -           10.23.00         STEEL         TANTER GATE STRUCTURE AND WALKWAY         31.00 TN         37         70.62 /MH         2,537         -         -           10.31.00         MECHANICAL EQUIPMENT TANTER GATES STRUCTURE AND WARKWAY         10.01 TN         13         121.33 /MH         4.050         -         -           10.41.00         WIN PROPAKE ELECTRIC GENERATOR TANTER GATES STRUCTURE AND WARKWAY         10.01 TN         13         121.33 /MH         4.050         -         -           10.41.00         MECHANICAL EQUIPMENT GENERATIOR BUT REMOVERDER TO THE STRUCTURE AND WARE TO THE STRUCTURE AND MECHANICAL EQUIPMENT         10.41 STONE FACH         1.50 TN         13         121.33 /MH<												(29,892)	(29,8
COUNT B         DEMOLITION ACCOUNT S           10.0.00         NHOLE PLANT DEMOLITION CONCRETE         TAINTER GATE : TOP PORTION WEIR COUNT BL         6,720.00         CV         8.317         748.016         -         -           10.0.00         OURCRETE         COUNT BL         RAINTER GATE : TOP PORTION WEIR COUNT BL         6,720.00         CV         8.317         748.016         -         -           10.2.00         STEEL STRUCTURE AND GIRT STEEL         TAINTER GATES STRUCTURE AND WALKWAY         33.00         TN         37         78.82         AM         2.937         -         -           10.3.100         MECHANICAL EQUIPMENT STRUCTURE AND GIRT STEEL         TAINTER GATES         1.50         TN         3         121.33         AM         54.000         -				SCRAP VALUE								(42,715)	(42,7
10.0.00       WHOLE PLANT DEMOLITION       TAINTER GATE: TOP PORTION: WERR       0.720.00 CY       8.317       89.94 MH       749.016       -       -         10.02.00       STEEL       CONCRETE       8.317       89.94 MH       749.016       -       -       -         10.23.00       STEEL       STEEL       STEEL       8.317       79.52 MH       2.537       -       -       -         10.23.00       MECHANICAL EQUIPMENT       TAINTER GATE: STRUCTURE AND       33.00 TN       37       79.52 MH       2.537       -       -       -         10.31.00       MECHANICAL EQUIPMENT       TAINTER GATE: STRUCTURE AND       50.00 TN       13       121.33 MH       405       -				ACCOUNT A DEMOLITION ACCOUNT A			748		68,721			(42,715)	26,0
10.0.00       WHOLE PLANT DEMOLITION       TAINTER GATE: TOP PORTION: WERR       0.720.00 CY       8.317       89.94 MH       749.016       -       -         10.02.00       STEEL       CONCRETE       8.317       89.94 MH       749.016       -       -       -         10.23.00       STEEL       STEEL       STEEL       8.317       79.52 MH       2.537       -       -       -         10.23.00       MECHANICAL EQUIPMENT       TAINTER GATE: STRUCTURE AND       33.00 TN       37       79.52 MH       2.537       -       -       -         10.31.00       MECHANICAL EQUIPMENT       TAINTER GATE: STRUCTURE AND       50.00 TN       13       121.33 MH       405       -	CCOUNT B			DEMOLITION ACCOUNT B									
10.2.200       CONCRETE EXUIPMENT/ BULING FOLNATION OCNCRETE       TANTER CATE - TOP PORTION: WER. OCT WALLS & HEAD WALL       6,720.00 CY       8.317       89.4 / MH       748.016       -       <		10.00.00											
EQUIPMENT /BUILDING FOUNDATION       TANTER CATE:: TOP PORTION: WERR, 0,20:00 CY       8.317       748.016       -       -         CONCRETE       8.317       748.016       -       -       -         10.23.00       STELL STRUCTURAL AND GIRT STEEL       TANTER CATES STRUCTURE AND WALKWAY       3300 TN       37       78.2 AM       2.337       -       -       -         10.31.00       MECHANICAL EQUIPMENT BO KW PROPAME ELECTRIC GENERATOR TANTER CATES       11 ATS TONS EACH       150 TN       3       121.33 AMI       405       -       -       -         10.41.00       ECHANICAL EQUIPMENT BO KW PROPAME ELECTRIC GENERATOR TAINTER CATES       11 ATS TONS EACH       150 TN       3       121.33 AMI       405       -			10.22.00										
GATE WALLS & HEAD WALL         5.317         748.016           10.32.00         STEL         5.317         748.016           10.32.00         STEL         7.00000         7.00000         7.00000         7.00000         7.00000         7.00000         7.000000         7.000000         7.0000000         7.000000000000000000000000000000000000			10122100		TAINTER GATE - TOP PORTION: WEIR.	6.720.00 CY	8.317	89.94 /MH	748.016		-		748
10.23.00       STELL STRUCTURAL AND GRT STEEL       TANTER GATES STRUCTURE AND WALKWAY       33.00 TN       37       79.62 /MH       2.937       -       -       -         10.31.00       MECHANICAL EQUIPMENT BOKW PROPANE ELECTRIC GENERATOR TAINTER CATES TAINTER HADDATES       1.50 TN       3       121.33 /MH       405       - <td< td=""><td></td><td></td><td></td><td></td><td></td><td>.,</td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></td<>						.,							
STRUCTURAL AND GIRT STEEL       TANTER GATES STRUCTURE AND       33.00 TN       37       79.62 MH       2.937       -       -         STEEL       37       2,937       - <t< td=""><td></td><td></td><td></td><td>CONCRETE</td><td></td><td></td><td>8,317</td><td></td><td>748,016</td><td></td><td></td><td></td><td>748,</td></t<>				CONCRETE			8,317		748,016				748,
STEEL         WALKWAY         37         2,937           10.31.00         MECHANICAL EQUIPMENT GO KW PROPANE ELECTRIC GENERATOR TAINTER HEADGATES TAINTER HEADGATES MECHANICAL EQUIPMENT         11 AT 5 TONS EACH         150 TN         3         121.33 MH         405         -           10.41.00         ELECTRICAL EQUIPMENT GENERATOR BUS TRANSFORMERS GENERATOR BUS TRANSFORMERS GENERATOR BUS TRANSFORMERS GENERATOR BUS TRANSFORMERS GENERATOR BUS TRANSFORMERS GENERATOR BUS TRANSFORMERS A 116 b 34.5 KV, 1500 KVA (CU)         3.00 TN         9         80.14 MH         1.413 TOT         -         -           10.41.00         ELECTRICAL EQUIPMENT GENERATOR BUS TRANSFORMERS GENERATOR BUS TRANSFORMERS A 116 b 34.5 KV, 1500 KVA (CU)         3.00 TN         9         80.14 MH         1.413 TOT         -         -           10.41.00         ELECTRICAL EQUIPMENT GENERATOR BUS TRANSFORMERS GENERATOR BUS TRANSFORMERS A 116 b 34.5 KV, 1500 KVA (CU)         3.00 TN         9         80.14 MH         1.413 TOT         -         -           10.41.01         ELECTRICAL EQUIPMENT GENERATOR BUS TRANSFORMERS GENERATOR BUS TRANSFORMERS A 110 D 34.5 KV, 2500 KVA (CU)         4.00 TN         14         80.14 MH         1.014 TOT         -         -               GENERATOR BUS TRANSFORMERS GENERATOR BUS TRANSFORMERS A 101 D 34.5 KV, 2500 KVA (CU)         4.00 TN         14         80.14 MH         1.0212         -         -               MINCELICAL E			10.23.00	STEEL									
STEEL         37         2,937           10.31.00         MECHANICAL EQUIPMENT 50 KW PROPANE ELECTRIC GENERATOR TAINTER HEADGATES         11 AT 5 TONS EACH         1.50 TN         3         121.33 MH         405         -           10.10         MECHANICAL EQUIPMENT         11 AT 5 TONS EACH         20.00 TN         123         121.33 MH         4065         -           10.11         MECHANICAL EQUIPMENT         11 AT 5 TONS EACH         20.00 TN         45         121.33 MH         5.406         -           10.41.00         EQUERATOR BUS TRANSFORMERS         4.16 to 34.5 KV, 1500 KVA (STEEL)         6.00 TN         18         8.0.14 MH         1.413         -         -           10.41.00         EQUERATOR BUS TRANSFORMERS         4.16 to 34.5 KV, 1500 KVA (STEEL)         7.25 TN         21         80.14 MH         1.413         -         -           10.41.00         EQUERATOR BUS TRANSFORMERS         4.16 to 34.5 KV, 1500 KVA (CIU)         3.00 TN         9         80.14 MH         1.413         -         -           GENERATOR BUS TRANSFORMERS         4.16 to 34.5 KV, 1500 KVA (STEEL)         7.25 TN         21         80.14 MH         1.180         -         -         -           GENERATOR BUS TRANSFORMERS         4.16 to 34.5 KV, 2500 KVA (CIU)         4.60 TN         1				STRUCTURAL AND GIRT STEEL		33.00 TN	37	79.62 /MH	2,937		-	-	2
60 KW PROPANE ELECTRIC GENERATOR       1.50 TN       3       121.33 /MH       405       -         TAINTER GATES       11 AT 5 TONS EACH       55.00 TN       123       121.33 /MH       14.866       -         TAINTER HEADGATES       4 AT 5 TONS EACH       50.00 TN       45       12.33 /MH       14.866       -       -         10.41.00       ELECTRICAL EQUIPMENT       70       20.677       -       -       -         10.41.00       ELECTRICAL EQUIPMENT       6.00 TN       18       80.14 /MH       1.413       -       -         10.41.00       ELECTRICAL EQUIPMENT       6.00 TN       18       80.14 /MH       1.413       -       -         10.41.00       ELECTRICAL EQUIPMENT       7.25 TN       21       80.14 /MH       1.413       -       -         11.50 TN       5.00 TN       18       80.14 /MH       1.413       -       -       -         11.50 TANSFORMERS       4.16 to 34.5 KV, 1500 KVA (CU)       3.00 TN       18       80.14 /MH       1.104       -       -         11.50 TANSFORMERS       4.16 to 34.5 KV, 2500 KVA (CU)       4.50 TN       14       80.14 /MH       1.084       -       -         11.50 TANSFORMERS       AUTO TRANSFORMER 27/33 KV, 7				STEEL	WALKWAY		37		2,937				2,
60 KW PROPANE ELECTRIC GENERATOR       1.50 TN       3       121.33 /MH       405       -         TAINTER GATES       11 AT 5 TONS EACH       55.00 TN       123       121.33 /MH       14.866       -         TAINTER HEADGATES       4 AT 5 TONS EACH       50.00 TN       45       12.33 /MH       14.866       -       -         10.41.00       ELECTRICAL EQUIPMENT       70       20.677       -       -       -         10.41.00       ELECTRICAL EQUIPMENT       6.00 TN       18       80.14 /MH       1.413       -       -         10.41.00       ELECTRICAL EQUIPMENT       6.00 TN       18       80.14 /MH       1.413       -       -         10.41.00       ELECTRICAL EQUIPMENT       7.25 TN       21       80.14 /MH       1.413       -       -         11.50 TN       5.00 TN       18       80.14 /MH       1.413       -       -       -         11.50 TANSFORMERS       4.16 to 34.5 KV, 1500 KVA (CU)       3.00 TN       18       80.14 /MH       1.104       -       -         11.50 TANSFORMERS       4.16 to 34.5 KV, 2500 KVA (CU)       4.50 TN       14       80.14 /MH       1.084       -       -         11.50 TANSFORMERS       AUTO TRANSFORMER 27/33 KV, 7													
TAINTER GATES       11 AT 5 TONS EACH       500 TN       123       121.33 MH       14,866       -         TAINTER HEADGATES       47 5 TONS EACH       20.00 TN       43       121.33 MH       14,866       -         MECHANICAL EQUIPMENT       170       20.00 TN       45       121.33 MH       14,866       -       -         10.41.00       ELECTRICAL EQUIPMENT       170       20.00 TN       45       01.4 MH       1,413       -       -         GENERATOR BUS TRANSFORMERS       4.16 to 34.5 KV, 1500 KVA (STEEL)       6.00 TN       18       80.14 MH       707       -       -         GENERATOR BUS TRANSFORMERS       4.16 to 34.5 KV, 1500 KVA (CU)       3.00 TN       9       80.14 MH       707       -       -         GENERATOR BUS TRANSFORMERS       4.16 to 34.5 KV, 2500 KVA (CU)       4.90 TN       14       80.14 MH       1,054       -       -         GENERATOR BUS TRANSFORMERS       4.16 to 34.5 KV, 2500 KVA (CU)       4.90 TN       14       80.14 MH       1,054       -       -         GENERATOR BUS TRANSFORMERS       4.16 to 34.5 KV, 2500 KVA (CU)       4.90 TN       14       80.14 MH       1,084       -       -         GENERATOR BUS TRANSFORMERS       4.16 to 34.5 KV, 2500 KVA (CU)       4.90			10.31.00			4.50 Th	0	404.00 000	105				
TAINTER HEADGATES MECHANICAL EQUIPMENT       4A 5 50NS EACH       20.00 TN       45       121.33 /MH       5.406 20,677       -       -       -         10.41.00       ELECTRICAL EQUIPMENT       GENERATOR BUS TRANSFORMERS       4.16 to 34.5 KV, 1500 KVA (STEEL)       6.00 TN       18       80.14 /MH       1.413       -       -       -         GENERATOR BUS TRANSFORMERS       4.16 to 34.5 KV, 1500 KVA (STEEL)       6.00 TN       18       80.14 /MH       1.413       -					11 AT 5 TONS FACH						-		14
MECHANICAL EQUIPMENT         170         20,677           10.41.00         ELECTRICAL EQUIPMENT         GENERATOR BUS TRANSFORMERS         4.16 to 34.5 KV, 1500 KVA (STEEL)         6.00 TN         18         80.14 /MH         1.413         -         -           GENERATOR BUS TRANSFORMERS         4.16 to 34.5 KV, 1500 KVA (STEEL)         6.00 TN         9         80.14 /MH         1.413         -         -           GENERATOR BUS TRANSFORMERS         4.16 to 34.5 KV, 2500 KVA (CUU)         3.00 TN         9         80.14 /MH         1.708         -         -           GENERATOR BUS TRANSFORMERS         4.16 to 34.5 KV, 2500 KVA (CUU)         4.90 TN         1.4         80.14 /MH         1.154         -         -           GENERATOR BUS TRANSFORMERS         4.16 to 34.5 KV, 2500 KVA (CUU)         4.90 TN         1.4         80.14 /MH         1.154         -         -         -           GENERATOR BUS TRANSFORMERS         A.16 to 34.5 KV, 2500 KVA (CUU)         4.90 TN         2.8         80.14 /MH         1.084         -         -         -           GENERATOR BUS TRANSFORMERS         AUTO TRANSFORMER 27/33 KV, 7500 KVA         4.60 TN         1.4         80.14 /MH         1.084         -         -         -           MISCELLANEOUS ELECTRICAL EQUIPMENT         ELECTRICAL EQUIPMENT <td></td> <td>5</td>													5
GENERATOR BUS TRANSFORMERS       4.16 to 34.5 KV, 1500 KVA (STEEL)       6.00 TN       18       80.14 /MH       1,413       -       -         GENERATOR BUS TRANSFORMERS       4.16 to 34.5 KV, 1500 KVA (CU)       3.00 TN       9       80.14 /MH       707       -       -         GENERATOR BUS TRANSFORMERS       4.16 to 34.5 KV, 1500 KVA (CU)       3.00 TN       9       80.14 /MH       707       -       -         GENERATOR BUS TRANSFORMERS       4.16 to 34.5 KV, 2500 KVA (CU)       4.90 TN       14       80.14 /MH       1,154       -       -         GENERATOR BUS TRANSFORMERS       AUTO TRANSFORMER 27/33 KV, 7500 KVA       9.60 TN       28       80.14 /MH       1,084       -       -         GENERATOR BUS TRANSFORMERS       AUTO TRANSFORMER 27/33 KV, 7500 KVA       9.60 TN       14       80.14 /MH       1,084       -       -         GENERATOR BUS TRANSFORMERS       AUTO TRANSFORMER 27/33 KV, 7500 KVA       4.60 TN       14       80.14 /MH       1,084       -       -       -         MISCELLANEOUS ELECTRICAL EQUIPMENT       ELECTRICAL EQUIPMENT       8.00 TN       24       80.14 /MH       1,084       -       -       -         18.00.00       SCRAP VALUE       MIXED STEEL       60 KW PROPANE ELECTRIC GENERATOR       -1.50 TN       <						20.00 111		121.00 /////					20
GENERATOR BUS TRANSFORMERS       4.16 to 34.5 KV, 1500 KVA (STEEL)       6.00 TN       18       80.14 /MH       1,413       -       -         GENERATOR BUS TRANSFORMERS       4.16 to 34.5 KV, 1500 KVA (CU)       3.00 TN       9       80.14 /MH       707       -       -         GENERATOR BUS TRANSFORMERS       4.16 to 34.5 KV, 1500 KVA (CU)       3.00 TN       9       80.14 /MH       707       -       -         GENERATOR BUS TRANSFORMERS       4.16 to 34.5 KV, 2500 KVA (CU)       4.90 TN       14       80.14 /MH       1,154       -       -         GENERATOR BUS TRANSFORMERS       AUTO TRANSFORMER 27/33 KV, 7500 KVA       9.60 TN       28       80.14 /MH       1,084       -       -         GENERATOR BUS TRANSFORMERS       AUTO TRANSFORMER 27/33 KV, 7500 KVA       9.60 TN       14       80.14 /MH       1,084       -       -         GENERATOR BUS TRANSFORMERS       AUTO TRANSFORMER 27/33 KV, 7500 KVA       4.60 TN       14       80.14 /MH       1,084       -       -       -         MISCELLANEOUS ELECTRICAL EQUIPMENT       ELECTRICAL EQUIPMENT       8.00 TN       24       80.14 /MH       1,084       -       -       -         18.00.00       SCRAP VALUE       MIXED STEEL       60 KW PROPANE ELECTRIC GENERATOR       -1.50 TN       <			40.44.00										
GENERATOR BUS TRANSFORMERS       4.16 to 34.5 KV, 1500 KVA (CU)       3.00 TN       9       80.14 /MH       707       -       -         GENERATOR BUS TRANSFORMERS       4.16 to 34.5 KV, 2500 KVA (STEEL)       7.25 TN       21       80.14 /MH       1,708       -       -         GENERATOR BUS TRANSFORMERS       4.16 to 34.5 KV, 2500 KVA (STEEL)       7.25 TN       21       80.14 /MH       1,708       -       -         GENERATOR BUS TRANSFORMERS       4.16 to 34.5 KV, 2500 KVA (CU)       4.90 TN       14       80.14 /MH       1,154       -       -         GENERATOR BUS TRANSFORMERS       AUTO TRANSFORMER 27/33 KV, 7500 KVA       9.60 TN       28       80.14 /MH       1,084       -       -         GENERATOR BUS TRANSFORMERS       AUTO TRANSFORMER 27/33 KV, 7500 KVA       4.60 TN       14       80.14 /MH       1,084       -       -       -         MISCELLANEOUS ELECTRICAL EQUIPMENT       8.00 TN       24       80.14 /MH       1,084       - <td></td> <td></td> <td>10.41.00</td> <td></td> <td></td> <td>6 00 TH</td> <td>10</td> <td>90 44 /0.01</td> <td>4.440</td> <td></td> <td></td> <td></td> <td>1</td>			10.41.00			6 00 TH	10	90 44 /0.01	4.440				1
GENERATOR BUS TRANSFORMERS       4.16 to 34.5 KV, 2500KVA (STEEL)       7.25 TN       21       80.14 /MH       1,708       -       -         GENERATOR BUS TRANSFORMERS       4.16 to 34.5 KV, 2500KVA (STEEL)       7.25 TN       21       80.14 /MH       1,708       -       -         GENERATOR BUS TRANSFORMERS       4.16 to 34.5 KV, 2500KVA (STEEL)       7.25 TN       14       80.14 /MH       1,154       -       -         GENERATOR BUS TRANSFORMERS       4.16 to 34.5 KV, 2500KVA (STEEL)       4.80 TN       14       80.14 /MH       1,154       -       -         GENERATOR BUS TRANSFORMERS       AUTO TRANSFORMER 27/33 KV, 7500KVA       9.60 TN       28       80.14 /MH       1,084       -       -       -         MISCELLANEOUS ELECTRICAL EQUIPMENT       8.00 TN       24       80.14 /MH       1,085       -											-		I
GENERATOR BUS TRANSFORMERS       4.16 to 34.5 KV, 2500 KVA (CU)       4.90 TN       14       80.14 /MH       1,154       -       -         GENERATOR BUS TRANSFORMERS       AUTO TRANSFORMER 27/33 KV, 7500 KVA       9.60 TN       28       80.14 /MH       2.261       -       -         GENERATOR BUS TRANSFORMERS       AUTO TRANSFORMER 27/33 KV, 7500 KVA       4.60 TN       14       80.14 /MH       1.084       -       -         MISCELLANEOUS ELECTRICAL EQUIPMENT       AUTO TRANSFORMER 27/33 KV, 7500 KVA       4.60 TN       14       80.14 /MH       1.084       -       -         MISCELLANEOUS ELECTRICAL EQUIPMENT       AUTO TRANSFORMER 27/33 KV, 7500 KVA       4.60 TN       14       80.14 /MH       1.084       -       -       -         MISCELLANEOUS ELECTRICAL EQUIPMENT       B.00 TN       24       80.14 /MH       1.084       - <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td>-</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td>1</td>							-						1
Image: Second problem strands formers       (STEEL) AUTO TRANDSFORMER 27/33 KV, 7500KVA       4.60 TN       14       80.14 /MH       1,084       -       -         MISCELLANEOUS ELECTRICAL EQUIPMENT       8.00 TN       24       80.14 /MH       1,085       -       -       -         WHOLE PLANT DEMOLITION       8.00 TN       24       80.14 /MH       1,085       -       -       -         18.00.00       SCRAP VALUE       8.06 TN       127       10,212       -       -       -         18.10.00       MIXED STEEL       60 KW PROPANE ELECTRIC GENERATOR       -1.50 TN       79.62 /MH       -       -       (177)													1
GENERATOR BUS TRANSFORMERS       AUTO TRANSFORMER 27/33 KV, 7500KVA       4.60 TN       14       80.14 /MH       1,084       -       -         MISCELLANEOUS ELECTRICAL EQUIPMENT       8.00 TN       24       80.14 /MH       1,885       -       -       -         MISCELLANEOUS ELECTRICAL EQUIPMENT       8.00 TN       24       80.14 /MH       1,885       -       -       -         WHOLE PLANT DEMOLITION       8.00 TN       24       80.52       781,842       -       -       -         18.00.00       SCRAP VALUE       MIXED STEEL       60 KW PROPANE ELECTRIC GENERATOR       -1.50 TN       79.62 /MH       -       -       -       -       -       -       (177)				GENERATOR BUS TRANSFORMERS		9.60 TN	28	80.14 /MH	2,261		-	-	2
MISCELLANEOUS ELECTRICAL EQUIPMENT     8.00 TN     24     80.14 /MH     1,885     -     -       ELECTRICAL EQUIPMENT     10,212     10,212     10,212     10,212     10,212       WHOLE PLANT DEMOLITION     8,652     781,842     781,842       18.00.00     SCRAP VALUE     80 TK     79,62 /MH     -     -     -       18.10.00     MIXED STEEL     60 KW PROPANE ELECTRIC GENERATOR     -     -     -     (177)				GENERATOR BUS TRANSFORMERS		4.60 TN	14	80.14 /MH	1,084		-	-	1
ELECTRICAL EQUIPMENT         127         10,212           WHOLE PLANT DEMOLITION         8,652         781,842           18.00.00         SCRAP VALUE           18.10.00         MIXED STEEL           MIXED STEEL         60 KW PROPANE ELECTRIC GENERATOR					(CU)	8.00 TN	24	80.14 /MH	1 885		_		1
18.00.00         SCRAP VALUE           18.10.00         MIXED STEEL           MIXED STEEL         60 KW PROPANE ELECTRIC GENERATOR         -1.50 TN         79.62 /MH         -         -         (177)						0.00 11		00.14 /WIT			-		10
18.10.00         MIXED STEEL           MIXED STEEL         60 KW PROPANE ELECTRIC GENERATOR         -1.50 TN         79.62 /MH         -         -         (177)													781,
18.10.00         MIXED STEEL           MIXED STEEL         60 KW PROPANE ELECTRIC GENERATOR         -1.50 TN         79.62 /MH         -         -         (177)		18.00 00		SCRAP VALUE									
MIXED STEEL 60 KW PROPANE ELECTRIC GENERATOR -1.50 TN 79.62 /MH (177)			18.10.00										
MIXED STEEL TAINTER GATES -55.00 TN 79.62 /MH /6.404\				MIXED STEEL				79.62 /MH		-	-		(
				MIXED STEEL	TAINTER GATES	-55.00 TN		79.62 /MH		-	-	(6,494)	(6,4

Area	Group	Phase	Description	Notes	Quantity	Man Hours	Crew Rate	Labor Cost	Material Cost	Subcontract Cost	Scrap Value	Total Cost
		18.10.00	MIXED STEEL									
			MIXED STEEL	TAINTER HEADGATES	-20.00 TN		79.62 /MH				(2,362)	(2,362
			MIXED STEEL	4.16 to 34.5 KV, 1500KVA (STEEL)	-6.00 TN		79.62 /MH		_		(708)	(708
			MIXED STEEL	4.16 to 34.5 KV, 2500KVA (STEEL)	-7.25 TN		79.62 /MH				(856)	(856
									-	-		
			MIXED STEEL	AUTO TRANSFORMER 27/33 KV, 7500KVA (STEEL)	-4.60 TN		79.62 /MH		-	-	(543)	(543
			MIXED STEEL	TAINTER GATES STRUCTURE AND WALKWAY	-33.00 TN		79.62 /MH		-	-	(3,897)	(3,897
			MIXED STEEL								(15,037)	(15,037
		18.30.00	COPPER									
			COPPER	CABLE	-10.00 TN		79.62 /MH		-	-	(31,800)	(31,80
			COPPER	MISC. TRANSFORMERS & MOTORS UNIT 1	-6.00 TN		79.62 /MH		-	-	(19,080)	(19,08
			COPPER	4.16 to 34.5 KV, 1500 KVA (CU)	-3.00 TN		79.62 /MH		-	-	(9,540)	(9,54
			COPPER	4.16 to 34.5 KV, 2500 KVA (CU)	-4.90 TN		79.62 /MH		_		(15,582)	(15,58
			COPPER	AUTO TRANSFORMER 27/33 KV, 7500KVA	-4.60 TN		79.62 /MH				(14,628)	(14,62
			COPPER	(CU)							(90,630)	(90,630
			SCRAP VALUE								(105,667)	(105,667
	21.00.00		CIVIL WORK									
		21.17.00	EXCAVATION									
			FOUNDATION EXCAVATION, CLAY USING 1 CY BACKHOE	RIVERBED EXCAVATION FOR RIPRAP	115.00 CY	22	88.08 /MH	1,894		-	-	1,89
			EXCAVATION			22		1,894				1,89
		21.41.00	Erosion and Sedimentation Control									
			RIPRAP, RANDOM BROKEN STONE, MACHINE PLACED	FOR CAUSEWAYS INSTALLATION	9,778.00 CY	4,314	74.10 /MH	319,631	399,920		-	719,5
			RIPRAP, RANDOM BROKEN STONE, MACHINE PLACED	NEW STONE REQD IF CAUSEWAY STONE IS	29,642.00 CY	9,682	74.10 /MH	717,418	1,212,358	-	-	1,929,7
			RIPRAP, RANDOM BROKEN STONE, MACHINE PLACED	REUSED (39420-9778) RELOCATE CAUSE WAY STONE FOR RIVER BEND PROTECTION	9,778.00 CY	3,194	74.10 /MH	236,654		-	-	236,6
			RIPRAP, RANDOM BROKEN STONE, MACHINE PLACED	RIP RAP PROTECTION AT FLOOR SLABS TO REMAIN IN PLACE	115.00 CY	38	74.10 /MH	2,783	4,704	-		7,48
			Erosion and Sedimentation Control			17,227		1,276,486	1,616,982			2,893,46
		21.47.00	LANDSCAPING									
			HYDRO OR AIR SEED & MULCH & FERTILIZER	RIVERBAND STABILIZATIION	299.00 AC	4,243	74.64 /MH	316,715	456,424		-	773,13
			LANDSCAPING			4,243		316,715	456,424			773,13
		21.65.00	Soil Remediation									
			REMOVAL OF LOCALIZED SILT AT DAM	LIME ADDITIVE FOR DRYING	2.639.00 CY		196.64 /MH			105,560	-	105.56
			REMOVAL OF LOCALIZED SILT AT DAM	LOAD, MIX AND HAUL LIME AND SEDIMENT MIX (5278+2639)	7,917.00 CY		196.64 /MH			475,020	-	475,0
			REMOVAL OF LOCALIZED SILT AT HEADGATE	LOAD, MIX AND HAUL LIME AND SEDIMENT MIX 926+463	1,389.00 CY		196.64 /MH			83,340		83,34
			Soil Remediation							663,920		663,92
			CIVIL WORK			21,491		1,595,096	2,073,405	663,920		4,332,42
			ACCOUNT B DEMOLITION ACCOUNT B			30,143		2,376,937	2,073,405	663,920	(105,667)	5,008,59
CCOUNT C	40.00.00		DEMOLITION ACCOUNT C									
	10.00.00		WHOLE PLANT DEMOLITION									
		10.22.00	CONCRETE									
			EQUIPMENT/ BUILDING FOUNDATION	TAINTER GATE - BOTTOM PORTION : APRON AND THROAT	3,580.00 CY	4,431	89.94 /MH	398,497		-	-	398,4
			EQUIPMENT/ BUILDING FOUNDATION	GENERATOR HOUSE	6.582.00 CY	8,146	89.94 /MH	732,655		-	-	732,6
			CONCRETE		0,002.00 01	12,577	00.01 /////	1,131,151			-	1,131,1
		10.23.00	STEEL									
		10.20.00		GENERATOR HOUSE	111.80 TN	40-	70.60 44.	9,949				~ ~
			STRUCTURAL AND GIRT STEEL STEEL	GENERATOR HOUSE	111.80 IN	125 125	79.62 /MH	9,949 9,949		-		9,9 <b>9,9</b>
		10.24.00	ARCHITECTURAL									
		10.24.00										
			GENERATOR HOUSE	TALL	447,520.00 CF	1,920	89.81 /MH	172,440		-	· · · ·	172,4
			ARCHITECTURAL			1,920		172,440				172,4
		10.31.00	MECHANICAL EQUIPMENT									
			DEMO 1.44 MW PENSTOCKS	1 AT 20000# EA	10.00 TN	110	85.53 /MH	9,409				9,4
										-		
			DEMO 1.00 MW PENSTOCKS	2 GENERATORS AT 8 TN EA	16.00 TN	176	85.53 /MH	15,055				15,05

Page 5

Area	Group	Phase	Description	Notes	Quantity	Man Hours	Crew Rate	Labor Cost	Material Cost	Subcontract Cost	Scrap Value	Total Cost
			MECHANICAL EQUIPMENT			286		24,464				24,464
		10.86.00	WASTE									
		10.00.00	WASTE WASTE - USER DEFINED	MISC	1.00 LS	0	121.33 /MH	13		10,000		10,013
			WASTE			0		13		10,000		10,013
			WHOLE PLANT DEMOLITION			14,908		1,338,018		10,000		1,348,018
	18.00.00		SCRAP VALUE									
		18.10.00	MIXED STEEL									
			MIXED STEEL	DEMO 1.44 MW PENSTOCKS	-10.00 TN		79.62 /MH		-	-	(1,181)	(1,181)
			MIXED STEEL	DEMO 1.00 MW PENSTOCKS	-19.00 TN		79.62 /MH		-	-	(2,244)	(2,244)
			MIXED STEEL	GENERATOR HOUSE	-111.80 TN		79.62 /MH		-	-	(13,201)	(13,201)
			MIXED STEEL SCRAP VALUE								(16,626)	(16,626)
			SCRAF VALUE								(10,020)	(10,020)
	21.00.00		CIVIL WORK									
		21.17.00	EXCAVATION									
			FOUNDATION EXCAVATION, CLAY USING 1 CY BACKHOE	EARTHWORK CUT AT DAM ABUTMENTS (330-115)	215.00 CY	40	88.08 /MH	3,542		-	-	3,542
			EXCAVATION			40		3,542				3,542
		21.41.00	Erosion and Sedimentation Control									
			RIPRAP, RANDOM BROKEN STONE, MACHINE PLACED	RIP RAP PROTECTION AT ABUTMENTS TO	280.00 CY	91	74.10 /MH	6,777	11,452	-	-	18,229
			Erosion and Sedimentation Control	REMAIN IN PLACE (395-115)		91		6,777	11,452			18,229
			Erosion and Sedimentation Control			31		0,777	11,452			10,229
		21.47.00	LANDSCAPING									
			HYDRO OR AIR SEED & MULCH & FERTILIZER	CREDIT (299-290)	-9.00 AC	-128	74.64 /MH	(9,533)	(13,738)	-	÷.,	(23,272)
			LANDSCAPING			-128		(9,533)	(13,738)			(23,272)
		21.65.00	Soil Remediation									
			REMOVAL OF LOCALIZED SILT AT DAM	LIME ADDITIVE FOR DRYING (5278-2639)	2,639.00 CY		196.64 /MH			105,560	-	105,560
			REMOVAL OF LOCALIZED SILT AT DAM	LOAD, MIX AND HAUL LIME AND SEDIMENT MIX CREDIT 16284-7917)	8,367.00 CY		196.64 /MH			502,020	-	502,020
			Soil Remediation	WIX CREDIT 10204-7917)						607,580		607,580
			CIVIL WORK			4		785	(2,286)	607,580		606,079
	22.00.00		CONCRETE									
		22.13.00	Concrete									
			FLOWABLE FILL, 1500 PSI	FILL PENSTOCKS TO PREVENT BYPASS FLOW	294.00 CY	162	76.27 /MH	12,334	27,930	-		40,264
			Concrete			162		12,334	27,930		-	40,264
			CONCRETE			162		12,334	27,930			40,264
			ACCOUNT C DEMOLITION ACCOUNT C			15,074		1,351,137	25,644	617,580	(16,626)	1,977,735



# EXHIBIT 3 Elkhart Hydroelectric Plant Asbestos Removal Conceptual Cost Estimate No. 33740B

\\Snl6c\data6\AEPFossil\Rockport\_Tanners Creek CDCEU 2015\6.0 Evaluations-Reports\6.06 Studies\Elkhart\Elkhart\Elkhart\Hydro\_Conceptual Demolition Cost Estimate\_No 33708\_Rev 0.doc

Sargent & Lundy

AEP ELKHART HYDROELECTRIC PLANT DISMANTLEMENT STUDY - ASBESTOS REMOVAL CONCEPTUAL COST ESTIMATE Indiana Michigan Power Company Attachment JAC-3 Witness; Cash Page 126 of 205

Client	AEP
Estimator	RCK
Labor rate table	15INSOU
Project No. Station Name	13465-000 ELKHART
Unit	ALL
Estimate Date	02/12/2016
Reviewed By	ADC
Approved By	MNO
Estimate No.	33740B
Estimate Class	Conceptual
Cost index	INSOU

Estimate No.: 33740B Project No.: 13465-000 Estimate Date: 02/12/2016 Prep/Rev/App: RCK/ADC/MNO

#### AEP ELKHART HYDROELECTRIC PLANT DISMANTLEMENT STUDY - ASBESTOS REMOVAL CONCEPTUAL COST ESTIMATE

Area	Description	Subcontract Cost	Scrap Value	Material Cost	Man Hours	Labor Cost	Total Cost
ASBESTOS	ASBESTOS REMOVAL TOTAL DIRECT	275,500 275,500					275,500 275,500

#### AEP ELKHART HYDROELECTRIC PLANT DISMANTLEMENT STUDY - ASBESTOS REMOVAL CONCEPTUAL COST ESTIMATE

#### **Estimate Totals**

Description	Amount	Totals	Hours
Direct Costs:			
Labor			
Material			
Subcontract	275,500		
Scrap Value			
	275,500	275,500	
Other Direct & Construction			
Indirect Costs:			
91-1 Scaffolding			
91-2 Cost Due To OT 5-10's			
91-3 Cost Due To OT 6-10's 91-4 Per Diem			
91-4 Per Diem 91-5 Consumables			
91-8 Freight on Material			
91-9 Freight on Process Equip 91-10 Sales Tax			
91-11 Contractors G&A			
91-12 Contractors Profit			
		275,500	
		275,500	
Indirect Costs:			
93-1 Engineering Services			
93-2 CM Support			
93-3 Start-Up/Commissioning			
93-4 Start-Up/Spare Parts 93-5 Excess Liability Insur.			
93-6 Sales Tax On Indirects			
93-7 Owners Cost	27,550		
93-8 EPC Fee	21,000		
	27,550	303,050	
Contingency:			
94-1 Contingency on Material			
94-2 Contingency on Labor			
94-3 Contingency on Sub.	55,100		
94-6 Contingency on Scrap	E E 40		
94-5 Contingency on Indirect	5,510		
	60,610	363,660	
Escalation:			
96-1 Escalation on Material			
96-2 Escalation on Labor			
96-3 Escalation on Subcontract			
96-4 Escalation on Scrap			
96-5 Escalation on Indirects			
		363,660	
		363,660	
Total		363,660	

#### AEP ELKHART HYDROELECTRIC PLANT DISMANTLEMENT STUDY - ASBESTOS REMOVAL CONCEPTUAL COST ESTIMATE


Area	Group	Phase	Description	Notes	Quantity	Man Hours	Crew Rate	Labor Cost	Material Cost	Subcontract Cost	Scrap Value	Total Cost
ASBESTOS	10.00.00	10.37.00	ASBESTOS REMOVAL WHOLE PLANT DEMOLITION ASBESTOS REMOVAL ASBESTOS REMOVAL - MISC MATERIALS ASBESTOS REMOVAL - 4 KV CUBICLES ASBESTOS REMOVAL - 9 - CONTROL AND INSTRUMENT	WINDOW CAULKING MISC MATERIALS 18-4 KV CUBICLES 9 PANELS 3'X1'X9'	2.00 CY 134.00 CY 9.00 CY		121.33 /MH 121.33 /MH 121.33 /MH			3,800 254,600 17,100	:	3,800 254,600 17,100
			PANELS ASBESTOS REMOVAL WHOLE PLANT DEMOLITION ASBESTOS ASBESTOS REMOVAL							275,500 275,500 275,500		275,500 275,500 275,500




# EXHIBIT 4 Elkhart Hydroelectric Plant Retirement Option 1-3 Demolition Scope and Sequence

\\Snl6c\data6\AEPFossil\Rockport\_Tanners Creek CDCEU 2015\6.0 Evaluations-Reports\6.06 Studies\Elkhart\Elkhart\Elkhart\Hydro\_Conceptual Demolition Cost Estimate\_No 33708\_Rev 0.doc


Sargent & Lundy
















# ELKHART HYDRO RETIREMENT DEMO SEQUENCE SKETCHES & CIVIL QUANTITIES BY: S&L


	ELKHART		
	OPTION 2		
ITEM	QUANTITY	UNIT	REMARKS
GRASS SEEDING	299	ACRE	
RIPRAP PROTECTION	39,420	CY	2 ft riprap protection @ D(50)=12"
RIVERBED EXCAVATION FOR RIPRAP	115	CY	TO BE REPLACED BY RIPRAP
RIPRAP PROTECTION AT SPILLWAY FLOOR SLAB	115	CY	2 ft riprap protection @ D(50)=12"

	OPTION 3		
ITEM	QUANTITY	UNIT	REMARKS
GRASS SEEDING	290	ACRE	
RIPRAP PROTECTION AT RIVER BENDS	39,420	CY	2 ft riprap protection @ D(50)=12"
RIPRAP PROTECTION AT DAM ABUTMENTS	395	CY	2 ft riprap protection @ D(50)=12"
EARTHWORK CUT AT DAM ABUTMENTS	330	CY	Riverbed removal for riprap placemen
	GRASS SEEDING RIPRAP PROTECTION AT RIVER BENDS RIPRAP PROTECTION AT DAM ABUTMENTS	ITEMQUANTITYGRASS SEEDING290RIPRAP PROTECTION AT RIVER BENDS39,420RIPRAP PROTECTION AT DAM ABUTMENTS395	ITEMQUANTITYUNITGRASS SEEDING290ACRERIPRAP PROTECTION AT RIVER BENDS39,420CYRIPRAP PROTECTION AT DAM ABUTMENTS395CY

Note:


Localized miscellaneous silt removal and earthwork as part of dam demolition by Brandenburg

JANUARY 26, 2016 Indiana Michigan Power Company Attachment JAC-3 PAGE 4 OF 7







ELKHART HYDRO RETIREMENT DEMO SEQUENCE SKETCHES & CIVIL QUANTITIES BY: S&L



JANUARY 26, 2016 Indiana Michigan Power Company PAGE Attachmerit JAC-3 Witness; Cash Page 135 of 205







# Mottville Hydroelectric Plant CONCEPTUAL DEMOLITION COST ESTIMATE

Prepared for: Indiana Michigan Power Company (Owner) and American Electric Power Service Corporation

> Project No. 13465-000 February 12, 2016 Revision 0



55 East Monroe Street Chicago, IL 60603-5780 USA





February 12, 2016

# **Issue Summary Page**

Revision Number	Date	Purpose	Prepared By	Reviewed By	Approved By	Pages Affected
A	02/02/16	Comments	R. C. Kinsinger	A.D. Chapin D. F. Franczak	M. N. Ozan	All
0	02/12/16	Use	R. C. Kinsinger Ø <i>Kindunger</i> AC	A.D. Chapin AChapin D. F. Franczak S. T. Trazel	T. J. Meehan Zmut	All

Page IS-1

\\Snl6e\data6\AEPFossil\Rockport\_Tanners Creek CDCEU 2015\6.0 Evaluations-Reports\6.06 Studies\Mottville\Mottville\Hydro\_Conceptual Demolition Cost Estimate\_No 33709\_Rev 0.doc



**Section** 

Indiana Michigan Power Company Attachment JAC-3 Witness; Cash Mottville Hydroelectric Plant<sup>e 140 of 205</sup> Indiana Michigan Power Company American Electric Power Service Corporation Conceptual Demolition Cost Estimate February 12, 2016

# TABLE OF CONTENTS

Do	σo
ra	ge

1	INTRODUCTION	1
2	COST ESTIMATE SUMMARY	1
3	TECHNICAL BASIS	4
4	COMMERICAL BASIS	6
4.1	General Information	6
4.2	Quantities/Material Cost	6
4.3	Construction Labor Wages	6
4.4	Scrap Value	7
4.5	Indirect Costs	8
4.6	Escalation	8
4.7	Contingency	8
4.8	Assumptions	8
5	REFERENCES	9

<u>EXHIBIT</u>	DESCRIPTION
1	Conceptual Cost Estimate Summary
2	Conceptual Demolition Cost Estimate No. 33709B
3	Asbestos Removal Conceptual Cost Estimate No. 33741B
4	Retirement Option 1-3 Demolition Scope and Sequence

TOC-1





Indiana Michigan Power Company Attachment JAC-3 Witness; Cash Mottville Hydroelectric Plant<sup>141 of 205</sup> Indiana Michigan Power Company American Electric Power Service Corporation Conceptual Demolition Cost Estimate February 12, 2016

# 1.0 INTRODUCTION

The Mottville Hydroelectric Plant located in the City of Mottville, Michigan is owned and operated by Indiana Michigan Power Company (I&M), a subsidiary of American Electric Power (AEP). The plant consists of (from right to left referenced facing downstream) an earth embankment right of the powerhouse, an integral intake and powerhouse, a gated reinforced concrete spillway and an earth embankment to the left of the spillway. An abandoned fish ladder, separate the powerhouse and spillway. The spillway is equipped with ten (10) tainter gates which regulate headwater. The combined intakepowerhouse is situated to the right of the spillway. The powerhouse contains four (4) vertical shaft operating Allis-Chalmers turbine generators. Each unit is rated at 0.42 MW and were installed in 1923.

AEP recently contracted S&L to prepare conceptual demolition cost estimates considering three (3) retirement options defined as follows: (1) Option 1, Non-Power Operation, (2) Option 2, Partial Removal of the Dam Structures, and (3) Option 3, Complete Removal of the Dam and Powerhouse. Also, in addition S&L was requested to prepare a separate Asbestos Removal Conceptual Cost Estimate.

The objective of the conceptual demolition cost estimates is to determine the gross demolition costs for Mottville Hydroelectric Plant (including gross salvage credits and any other benefits), in support of documenting a component of future AEP book depreciation rates to be approved by the I&M's state commissions and potential future inclusion in submittal of a rate case to the state commissions, and other potential uses. The cost estimate considers the demolition/dismantlement methodology which complies with current OSHA rules and regulations.

## 2.0 COST ESTIMATE SUMMARY

Conceptual Demolition Cost Estimate No. 33709B, dated February 12, 2016, was prepared and is included as Exhibit 2. This cost estimate was prepared for retirement option 3, but includes accounts allowing the determination of cost estimates for retirement options 1 and 2 as well. A summary of the conceptual demolition cost estimates for all three (3) retirement options is provided in Exhibit 1 and detailed in the following tables.





The cost estimate is structured into a code of accounts as identified in Table 2-1.

Account Number	Description
10, 21, 22	Demolition Costs (including steel, equipment & piping scrap value)
18	Scrap Value Costs
91	Other Direct & Construction Indirect Costs
93	Indirect Costs
94	Contingency Costs
96	Escalation Costs

 Table 2-1

 Cost Estimate Code of Accounts

The results of the cost estimate for retirement option 3 are provided in Table 2-2 below.

# Table 2-2Cost Estimate Results SummaryRetirement Option 3

Description	Total Cost
Demolition Cost	\$4,889,193
Scrap Value	(\$85,278)
Direct Cost Subtotal	\$4,803,914
Indirect Cost	\$489,000
Contingency Cost	\$1,089,000
Escalation Cost	\$0
Total Project Cost	\$6,381,915



The results of the cost estimate for retirement option 1 are provided in Table 2-3 below.

Description	Total Cost	
Demolition Cost	\$65,833	
Scrap Value	(\$28,733)	
Direct Cost Subtotal	\$37,100	
Indirect Cost	\$4,000	
Contingency Cost	\$18,200	
Escalation Cost	\$0	
Total Project Cost	\$59,300	

# Table 2-3Cost Estimate Results SummaryRetirement Option 1

The results of the cost estimate for retirement option 2 are provided in Table 2-4 below.

# Table 2-4 Cost Estimate Results Summary Retirement Option 2

Description	Total Cost	
Demolition Cost	\$4,337,930	
Scrap Value	(\$34,814)	
Direct Cost Subtotal	\$4,303,116	
Indirect Cost	\$438,000	
Contingency Cost	\$961,000	
Escalation Cost	\$0	
Total Project Cost	\$5,702,116	

Page 3 of 9 \\Snl6c\data6\AEPFossil\Rockport\_Tanners Creek CDCEU 2015\6.0 Evaluations-Reports\6.06 Studies\Mottville\Mottville Hydro\_Conceptual Demolition Cost Estimate\_No 33709\_Rev 0.doc



Asbestos Removal Conceptual Cost Estimate No. 33741B, dated February 12, 2016, was prepared and is included as Exhibit 3. The total estimated cost for asbestos removal prior to plant dismantlement is \$5,100. Quantities were derived from drawings and past experience. Asbestos removal applies to the powerhouse, thus the removal cost applies to all three (3) retirement options. The cost of asbestos removal is excluded from the total conceptual demolition cost estimates for each retirement option detailed in the tables above.

# 3.0 TECHNICAL BASIS

The scope of dismantlement is based on three (3) retirement options, as requested by AEP, as follows:

<u>Retirement Option 1, Non-Power Operation:</u> This scenario would consider leaving intact all of the existing water-impounding structures and the powerhouse. Only the electric generating units and their auxiliary equipment would be removed so as to preclude the generation of electricity by the former hydroelectric plant. In addition, the spillway would be modified as required in order to pass river flows and maintain the impoundment's water surface elevation at the current conditions.

<u>Retirement Option 2, Partial Removal of the Dam Structures:</u> This scenario would consider demolition and removal of certain elements of the hydroelectric site in order to drain the existing impoundment and create a natural river channel through the dam site. This would generally include removal of the generating units and powerhouse and possibly but not inclusively demolition and removal of substantial portions of concrete spillway structures. This option would address the removal and stabilization of any sediments that have accumulated at the upstream end of the dam and the stabilization of the newly exposed reservoir/riverbanks.

<u>Retirement Option 3, Complete Removal of the Dam and Powerhouse:</u> This scenario would consider complete removal of the electric generating components and powerhouse and complete removal of the dam. Similar to option 2, this option would address the removal and stabilization of any sediments that have accumulated at the upstream end of the dam and the stabilization of the newly exposed reservoir/riverbanks.

The scope of dismantlement for each retirement option, as interpreted from the definitions above, are identified on marked plant drawings included as Exhibit 4. The scope of dismantlement and the sequence of demolition for each retirement option are defined on these sketches.

Page 4 of 9



Retirement options 2 and 3 include the same demolition work as retirement option 1, removal of the generating unit components from the powerhouse. The powerhouse is not removed in retirement option 1, but is removed in retirement option 3. For retirement option 2 the powerhouse may or may not be removed, depending on if removal of portions of the dam can restore river flow to natural flow without removing the powerhouse (refer to Exhibit 4).

For each of the retirement options the scope of sediment removal is based on the quantity that would be disturbed from the demolition work itself and not complete removal of all sediment potentially disturbed by the partial or complete removal of the dam. The subcontractor costs included in retirement options 2 and 3 are for lime stabilization of the sediment and removal of the sediment and other wastes (such as timber) to the waste disposal site. These costs do not apply to retirement option 1 since only generating unit components in the powerhouse are removed and this material has scrap value.

Retirement options 2 and 3 include the stabilization of newly exposed riverbanks, which include the dam area and areas upstream of the dam. The extent of stabilization for retirement option 3 may be slightly more than retirement option 2, since the entire dam is being removed in retirement option 3.

The following are excluded from the scope of the conceptual demolition cost estimates:

- Asbestos removal (separate cost estimate prepared).
- The conceptual demolition cost estimate includes the cost to remove the one (1) main power transformer located in the switchyard, but not the cost to remove the switchyard itself (and remaining components in the switchyard).
- > Evaluation of the effect of the complete removal of the series of dams on the river watershed.
- Evaluation of the effect of the removal of any one dam, on either the upstream or downstream side dam and reservoir, after removal of the dam.
- Potential social or environmental impact of the draining of the reservoirs and the impact on property values or other community impact.
- The conceptual demolition cost estimate excludes any costs related to performing surveys to quantify the amount of sediment and chemical testing of the sediment. The quantity of sediment to be removed was estimated for retirement options 2 and 3 and the cost to remove the sediment is included in the conceptual demolition cost estimate. As stated above, the scope of sediment removal is based on the quantity that would be disturbed from the demolition work itself and not complete removal of the sediment potentially disturbed by the partial or complete removal of the dam.







The scope of the demolition cost estimate was reaffirmed during a review of the facility by two S&L employees in conjunction with a representative from Bradenburg Industrial Service Co. and AEP corporate and plant personnel. The facility review was held on Tuesday December 15, 2015.

# 4.0 COMMERCIAL BASIS

### 4.1 General Information

The Conceptual Demolition Cost Estimates prepared for the Mottville Hydroelectric Plant is a conceptual estimate of the cost to dismantle the powerhouse and dam in accordance with the scope defined for each of the three (3) retirement options. Costs were calculated for (1) demolition of existing plant structures and equipment and associated site restoration costs, (2) scrap value of steel, copper and stainless steel, as applicable, (3) associated indirect costs, and (4) contingency.

All units used in the cost estimate are U.S. Standard and all costs are in US Dollars (4<sup>th</sup> Quarter 2015 levels). A three (3) year demolition schedule is anticipated for retirement option 3 including asbestos removal (to be performed prior to start of demolition work). The schedule takes into consideration environmental permitting, asbestos removal which includes mapping out all asbestos contamination throughout the powerhouse and associated abatement, followed by total plant demolition and site restoration. The schedule for the other two (2) retirement options would be correspondingly less.

# 4.2 Quantities/Material Cost

Quantities of pieces of equipment and/or bulk material commodities used in the cost estimates were intended to be reasonable and representative of projects of this type. Material quantities were estimated from the hydroelectric plant drawings and data provided by AEP, and the information obtained from Plant personnel during the facility review.

## 4.3 Construction Labor Wages

Craft labor rates (Craft Hourly Rate) for the cost estimate were calculated as Union Labor rates for South Bend, Indiana, based on 2015, R. S. Means "Labor Rates for the Construction Industry". The craft rates were incorporated into work crews appropriate for the activities by adding allowances for small tools, construction equipment, insurance, and site overheads to arrive at crew hourly rates detailed in the cost estimate. A 1.10 regional labor productivity multiplier was included based on Compass International Global Construction Yearbook, 2015 Edition, for union work in Indiana. National Maintenance

Page 6 of 9



Agreement Rates (typically negotiated by AEP) do not apply as this work is assumed to be performed as a lump sum contract.

# 4.3.1 Labor Work Schedule and Incentives

The estimate assumed a 5x8 work week. No per diem or other labor incentives are included.

# 4.3.2 Construction Indirects

Allowances were included in the cost estimate as direct costs as noted for the following:

- > Freight: Material and scrap freight included in the material and scrap costs.
- Additional Crane Allowance: None included. Cost of cranes and construction machinery are included in the labor wage rates.
- Mobilization and Demobilization: Included in labor wage rates.
- Scaffolding: Included in labor wage rates.
- > Consumables: Included in material and labor costs.
- > Per Diem Costs: Excluded from the estimate.
- > Contractor's General and Administrative Costs and Profit: Included in the labor wage rates.

# 4.4 Scrap Value

The value of scrap was determined by a 3 month average (November and December 2015 and January 2016) using Zone 4 (USA Midwest) of the "Scrap Metals Market Watch" (<u>www.americanrecycler.com</u>).

Since the values obtained are delivered pieces, 25% of the values obtained were deducted to pay for separation, preparation and shipping to the mills. This resulted in realized prices of:

- Mixed Steel Value @ \$118/Ton
- Copper Value @ \$3,180/Ton
- Stainless Steel @ \$675/Ton
- <u>Note:</u> 1 Ton = 2,000 Lbs

All steel is considered to be mixed steel unless otherwise noted.

February 12, 2016

American Electric Power Service Corporation

**Conceptual Demolition Cost Estimate** 

#### 4.5 Indirect Costs

Allowances were included in the cost estimate as indirect costs as noted for the following:

- > Engineering, Procurement and Project Services: None included.
- Construction Management Support: None included.
- Owners Cost: Included as 10.0% of the total direct cost. Owners Costs include owner project engineering, administration and construction management, permits and fees, legal expenses, taxes, removal of chemicals, etc.

#### 4.6 Escalation

No allowance for escalation was included in the cost estimate. All costs are determined in 4<sup>th</sup> Quarter

2015 levels.

#### 4.7 Contingency

Allowances were included in the cost estimate as contingency as noted for the following:

- Scrap Value: Included as 15.0% reduction in the salvage value resulting in a total net reduction in the salvage value. The contingency assumes a potential drop in salvage value thus increasing the project cost. Scrap costs are very volatile but by taking a 3-month average some of the effect of volatility is reduced. However there are other variables that affect scrap pricing such as the quantity and processing fees. The contingency applied is based on the estimators confidence in scrap pricing used in the demolition cost estimate.
- Material: Included as 20.0% of the total material cost.
- Labor: Included as 20.0% of the total labor cost.
- ▶ Indirect: Included as 20.0% of the total indirect cost.
- Subcontractor: Included as 20.0% of the total subcontractor cost.

#### 4.8 Assumptions

The following assumptions apply to the cost estimates.

- The cost estimate for each retirement option is based on the scope and the demolition sequences defined on the sketches provided in Exhibit 4.
- All chemicals will be removed by the Owner prior to demolition, from the facilities to be demolished.



Mottville Hydroelectric Plant<sup>149</sup> of <sup>205</sup> Indiana Michigan Power Company American Electric Power Service Corporation Conceptual Demolition Cost Estimate February 12, 2016

- All electrical equipment and wiring is de-energized prior to start of dismantlement, except for that required for remote operation of two (2) of the tainter gates after demolition is completed for retirement option 1.
- > No extraordinary environmental costs for demolition have been included.
- Handling, on-site and off-site disposal of hazardous materials would be performed in compliance with methods approved by Owner.
- The window glazing in the powerhouse may be asbestos contaminated and an allowance for removal and disposal is included in the asbestos removal cost estimate. There is no building or pipe insulation in the facility and consequently no insulation related asbestos contamination.
- Switchyards within the plant boundaries are not part of the scope, neither are access roads to these facilities. Fences and gates needed to protect the switchyard will be left in place.
- All demolished materials are considered debris, except for organic combustibles and nonembedded metals which have scrap value.
- The basis for salvage estimating is for scrap value only. No resale of equipment or material is included.
- Sediment removed due to demolition work is treated with lime and hauled offsite to an approved waste disposal facility.

## 5.0 REFERENCES

- 5.1 Mottville Plant Drawings: One-Line Diagrams, No. E-1000, Revision 16 and No. 14-12001-2, 12/17/91.
- **5.2** American Electric Power, Supporting Technical Information Document, Mottville Hydroelectric Project, September, 2007.





Indiana Michigan Power Company Attachment JAC-3 Witness; Cash Mottville Hydroelectric Plant<sup>150 of 205</sup> Indiana Michigan Power Company American Electric Power Service Corporation Conceptual Demolition Cost Estimate February 12, 2016

# EXHIBIT 1 Mottville Hydroelectric Plant Conceptual Demolition Cost Estimate Summary

\\Snl6c\data6\AEPFossil\Rockport\_Tanners Creek CDCEU 2015\6.0 Evaluations-Reports\6.06 Studies\Mottville\Mottville\Mottville\Hydro\_Conceptual Demolition Cost Estimate\_No 33709\_Rev 0.doc



	Reti	ement Option 1	Retirement Option 2	Retirement Option 3
Demolition Cost	\$	65,833	\$ 4,337,930	\$ 4,889,193
Scrap Value	\$	(28,733)	\$ (34,814)	\$ (85,278)
Direct Cost Subtotal	\$	37,100	\$ 4,303,116	\$ 4,803,914
Indirect Cost	\$	4,000	\$ 438,000	\$ 489,000
Contingency Cost	\$	18,200	\$ 961,000	\$ 1,089,000
Escalation Cost	\$	-	\$ -	\$ -
Total Demolition Cost	\$	59,300	\$ 5,702,116	\$ 6,381,915



# EXHIBIT 2 Mottville Hydroelectric Plant Conceptual Demolition Cost Estimate No. 33709B

\Snl6c\data6\AEPFossil\Rockport\_Tanners Creek CDCEU 2015\6.0 Evaluations-Reports\6.06 Studies\Mottville\Mottville\Mottville\Hydro\_Conceptual Demolition Cost Estimate\_No 33709\_Rev 0.doc

Sargent & Lundy

Indiana Michigan Power Company Attachment JAC-3 Witness; Cash Page 153 of 205

Client	AEP
Estimator	RCK
Labor rate table	15INSOU
Project No. Station Name	13465-000 FI KHART
Unit	ALL
Estimate Date	02/12/2016
<b>Reviewed By</b>	ADC
Approved By	MNO
Estimate No.	33709B
Estimate Class	Conceptual
Cost index	INSOU

Estimate No.: 33709B Project No.: 13465-000 Estimate Date: 02/12/2016 Prep/Rev/App: RCK/ADC/MNO

Area	Description	Subcontract Cost	Scrap Value	Material Cost	Man Hours	Labor Cost	Total Cost
ACCOUNT A	DEMOLITION ACCOUNT A		(28,733)	11,020	587	54,813	37,100
ACCOUNT B	DEMOLITION ACCOUNT B	506,220	(6,081)	2,248,154	20,696	1,517,723	4,266,016
ACCOUNT C	DEMOLITION ACCOUNT C	135,460	(50,464)		4,820	415,803	500,798
	TOTAL DIRECT	641,680	(85,278)	2,259,174	26,103	1,988,339	4,803,915

#### **Estimate Totals**

Description	Amount	Totals	Hours
Direct Costs:			
Labor	1,988,339		26,103
Material	2,259,174		
Subcontract	641,680		
Scrap Value	(85,278)		
	4,803,915	4,803,915	
Other Direct & Construction			
Indirect Costs:			
91-1 Scaffolding			
91-2 Cost Due To OT 5-10's			
91-3 Cost Due To OT 6-10's			
91-4 Per Diem			
91-5 Consumables			
91-8 Freight on Material			
91-9 Freight on Process Equip			
91-10 Sales Tax			
91-11 Contractors G&A			
91-12 Contractors Profit			
		4,803,915	
Indirect Costs:			
93-1 Engineering Services			
93-2 CM Support			
93-3 Start-Up/Commissioning			
93-4 Start-Up/Spare Parts			
93-5 Excess Liability Insur.			
93-6 Sales Tax On Indirects	400.000		
93-7 Owners Cost 93-8 EPC Fee	489,000		
95-6 EFC Fee	489,000	5,292,915	
Contingency:			
94-1 Contingency on Material	452,000		
94-2 Contingency on Labor	398,000		
94-3 Contingency on Sub.	128,000		
94-6 Contingency on Scrap	13,000		
94-5 Contingency on Indirect	98,000		
	1,089,000	6,381,915	
Escalation: 96-1 Escalation on Material			
96-1 Escalation on Material 96-2 Escalation on Labor			
96-3 Escalation on Subcontract			
96-4 Escalation on Subcontract			
96-5 Escalation on Indirects			
SO-S LSCARTON ON MULLECTS		6,381,915	
		6,381,915	

Area	Group	Phase	Description	Notes	Quantity	Man Hours	Crew Rate	Labor Cost	Material Cost	Subcontract Cost	Scrap Value	Total Cost
ACCOUNT A			DEMOLITION ACCOUNT A									
	10.00.00		WHOLE PLANT DEMOLITION									
		10.31.00	MECHANICAL EQUIPMENT DEMO .4 MW GENERATOR	4 GENERATORS AT 7500# EA	15.00 TN	149	83.69 /MH	12,429				12,429
			DEMO TURBINE AND GEARS	4 TUBINES & GEARS AT 11000# EA	22.00 TN	218	83.69 /MH	18,230		-		18,230
			TURBINE ROOM 15 TON BRIDGE CRANE	15 TON BRIDGE CRANE	11.30 TN	112	122.82 /MH	13,741		-		13,741
				4 AT 5 TONS EACH	20.00 TN	45	122.82 /MH	5,472		-		5,472
			MECHANICAL EQUIPMENT WHOLE PLANT DEMOLITION			523 523		49,872 49,872				49,872 49,872
	18.00.00	18.10.00	SCRAP VALUE MIXED STEEL									
		10.10.00	MIXED STEEL	.4 MW GENERATOR, 4 @4,125# EA	-8.25 TN		77.78 /MH			-	(974)	(974)
			MIXED STEEL	4 TUBINES & GEARS AT 11000# EA	-22.00 TN		77.78 /MH		-	-	(2,598)	(2,598)
			MIXED STEEL	TURBINE ROOM 15 TON BRIDGE CRANE	-11.30 TN		77.78 /MH		-	-	(1,334)	(1,334)
			MIXED STEEL	BAR RACKS	-20.00 TN		77.78 /MH		-	-	(2,362)	(2,362)
			MIXED STEEL								(7,268)	(7,268)
		18.30.00	COPPER		0.75 TH						(04.405)	(24, 425)
			COPPER	4 GENERATORS AT 3375# EA	-6.75 TN		77.78 /MH		-	-	(21,465)	(21,465)
			COPPER SCRAP VALUE								(21,465) (28,733)	(21,465) (28,733)
											(20,700)	(20,700)
	22.00.00		CONCRETE									
		22.13.00	Concrete FLOWABLE FILL, 1500 PSI	FILL PENSTOCKS TO PREVENT BYPASS	116.00 CY	64	77.44 /MH	4,941	11,020			15,961
				FLOW								
			Concrete CONCRETE			<u>64</u>		4,941 4,941	<u>11,020</u> 11,020			<u>15,961</u> 15,961
			ACCOUNT A DEMOLITION ACCOUNT A			587		54,813	11,020		(28,733)	37,100
												·
ACCOUNT B			DEMOLITION ACCOUNT B									
	10.00.00		WHOLE PLANT DEMOLITION									
		10.22.00	CONCRETE EQUIPMENT/ BUILDING FOUNDATION	FISH LADDER	113.00 CY	140	85.21 /MH	11,917				11,917
			EQUIPMENT/ BUILDING FOUNDATION	TAINTER GATE - OGEE SECTION	245.00 CY	303	85.21 /MH	25,837		-	-	25,837
			EQUIPMENT/ BUILDING FOUNDATION	TAINTER GATE - BUTTRESSES	301.00 CY	373	85.21 /MH	31,743		-	-	31,743
			EQUIPMENT/ BUILDING FOUNDATION	TAINTER GATE - WEIR AND STILLING POND	255.00 CY	316	85.21 /MH	26,892		-	-	26,892
			CONCRETE			1,131		96,389				96,389
		10.23.00	STEEL									
			STRUCTURAL AND GIRT STEEL	TAINTER GATES STRUCTURE AND WALKWAY	50.00 TN	56	77.78 /MH	4,347		-	-	4,347
			STEEL			56		4,347				4,347
		10.31.00	MECHANICAL EQUIPMENT									
		10.01.00	60 KW PROPANE ELECTRIC GENERATOR	60 KW PROPANE ELECTRIC GENERATOR	1.50 TN	3	122.82 /MH	410		-		410
			MECHANICAL EQUIPMENT			3		410				410
			WHOLE PLANT DEMOLITION			1,190		101,146				101,146
	18.00.00		SCRAP VALUE									
		18.10.00	MIXED STEEL									
			MIXED STEEL MIXED STEEL	60 KW PROPANE ELECTRIC GENERATOR TAINTER GATES & WALKWAY	-1.50 TN -50.00 TN		77.78 /MH 77.78 /MH		-	-	(177)	(177)
			MIXED STEEL	TAINTER GATES & WALKWAT	-50.00 11		//./o //vin		-	-	(5,904) (6,081)	(5,904) (6,081)
			SCRAP VALUE								(6,081)	(6,081)
	21.00.00		CIVIL WORK									
	11.00.00	21.17.00	EXCAVATION									
			FOUNDATION EXCAVATION, CLAY USING 1 CY BACKHOE	RIVERBED EXCAVATION FOR RIPRAP	90.00 CY	17	84.18 /MH	1,417		-	-	1,417
			EXCAVATION			17		1,417				1,417
		21.41.00	Erosion and Sedimentation Control									
			RIPRAP, RANDOM BROKEN STONE, MACHINE PLACED	NEW STONE REQD IF CAUSEWAY STONE IS	43,444.00 CY	14,190	71.48 /MH	1,014,287	1,776,860	-	-	2,791,146
			RIPRAP, RANDOM BROKEN STONE, MACHINE PLACED	REUSED (46850-3408) FOR CAUSEWAYS	3,408.00 CY	1,113	71.48 /MH	79,567	139,387			218,954
			RIPRAP, RANDOM BROKEN STONE, MACHINE PLACED RIPRAP, RANDOM BROKEN STONE, MACHINE PLACED	RELOCATE CAUSE WAY STONE FOR RIVER	3,408.00 CY	1,113	71.46 /MH 71.48 /MH	79,567	135,307	-	-	79,567
					Page 4							

Area	Group	Phase	Description	Notes	Quantity	Man Hours	Crew Rate	Labor Cost	Material Cost	Subcontract	Scrap Value	Total Cost
7.000	Cicup				Luunity	maintiouro	eren nate			Cost	conup rando	· • • • • • • • • • • • • • • • • • • •
		21.41.00	Erosion and Sedimentation Control RIPRAP, RANDOM BROKEN STONE, MACHINE PLACED	BEND PROTECTION	3,408.00 CY	1,113	71.48 /MH	79,567		-		79,567
			RIPRAP, RANDOM BROKEN STONE, MACHINE PLACED	RIP RAP PROTECTION AT FLOOR SLABS TO	90.00 CY	29	71.48 /MH	2,101	3,681	-	-	5,782
			RIPRAP, RANDOM BROKEN STONE, MACHINE PLACED	REMAIN IN PLACE RIP RAP PROTECTION AT ABUTMENTS TO REMAIN IN PLACE (240-90)	150.00 CY	49	71.48 /MH	3,502	6,135	-	-	9,637
			Erosion and Sedimentation Control	REMAIN IN PLACE (240-90)		16,494		1,179,023	1,926,063			3,105,086
		21.47.00	LANDSCAPING									
			HYDRO OR AIR SEED & MULCH & FERTILIZER LANDSCAPING		211.00 AC	2,994 <b>2,994</b>	78.86 /MH	236,138 236,138	322,092 322,092	-	-	558,229 558,229
		21.65.00	Soil Remediation									
			REMOVAL OF LOCALIZED SILT AT DAM REMOVAL OF LOCALIZED SILT AT DAM	LIME ADDITIVE FOR DRYING LOAD, MIX AND HAUL LIME AND SEDIMENT	2,301.00 CY 6,903.00 CY		187.65 /MH 187.65 /MH			92,040 414,180	-	92,040 414,180
			Soil Remediation	MIX (4602+2301)						506,220		506,220
			CIVIL WORK			19,506		1,416,577	2,248,154	506,220		4,170,952
			ACCOUNT B DEMOLITION ACCOUNT B			20,696		1,517,723	2,248,154	506,220	(6,081)	4,266,016
ACCOUNT C	10.00.00	10.22.00	DEMOLITION ACCOUNT C WHOLE PLANT DEMOLITION CONCRETE									
		10122100	EQUIPMENT/ BUILDING FOUNDATION	DOWNSTREAM APRON	288.00 CY	356	85.21 /MH	30,372		-	-	30,372
			EQUIPMENT/ BUILDING FOUNDATION EQUIPMENT/ BUILDING FOUNDATION	GENERATOR HOUSE - GENERATOR HOUSE - TAILRACE APRON	1,800.00 CY 200.00 CY	2,228 248	85.21 /MH 85.21 /MH	189,824 21,092		-	-	189,824 21,092
			CONCRETE		200.00 01	2,832	00.21 ////1	241,288		-	-	241,288
		10.23.00	STEEL									
			STRUCTURAL AND GIRT STEEL STEEL	GENERATOR HOUSE	65.00 TN	73 <b>73</b>	77.78 /MH	<u>5,651</u> 5,651		-	-	5,651 5,651
		10.24.00	ARCHITECTURAL									
			GENERATOR HOUSE ARCHITECTURAL	132.5'x28'x70' TALL	259,700.00 CF	1,114 <b>1,114</b>	89.78 /MH	100,035 100,035		-	-	100,035 100,035
		10.31.00	MECHANICAL EQUIPMENT									
			DEMO PENSTOCKS	4 PENSTOCKS AT 9,300# EA	70.80 TN	701	83.69 /MH	58,666		-		58,666
			STOP LOGS MECHANICAL EQUIPMENT	4 AT 5 TONS EACH	20.00 TN	45 <b>746</b>	122.82 /MH	5,472 64,138		-		<u>5,472</u> 64,138
		10.41.00	ELECTRICAL EQUIPMENT									
			GENERATOR BUS TRANSFORMERS	2.4 to 34.5 KV, 2500 KVA (STEEL)	6.65 TN	20	82.70 /MH	1,617		-	-	1,617
			GENERATOR BUS TRANSFORMERS MISCELLANEOUS ELECTRICAL EQUIPMENT	2.4 to 34.5 KV, 2500 KVA (CU)	1.44 TN 5.00 TN	4	82.70 /MH 82.70 /MH	350 1,215		-	-	350 1,215
			ELECTRICAL EQUIPMENT			38		3,182				3,182
		10.86.00	WASTE				100.00 844				40.000	
			WASTE - USER DEFINED WASTE	MISC	1.00 LS	0	122.82 /MH	14		-	10,000 10,000	10,014 10,014
			WHOLE PLANT DEMOLITION			4,803		414,307			10,000	424,307
	18.00.00		SCRAP VALUE									
		18.10.00	MIXED STEEL MIXED STEEL	4 PENSTOCKS AT 9,300# EA	-4.60 TN		77.78 /MH				(543)	(543)
			MIXED STEEL	STOP LOGS	-20.00 TN		77.78 /MH		-	-	(2,362)	(2,362)
			MIXED STEEL	GENERATOR HOUSE	-65.00 TN		77.78 /MH		-	-	(7,675)	(7,675)
			MIXED STEEL MIXED STEEL	GENERATOR BUS TRANSFORMERS	-6.65 TN		77.78 /MH				(785) (11,365)	(785) (11,365)
		18.30.00	COPPER									
			COPPER	CABLE	-10.00 TN		77.78 /MH		-	-	(31,800)	(31,800)
			COPPER COPPER	MISC. TRANSFORMERS & MOTORS UNIT 1 GENERATOR BUS TRANSFORMERS	-4.00 TN -1.44 TN		77.78 /MH 77.78 /MH			-	(12,720)	(12,720)
			COPPER	GENERATOR DUS TRANSFURMERS	-1.44 IN		//./8 /MH		-	-	(4,579) (49,099)	(4,579) (49,099)
			SCRAP VALUE								(60,464)	(60,464)

Area	Group	Phase	Description	Notes	Quantity	Man Hours	Crew Rate	Labor Cost	Material Cost	Subcontract Cost	Scrap Value	Total Cost
	21.00.00		CIVIL WORK									
		21.17.00	EXCAVATION									
			FOUNDATION EXCAVATION, CLAY USING 1 CY BACKHOE	RIVERBED EXCAVATION FOR DAM ABUTMENTS	100.00 CY	19	84.18 /MH	1,574		-	-	1,574
			FOUNDATION EXCAVATION, CLAY USING 1 CY BACKHOE	RIVERBED EXCAVATION FOR RIPRAP CREDIT (85-90)	-5.00 CY	-1	84.18 /MH	(79)			-	(79)
			EXCAVATION			18		1,496				1,496
		21.65.00	Soil Remediation									
			REMOVAL OF LOCALIZED SILT AT DAM	LIME ADDITIVE FOR DRYING DELTA (2917-2301)	616.00 CY		187.65 /MH			24,640	-	24,640
			REMOVAL OF LOCALIZED SILT AT DAM	LOAD, MIX AND HAUL LIME AND SEDIMENT MIX DELTA (8750-6903)	1,847.00 CY		187.65 /MH			110,820	-	110,820
			Soil Remediation							135,460		135,460
			CIVIL WORK			18		1,496		135,460		136,956
			ACCOUNT C DEMOLITION ACCOUNT C			4,820		415,803		135,460	(50,464)	500,798



# EXHIBIT 3 Mottville Hydroelectric Plant Asbestos Removal Conceptual Cost Estimate No. 33741B

\\Snl6c\data6\AEPFossil\Rockport\_Tanners Creek CDCEU 2015\6.0 Evaluations-Reports\6.06 Studies\Mottville\Mottville\Mottville\Hydro\_Conceptual Demolition Cost Estimate\_No 33709\_Rev 0.doc

Sargent & Lundy

AEP MOTTVILLE HYDROELECTRIC PLANT DISMANTLEMENT STUDY - ASBESTOS REMOVAL CONCEPTUAL COST ESTIMATE

Indiana Michigan Power Company Attachment JAC-3 Witness; Cash Page 160 of 205

Client	AEP
Estimator	RCK
Labor rate table	15INSOU
Project No.	13465-000
Station Name	ELKHART
Unit	ALL
Estimate Date	02/12/2016
<b>Reviewed By</b>	ADC
Approved By	MNO
Estimate No.	33741B
Estimate Class	Conceptual
Cost index	INSOU

Estimate No.: 33741B Project No.: 13465-000 Estimate Date: 02/12/2016 Prep/Rev/App: RCK/ADC/MNO

#### AEP MOTTVILLE HYDROELECTRIC PLANT DISMANTLEMENT STUDY - ASBESTOS REMOVAL CONCEPTUAL COST ESTIMATE

Area	Description	Subcontract Cost	Scrap Value	Material Cost	Man Hours	Labor Cost	Total Cost
ASBESTOS	ASBESTOS REMOVAL TOTAL DIRECT	3,800 3,800					3,800 3,800

#### AEP MOTTVILLE HYDROELECTRIC PLANT DISMANTLEMENT STUDY - ASBESTOS REMOVAL CONCEPTUAL COST ESTIMATE

#### **Estimate Totals**

Descript	ion Amount	Totals	Hours
Direct Costs:			
Labor			
Material			
Subcontract	3,800		
Scrap Value			
	3,800	3,800	
Other Direct & Construction			
Indirect Costs:			
91-1 Scaffolding			
91-2 Cost Due To OT 5-10's 91-3 Cost Due To OT 6-10's			
91-3 Cost Due 10 OT 6-10 s 91-4 Per Diem			
91-5 Consumables			
91-8 Freight on Material			
91-9 Freight on Process Equip			
91-10 Sales Tax			
91-11 Contractors G&A			
91-12 Contractors Profit			
		3,800	
Indirect Costs:			
93-1 Engineering Services			
93-2 CM Support			
93-3 Start-Up/Commissioning			
93-4 Start-Up/Spare Parts 93-5 Excess Liability Insur.			
93-6 Sales Tax On Indirects			
93-7 Owners Cost	400		
93-8 EPC Fee			
	400	4,200	
Contingency:			
94-1 Contingency on Material			
94-2 Contingency on Labor			
94-3 Contingency on Sub.	800		
94-6 Contingency on Scrap	400		
94-5 Contingency on Indirect	100	5 400	
	900	5,100	
Escalation:			
96-1 Escalation on Material			
96-2 Escalation on Labor			
96-3 Escalation on Subcontract			
96-4 Escalation on Scrap 96-5 Escalation on Indirects			
50-5 ESCARLION ON INDIFECTS		5,100	
		5,100	
Total		E 400	
IOIAI		5,100	

#### AEP MOTTVILLE HYDROELECTRIC PLANT DISMANTLEMENT STUDY - ASBESTOS REMOVAL CONCEPTUAL COST ESTIMATE


Area	Group	Phase	Description	Notes	Quantity	Man Hours	Crew Rate	Labor Cost	Material Cost	Subcontract Cost	Scrap Value	Total Cost
ASBESTOS			ASBESTOS REMOVAL									
	10.00.00		WHOLE PLANT DEMOLITION									
		10.37.00	ASBESTOS REMOVAL									
			ASBESTOS REMOVAL - MISC MATERIALS	WINDOW CAULKING MISC MATERIALS	2.00 CY		121.33 /MH			3,800	-	3,800
			ASBESTOS REMOVAL							3,800		3,800
			WHOLE PLANT DEMOLITION							3,800		3,800
			ASBESTOS ASBESTOS REMOVAL							3,800		3,800





# EXHIBIT 4 Mottville Hydroelectric Plant Retirement Option 1-3 Demolition Scope and Sequence

\\Snl6c\data6\AEPFossil\Rockport\_Tanners Creek CDCEU 2015\6.0 Evaluations-Reports\6.06 Studies\Mottville\Mottville\Mottville\Hydro\_Conceptual Demolition Cost Estimate\_No 33709\_Rev 0.doc









# MOTTVILLE HYDRO RETIREMENT DEMO SEQUENCE SKETCHES & CIVIL QUANTITIES BY: S&L


M	MOTTVILLE										
OPTION 2											
ITEM	QUANTITY	UNIT	REMARKS								
GRASS SEEDING	211	ACRE									
RIPRAP PROTECTION	46,850	CY	2 ft riprap protection @ D(50)=12"								
RIPRAP PROTECTION AT FLOOR SLAB TO REMAIN IN PLACE	90	CY									
RIVERBED EXCAVATION FOR RIPRAP	90	CY	TO BE REPLACED BY RIPRAP								

OPTION 3				
ITEM	QUANTITY	UNIT	REMARKS	
GRASS SEEDING	211	ACRE		
RIPRAP PROTECTION AT RIVER BENDS	46,850	CY	2 ft riprap protection @ D(50)=12"	
RIPRAP PROTECTION AT DAM ABUTMENTS	100	CY	2 ft riprap protection @ D(50)=12"	
RIVERBED EXCAVATION FOR RIPRAP	85	СҮ	TO BE REPLACED BY RIPRAP	


Note:


Localized miscellaneous silt removal and earthwork as part of dam demolition by Brandenburg

# JANUARY 25, 2016 PAGE 4 OF 7











# Twin Branch Hydroelectric Plant CONCEPTUAL DEMOLITION COST ESTIMATE

Prepared for: Indiana Michigan Power Company (Owner) and American Electric Power Service Corporation

> Project No. 13465-000 February 12, 2016 Revision 0



55 East Monroe Street Chicago, IL 60603-5780 USA





February 12, 2016

Conceptual Demolition Cost Estimate

# **Issue Summary Page**

Revision Number	Date	Purpose	Prepared By	Reviewed By	Approved By	Pages Affected
A	02/02/16	Comments	R. C. Kinsinger	A.D. Chapin D. F. Franczak	M. N. Ozan	All
0	02/12/16	Use	R. C. Kinsinger Rkinsinger	A.D. Chapin AChapin D. F. Franczak D. T. Trayod	T. J. Meehan	All

Page IS-1

\\Snl6e\data6\AEPFossil\Rockport\_Tanners Creek CDCEU 2015\6.0 Evaluations-Reports\6.06 Studies\Twin Branch\Twin Branch\Yudo\_Conceptual Demolition Cost Estimate\_No 33710\_Rev 0.doc



**Section** 

Indiana Michigan Power Company Attachment JAC-3 Witness; Cash Twin Branch Hydroelectric Plane Indiana Michigan Power Company American Electric Power Service Corporation

Conceptual Demolition Cost Estimate February 12, 2016

## TABLE OF CONTENTS

_	
Do	an
1 a	26

Sargent & Lundy

1	INTRODUCTION	1
2	COST ESTIMATE SUMMARY	1
3	TECHNICAL BASIS	4
4	COMMERICAL BASIS	6
4.1	General Information	6
4.2	Quantities/Material Cost	6
4.3	Construction Labor Wages	6
4.4	Scrap Value	7
4.5	Indirect Costs	8
4.6	Escalation	8
4.7	Contingency	8
4.8	Assumptions	8
5	REFERENCES	9

<u>EXHIBIT</u>	DESCRIPTION
1	Conceptual Cost Estimate Summary
2	Conceptual Demolition Cost Estimate No. 33710B
3	Asbestos Removal Conceptual Cost Estimate No. 33742B
4	Retirement Option 1-3 Demolition Scope and Sequence

TOC-1



Indiana Michigan Power Company Attachment JAC-3 Witness; Cash Twin Branch Hydroelectric Plant<sup>175 of 205</sup> Indiana Michigan Power Company American Electric Power Service Corporation Conceptual Demolition Cost Estimate February 12, 2016

#### **1.0 INTRODUCTION**

The Twin Branch Hydroelectric Plant located near the City of South Bend, Indiana is owned and operated by Indiana Michigan Power Company (I&M), a subsidiary of American Electric Power (AEP). The plant consists of (from right to left referenced facing downstream) an embankment section referred to as the "saddle dike", the old steam plant intake structure, the right abutment embankment, the spillway, the powerhouse and the left abutment embankment. The spillway is a concrete-capped timber crib structure and consists of two flashboard rollway sections (on either end of the spillway) and a central tainter gate section consisting of seven (7) gates. The powerhouse is located to the left of the south rollway section. The powerhouse contains eight (8) operating vertical shaft Flygt Kaplan turbines equipped with Siemens generators rated at 0.6 MW each. Four (4) of the units were installed in 1989 and four (4) in 1992. There are two (2) in place, non-operating generators inside the powerhouse which have been abandoned.

AEP recently contracted S&L to prepare conceptual demolition cost estimates considering three (3) retirement options defined as follows: (1) Option 1, Non-Power Operation, (2) Option 2, Partial Removal of the Dam Structures, and (3) Option 3, Complete Removal of the Dam and Powerhouse. Also, in addition S&L was requested to prepare a separate Asbestos Removal Conceptual Cost Estimate.

The objective of the conceptual demolition cost estimates is to determine the gross demolition costs for Twin Branch Hydroelectric Plant (including gross salvage credits and any other benefits), in support of documenting a component of future AEP book depreciation rates to be approved by the I&M's state commissions and potential future inclusion in submittal of a rate case to the state commissions, and other potential uses. The cost estimate considers the demolition/dismantlement methodology which complies with current OSHA rules and regulations.

### 2.0 COST ESTIMATE SUMMARY

Conceptual Demolition Cost Estimate No. 33710B, dated February 12, 2016, was prepared and is included as Exhibit 2. This cost estimate was prepared for retirement option 3, but includes accounts allowing the determination of cost estimates for retirement options 1 and 2 as well. A summary of the conceptual demolition cost estimates for all three (3) retirement options is provided in Exhibit 1 and detailed in the following tables.

Page 1 of 9

#### \\Snl6c\data6\AEPFossil\Rockport\_Tanners Creek CDCEU 2015\6.0 Evaluations-Reports\6.06 Studies\Twin Branch\Twin Branch Hydro\_Conceptual Demolition Cost Estimate\_No 33710\_Rev 0.doc



The cost estimate is structured into a code of accounts as identified in Table 2-1.

Account Number	Description
10, 21, 22	Demolition Costs (including steel, equipment & piping scrap value)
18	Scrap Value Costs
91	Other Direct & Construction Indirect Costs
93	Indirect Costs
94	Contingency Costs
96	Escalation Costs

 Table 2-1

 Cost Estimate Code of Accounts

The results of the cost estimate for retirement option 3 are provided in Table 2-2 below.

# Table 2-2Cost Estimate Results SummaryRetirement Option 3

Description	Total Cost
Demolition Cost	\$10,506,420
Scrap Value	(\$166,151)
Direct Cost Subtotal	\$10,340,269
Indirect Cost	\$1,051,000
Contingency Cost	\$2,337,000
Escalation Cost	\$0
Total Project Cost	\$13,728,269



The results of the cost estimate for retirement option 1 are provided in Table 2-3 below.

Description	Total Cost	
Demolition Cost	\$127,208	
Scrap Value	(\$86,961)	
Direct Cost Subtotal	\$40,247	
Indirect Cost	\$5,000	
Contingency Cost	\$40,000	
Escalation Cost	\$0	
Total Project Cost	\$85,247	

# Table 2-3Cost Estimate Results SummaryRetirement Option 1

The results of the cost estimate for retirement option 2 are provided in Table 2-4 below.

# Table 2-4Cost Estimate Results SummaryRetirement Option 2

Description	Total Cost
Demolition Cost	\$8,260,082
Scrap Value	(\$157,447)
Direct Cost Subtotal	\$8,102,635
Indirect Cost	\$824,000
Contingency Cost	\$1,842,000
Escalation Cost	\$0
Total Project Cost	\$10,768,635



Twin Branch Hydroelectric Plant<sup>178 of 205</sup> Indiana Michigan Power Company American Electric Power Service Corporation Conceptual Demolition Cost Estimate February 12, 2016

Asbestos Removal Conceptual Cost Estimate No. 33742B, dated February 12, 2016, was prepared and is included as Exhibit 3. The total estimated cost for asbestos removal prior to plant dismantlement is \$49,330. Quantities were derived from drawings and past experience. Asbestos removal applies to the powerhouse, thus the removal cost applies to all three (3) retirement options. The cost of asbestos removal is excluded from the total conceptual demolition cost estimates for each retirement option detailed in the tables above.

### 3.0 TECHNICAL BASIS

The scope of dismantlement is based on three (3) retirement options, as requested by AEP, as follows:

<u>Retirement Option 1, Non-Power Operation:</u> This scenario would consider leaving intact all of the existing water-impounding structures and the powerhouse. Only the electric generating units and their auxiliary equipment would be removed so as to preclude the generation of electricity by the former hydroelectric plant. In addition, the spillway would be modified as required in order to pass river flows and maintain the impoundment's water surface elevation at the current conditions.

<u>Retirement Option 2, Partial Removal of the Dam Structures:</u> This scenario would consider demolition and removal of certain elements of the hydroelectric site in order to drain the existing impoundment and create a natural river channel through the dam site. This would generally include removal of the generating units and powerhouse and possibly but not inclusively demolition and removal of substantial portions of concrete spillway structures. This option would address the removal and stabilization of any sediments that have accumulated at the upstream end of the dam and the stabilization of the newly exposed reservoir/riverbanks.

<u>Retirement Option 3, Complete Removal of the Dam and Powerhouse:</u> This scenario would consider complete removal of the electric generating components and powerhouse and complete removal of the dam. Similar to option 2, this option would address the removal and stabilization of any sediments that have accumulated at the upstream end of the dam and the stabilization of the newly exposed reservoir/riverbanks.

The scope of dismantlement for each retirement option, as interpreted from the definitions above, are identified on marked plant drawings included as Exhibit 4. The scope of dismantlement and the sequence of demolition for each retirement option are defined on these sketches.

Page 4 of 9



Twin Branch Hydroelectric Plant<sup>179</sup> of <sup>205</sup> Indiana Michigan Power Company American Electric Power Service Corporation Conceptual Demolition Cost Estimate February 12, 2016

Retirement options 2 and 3 include the same demolition work as retirement option 1, removal of the generating unit components from the powerhouse. The powerhouse is not removed in retirement option 1, but is removed in retirement option 3. For retirement option 2 the powerhouse may or may not be removed, depending on if removal of portions of the dam can restore river flow to natural flow without removing the powerhouse (refer to Exhibit 4).

For each of the retirement options the scope of sediment removal is based on the quantity that would be disturbed from the demolition work itself and not complete removal of all sediment potentially disturbed by the partial or complete removal of the dam. The subcontractor costs included in retirement options 2 and 3 are for lime stabilization of the sediment and removal of the sediment and other wastes (such as timber) to the waste disposal site. These costs do not apply to retirement option 1 since only generating unit components in the powerhouse are removed and this material has scrap value.

Retirement options 2 and 3 include the stabilization of newly exposed riverbanks, which include the dam area and areas upstream of the dam. The extent of stabilization for retirement option 3 may be slightly more than retirement option 2, since the entire dam is being removed in retirement option 3.

The following are excluded from the scope of the conceptual demolition cost estimates:

- Asbestos removal (separate cost estimate prepared).
- The conceptual demolition cost estimate includes the cost to remove the one (1) main power transformer located in the switchyard, but not the cost to remove the switchyard itself (and remaining components in the switchyard).
- The old steam plan intake structure serves as a screen house/intake for a nearby industrial building and will remain in place.
- > Evaluation of the effect of the complete removal of the series of dams on the river watershed.
- Evaluation of the effect of the removal of any one dam, on either the upstream or downstream side dam and reservoir, after removal of the dam.
- Potential social or environmental impact of the draining of the reservoirs and the impact on property values or other community impact.
- The conceptual demolition cost estimate excludes any costs related to performing surveys to quantify the amount of sediment and chemical testing of the sediment. The quantity of sediment to be removed was estimated for retirement options 2 and 3 and the cost to remove the sediment is included in the conceptual demolition cost estimate. As stated above, the scope of sediment removal is based on the quantity that would be disturbed from the demolition work itself and not



Twin Branch Hydroelectric Plant Indiana Michigan Power Company American Electric Power Service Corporation Conceptual Demolition Cost Estimate February 12, 2016

complete removal of the sediment potentially disturbed by the partial or complete removal of the dam.

The scope of the demolition cost estimate was reaffirmed during a review of the facility by two S&L employees in conjunction with a representative from Bradenburg Industrial Service Co. and AEP corporate and plant personnel. The facility review was held on Wednesday December 16, 2015.

### 4.0 COMMERCIAL BASIS

#### 4.1 General Information

The Conceptual Demolition Cost Estimates prepared for the Twin Branch Hydroelectric Plant is a conceptual estimate of the cost to dismantle the powerhouse and dam in accordance with the scope defined for each of the three (3) retirement options. Costs were calculated for (1) demolition of existing plant structures and equipment and associated site restoration costs, (2) scrap value of steel, copper and stainless steel, as applicable, (3) associated indirect costs, and (4) contingency.

All units used in the cost estimate are U.S. Standard and all costs are in US Dollars (4<sup>th</sup> Quarter 2015 levels). A three (3) year demolition schedule is anticipated for retirement option 3 including asbestos removal (to be performed prior to start of demolition work). The schedule takes into consideration environmental permitting, asbestos removal which includes mapping out all asbestos contamination throughout the powerhouse and associated abatement, followed by total plant demolition and site restoration. The schedule for the other two (2) retirement options would be correspondingly less.

#### 4.2 Quantities/Material Cost

Quantities of pieces of equipment and/or bulk material commodities used in the cost estimates were intended to be reasonable and representative of projects of this type. Material quantities were estimated from the hydroelectric plant drawings and data provided by AEP, and the information obtained from Plant personnel during the facility review.

#### 4.3 Construction Labor Wages

Craft labor rates (Craft Hourly Rate) for the cost estimate were calculated as Union Labor rates for South Bend, Indiana, based on 2015, R. S. Means "Labor Rates for the Construction Industry". The craft rates were incorporated into work crews appropriate for the activities by adding allowances for small tools, construction equipment, insurance, and site overheads to arrive at crew hourly rates detailed in the cost

Page 6 of 9



Twin Branch Hydroelectric Plant<sup>181 of 205</sup> Indiana Michigan Power Company American Electric Power Service Corporation Conceptual Demolition Cost Estimate February 12, 2016

estimate. A 1.10 regional labor productivity multiplier was included based on Compass International Global Construction Yearbook, 2015 Edition, for union work in Indiana. National Maintenance Agreement Rates (typically negotiated by AEP) do not apply as this work is assumed to be performed as a lump sum contract.

## 4.3.1 Labor Work Schedule and Incentives

The estimate assumed a 5x8 work week. No per diem or other labor incentives are included.

## 4.3.2 Construction Indirects

Allowances were included in the cost estimate as direct costs as noted for the following:

- Freight: Material and scrap freight included in the material and scrap costs.
- Additional Crane Allowance: None included. Cost of cranes and construction machinery are included in the labor wage rates.
- Mobilization and Demobilization: Included in labor wage rates.
- Scaffolding: Included in labor wage rates.
- Consumables: Included in material and labor costs.
- > Per Diem Costs: Excluded from the estimate.
- > Contractor's General and Administrative Costs and Profit: Included in the labor wage rates.

## 4.4 Scrap Value

The value of scrap was determined by a 3 month average (November and December 2015 and January 2016) using Zone 4 (USA Midwest) of the "Scrap Metals Market Watch" (<u>www.americanrecycler.com</u>).

Since the values obtained are delivered pieces, 25% of the values obtained were deducted to pay for separation, preparation and shipping to the mills. This resulted in realized prices of:

- ➢ Mixed Steel Value @ \$118/Ton
- Copper Value @ \$3,180/Ton
- ➢ Stainless Steel @ \$675/Ton

<u>Note:</u> 1 Ton = 2,000 Lbs



All steel is considered to be mixed steel unless otherwise noted.

#### 4.5 Indirect Costs

Allowances were included in the cost estimate as indirect costs as noted for the following:

- Engineering, Procurement and Project Services: None included.
- Construction Management Support: None included.
- Owners Cost: Included as 10.0% of the total direct cost. Owners Costs include owner project engineering, administration and construction management, permits and fees, legal expenses, taxes, removal of chemicals, etc.

#### 4.6 Escalation

No allowance for escalation was included in the cost estimate. All costs are determined in 4<sup>th</sup> Quarter 2015 levels.

#### 4.7 Contingency

Allowances were included in the cost estimate as contingency as noted for the following:

- Scrap Value: Included as 15.0% reduction in the salvage value resulting in a total net reduction in the salvage value. The contingency assumes a potential drop in salvage value thus increasing the project cost. Scrap costs are very volatile but by taking a 3-month average some of the effect of volatility is reduced. However there are other variables that affect scrap pricing such as the quantity and processing fees. The contingency applied is based on the estimators confidence in scrap pricing used in the demolition cost estimate.
- Material: Included as 20.0% of the total material cost.
- Labor: Included as 20.0% of the total labor cost.
- ▶ Indirect: Included as 20.0% of the total indirect cost.
- Subcontractor: Included as 20.0% of the total subcontractor cost.

#### 4.8 Assumptions

The following assumptions apply to the cost estimates.

- The cost estimate for each retirement option is based on the scope and the demolition sequences defined on the sketches provided in Exhibit 4.
- All chemicals will be removed by the Owner prior to demolition, from the facilities to be demolished.



Twin Branch Hydroelectric Plant<sup>183 of 205</sup> Indiana Michigan Power Company American Electric Power Service Corporation Conceptual Demolition Cost Estimate February 12, 2016

- All electrical equipment and wiring is de-energized prior to start of dismantlement, except for that required for remote operation of two (2) of the tainter gates after demolition is completed for retirement option 1.
- > No extraordinary environmental costs for demolition have been included.
- Handling, on-site and off-site disposal of hazardous materials would be performed in compliance with methods approved by Owner.
- The window glazing in the powerhouse may be asbestos contaminated and an allowance for removal and disposal is included in the asbestos removal cost estimate. There are a number of devices in the powerhouse mounted on transite (asbestos) panels and an allowance for removal and disposal is included in the asbestos removal cost estimate. There is no building or pipe insulation in the facility and consequently no insulation related asbestos contamination.
- Switchyards within the plant boundaries are not part of the scope, neither are access roads to these facilities. Fences and gates needed to protect the switchyard will be left in place.
- All demolished materials are considered debris, except for organic combustibles and nonembedded metals which have scrap value.
- The basis for salvage estimating is for scrap value only. No resale of equipment or material is included.
- Sediment removed due to demolition work is treated with lime and hauled offsite to an approved waste disposal facility.

## 5.0 REFERENCES

- **5.1** Twin Branch Plant Drawings: One-Line Diagrams, No. E-1000, Revision 16 and No. 16-12001-2, 2/7/91.
- **5.2** Findlay Engineering, Inc., Supporting Technical Information Document, Twin Branch Hydroelectric Project, August, 2005.



Indiana Michigan Power Company Attachment JAC-3 Witness; Cash Twin Branch Hydroelectric Plant<sup>184 of 205</sup> Indiana Michigan Power Company American Electric Power Service Corporation Conceptual Demolition Cost Estimate February 12, 2016

# EXHIBIT 1 Twin Branch Hydroelectric Plant Conceptual Demolition Cost Estimate Summary

\\Snl6c\data6\AEPFossil\Rockport\_Tanners Creek CDCEU 2015\6.0 Evaluations-Reports\6.06 Studies\Twin Branch\Twin Branch\Twin Branch Hydro\_Conceptual Demolition Cost Estimate\_No 33710\_Rev 0.doc

	Retir	rement Option 1	Retirement Option 2	Retirement Option 3		
Demolition Cost	\$	127,208	\$ 8,260,082	\$	10,506,420	
Scrap Value	\$	(86,961)	\$ (157,447)	\$	(166,151)	
Direct Cost Subtotal	\$	40,247	\$ 8,102,635	\$	10,340,269	
Indirect Cost	\$	5,000	\$ 824,000	\$	1,051,000	
Contingency Cost	\$	40,000	\$ 1,842,000	\$	2,337,000	
Escalation Cost	\$	-	\$ -	\$	-	
Total Demolition Cost	\$	85,247	\$ 10,768,635	\$	13,728,269	



February 12, 2016

# EXHIBIT 2 Twin Branch Hydroelectric Plant Conceptual Demolition Cost Estimate No. 33710B

\\Snl6c\data6\AEPFossil\Rockport\_Tanners Creek CDCEU 2015\6.0 Evaluations-Reports\6.06 Studies\Twin Branch\Twin Branch\Twin Branch Hydro\_Conceptual Demolition Cost Estimate\_No 33710\_Rev 0.doc

Indiana Michigan Power Company Attachment JAC-3 Witness; Cash Page 187 of 205

Client	AEP
Estimator	RCK
Labor rate table	15INSOU
Project No.	13465-000
Station Name	TWIN BRANCH
Unit	ALL
Estimate Date	02/12/2016
<b>Reviewed By</b>	ADC
Approved By	MNO
Estimate No.	33710B
Estimate Class	Conceptual
Cost index	INSOU

Estimate No.: 33710B Project No.: 13465-000 Estimate Date: 02/12/2016 Prep/Rev/App: RCK/ADC/MNO

Area	Description	Subcontract Cost	Scrap Value	Material Cost	Man Hours	Labor Cost	Total Cost
ACCOUNT A	DEMOLITION ACCOUNT A		(86,961)		1,464	127,208	40,247
ACCOUNT B	DEMOLITION ACCOUNT B	1,419,180	(70,486)	3,177,934	45,622	3,535,760	8,062,388
ACCOUNT C	DEMOLITION ACCOUNT C	874,760	(8,704)		15,233	1,371,578	2,237,634
	TOTAL DIRECT	2,293,940	(166,151)	3,177,934	62,319	5,034,546	10,340,269

### AEP TWIN BRANCH HYDROELECTRIC PLANT DISMANTLEMENT STUDY CONCEPTUAL COST ESTIMATE

### **Estimate Totals**

Description	Amount	Totals	Hours
Direct Costs:			
Labor	5,034,546		62,319
Material	3,177,934		
Subcontract	2,293,940		
Scrap Value	(166,151)		
	10,340,269	10,340,269	
Other Direct & Construction			
Indirect Costs:			
91-1 Scaffolding			
91-2 Cost Due To OT 5-10's			
91-3 Cost Due To OT 6-10's			
91-4 Per Diem			
91-5 Consumables			
91-8 Freight on Material			
91-9 Freight on Process Equip			
91-10 Sales Tax			
91-11 Contractors G&A			
91-12 Contractors Profit			
		10,340,269	
Indirect Costs:			
93-1 Engineering Services			
93-2 CM Support			
93-3 Start-Up/Commissioning			
93-4 Start-Up/Spare Parts			
93-5 Excess Liability Insur.			
93-6 Sales Tax On Indirects	4.054.000		
93-7 Owners Cost	1,051,000		
93-8 EPC Fee	1,051,000	11,391,269	
Contingency:			
94-1 Contingency on Material	636,000		
94-2 Contingency on Labor	1,007,000		
94-3 Contingency on Sub.	459,000		
94-6 Contingency on Scrap	25,000		
94-5 Contingency on Indirect	210,000		
	2,337,000	13,728,269	
Escalation:			
96-1 Escalation on Material			
96-2 Escalation on Labor			
96-3 Escalation on Subcontract			
96-4 Escalation on Scrap			
96-5 Escalation on Indirects		42 720 000	
		13,728,269	
Total		13,728,269	

Area	Group	Phase	Description	Notes	Quantity	Man Hours	Crew Rate	Labor Cost	Material Cost	Subcontract Cost	Scrap Value	Total Cost
ACCOUNT A			DEMOLITION ACCOUNT A									
	10.00.00		WHOLE PLANT DEMOLITION									
		10.31.00	MECHANICAL EQUIPMENT DEMO .6 MW FLYGT GENERATOR		38.00 TN	418	85.53 /MH	35.755				35.755
			DEMO 18 MW FLYGT GENERATOR DEMO FLYGT TURBINE AND GEARS	8 GENERATORS AT 9500# EA 8 GENERATORS AT 14000# EA	56.00 TN	418 616	85.53 /MH 85.53 /MH	35,755 52,692		-		35,755 52,692
			DEMO HOIZONTAL CAMELBACK GENERATOR	2 GENERATORS AT 14000# EA	14.00 TN	154	85.53 /MH	13,173		-		13,173
			GENERATOR ROOM 20 TON TRAVELING CRANE	CRANE IS NOT MOTORIZED	15.00 TN	33	121.33 /MH	4,054		-		4,054
			BAR RACKS MECHANICAL EQUIPMENT	6 AT 5 TONS EACH	30.00 TN	67 1,288	121.33 /MH	8,109 113,783		-		8,109 113,783
			WHOLE PLANT DEMOLITION			1,288		113,783				113,783
	18.00.00		SCRAP VALUE									
	18.00.00	18.10.00	MIXED STEEL									
		10.10.00	MIXED STEEL	.6 MW FLYGT GENERATOR, 8 @5,225# EA	-20.90 TN		79.62 /MH				(2,468)	(2,468)
			MIXED STEEL	DEMO FLYGT TURBINE AND GEARS	-56.00 TN		79.62 /MH		-	-	(6,612)	(6,612)
			MIXED STEEL	DEMO HOIZONTAL CAMELBACK	-14.00 TN		79.62 /MH		-	-	(1,653)	(1,653)
			MIXED STEEL	GENERATOR, 2 @ 4.2 TN EA GENERATOR ROOM 20 TON TRAVELING	-15.00 TN		79.62 /MH				(1,771)	(1,771)
			MIXED STEEL	CRANE	-15.00 11		/9.02 /WH		-	-	(1,771)	(1,771)
			MIXED STEEL	BAR RACKS	-30.00 TN		79.62 /MH		-	-	(3,542)	(3,542)
			MIXED STEEL								(16,047)	(16,047)
		18.30.00	COPPER									
			COPPER	126 MW FLYGT GENERATOR 8@ 4,275 LB	-17.10 TN		79.62 /MH		-	-	(54,378)	(54,378)
			COPPER	EA DEMO HOIZONTAL CAMELBACK GENERATOR, 2 @ 2.6 TN EA	-5.20 TN		79.62 /MH		-	-	(16,536)	(16,536)
			COPPER	SENERATOR, 2 @ 2.0 IN EX							(70,914)	(70,914)
			SCRAP VALUE								(86,961)	(86,961)
	22.00.00		CONCRETE									
	22.00.00	22.13.00	Concrete									
			FLOWABLE FILL, 1500 PSI	INSTALL COVER PLATES IN TURBINE BAY	1.00 LT	176	76.27 /MH	13,425		-	-	13,425
				TO PREVENT BYPASS FLOW								
			Concrete			176		13,425				13,425
			CONCRETE ACCOUNT A DEMOLITION ACCOUNT A			<u>176</u> 1,464		13,425			(86,961)	<u>13,425</u> 40,247
						.,		,			(00,001)	,
ACCOUNT B			DEMOLITION ACCOUNT B									
	10.00.00		WHOLE PLANT DEMOLITION									
		10.22.00	CONCRETE									
			EQUIPMENT/ BUILDING FOUNDATION	TAINTER GATE SECTION: WEIR, , GATE WALLS & OGEE	1,522.00 CY	1,884	89.94 /MH	169,417		-	-	169,417
			EQUIPMENT/ BUILDING FOUNDATION	NORTH ROLLWAY SECTION - TIMBER	3,428.00 CY	3,394	89.94 /MH	305,262		68,560	-	373,822
			EQUIPMENT/ BUILDING FOUNDATION	CRIBING, INCL DISPOSAL NORTH ROLLWAY SECTION - CONCRETE	457.00 CY	566	89.94 /MH	50,870			-	50,870
			EQUIPMENT/ BUILDING FOUNDATION	OGIVE SOUTH ROLLWAY SECTION - TIMBER	3,360.00 CY	3,327	89.94 /MH	299,206		67,200	-	366,406
			CONCRETE	CRIBBING INCLUDES DISPOSAL;		0.470		004 754		425 700		000 544
			CONCRETE			9,170		824,754		135,760		960,514
		10.23.00	STEEL									
			STRUCTURAL AND GIRT STEEL	NORTH ROLLWAY WALKWAY	10.00 TN	11	79.62 /MH	890		-	-	890
			STRUCTURAL AND GIRT STEEL	SOUTH ROLLWAY WALKWAY	10.00 TN	11	79.62 /MH	890		-	-	890
			STRUCTURAL AND GIRT STEEL STEEL	GENERATOR HOUSE	89.00 TN	99 122	79.62 /MH	7,920		-		7,920 9,700
			STEEL			122		9,700				9,700
		10.31.00	MECHANICAL EQUIPMENT									
			60 KW PROPANE ELECTRIC GENERATOR		1.50 TN	3	121.33 /MH	405		-		405
			TAINTER GATES	7 AT 5 TONS EACH	35.00 TN	78	121.33 /MH	9,460		-		9,460
			MECHANICAL EQUIPMENT			81		9,866				9,866
		10.41.00	ELECTRICAL EQUIPMENT									
			GENERATOR BUS TRANSFORMERS	4.16 to 34.5 KV, 7500/9375 KVA (STEEL)	5.12 TN	15	80.14 /MH	1,206		-	-	1,206
			GENERATOR BUS TRANSFORMERS	4.16 to 34.5 KV, 6800/9068 KVA (CU)	4.62 TN	14	80.14 /MH	1,088		-	-	1,088
			MISCELLANEOUS ELECTRICAL EQUIPMENT ELECTRICAL EQUIPMENT		5.00 TN	15 43	80.14 /MH	1,178 3,472		-	-	1,178 3,472
			LEED INIGAE EQUILIMENT			43		3,472				3,472

#### AEP TWIN BRANCH HYDROELECTRIC PLANT DISMANTLEMENT STUDY CONCEPTUAL COST ESTIMATE

	_											
Area	Group	Phase	Description	Notes	Quantity	Man Hours	Crew Rate	Labor Cost	Material Cost	Subcontract Cost	Scrap Value	Total Cost
			WHOLE PLANT DEMOLITION			9,417		847,792		135,760		983,552
	18.00.00		SCRAP VALUE									
		18.10.00	MIXED STEEL									
			MIXED STEEL	60 KW PROPANE ELECTRIC GENERATOR	-1.50 TN		79.62 /MH		-	-	(177)	(177)
			MIXED STEEL MIXED STEEL	TAINTER GATES AND WALKWAY GENERATOR BUS TRANSFORMERS	-35.00 TN -5.12 TN		79.62 /MH 79.62 /MH		-	-	(4,133) (605)	(4,133) (605)
			MIXED STEEL								(4,914)	(4,914)
		18.30.00	COPPER COPPER	CABLE	-10.00 TN		79.62 /MH		-	-	(31,800)	(31,800)
			COPPER	MISC. TRANSFORMERS & MOTORS UNIT 1	-6.00 TN		79.62 /MH		-	-	(19,080)	(19,080)
			COPPER	GENERATOR BUS TRANSFORMERS	-4.62 TN		79.62 /MH		-	-	(14,692)	(14,692)
			COPPER								(65,572)	(65,572)
			SCRAP VALUE								(70,486)	(70,486)
	21.00.00		CIVIL WORK									
		21.17.00	Earthwork, Excavation									
			FOUNDATION EXCAVATION, COMMON EARTH USING 1 CY	RIVERBED EXCAVATION FOR RIPRAP	170.00 CY	28	88.08 /MH	2,471		-	-	2,471
			BACKHOE Earthwork, Excavation			28		2,471				2,471
								_,				_,
		21.41.00	Erosion and Sedimentation Control		47.007.00	00.004	74.40 0.00	4 540 700	1 004 504			0.475.077
			RIPRAP, RANDOM BROKEN STONE, MACHINE PLACED	54560CY - 7333CY ASSUMING REUSE OF CAUSEWAY STONE	47,227.00 CY	20,834	74.10 /MH	1,543,793	1,931,584	-	-	3,475,377
			RIPRAP, RANDOM BROKEN STONE, MACHINE PLACED	FOR CAUSEWAYS INSTALLATION	7,333.00 CY	3,235	74.10 /MH	239,707	299,920	-	-	539,627
			RIPRAP, RANDOM BROKEN STONE, MACHINE PLACED	REUSE CAUSEWAY RIP RAP FOR BANK PROTECTION	7,333.00 CY	3,235	74.10 /MH	239,707		-	-	239,707
			RIPRAP, RANDOM BROKEN STONE, MACHINE PLACED	RIP RAP PROTECTION AT SPILLWAY FLOOR	170.00 CY	75	74.10 /MH	5,557		-	-	5,557
			Erosion and Sedimentation Control	SLAB		27,379		2,028,764	2,231,504			4,260,268
			Erosion and ocumentation control			21,010		2,020,704	2,201,004			4,200,200
		21.47.00				0.700		050 700				
			HYDRO OR AIR SEED & MULCH & FERTILIZER LANDSCAPING		620.00 AC	8,799 <b>8,799</b>	74.64 /MH	656,733 656,733	946,430 946,430	-		1,603,163 1,603,163
			LANDGOAFING			0,735		000,700	340,430			1,003,103
		21.65.00	Soil Remediation									
			REMOVAL OF SOIL - LOCALIZED REMOVAL OF SOIL - LOCALIZED	LIME ADDITIVE FOR DRYING LOAD, MIX AND HAUL LIME AND SEDIMENT	5,834.00 CY 17,501.00 CY		196.64 /MH 196.64 /MH			233,360 1,050,060	-	233,360 1,050,060
			REMOVAL OF SOIL - LOCALIZED	MIX 7111+3556	17,301.00 C1		190.04 ////11			1,030,000	-	1,050,000
			Soil Remediation							1,283,420		1,283,420
			CIVIL WORK			36,205		2,687,968	3,177,934	1,283,420	(70.100)	7,149,322
			ACCOUNT B DEMOLITION ACCOUNT B			45,622		3,535,760	3,177,934	1,419,180	(70,486)	8,062,388
ACCOUNT C			DEMOLITION ACCOUNT C									
	10.00.00		WHOLE PLANT DEMOLITION									
		10.22.00	CONCRETE									
			EQUIPMENT/ BUILDING FOUNDATION EQUIPMENT/ BUILDING FOUNDATION	TAINTER GATE: APRON NORTH ROLLWAY SECTION - CONCRETE	838.00 CY 488.00 CY	1,037 604	89.94 /MH 89.94 /MH	93,279 54,320		-	-	93,279 54,320
			EQUIPMENT/ BUILDING FOUNDATION	BASE	400.00 01	004	05.54 ////1	34,320			-	54,520
			EQUIPMENT/ BUILDING FOUNDATION	NORTH ROLLWAY SECTION - PLANK	480.00 CY	475	89.94 /MH	42,744		9,600	-	52,344
			EQUIPMENT/ BUILDING FOUNDATION	APRON, INCL DISPOSAL SOUTH ROLLWAY SECTION - CONCRETE	471.00 CY	583	89.94 /MH	52,428		-	-	52,428
			EQUIPMENT/ BUILDING FOUNDATION	BASE SOUTH ROLLWAY SECTION - PLANK	3,360.00 CY	3,327	89.94 /MH	299,206		67,200		366,406
			EQUIPMENT/ BUILDING FOUNDATION	APRON, INCL DISPOSAL	3,300.00 C1	3,327	05.54 /1011	299,200		07,200	-	300,400
			EQUIPMENT/ BUILDING FOUNDATION	GENERATOR ROOM	1,723.00 CY	2,132	89.94 /MH	191,790		-	-	191,790
			EQUIPMENT/ BUILDING FOUNDATION EQUIPMENT/ BUILDING FOUNDATION	TURBINE BAY DRAFT TUBE TUNNEL	1,913.00 CY 2,266.00 CY	2,368 2,804	89.94 /MH 89.94 /MH	212,940 252,233		-	-	212,940 252,233
			CONCRETE	S	2,200.00 01	13,330	00.94 /IVIN	1,198,940		76,800		1,275,740
		10.24.00	ARCHITECTURAL GENERATOR HOUSE	40'X181'	353,600.00 CF	1,517	89.81 /MH	136,250				136,250
			ARCHITECTURAL	-07.01	333,000.00 CF	1,517	05.01 /WH	136,250		-		136,250
						-,		,				,
		10.31.00	MECHANICAL EQUIPMENT		ar	-						
			DEMO CAMELBACK PENSTOCKS STOP LOGS	2 GENERATORS AT 15 TN EA 6 AT 5 TONS EACH	30.00 TN 30.00 TN	330 67	85.53 /MH 121.33 /MH	28,228 8,109				28,228 8,109
					Page 5	01		0,100		-		5,105

Page 5

Area	Group	Phase	Description	Notes	Quantity	Man Hours	Crew Rate	Labor Cost	Material Cost	Subcontract Cost	Scrap Value	Total Cost
		10.31.00	MECHANICAL EQUIPMENT									
			TURBINE ROOM 15 TON GANTRY CRANE MECHANICAL EQUIPMENT	INTAKE DECK	10.00 TN	22 <b>419</b>		2,703 39,039		-	-	2,703 39,039
		10.86.00	WASTE									
			WASTE	MISC	1.00 LS		121.33 /MH			-	10,000	10,000
			WASTE WHOLE PLANT DEMOLITION			15,267		1,374,230		76,800	<u>10,000</u> 10,000	<u>10,000</u> 1,461,030
	18.00.00		SCRAP VALUE									
		18.10.00	MIXED STEEL MIXED STEEL	DEMO CAMELBACK PENSTOCKS	-30.00 TN		79.62 /MH				(3,542)	(3,542)
			MIXED STEEL	STOP LOGS	-30.00 TN		79.62 /MH		-	-	(3,542)	(3,542)
			MIXED STEEL	TURBINE ROOM 15 TON GANTRY CRANE	-10.00 TN		79.62 /MH		-	-	(1,181)	(1,181)
			MIXED STEEL	GENERATOR HOUSE	-88.40 TN		79.62 /MH		-	-	(10,438)	(10,438)
			MIXED STEEL								(18,704)	(18,704)
			SCRAP VALUE								(18,704)	(18,704)
	21.00.00	24 47 00	CIVIL WORK									
		21.17.00	Earthwork, Excavation FOUNDATION EXCAVATION, COMMON EARTH USING 1 CY	RIVERBED EXCAVATION FOR RIPRAP	-70.00 CY	-12	88.08 /MH	(1,017)				(1,017)
			BACKHOE	CREDIT (170-100	-70.00 01	=12	00.00 /////1	(1,017)			-	(1,017)
			Earthwork, Excavation			-12		(1,017)			-	(1,017)
		21.41.00	Erosion and Sedimentation Control									
			RIPRAP, RANDOM BROKEN STONE, MACHINE PLACED	RIP RAP PROTECTION AT RETAINING WALLS CEDIT(170-120)	-50.00 CY	-22		(1,634)		-	-	(1,634)
			Erosion and Sedimentation Control			-22		(1,634)				(1,634)
		21.65.00	Soil Remediation									
			REMOVAL OF SOIL - LOCALIZED	ADDITIONAL LIME ADDITIVE FOR DRYING ACCOUNT (9463-5834)	3,629.00 CY		196.64 /MH			145,160	-	145,160
			REMOVAL OF SOIL - LOCALIZED	ADDITIONAL LOAD, MIX AND HAUL LIME AND SEDIMENT MIX (28389-17501))	10,880.00 CY		196.64 /MH		_	652,800		652,800
			Soil Remediation							797,960		797,960
			CIVIL WORK			-34		(2,652)		797,960		795,308
			ACCOUNT C DEMOLITION ACCOUNT C			15,233		1,371,578		874,760	(8,704)	2,237,634



# EXHIBIT 3 Twin Branch Hydroelectric Plant Asbestos Removal Conceptual Cost Estimate No. 33742B

\\Snl6c\data6\AEPFossil\Rockport\_Tanners Creek CDCEU 2015\6.0 Evaluations-Reports\6.06 Studies\Twin Branch\Twin Branch\Twin Branch Hydro\_Conceptual Demolition Cost Estimate\_No 33710\_Rev 0.doc

Indiana Michigan Power Company Attachment JAC-3 Witness; Cash Page 194 of 205

## AEP TWIN BRANCH HYDROELECTRIC PLANT DISMANTLEMENT STUDY - ASBESTOS REMOVAL CONCEPTUAL COST ESTIMATE

Client	AEP
Estimator	RCK
Labor rate table	15INSOU
Project No.	13465-000
Station Name	TWIN BRANCH
Unit	ALL
Estimate Date	02/12/2016
<b>Reviewed By</b>	ADC
Approved By	MNO
Estimate No.	33742B
Estimate Class	Conceptual
Cost index	INSOU

Estimate No.: 33742B Project No.: 13465-000 Estimate Date: 02/12/2016 Prep/Rev/App: RCK/ADC/MNO

### AEP TWIN BRANCH HYDROELECTRIC PLANT DISMANTLEMENT STUDY - ASBESTOS REMOVAL CONCEPTUAL COST ESTIMATE

Area	Description	Subcontract Cost	Scrap Value	Material Cost	Man Hours	Labor Cost	Total Cost
ASBESTOS	ASBESTOS REMOVAL TOTAL DIRECT	37,430 37,430					37,430 37,430

### AEP TWIN BRANCH HYDROELECTRIC PLANT DISMANTLEMENT STUDY - ASBESTOS REMOVAL CONCEPTUAL COST ESTIMATE

### **Estimate Totals**

De	escription	Amount	Totals	Hours
Direct Costs:				
Labor				
Material				
Subcontract		37,430		
Scrap Value				
		37,430	37,430	
Other Direct & Construction	n			
Indirect Costs:				
91-1 Scaffolding				
91-2 Cost Due To OT 5-10's				
91-3 Cost Due To OT 6-10's	6			
91-4 Per Diem				
91-5 Consumables				
91-8 Freight on Material				
91-9 Freight on Process Equ	ıip			
91-10 Sales Tax				
91-11 Contractors G&A				
91-12 Contractors Profit				
			37,430	
Indirect Costs:				
93-1 Engineering Services				
93-2 CM Support				
93-3 Start-Up/Commissionin	g			
93-4 Start-Up/Spare Parts				
93-5 Excess Liability Insur.				
93-6 Sales Tax On Indirects				
93-7 Owners Cost		3,700		
93-8 EPC Fee	_	3,700	41,130	
Contingency:	-1			
94-1 Contingency on Materia	al			
94-2 Contingency on Labor		7 500		
94-3 Contingency on Sub.		7,500		
94-6 Contingency on Scrap	+	700		
94-5 Contingency on Indirec	·	8,200	49,330	
		0,200	49,550	
Escalation:				
96-1 Escalation on Material				
96-2 Escalation on Labor				
96-3 Escalation on Subcontr	act			
96-4 Escalation on Scrap				
96-5 Escalation on Indirects				
			49,330	
Total			49,330	
i otar			45,330	

#### AEP TWIN BRANCH HYDROELECTRIC PLANT DISMANTLEMENT STUDY - ASBESTOS REMOVAL CONCEPTUAL COST ESTIMATE

Area	Group	Phase	Description	Notes	Quantity	Man Hours	Crew Rate	Labor Cost	Material Cost	Subcontract Cost	Scrap Value	Total Cost
ASBESTOS			ASBESTOS REMOVAL/DISPOSAL									
	10.00.00		WHOLE PLANT DEMOLITION									
		10.37.00	ASBESTOS REMOVAL									
			ASBESTOS REMOVAL - MISC MATERIALS	WINDOW CAULKING MISC MATERIALS	2.00 CY		121.33 /MH			3,800	-	3,800
			ASBESTOS REMOVAL - MISC MATERIALS	CONTROL PANEL APPROX 20' X 9' TALL	6.70 CY		121.33 /MH			12,730	-	12,730
			ASBESTOS REMOVAL - MISC MATERIALS	SWITCHBOARDS	2.00 CY		121.33 /MH			3,800	-	3,800
			ASBESTOS REMOVAL - MISC MATERIALS	UNIDENTIFIED ABANDONED EQUIPMENT	9.00 CY		121.33 /MH			17,100	-	17,100
			ASBESTOS REMOVAL							37,430		37,430
			WHOLE PLANT DEMOLITION							37,430		37,430
			ASBESTOS ASBESTOS REMOVAL/DISPOSAL							37,430		37,430




February 12, 2016


EXHIBIT 4 Twin Branch Hydroelectric Plant Retirement Option 1-3 Demolition Scope and Sequence


\\Snl6c\data6\AEPFossil\Rockport\_Tanners Creek CDCEU 2015\6.0 Evaluations-Reports\6.06 Studies\Twin Branch\Twin Branch Hydro\_Conceptual Demolition Cost Estimate\_No 33710\_Rev 0.doc

Sargent & Lundy



		Indiana Mich	nigan Power Comp Attachment JA
ALYY	NUAR	Y 25	Attachment JA Witness; C 2 Page 199 of 2
IAN			0F 7
//			Y 1
	$\langle \rangle \rangle \rangle \rangle$	/ /	
	/ Y /	//	/ '
6///	YAN	/ /	
POWER DRIVE	1 X V	//	/ ,
		11	A
	(		r-7
	l		
R			
	)		
	(		
	$\checkmark$		
57	)		
X	/		
TRANSMIS	SION TOWERS		
	/		÷
N N		7	1
1 C Ba			
	-		
		Ŧ	
		1	1
			SHEET 1 OF 3
	EXHIBIT F	CHIGAN POWEI	R COMPANY
		VIN BRANCH	
F, IS A PART OF THE	INDIANA MI TV HYDROELEC GENERA	VIN BRANCH	ECT NO.2579 WINGS
NSE MADE BY	INDIANA MI TV HYDROELEC GENERA	TRIC PROJ	ECT NO.2579 WINGS
NSE MADE BY	INDIANA MI TV HYDROELEC GENERA	TRIC PROJ	ECT NO.2579 WINGS
F, IS A PART OF THE NSE MADE BY YER COMPANY SO MUD 1/91	INDIANA MI TV HYDROELEC GENERA	TRIC PROJ	ECT NO.2579 WINGS






# TWIN BRANCH HYDRO RETIREMENT DEMO SEQUENCE SKETCHES & CIVIL QUANTITIES BY: S&L

	TWIN BRANCH	1	
	OPTION 2		
ITEM	QUANTITY	UNIT	REMARKS
GRASS SEEDING	620	ACRE	
RIPRAP PROTECTION	54,560	CY	2 ft riprap protection @ D(50)=12"
RIVERBED EXCAVATION FOR RIPRAP	170	CY	TO BE REPLACED BY RIPRAP
RIPRAP PROTECTION AT SPILLWAY FLOOR SLAB	170	CY	2 ft riprap protection @ D(50)=12"


OPTION 3						
ITEM	QUANTITY	UNIT	REMARKS			
GRASS SEEDING	620	ACRE				
RIPRAP PROTECTION AT RIVER BENDS	54,560	CY	2 ft riprap protection @ D(50)=12"			
RIPRAP PROTECTION AT DAM ABUTMENTS	<del>2,120</del>	<del>CY</del>	2 ft riprap protection @ D(50)=12"			
EARTHWORK FILL AT DAM ABUTMENTS-	<del>15,305</del>	<del>CY</del>				
RIVERBED EXCAVATION FOR RIPRAP	100	СҮ	TO BE REPLACED BY RIPRAP			
RIPRAP PROTECTION AT RETAINING WALLS	120	СҮ	2 ft riprap protection @ D(50)=12"			


# JANUARY 25, 2016 PAGE 4 OF 7


Indiana Michigan Power Company Attachment JAC-3 Witness; Cash Page 202 of 205




TWIN BRANCH HYDRO RETIREMENT DEMO SEQUENCE SKETCHES & CIVIL QUANTITIES BY: S&L







Indiana Michigan Power Company ANUAR Attachment JAC-3 P GEWniness; Cash Page 204 of 205 0. A . 4. SPILLWAY FLOOR SLAB TO REMAIN IN PLACE RIPRAP ROTECTION PAD AT RIVER BUTTOM ADUNCENT TO SPILLWAY RANSMISSION TOWERS FLOOR SLAB TO REMAIN SELTIONA N.T. 5 VRIPRAP= (2×5) (450) (=)=170 CY VOUT=VRIPRAP= 170 CY EXHIBIT F SHEET 1 OF 3 INDIANA MICHIGAN POWER COMPANY **TWIN BRANCH** HYDROELECTRIC PROJECT NO.2579 GENERAL DESIGN DRAWINGS PLAN AND ELEVATION FERC NO. 2579 - 010 - 1



		Indiana Michig	an Power Company
1		-	Attachment DAC-3 GE Wings; Cash Page 205 of 205
//			Page 205 of 205
/ /			
	$\langle \gamma \rangle \langle \gamma \rangle$		
/ /	$\vee$ $\vee$ $\wedge$ $\vee$ $\vee$	1	
	$\bigvee$ $\land$ $\land$ $\land$ $\land$		
//	// / / /	/	
R DRIVE	$\gamma$ ( / $/$ / /		
	-1-1-	f	
	(	_7	
÷.			
	. )		
		5	
Dee	and to )		
WAL		+	4
TRANSMISSI	DN TOWERS 21	3'	~
1:	1 1		
1	- 47 P	· ] .	4
X	141 10	AP	5×vn
~		L.	RIVER
1.	N T		BED RIPRAP PROTECTION
(150.	+110 (=) =170 CY		ROTECTION
Cath	+110) (==)=170 cy		
50140	127)~1000/		
ļ	EXHIBIT F	SHEET .1 OF 3	1
	INDIANA MICHIGAN POWER COM TWIN BRANCH	MPANY	
	HYDROELECTRIC PROJECT		
THE	GENERAL DESIGN DRAWING PLAN AND ELEVATION	S	
			1
_			
			1
	FERC NO. 2579 -	010 - 1	