

**FILED**  
June 1, 2021  
**INDIANA UTILITY**  
**REGULATORY COMMISSION**

**Table of Contents**

Introduction ..... 2

Summary of NIPSCO’s 2021-2026 Electric Plan ..... 12

Development of the 2021-2026 Electric Plan ..... 19

Risk Reduction..... 23

Flexible Investment Plan..... 28

Plan Update Process ..... 36

Cost Estimates and Estimate Development ..... 38

Contingency As a Component of Estimation ..... 49

Aging Infrastructure Investments ..... 53

Aging Infrastructure Projects ..... 60

System Deliverability Projects..... 78

Grid Modernization Projects ..... 84

Economic Development Projects ..... 92

Execution of the 2021-2026 Electric Plan ..... 93

Eligible Improvements ..... 95

Conclusion ..... 96

---

---

**VERIFIED DIRECT TESTIMONY OF CHARLES A. VAMOS**

---

---

1 **INTRODUCTION**

2 **Q1. Please state your name, business address, and job title.**

3 A1. My name is Charles A. Vamos. My business address is 801 E. 86<sup>th</sup> Avenue,  
4 Merrillville, Indiana 46410. I am Director, Electric T&D (Transmission and  
5 Distribution) Engineering for Northern Indiana Public Service Company  
6 LLC ("NIPSCO" or "Company").

7 **Q2. Please briefly describe your educational and business experience.**

8 A2. I received a Bachelor of Science degree in Electric Engineering Technology  
9 from Purdue University in Hammond, Indiana in 1992. I received an  
10 M.B.A. from Indiana University in Gary, Indiana in 1996 and an M.S. in  
11 Electricity Markets from the Illinois Institute of Technology in Chicago,  
12 Illinois in 2010. I am a Registered Professional Engineer in the State of  
13 Indiana (2000) and a certified Project Management Professional (2012). I  
14 began my employment with NIPSCO in 1993 and have more than 25 years'  
15 experience in electric generation, transmission, and distribution as follows:  
16 Electrical Engineer (1993-2000), Asset Manager (2000-2003), Manager  
17 Electric Substations (2003-2011), Manager Electric Engineering (2011-2014),

1           Manager Electric Asset Management (2014-2018) and Director, Electric  
2           T&D Engineering (2018 to present).

3   **Q3. What are your responsibilities as Director of Electric T&D Engineering?**

4   A3. As Director of Electric T&D Engineering, I am responsible for directing the  
5           Transmission and Distribution Engineering functions for NIPSCO's line,  
6           substation, and protective relaying groups. I currently oversee NIPSCO  
7           engineering departments to ensure the safe, reliable, and constructible  
8           designs for over \$200 million in transmission and distribution projects  
9           yearly.

10   **Q4. What are your responsibilities with respect to NIPSCO's electric TDSIC**  
11       **projects?**

12   A4. I was responsible for development of NIPSCO's Electric TDSIC Plan for the  
13           period January 2016 through December 2022 ("Electric Plan 1")<sup>1</sup> including  
14           the development of detailed asset registers defining the projects included  
15           in Electric Plan 1. This responsibility also includes maintaining the risk  
16           model and updates to the condition-based assessment of assets in the

---

<sup>1</sup> NIPSCO's Electric Plan 1 is set to expire December 31, 2022. In accordance with Ind. Code § 8-1-39-10(d), NIPSCO provided the Commission with a notice on April 1, 2021 that Electric Plan 1 will terminate on May 31, 2021.

1 Electric Plan 1 and making future updates as appropriate. I was also  
2 responsible for developing the project cost estimates and supporting the  
3 financial performance of the projects included in Electric Plan 1. I have been  
4 responsible for coordinating the preparation of NIPSCO's Electric TDSIC  
5 Plan for the period June 1, 2021 through December 31, 2026 (the "2021-2026  
6 Electric Plan" or "Plan"), attached hereto as Confidential Attachment 2-A.  
7 In that role, I have worked with engineers under my supervision, including  
8 those in a consulting role, as well as with others within the Company to  
9 compile, review, prioritize and analyze projects for incorporation into the  
10 Plan.

11 **Q5. Have you previously testified before this or any other regulatory**  
12 **commission?**

13 A5. Yes. I previously submitted testimony before the Indiana Utility  
14 Regulatory Commission ("Commission") in NIPSCO's electric TDSIC  
15 tracker filings in Cause Nos. 44733-TDSIC-X (beginning in TDSIC-4).

16 **Q6. What is the purpose of your direct testimony in this proceeding?**

17 A6. The purpose of my direct testimony is to (1) provide a summary of the 2021-  
18 2026 Electric Plan, (2) explain how NIPSCO developed its 2021-2026 Electric  
19 Plan, (3) explain the reduction of risks after executing Electric Plan 1, (4)

1 explain the proposed plan update process; (5) explain the cost estimates  
2 associated with the 2021-2026 Electric Plan, (6) discuss contingency as a  
3 component of estimating, (7) explain the various components of projects  
4 included in the 2021-2026 Electric Plan, (8) discuss NIPSCO's proposed  
5 execution of the 2021-2026 Electric Plan, (9) explain why the 2021-2026  
6 Electric Plan constitutes eligible transmission, distribution, and storage  
7 system improvements ("eligible improvements"),<sup>2</sup> including the expected  
8 benefits from certain projects.

9 **Q7. Are you sponsoring any attachments to your direct testimony?**

10 A7. Yes. I am sponsoring the following documents, all of which were prepared  
11 by me or under my direction and supervision.

12

---

<sup>2</sup> "Eligible transmission, distribution, and storage system improvements' means new or replacement electric or gas transmission, distribution, or storage utility projects that: (1) a public utility undertakes for purposes of safety, reliability, grid modernization, or economic development, including the extension of gas service to rural areas; (2) were not included in the public utility's rate base in its most recent general rate case; and (3) either were (A) described in the public utility's TDSIC plan and approved by the commission under section 10 of this chapter and authorized for TDSIC treatment; (B) described in the public utility's update to the public utility's TDSIC plan under section 9 of this chapter and authorized for TDSIC treatment by the commission; or (C) approved as a targeted economic development project under section 11 of this chapter. The term includes (1) projects that do not include specific locations or an exact number of inspections, repairs, or replacements, including inspection based projects such as pole or pipe inspection projects, and pipe or pipe replacement projects; and (2) projects involving advanced technology investments to support the modernization of a transmission, distribution, or storage system, such as advanced metering infrastructure, information technology systems, or distributed energy resource management systems." Ind. Code § 8-1-39-2.

Attachment No.	Description
Confidential Attachment 2-A	NIPSCO’s 2021-2026 Electric Plan
Confidential Attachment 2-B	2021–2026 TDSIC Investment Plan Business Case dated May 2021 prepared by Sargent & Lundy
Confidential Attachment 2-C	2021-2026 TDSIC Investment Plan Cost Analysis dated May 2021 prepared by Sargent & Lundy
Attachment 2-D	NIPSCO’s Transmission Planning System Assessment Methodology and Planning Criteria dated January 14, 2021
Confidential Attachment 2-E	Distribution Automation Program Business Case dated April 2020 prepared by Leidos Engineering, LLC
Confidential Attachment 2-F	Long-Term Communications Plan dated May 2021 prepared by Sargent & Lundy
Attachment 2-G	Execution and Management of the Plan

1  
2  
3  
4  
5  
6  
7  
8  
9

**Q8. Please describe the reports prepared by Sargent & Lundy.**

A8. Sargent & Lundy, L.L.C. (“S&L”) prepared four reports: (1) 2021–2026 TDSIC Investment Plan Business Case (“Long-Term Investment Plan”), which is attached hereto as Confidential Attachment 2-B; (2) 2021–2026 TDSIC Investment Plan Cost Analysis, which is attached hereto as Confidential Attachment 2-C; (3) Long-Term Communications Plan, which is attached hereto as Confidential Attachment 2-E; and (4) Economic Impacts of Projected NIPSCO T&D Expenditures, 2021–2026 (“Economic

1 Impact Report"), which is sponsored by Witness Becker as Confidential  
2 Attachment 1-D.

3 **Q9. Please explain the Long-Term Investment Plan (Confidential Attachment**  
4 **2-B)**.

5 A9. The Long-Term Investment Plan explains the three main objectives of  
6 NIPSCO's 2021-2026 Electric Plan: (1) maintaining safe and reliable  
7 performance while proactively replacing aging, high risk equipment across  
8 the system; (2) maintaining adequate system capacity to reliably serve  
9 customer loads; and (3) modernizing NIPSCO's electric grid with  
10 technologies that support improved reliability, asset health and condition,  
11 and preparing for future customer expectations.

12 To develop this document, NIPSCO (with support from S&L) outlined the  
13 long term plan to address aging assets and documented NIPSCO's risk-  
14 based approach to evaluating its transmission and distribution system.

15 That approach is used to focus long term capital investment (and, by  
16 extension, TDSIC funds) towards the highest-risk assets on the system.

17 These capital investments also include a one-time recouping of the  
18 operation and maintenance ("O&M") expenses associated with the  
19 installation of advanced metering infrastructure ("AMI").

1       The Long-Term Investment Plan includes three appendices: (1)  
2       Confidential Appendix A, which provides the NIPSCO T&D Risk Model  
3       Results ("TDSIC Risk Model"), (2) Confidential Appendix B, which  
4       provides the NIPSCO Effective Age Methodology; and (3) Confidential  
5       Appendix C, which provides the 2021-2026 NIPSCO Electric AMI Business  
6       Case developed by West Monroe Partners.

7       The Long-Term Investment Plan was developed through the process of  
8       evaluating risk-based projects, programmatic minor asset projects,  
9       deliverability-based projects, and strategic grid modernization initiatives to  
10      support customer experience and system reliability.

11      The first process is evaluating risk-based projects in the Long-Term  
12      Investment Plan. This approach prioritizes the major assets that should be  
13      included in the 2021-2026 project portfolio based on the consequence of an  
14      asset failing and likelihood of an asset failing. Through the proactive  
15      replacing of the highest risk assets, the overall risk of failure is reduced, as  
16      compared to simply replacing assets as they deteriorate and fail.<sup>3</sup> This

---

<sup>3</sup> Replacing assets as they fail is sometimes referred to as a "break/fix" approach to asset replacement.



1 dynamic risk assessment considers age, condition, and prioritization of  
2 assets that are approaching or have met end of life. Additionally,  
3 programmatic minor asset projects<sup>4</sup> are included in the category of Aging  
4 Infrastructure. Like major equipment, minor assets are vital to the safe and  
5 reliable operation of the electric system. These assets include annunciators,  
6 arresters, protective relays, insulators, line and substation switches,  
7 potential transformers, steel structures, substation batteries and chargers,  
8 substation capacitors, and wood poles. While these minor assets are critical,  
9 they are not assigned a risk score within the Long-Term Investment Plan.  
10 The increased quantity included through the electrical system would make  
11 assigning these individual assets a risk score overly burdensome. Instead,  
12 the aged and/or damaged minor assets go through inspection and analysis  
13 processes that result in either mitigation or replacement. These investments  
14 make up approximately 54% of the capital expenditures included in the  
15 2021-2026 Electric Plan.

16 The second process is focused on increasing the deliverability of power to  
17 meet customer load, which in turn maintains and improves reliability for

---

<sup>4</sup> "Major equipment" and "minor asset" are accounting terms. Reference to an asset or asset category as minor or major does not imply it is more or less important to NIPSCO's system.

1 customers, especially when load grows. These projects increase the  
2 system's ability to provide power to increasing customer demand, as well  
3 as providing versatility as load demands become more diverse. These  
4 investments make up approximately 20% of the capital expenditures  
5 included in the 2021-2026 Electric Plan.

6 The third process is deploying strategic grid modernization initiatives to  
7 enhance customer service, improve reliability, and enable new technologies  
8 to improve NIPSCO's ability to meet customers' evolving operability  
9 expectations. The technologies proposed are AMI, intelligent sensing  
10 equipment (i.e., substation automation ("SA") and distribution automation  
11 ("DA") technologies), a distribution supervisory control and data  
12 acquisition ("DSCADA") system, as well as the inclusion of communication  
13 and telecommunication infrastructure. The implementation of AMI, DA,  
14 SA, DSCADA, and communication and telecommunication infrastructure  
15 systems will together increase reliability and functionality, both of which  
16 are directly realized by NIPSCO's customers. These investments make up  
17 approximately 26% of the expenditures included in the 2021-2026 Electric  
18 Plan.

1 The process of evaluating and prioritizing the implementation of DA  
2 investments is detailed in the Distribution Automation Program Business  
3 Case (Confidential Attachment 2-E). The report details the methodology in  
4 developing an economical implementation plan that maximizes benefits to  
5 NIPSCO's customers.

6 Communications is the backbone of grid modernization functions, as it  
7 provides a network for grid modernization technologies to increase system  
8 visibility. NIPSCO (with the assistance of S&L) developed the Long-Term  
9 Communications Plan (Confidential Attachment 2-F), which details the  
10 methodology to migrate NIPSCO's antiquated system to a new, more  
11 robust, and modern network.

12 **Q10. Please explain how the 2021-2026 Electric Plan is presented and**  
13 **organized.**

14 A10. The 2021-2026 Electric Plan is presented and organized as follows:

Plan by Project Category	Provides a high level summary showing the breakout of investment by year for both transmission and distribution.
Plan by FERC Account	Provides a high level summary showing the breakout of investment by year for both transmission and distribution by Federal Energy Regulatory Commission

	(“FERC”) Uniform System of Account account number.
Project Detail by Year	Provides project detail separately for each year of the Plan (2021-2026). Each line item shows the Project ID, the project category, the driver associated with the project, the project title, and the anticipated investment for each project (in direct dollars). Detailed scopes and estimate summaries (project estimates) are provided for Year 1 (2021) and Year 2 (2022).
Project Detail Summary by Year	Matrix showing all of the projects included in the Plan by project category by year showing the total investment for each project (in direct dollars).
Confidential Appendix A	Asset Register for Risk Based Projects
Confidential Appendix B	Asset Register for Non Risk Based Projects
Confidential Appendix C	Year 1 (2021) Project Estimates
Confidential Appendix D	Year 2 (2022) Project Estimates

1  
2  
3  
4  
5  
6  
7  
8

**SUMMARY OF NIPSCO’S 2021-2026 ELECTRIC PLAN**

**Q11. Please explain how NIPSCO’s 2021-2026 Electric Plan fits into its overall strategy to invest in its system.**

A11. The capital investment in NIPSCO’s 2021-2026 Electric Plan is one of many components within its overall investment strategy. Other components include annual capital maintenance work, generation investments and transition, public improvement projects, as well as investments related to

1 new business. As further explained below, the investments included in the  
2 2021-2026 Electric Plan focus primarily on making necessary investments  
3 to enable NIPSCO to continue to provide safe, reliable electric service to its  
4 customers, as well as driving necessary grid modernization and  
5 deliverability advancements to meet evolving customer expectations and  
6 load.

7 **Q12. Is the 2021-2026 Electric Plan NIPSCO's first TDSIC plan?**

8 A12. No. Following passage of the TDSIC Statute by the Indiana General  
9 Assembly,<sup>5</sup> NIPSCO implemented Electric Plan 1 (for the period January 1,  
10 2016 through December 31, 2022), which was approved by the Commission  
11 on July 12, 2016 in Cause No. 44733. The approved total capital  
12 expenditures under the Electric Plan 1 was approximately \$1.25 billion. On  
13 April 1, 2021, NIPSCO filed a notice to terminate the Electric Plan 1 effective  
14 May 31, 2021.

15 **Q13. What has NIPSCO accomplished through its investments under Electric**  
16 **Plan 1?**

---

<sup>5</sup> Ind. Code Ch. 8-1-39 (Transmission, Distribution, and Storage System Improvement Charges and Deferrals) was enacted as part of Senate Enrolled Act 560 and became effective on April 30, 2013, which was amended in House Enrolled Act No. 1470 and became effective on April 24, 2019 (the "TDSIC Statute").

1 A13. Through January 31, 2021, NIPSCO had invested approximately \$781  
2 million. NIPSCO focused its investment on proactively replacing aging,  
3 high risk equipment across its electric system. Some of the highlights  
4 include:<sup>6</sup>

- 5 • Power Transformers Replaced - 33
- 6 • Breakers Replaced - 319
- 7 • Protective Relays Upgrade Projects - 47
- 8 • Miles of Circuit Rebuilt – 564
- 9 • Miles of Underground Cable Replaced – 190 Miles
- 10 • Number of Line Transformers Replaced – 2,029
- 11 • Number of Switches Replaced – 389
- 12 • Complete update of all 4 kV distribution circuits to 12 kV

13  
14 Initial projections estimated a 30% risk reduction if all projects under  
15 Electric Plan 1 were executed through 2022. In actuality, through five-and-  
16 a-half years of work, NIPSCO has realized a 21% risk reduction when  
17 compared to a “break/fix” replacement strategy. This is a significant  
18 accomplishment, which demonstrates the efficacy of NIPSCO's proactive  
19 replacement and capital investment strategy.

---

<sup>6</sup> These are estimated statistics as of February, 2021.

1 **Q14. Please explain why NIPSCO decided to terminate Electric Plan 1 and file**  
2 **the 2021-2026 Electric Plan.**

3 A14. After careful consideration, NIPSCO decided to file a new TDSIC plan for  
4 several reasons. Electric Plan 1 was successful in reducing system risk by  
5 replacing aged assets and addressing changing system demands.  
6 However, the projects originally identified in 2016 for potential execution  
7 in 2021 and 2022 required reprioritizing to NIPSCO's most recent system  
8 loading and condition information. The asset registers developed for  
9 Electric Plan 1 were developed as a snapshot in time prior to the filing and  
10 do not account for changing asset health or changes in electric demand. For  
11 example, a transformer may have been in perfect health when the plan was  
12 created, but a car hitting a nearby pole after the plan was filed could subject  
13 the same transformer to detrimental fault currents and damage it to the  
14 point where it needs replacement. Similarly, NIPSCO has realized an  
15 unexpected, sudden increase in electric demand in the eastern part of its  
16 service territory caused by the recent increase in new manufacturing  
17 facilities. While local manufacturing expansion and load growth are  
18 positive developments for NIPSCO and the State of Indiana, this presents  
19 challenges for NIPSCO as it plans to address current and future load

1 growth. NIPSCO will also be pursuing grid modernization efforts that  
2 were not previously included in Electric Plan 1.

3 Additionally, the TDSIC Statute as it existed in 2016 (as interpreted by the  
4 Commission and courts) and the settlement agreement NIPSCO executed  
5 for the Electric Plan 1 did not allow for the addition of new projects.  
6 However, an amendment to the TDSIC Statute has expanded the categories  
7 of allowable TDSIC projects. All of this in combination led NIPSCO to the  
8 decision to terminate its Electric Plan 1 and develop and file the 2021-2026  
9 Electric Plan, a plan that proposes projects based upon a more updated  
10 view of NIPSCO's electric system and projects that will enable NIPSCO to  
11 modernize its system to provide the service its customers expect and  
12 deserve.

13 **Q15. Does the 2021-2026 Electric Plan require flexibility in its project**  
14 **portfolio?**

15 A15. Yes. NIPSCO will require the ability to move projects already within the  
16 plan timeline, as well as remove, adjust, or add projects. NIPSCO will  
17 provide details on any updates to its Plan in its tracker filings.

18 **Q16. Please provide a summary of NIPSCO's 2021-2026 Electric Plan.**



1 A16. NIPSCO's 2021-2026 Electric Plan is focused on electric transmission and  
2 distribution system investments made to enhance system safety and  
3 reliability, modernize its system, and improve the customer experience.  
4 The Plan also makes provision for appropriate economic development  
5 projects in the future, although none are proposed at this time. The Plan is  
6 comprised of four main segments: (1) investments that target replacement  
7 of aging assets (Aging Infrastructure), (2) investments intended to maintain  
8 the capability of NIPSCO's electric system to deliver power to customers  
9 when they need it (System Deliverability), (3) investments for  
10 modernization of NIPSCO's electric system to deliver safe and reliable  
11 service, including installation of AMI (Grid Modernization),<sup>7</sup> and (4)  
12 eligible economic development projects in the future (Economic  
13 Development). Table 1 summarizes the 2021-2026 Electric Plan by  
14 investment segment.


15

---

<sup>7</sup> The AMI investments are discussed by Witness Holtz.

1

**Figure 1 – Investment Plan Spending by Segment and Year**



2

3


4

5

6

\*2021 investment only includes projects associated with the 2021-2026 Electric Plan. The 2021 investments associated with Electric Plan 1 are not included here.

**Figure 2 – Potential Investment Spread**



7

1  
2

**Table 1 – Investment by Segment**

Investment Segment	2021-2026 Electric Plan Projected Investment (Direct Capital Dollars)
Aging Infrastructure	\$753,121,380
System Deliverability	\$281,439,419
Grid Modernization	\$362,054,616
Economic Development	\$0
<b>Plan Total</b>	<b>\$1,396,615,415</b>

3

4 **DEVELOPMENT OF THE 2021-2026 ELECTRIC PLAN**

5 **Q17. What is the primary goal of NIPSCO's 2021-2026 Electric Plan?**

6 A17. The primary goal of the Plan is to deploy a portfolio of investments in  
7 electric transmission and distribution facilities that preserves NIPSCO's  
8 ability to serve peak load, maintain system performance, ensure the safety  
9 of NIPSCO's systems, and enable evolving energy technologies, such as  
10 Distributed Energy Resources ("DERs") and electric vehicles ("EVs"). The  
11 portfolio of investments serves these goals by replacing aging assets,  
12 increasing system deliverability, and modernizing the system for future  
13 growth.

14 Within the four (4) categories (safety, reliability, grid modernization, and  
15 economic development), the Plan is estimated to reduce the overall system  
16 risk, increase the deliverability of electric service, and enhance system

1 automation to reduce customer outages and enable asset condition  
2 visibility.

3 **Q18. Please describe the assets reviewed in developing the 2021-2026 Electric**  
4 **Plan.**

5 A18. In developing the 2021-2026 Electric Plan, NIPSCO focused its review to all  
6 of its electric transmission and distribution assets. The NIPSCO electric  
7 transmission system consists of approximately 21 circuit miles of 765 kV;  
8 453 circuit miles of 345 kV; 810 circuit miles of 138 kV; and 1,679 circuit  
9 miles of 69 kV transmission lines. In addition, NIPSCO has 66 transmission  
10 substations. NIPSCO serves approximately 470,000 electric customers in  
11 Northern Indiana, primarily through more than 900 distribution circuits.  
12 These circuits operate at a nominal voltage of 34.5 kV and 12.5 kV,<sup>8</sup> and  
13 radiate from approximately 249 distribution substations. There are  
14 approximately 7,903 miles of overhead line, with about 2,592 miles of  
15 underground cable. NIPSCO's review included all substation  
16 transformers, circuit breakers, system protection devices, and other  
17 ancillary substation equipment in its transmission, sub-transmission, and  
18 distribution substations, including the structures and the corresponding

---

<sup>8</sup> As part of Electric Plan 1, NIPSCO successfully replaced all 4 kV distribution circuits.

1           overhead and underground conductors associated with the transmission,  
2           sub-transmission, and distribution circuits. In this review, NIPSCO  
3           confirmed the following key facts about its electric transmission and  
4           distribution infrastructure:

- 5           •       NIPSCO owns, operates, manages and controls transmission and  
6           distribution plant and equipment within the State of Indiana that is  
7           in service and used and useful in the furnishing of electric service to  
8           the public. NIPSCO has maintained and continues to maintain its  
9           properties in a reliable state of operating conditions.
  
- 10          •       NIPSCO's electric system grew significantly during the 1960s and  
11          1970s. Many assets installed during this era and before are reaching  
12          the end of their useful lives, and in many cases these assets are  
13          comprised of 1950s technology. These assets have increasing failure  
14          probabilities that will cause reliability degradation. This statistical  
15          likelihood of failure ("LOF") is increasing every day. Prior to the  
16          start of Electric Plan 1, NIPSCO began to experience increased asset  
17          failures due to deterioration. As discussed above, that plan began  
18          addressing aged major assets and minor programmatic asset  
19          projects, and the currently proposed Plan aims to continue this effort  
20          as assets continue to age and older technologies need to be replaced  
21          through grid modernization.
  
- 22          •       There are certain asset segments that are demonstrating specific  
23          failure trends or unique reliability concerns, including a population  
24          of unjacketed underground cable that is approximately 40-50 years  
25          old. These circuits are geographically isolated with limited  
26          contingency in the event of failure.
  
- 27          •       Some of NIPSCO's system protection devices are outdated and  
28          cannot protect the electric system and key assets in the manner  
29          consistent with modern standards.

- 1           •       Ongoing investments will be required to ensure the electric system  
2                    can continue to reliably deliver electric service to NIPSCO customers  
3                    during periods of peak demand.

4

5   **Q19. Why did NIPSCO select the transmission and distribution system**  
6           **improvements included in the 2021-2026 Electric Plan?**

7   A19. The 2021-2026 Electric Plan was developed to address risks identified and  
8           prioritized as of early 2021, and as such, the 2021-2026 Electric Plan  
9           represents the current best path forward to ensure the continued delivery  
10          of safe and reliable electric service to NIPSCO's customers. The 2021-2026  
11          Electric Plan builds on the capital investments prioritized in Electric Plan 1.  
12          Additionally, the Plan addresses identified areas of needed modernization.  
13          In considering Plan design, NIPSCO conducted comprehensive reviews of  
14          many segments of its electric system. The Plan addresses high priority  
15          safety and operational and integrity needs. Projects were also reviewed to  
16          provide a high level of confidence that they could be executed as proposed.  
17          A broader portfolio of projects was prioritized to develop the specific  
18          improvements included in the Plan, and plan for executions in a logical and  
19          efficient manner.

1           The transmission and distribution system investments included in the 2021-  
2           2026 Electric Plan are required for maintaining and improving the existing  
3           NIPSCO electrical portfolio. The Plan addresses safety, reliability, grid  
4           modernization, and allows for future economic development, all providing  
5           incremental benefits for NIPSCO's customers.

6           **RISK REDUCTION**

7           **Q20. Did NIPSCO achieve reduction in risk through completion of the**  
8           **projects in Electric Plan 1?**


9           A20. Yes. Based on the TDSIC Risk Model for major assets utilized in Electric  
10          Plan 1, the TDSIC electric projects completed from 2016 through 2020  
11          reduced the relative NIPSCO system risk by 21% from the 2016 baseline.  
12          For comparison purposes only, had those projects not been completed, the  
13          NIPSCO system risk would have *increased* 19% from the 2016 baseline  
14          (assuming no other work was performed during that period).

15          **Q21. What are NIPSCO's expectations for risk reductions under the 2021-2026**  
16          **Electric Plan?**

17          A21. One of the primary goals of the Plan is to reduce the overall system risk  
18          associated with aging asset populations and asset failures. NIPSCO  
19          acknowledges that the proposed investment levels in this Plan are

1 substantial, but, even with the 21% risk reduction realized under Electric  
2 Plan 1, which is discussed above, there are still many older, aging assets on  
3 NIPSCO’s system that need to be replaced before they fail. When  
4 comparing the proactive replacement strategy under TDSIC to a “break/fix”  
5 strategy, based on the TDSIC Risk Model, NIPSCO estimates an overall risk  
6 reduction of approximately 16%, as illustrated in Figure 3 below. Even with  
7 the investments made under Electric Plan 1, there is an opportunity for  
8 further investment under the 2021-2026 Electric Plan to continue to reduce  
9 risk, thereby increasing system reliability and better serve NIPSCO’s  
10 customers.

11 **Figure 3 – Risk Score for TDSIC Plan versus Break/Fix Strategy**



12

13



1 **Q22. What does the 16% risk reduction represent and are these results similar**  
2 **to those within Electric Plan 1?**

3 A22. The 16% represents a projection of the reduced risk score calculated for the  
4 specific major asset(s), (i.e., transformers, breakers, circuits), but does not  
5 necessarily represent a percentage reduction in the likelihood of an issue  
6 with the asset(s). For example, the Goshen Junction Substation Rebuild  
7 project (Project ID TSNRS12), which includes both transformer and breaker  
8 replacements, will reduce the risk score associated with the current  
9 substation assets. However, it does not mean that the replacement of the  
10 existing asset will eliminate all risk associated with the new substation.  
11 There are multiple reasons for the variance between the 21% realized risk  
12 reduction under Electric Plan 1 and the estimated 16% risk reduction under  
13 this Plan; however, two factors drive the majority of the difference. The  
14 first reason is that the initial assets addressed in Electric Plan 1 were of  
15 higher impact, because there were the highest risk assets of the whole  
16 NIPSCO asset population, including the assets being replaced under this  
17 Plan. The second reason is driven by lessons learned by NIPSCO as it  
18 executed Electric Plan 1. Under this approach, NIPSCO has identified the  
19 opportunity to replace some assets that are just as old as targeted assets of

1           the project in the same substation or the same circuit. These other assets  
2           have a finite life and will be required to be replaced in the near future. The  
3           most cost effective and least interruptive method to address all of the  
4           related assets in the Plan is to perform all of that work at the same time. For  
5           example, a typical substation includes circuit breakers for the lines entering  
6           and leaving the station, as well breakers for connecting the buses during  
7           maintenance. The line breakers are subject to harsher operating conditions  
8           than the bus breakers. Under Electric Plan 1, there were instances where  
9           just the line breakers were replaced, leaving the older bus breakers in  
10          service. Under the Plan, all the breakers at the substation would be  
11          replaced. NIPSCO's approach in this Plan is to take a more holistic  
12          approach to replacing aged assets on its system and replace them at the  
13          same time as the higher risk assets since resources are already deployed and  
14          outages are taken. Although this method is a more cost-effective and  
15          reliable method for customers in the long run, it also means that NIPSCO  
16          will be replacing some lower risk assets in conjunction with the higher risk  
17          assets identified through the TDSIC Risk Model.

18       **Q23. Does NIPSCO anticipate that the 2021-2026 Electric Plan will change over**  
19       **the plan period?**

1 A23. As stated above, the 2021-2026 Electric Plan was developed to address risks  
2 identified and prioritized as of early 2021, and, as such, the Plan represents  
3 the current best path forward to ensure the continued delivery of safe and  
4 reliable electric service to NIPSCO's customers, as allowed by the TDSIC  
5 Statute. NIPSCO performed a rigorous analysis of its current electric  
6 system as well as anticipated future system needs and does not expect the  
7 Plan to change significantly. With that said, it is certainly possible that  
8 projects in the Plan might change or be replaced, or that new projects might  
9 be proposed. This depends on a number of factors, including, but not  
10 limited to: (1) the continued evolution of the TDSIC Risk Model; (2)  
11 identification through routine and special inspection and assessment cycles  
12 of assets at risk for continued operability; (3) identification of risks through  
13 other NIPSCO process improvement and safety initiatives; (4) load growth  
14 and potential economic development projects; (5) the development of new  
15 technology to increase public safety or that offer more economical solution;  
16 and (6) the development of unpredicted asset failure, of which more  
17 expedient replacement or repair is required.

18

1 FLEXIBLE INVESTMENT PLAN

2 **Q24. How will NIPSCO update the 2021-2026 Electric Plan if a project in the**  
3 **Plan is proposed to be replaced or if a new project is proposed to be added**  
4 **to the Plan?**

5 A24. Any project in the Plan that is proposed to be replaced or any new project  
6 that is proposed to be added to the Plan would be included in a plan update  
7 filing pursuant to Section 9(b) of the TDSIC Statute. If approved, NIPSCO  
8 would then seek deferral of costs associated with the replaced or new  
9 project and recovery of the costs associated with a replaced or new project  
10 in future plan update filings, based on the reasons discussed immediately  
11 above.

12 **Q25. Please describe the incremental benefit associated with the 2021-2026**  
13 **Electric Plan.**

14 A25. The 2021-2026 Electric Plan focuses on maintaining safe, reliable service for  
15 NIPSCO's customers, while incorporating system upgrades. The Plan  
16 addresses eligible investments of safety, reliability, and grid modernization  
17 included in the TDSIC Statute. The Plan's investments positively impact  
18 electric reliability, safety, and grid modernization while resulting in  
19 positive economic impact for Indiana. The Plan also provides for

1 appropriate economic development projects in the future, although none  
2 are proposed at this time. Reliability drivers include the following:

- 3 • Reducing direct customer outages;
- 4 • Shortening customer outage durations;
- 5 • Maintaining continuity of service (self-healing system);
- 6 • Better managing peak system loading periods;
- 7 • Increasing flexibility for system sourcing;
- 8 • Increasing system visibility and validation;
- 9 • Enabling future technologies; and
- 10 • More timely notification of outages (AMI).

11  
12 Safety is of utmost importance to NIPSCO, its customers, and the broader  
13 public. Maintaining safety performance is a requirement for NIPSCO's  
14 workforce and its customers, and thus one of the main objectives of the  
15 Plan. The continued safety of NIPSCO's employees and customers is  
16 enhanced when the likelihood of violent failures (i.e., explosions, fires,  
17 downed power lines) are mitigated through aging infrastructure  
18 replacement. The increased visibility for fault detection and system  
19 modernization assists in preventing violent failures from occurring as well.

1           Lastly, the extension of new facilities provides for a more robust system to  
2           meet deliverability or interconnection requirements.

3           As discussed in detail above, NIPSCO has a large number of aging assets  
4           on its electric transmission and distribution system. The assets have aged  
5           naturally as a function of NIPSCO's service territory development during  
6           the rapid build out in the 1960s and 1970s, and many assets have met or are  
7           approaching their end of life. The proactive replacement of aging  
8           infrastructure will help maintain the reliability of NIPSCO's electric  
9           transmission and distribution systems, which are growing older, and  
10          therefore riskier, with each passing year. The 2021-2026 Electric Plan  
11          targets the highest risk and consequence of failure assets. In developing the  
12          Plan, NIPSCO carefully prioritized the list of planned investments to  
13          optimize the benefits of the investments while taking into account  
14          execution resources, engineering resources, and system constraints. For  
15          risk-based projects, the Plan represents an optimized risk reduction of  
16          approximately 16% versus a break/fix strategy.

17          The proactive replacement of aging infrastructure also provides  
18          opportunities to replace old equipment with modern technology in a  
19          systematic and deliberate manner. While costs are primarily delineated by

1 the four asset class categories and project types (T&D Substation and T&D  
2 Line), NIPSCO proactively evaluated the execution of projects throughout  
3 the Plan and combined projects or project categories for efficiency. This  
4 "combination" allows original project categories to be consolidated into  
5 singular projects to effectively gain time and reduce overall capital costs.  
6 For example, the original driver for a transformer replacement project may  
7 be age and condition; however, the new transformer will include substation  
8 automation and communication components that are primarily driven by  
9 grid modernization. Through this consolidation process, NIPSCO can  
10 reduce mobilization, overhead, and labor costs, and potentially reduce the  
11 number of scheduled outages.

12 Grid modernization benefits include optimizing NIPSCO's outage  
13 response, reducing unplanned asset failures, improving system flexibility,  
14 and laying a groundwork for future growth to implement modern  
15 technologies. By proactively enhancing the monitoring of asset and system  
16 health, NIPSCO will be able to avoid increasing levels of reactive or  
17 emergency work, which are often more expensive to perform due to  
18 premium labor rates and expediting fees, and often introduce additional,  
19 preventable safety risks. Unplanned asset failures are also typically more

1 disruptive to customer service and have the potential to damage customer  
2 equipment or jeopardize personnel safety. Grid modernization projects  
3 include modern system protection devices that provide for faster clearing  
4 of system faults which will protect the health of NIPSCO's assets and  
5 minimize the breadth of future outages.

6 Finally, the 2021-2026 Electric Plan fosters economic development, a key  
7 benefit of the Plan that will be spurred by these investments in the electric  
8 system. As Witness Becker discusses more fully, the Economic Impact  
9 Report prepared by Sargent & Lundy shows the positive economic impact  
10 of these investments to Northern Indiana. The Plan also provides for  
11 appropriate economic development projects in the future, although none  
12 are proposed at this time. Additionally, to the extent a future economic  
13 development investment is identified, NIPSCO would present the  
14 proposed project in a plan update filing pursuant to Section 9(b) of the  
15 TDSIC Statute.

16 **Q26. How has NIPSCO approached the quantification of incremental benefits**  
17 **associated with the 2021-2026 Electric Plan?**

18 A26. NIPSCO expects to see an aggregate reduction in the risk of major asset  
19 failure associated with the transmission and distribution projects in the



1 Plan of approximately 16%, and each project included in the Plan has been  
2 chosen and designed with the intent to reduce the likelihood of failure and  
3 the attendant risk to service reliability and continuity and the availability  
4 of system capacity. The benefit to NIPSCO's customers from Aging  
5 Infrastructure and System Deliverability investments cannot be easily  
6 calculated in an actuarial calculation. While it would be convenient if the  
7 benefit of each of the Aging Infrastructure and System Deliverability  
8 projects could be quantified in monetary terms to permit some kind of a  
9 cost-benefit analysis, the value to be placed on life and property potentially  
10 at risk from the failure of one of these assets is too high to realistically  
11 contemplate. However, investments in Grid Modernization is one area  
12 where the estimated benefits can be monetized. The Distribution  
13 Automation Program Business Case (Confidential Attachment 2-E)  
14 monetizes the value of the proposed distributed automation program.  
15 NIPSCO and Leidos utilized the U.S. Department of Energy's Interruption  
16 Cost Estimation (ICE) calculator to place a value on customer interruption  
17 costs and savings that would be realized by customers as a result of  
18 NIPSCO implementing specific Grid Modernization investments.<sup>9</sup> The

---

<sup>9</sup> Witness Kiergan also discusses a cost-benefit analysis conducted for the AMI Project.

1 report summarizes that investments in DA grid modernization result in a  
2 cost savings of approximately \$592 million over the period of twenty years,  
3 compared against the investment of approximately \$52 million for DA grid  
4 modernization projects over a 10-year period. The total NIPSCO DA plan  
5 will not be completed within the 2021-2026 Electric Plan window.

6 **Q27. Are the estimated costs of the eligible improvements included in the**  
7 **2021-2026 Electric Plan justified by incremental benefits attributable to**  
8 **the Plan, as required under Section 10(b)(3) of the TDSIC Statute?<sup>10</sup>**

9 A27. Yes. The estimated costs of the eligible improvements included in the 2021-  
10 2026 Electric Plan are justified by the incremental benefits. Some of the  
11 benefits identified above are readily quantifiable, and others are more  
12 qualitative in nature. The Plan contains solutions that will enhance  
13 customer and employee safety, avoid outages, preserve operational and  
14 planning contingencies, provide superior equipment protection, and meet  
15 evolving customer demands. By virtue of achieving all of these benefits in  
16 a thoughtful, planned and cost-efficient manner, the Plan provides

---

<sup>10</sup> Section 10(b)(3) of the TDSIC Statute requires a finding that the estimated costs of the eligible improvements (i.e., projects and programs) included in a proposed TDSIC plan be justified by the incremental benefits attributable to the plan.

1 incremental benefit for NIPSCO's customers that outweigh the estimated  
2 costs.<sup>11</sup>

3 **Q28. How has NIPSCO incorporated process improvements and lessons**  
4 **learned from its previous TDSIC filings?**

5 A28. Over the past few years, NIPSCO has been able to make significant  
6 improvements in the development of its TDSIC capital investment plan.  
7 Historically, NIPSCO forecasted capital planning in a logical and planned  
8 manner, but this was not based on the same level of project selection criteria  
9 and project level detail as its TDISC plan has been. Based on feedback  
10 received and internal learning through the plan development process,  
11 NIPSCO has been able to make considerable improvement providing a  
12 much greater level of detail utilizing risk modeling, condition-based  
13 assessment, system constraints, resource constraints, and long-range  
14 system planning to better define projects that are necessary and included in  
15 the Plan. Improvements have also occurred in developing more accurate  
16 project estimates, including extending Class 3 estimates out to 18 to 24  
17 months. Project management and construction has also been able to build

---

<sup>11</sup> Estimated costs for the 2021-2026 Electric Plan are discussed separately below.

1           on the experience over the past several years, becoming more experienced  
2           in project planning and execution.

3    **PLAN UPDATE PROCESS**

4    **Q29. Will the 2021-2026 Electric Plan need to be updated?**

5    A29. Yes. Section 9(b) of the TDSIC Statute states that “[t]he public utility shall  
6           update the public utility’s TDSIC plan under subsection (a)(2) at least  
7           annually.” Consistent with this provision, NIPSCO proposes to update the  
8           2021-2026 Electric Plan annually, but in no event more frequently than once  
9           every six months.<sup>12</sup> In addition to the statutory requirement to file an  
10          updated plan, it is prudent and necessary for NIPSCO to systematically and  
11          periodically review, revise, and update its Plan to respond to the dynamic  
12          nature of its transmission and distribution system, customer demand, and  
13          equipment failures. While considerable analysis and thought went into the  
14          development of the 2021-2026 Electric Plan, it is important to note that the  
15          Plan is reflective of the characteristics of the electric system and the needs  
16          of NIPSCO’s customers as they exist at the time the Plan was developed.  
17          As NIPSCO learns more in the upcoming years, the Plan will be updated as

---

<sup>12</sup> As provided in Section 9(f) of the TDSIC Statute, NIPSCO will not file a petition under Section 9 more frequently than once every 6 months.

1           necessary. Through normal operations, information is continually gathered  
2           around asset condition data. This information will be integrated into the  
3           TDSIC Risk Model and will serve to modify the probability of asset failure.  
4           Additionally, configuration of the system, connectivity of critical  
5           customers, and other system events will serve to modify the consequence  
6           of failure driver in the TDSIC Risk Model. As customer demands evolve,  
7           both from a location and utilization perspective, system deliverability  
8           requirements must evolve.

9           Lastly, the 2021-2026 Electric Plan seeks to address risk by proactively  
10          replacing the riskiest elements in NIPSCO's system. Some elements of the  
11          system are best utilized in a "run to failure" mode, while other elements  
12          may fail before their planned replacement cycle arrives. While the models  
13          utilized to develop the Plan are sound, it is impossible to perfectly predict  
14          the future. As such, when these unanticipated events occur, the Plan will  
15          be re-prioritized. As such, a prudent 6-year plan must be dynamic. As  
16          information inputs change, the Plan will continue to be optimized to ensure  
17          the best plan possible is being deployed, and, when necessary, NIPSCO will  
18          work with all stakeholders when seeking to add new projects to the Plan.

19   **Q30. Please describe the Plan update process proposed in this filing.**

1 A30. NIPSCO's proposed update process is similar to the process used for  
2 Electric Plan 1 with the exception that NIPSCO is proposing to update its  
3 Plan annually. NIPSCO proposes to continue the current process of  
4 meeting with its stakeholders approximately four weeks prior to filing each  
5 Plan update.

6 In its Fall filing, the Plan will be updated with NIPSCO's best estimate by  
7 project for each calendar year. The risk registers (Confidential Appendices  
8 A and B) will be updated as new, relevant information becomes available  
9 during the Plan update process. Project Change Request ("PCR") forms  
10 and testimonial explanations will be provided to support project estimate  
11 changes greater than \$100,000 and greater than 20% during the current year  
12 for projects. Actual costs (direct capital, indirect capital, and allowance for  
13 funds used during construction ("AFUDC")) will be included in the annual  
14 Plan update after a given calendar year is closed out. The annual Plan  
15 update will define the detailed project scopes and update unit cost  
16 estimates for the next calendar year, if needed.

17 **COST ESTIMATES AND ESTIMATE DEVELOPMENT**

18 **Q31. Please summarize the estimated costs associated with the 2021-2026**  
19 **Electric Plan.**

1 A31. As shown in Confidential Attachment 2-A, the total estimated capital cost  
2 of the 2021-2026 Electric Plan is \$1,625,520,697, including direct capital of  
3 \$1,396,615,415, indirect capital of \$181,560,012, and AFUDC of \$47,345,270.  
4 As explained by Witness Meece, indirect capital costs are incurred in  
5 performing capital projects but are not charged directly to a specific work  
6 order. As shown in Confidential Attachment 2-A, the total estimated O&M  
7 cost of the 2021-2026 Electric Plan is \$10,014,705. Table 2 shows the  
8 estimated costs associated with the 2021-2026 Electric Plan, by project year.

9 **Table 2 – Annual Cost Breakdown by Type**

	Year 1 2021	Year 2 2022	Year 3 2023	Year 4 2024	Year 5 2025	Year 6 2026	Total
Direct	\$105,324,448	\$222,556,740	\$229,233,442	\$275,229,152	\$276,892,422	\$287,379,211	\$1,396,615,415
Indirect	\$13,692,179	\$28,932,376	\$29,800,350	\$35,779,789	\$35,996,017	\$37,359,301	\$181,560,012
AFUDC	\$3,570,498	\$7,544,672	\$7,771,017	\$9,330,269	\$9,386,653	\$9,742,161	\$47,345,270
<b>Total Capital</b>	\$122,587,125	\$259,033,788	\$266,804,809	\$320,339,210	\$322,275,092	\$334,480,673	\$1,625,520,697
<b>Total O&amp;M</b>	\$83,418	\$2,329,335	\$2,263,358	\$2,301,811	\$1,680,577	\$1,356,206	\$10,014,705

10  
11 **Q32. Does the total estimated capital cost of the 2021-2026 Electric Plan include**  
12 **plan development costs and preliminary survey and investigation**  
13 **(“PS&I”) costs?**

14 A32. Yes. Both types of costs have been included in the Plan, but are included in  
15 the project costs in different ways. As has been NIPSCO’s standard  
16 practice, PS&I costs for specific projects will be included in the project’s

1 land acquisition, preconstruction, environmental, and construction work  
2 order (direct capital) and typically will be distributed when the work order  
3 is opened based upon the type of typical project planning and sequencing  
4 year of project execution. Additionally, approximately \$3 million of plan  
5 development costs will be amortized over the life of the Plan as capital  
6 overhead (or indirect capital).

7 **Q33. Please describe the different techniques used by NIPSCO and S&L to**  
8 **develop a cost estimate for a project.**

9 A33. A cost estimate is developed at a point in time, and is based on the  
10 information known when the estimate is developed. As the project  
11 progresses, the information used as inputs into the cost estimation process  
12 becomes more accurate. There are different techniques used by NIPSCO to  
13 develop a cost estimate for a project. NIPSCO utilizes the following  
14 standard AACE International ("AACE") class estimate definitions:

- 15 • Analogous Class 5 (the estimate is based on expert judgment and  
16 overall system factors) – these estimates have very little of the total  
17 project defined (0 – 2%) and require very little engineering in order  
18 to estimate.
- 19 • Parametric Class 4 (the estimate is developed using application of  
20 similar type estimates and specific equipment factors) – these  
21 estimates are done at about 1 – 15% of the total project being defined



1 and usually have an engineering or feasibility study associated with  
 2 them.

- 3 • Semi-detailed Class 2 / 3 (the estimate is developed with unit costs  
 4 and with assembly level line items) – these estimates are performed  
 5 at 10 – 70% project definition, have detailed engineering nearly  
 6 complete, and use bids tendered as development for the estimate.
  
- 7 • Detailed Class 1 (the estimate is developed with unit costs and with  
 8 detailed bill of materials) – these estimates are performed at 50 –  
 9 100% project definition with the detailed engineering complete, bids  
 10 tendered and verified to develop the estimate.

11 Table 3 shows the AACE level of estimate for each project or program type  
 12 at the time of filing. As plan years proceed the level of estimate will continue  
 13 to progress. Projects three years from execution will have gone through, or  
 14 are going through the scoping phase of the project and may progress to a  
 15 Class 4. Projects will have updated estimates at an AACE Class 3 level 18 to  
 16 24 months from execution. Programs will have been detailed engineered by  
 17 the execution year 1 and can be considered a Class 4.

**Table 3 – Estimate Classes**

<b>Class Estimate Table</b>						
<b>Project Type</b>	<b>Year 1</b>	<b>Year 2</b>	<b>Year 3</b>	<b>Year 4</b>	<b>Year 5</b>	<b>Year 6</b>
New or Replace Transformer	Class 3	Class 3	Class 5	Class 5	Class 5	Class 5
New or Replace Breaker	Class 3	Class 3	Class 5	Class 5	Class 5	Class 5
Upgrade Relay	Class 3	Class 3	Class 5	Class 5	Class 5	Class 5
New or Replace Communication Equipment	Class 3	Class 3	Class 5	Class 5	Class 5	Class 5
New or Upgrade Substation Automation	Class 4	Class 5	Class 5	Class 5	Class 5	Class 5
Replace Potential Transformer	Class 4	Class 5	Class 5	Class 5	Class 5	Class 5
Replace Disconnects/Substation Switch	Class 4	Class 5	Class 5	Class 5	Class 5	Class 5
New or Rebuild Circuit	Class 3	Class 3	Class 5	Class 5	Class 5	Class 5
New or Upgrade Fiber Optic Line	Class 3	Class 3	Class 5	Class 5	Class 5	Class 5
Replace Line Switch	Class 4	Class 5	Class 5	Class 5	Class 5	Class 5
Life Extension Steel Structure	Class 4	Class 5	Class 5	Class 5	Class 5	Class 5
Replace Underground Cable	Class 4	Class 5	Class 5	Class 5	Class 5	Class 5
Life Extension Wood Pole	Class 4	Class 5	Class 5	Class 5	Class 5	Class 5
New or Upgrade Distribution Line Automation	Class 4	Class 5	Class 5	Class 5	Class 5	Class 5
Upgrade Advanced Metering Infrastructure	Class 4	Class 5	Class 5	Class 5	Class 5	Class 5

19

1 **Q34. Please describe the cost estimates that are provided as part of the 2021-**  
2 **2026 Electric Plan.**

3 A34. The 2021-2026 Electric Plan (Confidential Attachment 2-A) provides a  
4 summary of project level estimates by year, which includes all investments  
5 represented in direct dollars. Confidential Attachment 2-A, Confidential  
6 Appendix C includes the detailed cost estimates for the 2021 projects.  
7 Confidential Attachment 2-A, Confidential Appendix D includes the  
8 detailed cost estimates for the 2022 projects. Confidential Attachment 2-C  
9 includes design basis cost estimates broken down by direct and indirect  
10 costs (including labor and material) for Program Projects for 2021 and 2022,  
11 and for all projects included in 2023-2026. The cycle that NIPSCO projects  
12 are refined include initial scoping and estimating efforts three years in  
13 advance of execution, detailed engineering two years in advance of  
14 execution, and resource planning one to two years in advance of execution.  
15 Other costs included in the years leading up to execution include land  
16 purchases, environmental studies, and other preconstruction activities.

17 **Q35. How did NIPSCO develop the direct capital cost estimates for the Site**  
18 **Specific Projects?**

19 A35. The direct capital cost estimates for 2021 and 2022 were developed by

1 NIPSCO's Project Scope and Estimate Development Team utilizing detailed  
2 site reviews, internal engineering, operations, and planning expertise and  
3 outside engineering input. All estimates were reviewed by NIPSCO's  
4 internal stakeholders. The project estimates for 2021 and 2022 are  
5 considered Class 3/4 estimates. The direct capital cost estimates for 2023-  
6 2026 were developed by S&L and NIPSCO using a modular cost estimating  
7 approach using historical unit cost data, labor rates for external contractors,  
8 labor rates for internal NIPSCO labor, vendor budgetary quotations for  
9 major substation assets, NIPSCO's Geographic Information System ("GIS")  
10 for evaluating line rebuild assets, and construction contractor per unit  
11 budgetary validations for installation. The modular estimates were then  
12 applied to each project based on type of known scope. These project  
13 estimates are considered Class 5. However, given the repetitive nature and  
14 the large number of projects, along with NIPSCO's experience with this  
15 type of work, there is a high level of confidence in these cost estimates. The  
16 estimate review process is continuous throughout the project development  
17 process.

18 **Q36. How did NIPSCO develop the direct capital cost estimates for the**  
19 **Program Projects?**

1 A36. The direct capital cost estimates for 2021-2026 were developed by S&L and  
2 NIPSCO internal stakeholders using historical unit cost data, vendor  
3 quotations for typical equipment utilized for the project application, and  
4 knowledge of executing projects within NIPSCO's service territory.

5 **Q37. How did NIPSCO develop the estimated indirect capital costs?**

6 A37. NIPSCO used historical data from its Electric Plan 1 update filings to  
7 develop the estimated indirect percentage. The resulting percentage was  
8 then applied to the direct capital cost for each year of the Plan to arrive at  
9 the total indirect cost estimate. NIPSCO used 13.0% for indirect capital  
10 costs in the Plan.

11 **Q38. How did NIPSCO develop the estimated AFUDC rate?**

12 A38. NIPSCO used historical data from its Electric Plan 1 update filings to  
13 develop an estimated AFUDC rate. The resulting rate was then applied to  
14 the sum of the direct capital cost and indirect capital cost for each year of  
15 the Plan to arrive at the total AFUDC cost estimate. NIPSCO used 3.0% for  
16 AFUDC in the Plan.

17 **Q39. Do indirect capital costs and AFUDC fluctuate over time and how have**  
18 **they been incorporated into the project cost estimates?**

1 A39. Yes. Witness Meece discusses the origin and calculation of indirect capital  
2 costs and AFUDC. Indirect capital costs fluctuate based on a variety of  
3 inputs, including the level of direct capital costs and indirect labor and  
4 benefit costs. The actual indirect capital and AFUDC costs will be included  
5 in the Plan update when a given calendar year is closed out.

6 **Q40. How does the 2021-2026 Electric Plan provide the best estimate of the cost**  
7 **of the transmission and distribution system investments included in the**  
8 **Plan?**

9 A40. The 2021-2026 Electric Plan includes projects that are similar to work  
10 NIPSCO performed in Electric Plan 1. NIPSCO utilized S&L to complete  
11 the modular cost estimates, followed by internal stakeholder reviews of  
12 those estimates. NIPSCO has gained and continues to gain experience with  
13 respect to the costs necessary for project completion, and cost estimates for  
14 this work reflected from NIPSCO's experience on the range of executed  
15 projects of the previous Electric Plan 1 projects of different types.

16 S&L took a more in depth look at five large substation projects in the 2021-  
17 2026 Electric Plan. Walkdowns were performed, site boundary survey's  
18 produced, a preliminary work scope identified, with conceptual layouts  
19 prepared for project execution, route reviews, and NIPSCO internal

1 stakeholder reviews performed. The estimates prepared for these five large  
2 substations were based on a bottom up, non-modular estimating approach.  
3 Cost data from recent projects and updated budgetary quotations from  
4 construction contractors were used as the basis for the estimates in most  
5 cases, with experience modifiers considered for site specific conditions. For  
6 example, areas where extensive dewatering would be required were  
7 identified. A detailed bill of materials was developed through the  
8 preliminary engineering phase and updated prices were obtained from  
9 NIPSCO suppliers.<sup>13</sup> A preliminary, high level schedule was also  
10 developed to identify detailed engineering, land acquisition, and  
11 permitting lead time requirements.

12 Smaller project estimates, typically under \$1,000,000, are generally based on  
13 parametric or unit price estimates that reflect a mix of contractor and  
14 internal labor resources similar to the allocation of work maintained during  
15 Electric Plan 1. A review of route and site conditions was completed for  
16 many projects.

17 For all projects, broad internal stakeholder input was collected to assure

---

<sup>13</sup> "Bill of materials" is an industry term used to describe a list of the materials or equipment required for the completion of a specific project.

1 comprehensive integrated work scopes were documented and validated  
2 through a formal review process. NIPSCO followed a rigorous project  
3 development, cost estimating, and review process to provide its best  
4 estimate for each project included in the Plan. Further detail about the  
5 estimation process for each project is included in the individual project  
6 descriptions found below.

7 The 2021 Class 3 project estimates were scoped and resource-planned by  
8 NIPSCO. The 2022 projects were also scoped and resource-planned by  
9 NIPSCO. Estimates were prepared utilizing budgetary quotes from  
10 equipment suppliers for typical major equipment; review of NIPSCO's  
11 historical data for support costs like environmental, engineering, and  
12 construction management; and current labor rates for external resources.  
13 Estimates were then produced utilizing a modular approach to estimating.  
14 S&L substantiated the 2023-2026 project estimates by evaluating them  
15 against projects executed within the 2018-2019 year and against the 2021-  
16 2022 NIPSCO detailed cost estimates. The estimates produced by S&L were  
17 found to be well within the order of magnitude expected for a Class 5  
18 estimate. In addition, S&L conducted site visits utilizing design basis  
19 checklists to assess criteria such as the potential land constraints for projects

1 where site expansion is expected for project execution.

2 Based on the estimates produced by S&L and NIPSCO, and the comparison  
3 to actual costs of similar projects in recent years, NIPSCO is confident that  
4 these are the best estimates for the respective stages of planning for the  
5 projects included in the 2021-2026 Electric Plan. The Plan includes two  
6 types of projects: (a) Program Projects and (b) Site Specific Projects  
7 (substation or line projects). NIPSCO has provided estimates for the two  
8 types of projects:

- 9 • **Program Projects** include Class 5 estimates for years 2022-2026.  
10 Design Basis Documents were created for the generic Scope of Work  
11 associated with the program and a cost estimate was produced based  
12 on the Scope of Work. The program projects are executed based  
13 upon execution sequencing, criticality and potential for improved  
14 customer satisfaction. Class 4 estimates are provided after detailed  
15 engineering is completed.
- 16 • **Site Specific Projects** include Class 3 to Class 5 estimates. The Site  
17 Specific Projects are projects which were estimated using a “bottom  
18 up” modular cost estimating approach, based upon known scope at  
19 the time of the estimate. Estimate modules created for these projects  
20 were created using historical unit pricing, vendor equipment  
21 quotations based on average equipment executed for the type of  
22 application, published contractor rates, and current knowledge of  
23 assumed project execution. It is appropriate to estimate in this  
24 manner due to the volume of individual projects contained within  
25 the Plan and the year at which execution will begin.



1           In summary, NIPSCO worked with S&L to develop the best estimate of the  
2           cost for each investment. Therefore, the estimates included are NIPSCO's  
3           best estimates as of the time of filing. NIPSCO will continue to refine these  
4           estimates as it enters into different phases of the project cycle and provide  
5           the refined estimates in future plan updates.

6           **CONTINGENCY AS A COMPONENT OF ESTIMATION**

7           **Q41. Is inclusion of contingency consistent with the Commission's findings**  
8           **relating to the "best estimate" of costs under the TDSIC Statute?**

9           A41. Yes. When determining whether a company has presented the best  
10          estimate of project costs under the TDSIC Statute, my understanding is the  
11          Commission has repeatedly found that inclusion of contingency is  
12          necessary in order to be considered the "best estimate" of project costs. For  
13          example, in Cause No. 45330 related to a NIPSCO Gas TDSIC Plan, in  
14          response to challenges about the inclusion of contingency as part of project  
15          cost estimates from certain parties, the Commission found that "the  
16          exclusion of contingency in the cost estimate would be unreasonable and  
17          would not establish the best cost estimate as required by the TDSIC

1 Statute.”<sup>14</sup> Similarly, in another 2020 order, the Commission stated: “we  
2 find the exclusion of contingency from the cost estimate would be  
3 unreasonable and would not establish the best cost estimate as required by  
4 the TDSIC Statute.”<sup>15</sup>

5 **Q42. Did NIPSCO include contingency in its project cost estimates?**

6 A42. Yes. Consistent with the Commission’s findings that best cost estimates  
7 must include a level of contingency, NIPSCO included contingency  
8 consistent with the AACE Recommended Practice for cost estimate  
9 classification.<sup>16</sup> The contingency incorporated in the estimates for each of  
10 the 2021-2026 Electric Plan projects is consistent with industry practice for  
11 these types of projects and is consistent with the AACE Recommended  
12 Practice and NIPSCO’s experience for risk that can impact a project cost  
13 gained through the execution of projects within Electric Plan 1.

14 The AACE Recommended Practice is based on project maturity or progress  
15 of project engineering or project development. The preliminary

---

<sup>14</sup> Commission order in Cause No. 45330 at p. 23, issued July 22, 2020. In this order, the Commission also found that “the level of contingency reflected in [NIPSCO’s] cost estimates is reasonable.” *Id.*

<sup>15</sup> Commission order in Cause No. 45264 at pp. 22-23, issued March 4, 2020.

<sup>16</sup> The AACE is an organization with over 7,000 members in 100 countries and focuses on cost engineering, estimating and cost management.

1 engineering for most projects in the 2021-2026 Electric Plan would support  
2 a Class 5 estimate based on the application of recent construction  
3 experience, added efforts to inspect and understand site conditions,  
4 identification of real estate and environmental requirements, and  
5 characterization of project risks, especially on the larger transmission  
6 projects. A contingency amount, by project, can be found in the project  
7 estimate summaries included in Confidential Attachment 2-A, Confidential  
8 Appendix C for 2021, and Confidential Attachment 2-A, Confidential  
9 Appendix D for 2022. Confidential Attachment 2-C shows the contingency  
10 amount for each of the projects included in the 2021-2026 Electric Plan. As  
11 shown in Confidential Attachment 2-C, the total contingency is  
12 approximately 10% of the direct labor component of the estimates for all  
13 projects.

14 Attachment 2-H includes additional information supporting NIPSCO's  
15 inclusion of contingency in its project cost estimates, including (1) use of  
16 contingency for purposes of cost estimation, (2) inclusion of contingency

1 improves cost estimates, and (3) why contingency is used in the estimating  
2 process.<sup>17</sup>

3 **Q43. Please explain the process used by NIPSCO to determine the appropriate**  
4 **contingency for each project.**

5 A43. NIPSCO utilizes a process of progressive elaboration to develop project  
6 details and identify risk for the project. Once this is complete, an  
7 appropriate contingency for a project is assigned. As the project is  
8 developed further through an iterative process, the process is repeated.  
9 Many of the large projects within the 2021-2026 Electric Plan had several  
10 formal review meetings with a wide variety of internal stakeholders to  
11 validate the project details and relevant risks (including potential risks).  
12 The AACE Recommended Practices are based on the maturity of the project  
13 design or engineering. NIPSCO's process is intended to identify the  
14 potential issues or risks. Where there is a high probability that a risk will  
15 be realized and a mitigation plan can be defined with a cost estimate,  
16 NIPSCO defines the solution and includes the costs in the estimate. Where

---

<sup>17</sup> As shown in Confidential Attachment 2-C, Confidential Attachment 2-A, Confidential Appendix C (2021), and Confidential Attachment 2-A, Confidential Appendix D (2022), the 3% annual escalation factor is only applied to base cost capital estimates, but not to contingency amounts.

1           this is not possible, the Company adds the issue to the risk register and  
2           applies the contingency if the risk is realized.

3   **Q44. Has NIPSCO evaluated the risks considered in establishing the**  
4           **contingency for each project?**

5   A44. Yes. The potential risks associated with the project types are identified  
6           within the 2021-2026 TDSIC Investment Plan Cost Analysis developed by  
7           S&L (Confidential Attachment 2-C).

8   **Q45. Are these the same risks that NIPSCO considered in determining which**  
9           **projects to include in the 2021-2026 Electric Plan?**

10   A45. No. The risks referenced in the contingency questions above describe risks  
11           related to the *implementation* of specific projects. The TDSIC Risk Model  
12           used in determining which projects to *include* in 2021-2026 Electric Plan,  
13           evaluate the risk to the system associated with safety, reliability, and  
14           deliverability and selected the projects most likely to benefit the NIPSCO  
15           system and its customers.

16   **AGING INFRASTRUCTURE INVESTMENTS**

17   **Q46. Please describe the significance of replacing aging infrastructure.**

1 A46. Aging infrastructure is a common issue faced by utilities. The electric  
2 system is characterized by technology developed in the 1950s or earlier.  
3 Much of the infrastructure was constructed in the 1960s and 1970s during a  
4 rapid buildout of the electric grid using the best technology available at the  
5 time. Many of these assets have now exceeded the projected life expectancy  
6 by many years and have a failure rate that continues to increase. As this  
7 large asset base continues to age it produces a higher concentration of  
8 projects similar to the original buildout that must be replaced to maintain  
9 the increasing level of system reliability expected by the today's customers.  
10 As these assets are replaced, new technology is also introduced improving  
11 system performance by replacing the obsolete technologies currently in  
12 service. The additional benefits achieved include improved system  
13 performance impacting safety, reliability, and operational performance, as  
14 well as system hardening and resiliency.

15 **Q47. Please summarize the Aging Infrastructure investments included in the**  
16 **2021-2026 Electric Plan.**

17 A47. Aging Infrastructure investments are projects aimed at reducing reliability  
18 risk by replacing or rehabilitating electric transmission and distribution  
19 assets that are of high consequence and are either approaching, have met,

1 or have surpassed their expected life. Aging Infrastructure investments  
2 were identified in two ways. First, NIPSCO worked with the asset  
3 management team at S&L to update an overall risk model for its power  
4 transformers, circuit breakers, and circuits. This is the same risk model  
5 used in Electric Plan 1. This was used to develop the proposed 2021-2026  
6 Electric Plan (the results of the TDSIC Risk Model are included in the Long-  
7 Term Investment Plan (Confidential Attachment 2-B, Confidential  
8 Appendix A)). The result of this work includes the reports identified above  
9 as well as the Asset Register for Risk Based Projects included in the Plan as  
10 Confidential Attachment 2-A, Confidential Appendix A. An optimized  
11 portfolio of electric transmission and distribution assets was then selected  
12 to be addressed based on the result of this risk analysis. These major electric  
13 transmission and distribution assets are critical, highly-engineered  
14 components requiring significant lead time prior to execution. This process  
15 included assigning a consequence of failure ("COF") and likelihood of  
16 failure ("LOF") to each of the assets.

17 Second, NIPSCO independently evaluated groups of system assets to  
18 identify and prioritize the assets within each group with the greatest  
19 potential of failure based on their age and condition. Rather than using a

1 complex risk model for these more numerous assets, NIPSCO analyzed its  
 2 routine testing and maintenance records to identify the individual assets  
 3 within each group that were most in need of replacement and used the  
 4 results of that analysis to create asset registers for the following groups:

Deliverability and Condition Based Projects
Arrester Projects - Transmission
Battery & Charger Equipment Projects - Transmission
Potential Transformer Projects - Transmission
Substation Switch Projects - Transmission
LTC Control Upgrade Projects - Transmission
Annunciator Projects - Transmission
Line Switch Projects - Transmission
Substation Switch Projects - Distribution
Arrester Projects - Distribution
Battery & Charger Equipment Projects - Distribution
Substation Feeder Cable Projects - Distribution
Potential Transformer Projects - Distribution
Power Transformer Projects - Distribution
Switches to Clear Incoming Lines Projects - Distribution
Line Switch Projects - Distribution
LTC Control Upgrade - Regulator Projects
Fiber Optic Cable - Transmission
Upgrade 138kV Circuit Protection Breakers & Relays
Upgrade 69kV Circuit Protection Breakers & Relays
Upgrade 34kV Circuit Protection Relays
Underground Cable Replacement

\*2021 is Base year for Deliverability groups

5  
 6 S&L reviewed these asset groups and completed design basis statements of  
 7 work as provided in Confidential Attachment 2-C. The asset registers for



1 the Deliverability and Condition Based Projects are included in the Asset  
2 Register for Risk Based Projects (Confidential Attachment 2-A, Confidential  
3 Appendix B).

4 **Q48. Are there any projects not included in the asset registers?**

5 A48. Yes. Based on the nature of how specific projects are selected, the Circuit  
6 Performance Improvement, Steel Structure Life Extension, and Pole  
7 Replacement projects are not included in an asset register.

8 **Q49. Please summarize how the Circuit Performance Improvement**  
9 **investments were or will be selected for inclusion in the 2021-2026**  
10 **Electric Plan.**

11 A49. Circuit Performance Improvement investments are determined on an  
12 annual basis by analyzing reliability data and determining which circuits  
13 are most in need of improvement. For purposes of development of the Plan,  
14 expected projects are included in categories such as sectionalization,  
15 distribution automation, circuit rebuild, conductor replacement or other  
16 specified performance improvement based on root cause. The  
17 methodology NIPSCO utilizes to identify these needs and the appropriate  
18 solutions are detailed below. NIPSCO performs a structured assessment of  
19 its circuits systems on an on-going basis to identify and schedule needed

1 investments well in advance of execution to proactively address circuits  
2 with the poorest reliability. The Circuit Performance Improvement  
3 investments included in the 2021-2026 Electric Plan therefore differ from  
4 the other projects included in the Plan because the needed investments are  
5 identified based on the evaluation of reliability and condition. At the  
6 beginning of 2021, NIPSCO reviewed 2020 performance and determined  
7 the 2021 Circuit Performance Improvement projects and developed project  
8 scope and cost estimates. The estimates for 2021 are included in the Plan,  
9 and estimates for future years will be updated in NIPSCO's plan update  
10 filings.

11 **Q50. Please summarize how the Steel Structure Life Extension investments**  
12 **were or will be selected for inclusion in the 2021-2026 Electric Plan.**

13 A50. The Steel Structure Life Extension project is designed to extend the life of  
14 NIPSCO's steel structures or rehabilitate those that do not meet the  
15 accepted strength requirements. This project is necessary to address  
16 NIPSCO's aging steel structure population that is continuing to deteriorate.  
17 Over the life of the Plan, NIPSCO will inspect approximately 1,779  
18 structures, and based on historical experience expects approximately 20%  
19 of those assets inspected to require some type of rehabilitation. Based on

1 inspection, estimates will be updated in NIPSCO's plan update filings, and  
2 each structure will have the appropriate life-extending improvements  
3 made. This project will increase transmission system reliability through  
4 system hardening and resiliency.

5 **Q51. Please summarize how the Pole Replacement investments were or will be**  
6 **selected for inclusion in the 2021-2026 Electric Plan.**

7 A51. The Pole Replacement project is designed to inspect, treat, and replace  
8 NIPSCO's wood pole population. Wood poles are the largest asset  
9 classification on NIPSCO's transmission and distribution system. With the  
10 average age wood poles being greater than 40 years, it is necessary to  
11 actively assess the condition and make any necessary repairs or  
12 replacements to ensure integrity of the system. This is accomplished by  
13 development of a 10-year rolling inspection of each pole to determine  
14 condition and to replace or treat the pole for life extension if necessary. The  
15 inspection is based on industry standard methodology to determine  
16 remaining life. With each inspection, the pole will either be treated to  
17 reduce the rate of future decay, or, if it does not pass the test, the pole will  
18 be replaced. The pole inspection, treatment, and replacement project  
19 improves system reliability, safety, and system hardening during major

1 event days by ensuring all poles meet the strength requirements set forth in  
2 the National Electric Safety Code (“NESC”). NIPSCO plans to inspect  
3 approximately 184,000 poles over the life of the Plan. Based on historical  
4 experience, it is anticipated that approximately 5-6% of the inspected poles  
5 will be replaced, with the exception of those already inspected in years with  
6 above-average rejection rates. Based on inspections, estimates will be  
7 updated in NIPSCO’s plan update filings to account for variances to  
8 historical approximations.

9 **AGING INFRASTRUCTURE PROJECTS**

10 **Q52. Please describe the Aging Infrastructure projects included in the 2021-**  
11 **2026 Electric Plan.**

12 **A52. Table 4 shows the Aging Infrastructure projects included in the 2021-2026**  
13 **Electric Plan.**

14 **Table 4 – Aging Infrastructure Projects**

<b>Transmission</b>	
<b>Project ID</b>	<b>Project Name</b>
TSA1	Arrester Projects
TSB1	Battery & Charger Equipment Projects
TSPT1	Potential Transformer Projects
TSSW1	Substation Switch Projects
TSRUX	Relay Upgrade Projects
TSBRUX	Breaker and Relay Upgrade Projects
TSTUX	Transformer Upgrade Projects

TSNRSX	New/Rebuild Substation Projects
TLSW1	Line Switch Projects
TLST1	Steel Structure Life Extension Projects
TLNRLX	Circuit Rebuild Projects

1

Distribution	
Project ID	Project Name
DUG1	Underground Cable Replacement Projects
DSA1	Arrester Projects
DSB1	Battery & Charger Equipment Projects
DSSW1	Substation Switch Projects
DSFC1	Substation Feeder Cable Projects
DSTU1	Power Transformer Projects
DSBRUX	Breaker and Relay Upgrade Projects
DSTUX	Transformer Upgrade Projects
DSNRSX	New/Rebuild Substation Projects
DLCP1	Circuit Performance Improvement (CPI) Projects
DLWP1	Pole Replacement Projects
DLSW1	Switches to Clear Incoming Lines Projects
DLSW2	Line Switch Projects
DLLED1	LED Street Lighting
DLNRLX	Circuit Rebuild Projects

2

3

4

5

6

7

Aging infrastructure is a significant portion of the Plan, and the projects have been separated into three categories: (1) risk ranked projects, (2) projects ranked using other data sources, and (3) assets included in the TDSIC Risk Model (Confidential Attachment 2-B, Confidential Appendix A), but selected and prioritized based on independent assessments.

8

9

10

11

- Risk Ranked Projects. Overhead and underground circuit rebuild projects, transformers, and circuit breaker assets are identified and prioritized on the Asset Register for Risk Based Projects (Confidential Attachment 2-A, Confidential Appendix A). These are

1 major transmission and distribution projects requiring significant  
2 lead time and planning to execute.

- 3 • Projects Ranked Using Other Sources. This includes Aging  
4 Infrastructure assets that were selected and prioritized based on the  
5 Asset Register for Non-Risk Based Projects (Confidential  
6 Attachment 2-A, Confidential Appendix B). These are projects that  
7 were ranked using other factors such as age, condition, and capacity.  
8 For example, Distribution Batteries are included for replacement  
9 based upon field testing performed on an annual basis to determine  
10 which batteries are most in need of replacement.
  
- 11 • Projects Ranked Using Independent Assessments. Projects in this  
12 category include oil circuit breakers, wood poles, steel tower  
13 rehabilitation, underground cable, circuit performance, and system  
14 deliverability and, except as noted above, are included in the Asset  
15 Register for Non-Risk Based Projects (Confidential Attachment 2-A,  
16 Confidential Appendix B).<sup>18</sup>

17 The Underground Cable Replacement project focuses on the  
18 replacement of aged underground cable, and focuses on the non-  
19 jacketed type. Underground cable became more mainstream as  
20 technology developed during the 1970s and into the 1980s. This  
21 early design was a non-jacketed cable with early generation  
22 dielectric composition. NIPSCO is currently experiencing an  
23 increasing rate of failure of this early generation cable, which results  
24 in increased outages, which can be of a long duration due the repair  
25 process. Much of the cable requires direct replacement due to the  
26 non-jacketed design, while some of the 1980s cable that does have a  
27 jacket can be treated for life extension based on a condition  
28 assessment. The Underground Cable Replacement project includes  
29 a detail list of all cable planned for inspection followed by  
30 replacement during the life of the Plan. Replacement of this vintage  
31 of cable will improve system reliability by replacing obsolete

---

<sup>18</sup> The Circuit Performance Improvement, Steel Structure Life Extension, and Pole Replacement projects are all ranked using independent assessments, but they are not listed in the Asset Register for Non-Risk Based Projects (Confidential Attachment 2-A, Confidential Appendix B). Each of these projects has been described in detail above.

1           technology with new cable designs expected to last more than 40  
2           years.

3           NIPSCO's Aging Infrastructure investments include replacements  
4           from all categories within the TDSIC Risk Model (Confidential  
5           Attachment 2-B, Confidential Appendix A) including: transformers,  
6           breakers, and overhead and underground circuit rebuilds. Another  
7           category included in the Plan is system protection modernization  
8           efforts such as breaker relay upgrades and fiber optic lines. The Plan  
9           includes not only replacing aged assets, but the extension of the  
10          useful life of assets. The Plan also addresses assets such as arresters,  
11          batteries, switches, annunciators, and potential transformers.

12   **Q53. Please describe the TDSIC Risk Model (Confidential Attachment 2-B,**  
13   **Confidential Appendix A) used to rank and help select the risk ranked**  
14   **Aging Infrastructure projects included in the 2021-2026 Electric Plan.**

15   A53. When considering the proactive replacement of some of the aging  
16   infrastructure assets, NIPSCO used a systematic risk model to quantify the  
17   criticality of three types of major transmission and distribution assets to the  
18   overall electric system: (1) overhead and underground circuits, (2)  
19   transformers, and (3) circuit breakers. The results of that risk analysis is the  
20   Asset Register for Risk Based Projects (Confidential Attachment 2-A,  
21   Confidential Appendix A).

22   The model uses this standard definition of risk: Risk = COF x LOF.  
23   Through a quantified risk-scoring model, each major asset that is part of the  
24   NIPSCO transmission and distribution system is scored based on the

1 different COF and the asset's LOF with 1 being lowest and 5 highest.  
2 Additional detail on the risk scoring approach and analysis results is  
3 detailed in the Long- Term Investment Plan (Confidential Attachment 2-B),  
4 one of the building blocks of NIPSCO's 2021-2026 Electric Plan.  
5 Applications of that risk-based scoring and the results produced are used  
6 to inform the capital expenditure forecast for the system are also included  
7 in the Long-Term Investment Plan (Confidential Attachment 2-B). In short,  
8 the approach is used to allocate capital investment towards the assets with  
9 the highest risk scores.

10 While the COF for an asset does not necessarily change a great deal with  
11 the passage of time (unless redundancy is added to the asset base or system  
12 configurations alter the impact of the asset), the effect of infrastructure  
13 aging is that the likelihood of failure increases with each year, which over  
14 time results in an unacceptable level of risk for the utility. NIPSCO's 2021-  
15 2026 Electric Plan will reduce that risk in an efficient and orderly manner.  
16 It is important to note that the Plan has model constraints that consider  
17 NIPSCO's operational limits. The following is a hypothetical example of a  
18 model constraint:



- 1       •     Based on risk alone, the model may recommend 100 breaker  
2       replacements in a year.
  
- 3       •     NIPSCO's electric system requirements can only accommodate  
4       replacement of 60 in that year to avoid unacceptable operational  
5       consequences. This is because when NIPSCO replaces circuit  
6       breakers, NIPSCO is required to tie circuits together, and there are a  
7       limited number of circuit ties that can be performed concurrently  
8       and still maintain service to customers.
  
- 9       •     Therefore, rather than replacing the 100 breakers in a single year,  
10      NIPSCO will schedule replacement of 60 breakers by considering a  
11      variety of factors, including risk ranking, location of the individual  
12      project, and efficiencies related to performing simultaneous work at  
13      the same location or on the same asset(s).

14   **Q54. How did NIPSCO determine the LOF for each asset?**

15   A54. In determining the LOF, NIPSCO utilized the associated survivor curve for  
16   each category of equipment. Survivor curves are widely used by utilities  
17   as part of depreciation studies to estimate the probable average service life  
18   of different assets and to set depreciation rates in line with those lives.  
19   Service life is defined as the period in years from the initial installation to  
20   the retirement date from service as recorded in the continuing property  
21   records ("CPR") of the utility. A plot of the retirement dispersions  
22   calculated from the CPR data for each FERC account is used to determine  
23   "best fit" Iowa survivor (mortality) curves and probable life. Likelihoods  
24   of failure over the next seven years were then derived from the survivor  
25   curves by taking a "seven year forward look" on each asset's survivor

1           curve. This approach is detailed in the Long-Term Investment Plan  
2           (Confidential Attachment 2-B). In addition, NIPSCO incorporated  
3           condition data obtained from field observations. In order to target the  
4           poorest-condition assets on its system, the TDSIC Risk Model explicitly  
5           estimates and incorporates asset condition information into the scoring of  
6           transmission and distribution system risk. This has been accomplished  
7           through development of asset health indices (“AHI”) for different  
8           transmission and distribution asset types, including substation  
9           transformers and breakers. The AHI is a condition scoring algorithm used  
10          to calculate an effective age for each asset. Effective age is then used in the  
11          TDSIC Risk Model to develop an enhanced measure of transmission and  
12          distribution system risk. The benefits of incorporating asset condition  
13          information into the TDSIC Risk Model is that NIPSCO is able to target its  
14          poorest-condition assets, in addition to the most critical assets, within its  
15          2021-2026 Electric Plan. This will help NIPSCO to reduce the likelihood of  
16          asset failures and to decrease the impact of aging infrastructure on its  
17          customers.

18          Finally, using the condition data, NIPSCO determined the “effective age”  
19          of each of these assets. The effective age of an asset is the result of adjusting

1 an asset's chronological age due to relative differences in the asset's current  
2 condition as compared to an expected condition. The condition of an asset  
3 can be influenced by many factors such as operating conditions, service  
4 history, number of operations, loadings, and demand cycles. This  
5 information is gathered from NIPSCO's maintenance and testing programs  
6 and includes information and data from analytical testing as well as visual  
7 inspections.

8 **Q55. How did NIPSCO determine the COF for each asset?**

9 A55. The COF was estimated through a qualitative scoring analysis involving  
10 inputs from subject matter experts, including staff involved in the design,  
11 operation, and maintenance of the asset. Multiple electric transmission and  
12 distribution planning, engineering, and operations professionals  
13 responsible for each part of the system—transmission, sub-transmission,  
14 and distribution—were engaged in this scoring process. The process  
15 consisted of a series of criticality workshops including brainstorming  
16 sessions and several follow-up meetings and discussions to finalize the  
17 consequence criteria for each part of the system. The consequence criteria  
18 were determined for each asset within each system. The criteria consider a  
19 number of factors related to an asset failure on the system and are

1 categorized into (1) Customers Served/Lost, (2) Loss of Generation, (3)  
2 Reliability, (4) Safety and Environmental, and (5) Customer Type.

3 Each of these criteria were rated by NIPSCO staff on a scale of 1 to 5 (low to  
4 high) based on expert experience, system knowledge, and quantifiable data  
5 that was applicable. Once tabulated, the ratings were used to calculate a  
6 consequence score on a weighted average of the criteria that varies based  
7 on the system voltage, that is, transmission, sub-transmission, and  
8 distribution. The detailed definitions for each system and asset are  
9 included in the Long-Term Investment Plan (Confidential Attachment 2-B).

10 As with LOF, the methodology utilized to assess consequence of failure is  
11 detailed in the Long-Term Investment Plan (Confidential Attachment 2-B).

12 **Q56. How did NIPSCO determine which projects would be included in the**  
13 **Risk Ranked Aging Infrastructure investments of the 2021-2026 Electric**  
14 **Plan?**

15 A56. As indicated above, NIPSCO's approach in the development of the Plan  
16 was to reduce reliability risk in the most efficient manner possible. The  
17 TDSIC Risk Model (Confidential Attachment 2-B, Confidential Appendix  
18 A) provides the raw output of the risk rankings. NIPSCO used the TDSIC  
19 Risk Model results as well as system constraints to develop an optimized

1 aging asset replacement plan, which is provided in the Asset Register for  
2 Risk Based Projects (Confidential Attachment 2-A, Confidential Appendix  
3 A). The optimization methodology used in the development of the Plan  
4 sought to achieve the greatest risk reduction possible for the dollars  
5 invested. This included moving projects earlier or later in the planning  
6 schedule to create operational and construction efficiencies.

7 **Q57. How will NIPSCO use the TDSIC Risk Model including COF, LOF, and**  
8 **condition assessment to update the Plan?**

9 A57. Each year, NIPSCO will review the risk ranked assets and update the COF,  
10 LOF, and condition assessment. The results of that review will be used to  
11 update the risk reduction optimization, and, therefore the Asset Register  
12 for Risk Based Projects (Confidential Attachment 2-A, Confidential  
13 Appendix A), which could support moving a project to best utilize TDSIC  
14 funding to reduce risk.

15 **Q58. Are there assets that were included in the TDSIC Risk Model that were**  
16 **prioritized using other criteria?**

17 A58. Yes. Some assets contained in the TDSIC Risk Model have been identified  
18 through independent criteria such as safety, documented performance  
19 issues, or the availability of spare parts. Their replacement is also

1 considered due to constructability efficiencies gained when performing  
2 other grid modernizations. These projects include the Breakers associated  
3 with Relay and Control Modernization, Distribution Power Transformers,  
4 Circuit Performance Improvements, and Underground Cable  
5 Replacements.

6 **Q59. Please explain why NIPSCO is not prioritizing Breakers associated with**  
7 **Relay and Control Modernization, Distribution Power Transformers,**  
8 **Circuit Performance Improvements, and Underground Cable**  
9 **Replacements based solely on risk rankings.**

10 A59. Each of these assets has a specific reason why a risk-based assessment is not  
11 the best way to design the projects.

- 12 • Breakers associated with Relay and Control Modernization. The  
13 breakers chosen to be replaced during a system relay and protection  
14 upgrade are included if it is required to modernize the protection  
15 scheme of a circuit. The relay and modernization plan is prioritized  
16 based on NIPSCO's system needs for protection against overvoltage,  
17 overload, and short circuit conditions. These criteria are not  
18 included within the TDSIC Risk Model.
- 19 • Distribution Power Transformers. The Distribution Power  
20 Transformers project is intended to replace transformers that have  
21 been determined by the TDSIC Risk Model to have the highest  
22 probability of failure, regardless of the consequence of failure.  
23 NIPSCO is proactively replacing transformers that rank the highest  
24 and are at greatest risk of failing.

- 1       •     Circuit Performance Improvements. The Circuit Performance  
2       Improvement projects target the worst performing circuits and taps  
3       as determined through an annual assessment. These metrics are not  
4       included in the TDSIC Risk Model.
  
- 5       •     Underground Cable Replacement. NIPSCO's 12.5 kV underground  
6       cable system is comprised of two general types of conductor,  
7       jacketed and unjacketed. Approximately 90% of NIPSCO's  
8       underground failures have occurred within the unjacketed  
9       population because the 1970s and 1980s vintage cable is  
10      deteriorating at an accelerated rate. While the underground cable is  
11      included within the 12.5 kV circuit make-up within the TDSIC Risk  
12      Model, the model is not able to differentiate between type or vintage  
13      of material in the underground circuit, which could allow a poor  
14      performing asset to remain on NIPSCO's system. Therefore, it is  
15      more appropriate for NIPSCO engineers to design a project to  
16      replace this cable.

17   **Q60. Please explain the Underground Cable Replacement project [Project ID**  
18       **DUG1].**

19   A60. The Plan includes approximately 253 miles of underground primary cable.  
20       The 1970s vintage underground cable has demonstrated a high rate of  
21       failure at NIPSCO. Prior cable testing indicates that cable failures in this  
22       population segment are 13% above the national average. Due to the  
23       complexity of repairs, underground cable outages are among the longest  
24       duration outages. Replacement of these segments of un-jacketed cable will  
25       reduce this known risk in the most suspect vintage cable. In addition, this  
26       replacement process will create circuit loops where radials previously

1           existed, reducing outage duration risk for these outages. This project has a  
2           total cost estimate of approximately \$103 million.

3   **Q61. Please explain how and when NIPSCO selects the particular segments of**  
4           **cable to be replaced as part of the Underground Cable Replacement**  
5           **project.**

6   A61. NIPSCO's asset management team uses a progressive elaboration process  
7           in evaluating its entire underground system performance utilizing outage  
8           information and additional input provided by its local operations  
9           supervisors. This analysis provides historical data on the poorest  
10          performing sections and circuits and is used to prioritize the order of  
11          replacement of the unjacketed underground cable. Sections may also be  
12          selected and placed on an accelerated schedule if they are failing at a higher  
13          than expected rate. All circuits containing cable planned for replacement  
14          in the Plan is included in the Asset Register for Non-Risk Based Projects  
15          (Confidential Attachment 2-A, Confidential Appendix B).

16   **Q62. Please explain the Fiber Optic Cable Installation projects (included in the**  
17          **Relay Upgrades).**

18   A62. The Fiber Optic Cable Installation projects are aging infrastructure  
19          investments that improve communication between protective devices,



1       which in turn improves security and reliability of NIPSCO electric grid.  
2       The project is not evaluated as part of the TDSIC Risk Model. Selective  
3       high-speed clearance of faults on high voltage transmission lines is critical  
4       to the security of the power system. Modern system protection equipment  
5       provides more data and typically includes two-way communication across  
6       a large and well-coordinated network of devices. With older equipment,  
7       the lack of sufficient data from the device as well as the inability to  
8       communicate with many devices at the same time increases fault response  
9       times. Fiber optic cable provides the communication medium for these  
10      modern protective relay schemes. This project has a total cost estimate of  
11      \$2.8 million. This does not include the fiber optic projects that were not  
12      selected to support relay upgrades. Those projects are discussed below in  
13      the grid modernization section of my testimony.

14   **Q63. Please explain how and when NIPSCO selects the particular segments of**  
15   **fiber optic cable to be installed as part of the Fiber Optic Cable**  
16   **Installation project.**

17   A63. Fiber optic cable installations are performed in conjunction with relay  
18   upgrades. Relay upgrades are selected and prioritized by system needs in  
19   order to protect equipment and circuits from the consequences of

1           overvoltage, overload, and short circuit conditions. A Fiber Optic Cable  
2           Installation project will take place where existing communication paths will  
3           not support modern protective relay installations. Fiber optic cable  
4           installations will improve relay system protection of the transmission  
5           system while optically isolating the communication system from outside  
6           influences such as magnetic disturbances, lightning strikes, or other  
7           communication interruptions. These are Aging Infrastructure investments  
8           included in the Asset Register for Non-Risk Based Projects (Confidential  
9           Attachment 2-A, Confidential Appendix B).

10   **Q64. Please explain the projects included in the Asset Register for**  
11    **Deliverability and Condition Based Projects.**<sup>19</sup>

12    A64. An explanation of each of the other projects in this category is as follows:<sup>20</sup>

- 13           •     The **Arrester Replacements** project [Transmission Project ID TSA1  
14           and Distribution Project ID DSA1] is designed to replace 3-6  
15           transmission arresters and 3-12 distribution arresters per year. The  
16           number of arresters replaced in a given year varies according to the  
17           voltage levels of the units being replaced. Arresters protect  
18           equipment from lightning and switching surges. The number of  
19           assets to be replaced each year was determined by reviewing  
20           historical trends and considering arrester replacements that would

---

<sup>19</sup>       The Steel Pole Life Extension and Wood Pole Life Extension projects have been described above but are not listed here because each asset is not listed in the Asset Register.

<sup>20</sup>       Each project and/or applicable asset for each of these project categories has been included in the Asset Register for Non-Risk Based Projects (Confidential Attachment 2-A, Confidential Appendix B).

1 be included with other projects such as breaker and transformer  
2 replacements. NIPSCO will replace the assets on a proactive basis  
3 and update the replacement list as new asset health data becomes  
4 available. NIPSCO selected the particular units to be replaced in a  
5 particular year by considering age and condition data, historical  
6 model performance data, linkages to other projects, and infrared  
7 scans performed by engineers. Arresters are selected for  
8 replacement based on vintage, historical performance, condition,  
9 and criticality of protection. The arresters included in the Plan are  
10 porcelain design from the 1950s with lower protection capability and  
11 higher failure mode resulting in high velocity fragmentation when  
12 they fail, which poses potential safety concerns. Each of these  
13 arresters will be replaced with current design polymer units offering  
14 improved overvoltage protection and a non-fragmentation outer  
15 insulation. Greater transformer and breaker protection will result,  
16 as well as improving safety by eliminating the porcelain failure  
17 point.

- 18 • The **Battery and Charger Equipment Replacements** project  
19 [Transmission Project ID TSB1 and Distribution Project ID DSB1] is  
20 designed to replace 8-16 transmission batteries and chargers and 4-  
21 13 distribution batteries and chargers each year. Batteries provide  
22 the source of control power for substation equipment including  
23 relays, breakers, transformers, and communications equipment.  
24 Station batteries are critical during emergency events allowing  
25 protective devices to operate properly during abnormal operating  
26 conditions. This includes events such as transmission or distribution  
27 outages or loss of station service. Replacement batteries are  
28 determined by a combined evaluation of age and condition.  
29 Maintenance crews perform regular tests on batteries, including  
30 inter-cell and intra-cell resistance checks, specific gravity readings,  
31 and voltage tests to evaluate battery condition. The number of assets  
32 to be replaced per year was determined by reviewing historical  
33 replacement rates and the adequacy of these historical replacement  
34 rates to stay ahead of unplanned failures. NIPSCO will replace the  
35 assets on a proactive basis and update the replacement list as  
36 updated asset health data becomes available.

- 1           •    The **Potential Transformer (“PT”) Replacements** project  
2 [Transmission Project ID TSPT1 and Distribution Project ID DSPT1]  
3 is designed to replace 3-9 transmission potential transformers and 3-  
4 4 distribution potential transformers per year. The number of  
5 Potential Transformers replaced in a given year varies according to  
6 the voltage levels of the units being replaced. Potential transformers  
7 step down the high voltage to a level that can be utilized by relay  
8 and control equipment. The number of Potential Transformers  
9 replaced in a given year varies according to the voltage levels of the  
10 units being replaced. The number of assets to be replaced each year  
11 was determined by reviewing historical trends and considering  
12 potential transformer replacements that would be included with  
13 other projects such as breaker and transformer replacements.  
14 NIPSCO will replace the assets on a proactive basis and update the  
15 replacement list as updated asset health data becomes available.  
16 Potential transformers have been identified for replacement based  
17 upon age and condition.
  
- 18           •    The **Substation Switch Replacements** project [Transmission Project  
19 ID TSSW1 and Distribution Project ID DSSW1] is designed to update  
20 1-7 existing transmission and 1-4 existing substation switches and  
21 protection schemes per year. Ground switch protection schemes  
22 were commonly utilized when the system was originally  
23 constructed. Replacing these schemes with modern circuit switcher  
24 protection will improve system protection by greatly reducing  
25 overall fault clear times, reducing fault stress on power transformers,  
26 and minimizing the impacted area during a fault condition. This  
27 project involves replacing the ground switch with a circuit-switcher  
28 and upgrading and wiring the relays accordingly. This program also  
29 includes replacing other critical switches within the substation. The  
30 number of assets to be replaced each year was determined by subject  
31 matter experts considering factors such as which units would have  
32 the greatest impact and reliability improvement and how many  
33 could be completed considering constraints caused by other projects.  
34 NIPSCO selects the particular units to be replaced in a particular  
35 year by reviewing field data for problematic and very old model  
36 switches. After age, condition, and model problems are addressed,  
37 the level of substation source circuit fault current will drive the

1 relative order of subsequent transformer ground switches to be  
2 replaced.

- 3 • The **Annunciator Replacements** project [Project ID TSRU2] is  
4 designed to replace 4 transmission annunciators in 2022.  
5 Annunciators provide local and remote indication of equipment  
6 problems. The assets to be replaced in 2022 were determined by  
7 subject matter experts determining the optimum replacement rate  
8 based on existing annunciator reliability and expected life, spare  
9 parts availability, linkages to other projects, and constraints caused  
10 by other projects. NIPSCO selects the particular units to be replaced  
11 in a particular year by reviewing age, condition, and operating  
12 history and will replace the assets on a proactive basis.

- 13 • The **Line Switch Replacements** project [Transmission Project ID  
14 TLSW1 and Distribution Project ID DLSW2] is designed to replace 4-  
15 18 transmission switches and 4-12 distribution switches each year.  
16 Switches provide positive indication that equipment is disconnected  
17 for safety and operational purposes. The number of assets to be  
18 replaced each year was determined by subject matter experts after  
19 reviewing logs of equipment operating history, equipment, age and  
20 type of switch.

- 21 • The **Distribution Power Transformers** project [Project ID DSTU1] is  
22 designed to replace the worst condition transformers or those that  
23 have an accelerated rate of degradation. Power transformers  
24 represent an asset class with the greatest lead time from  
25 manufacturers. This extended lead time increases the associated risk  
26 due to the amount of time required to replace the unit when a failure  
27 occurs. Although NIPSCO has taken steps to provide spare units  
28 through inventory or other system spare programs in the industry,  
29 the preferred method is to replace a high-risk unit prior to failure.  
30 The Distribution Power Transformer project is intended to replace  
31 transformers that have been determined by the TDSIC Risk Model  
32 to have the highest probability of failure, regardless of the  
33 consequence of failure. NIPSCO is proactively replacing  
34 transformers that rank the highest and are at greatest risk of failing.  
35 NIPSCO determined the number of transformers that are expected  
36 to actually fail each year based on subject matter experts, test data

1 and anticipated failure rates. This project will improve system  
2 performance by removing high risk units from service through a  
3 planned event that will reduce or eliminate the need for a customer  
4 outage.

- 5 • The **Switches to Clear Incoming Lines** project [Project ID DLSW1]  
6 is designed to replace 9-42 incoming line switches per year.  
7 Incoming line switches provide a visible means to verify the  
8 incoming line to a switchgear or recloser from an incoming circuit  
9 has been disconnected from the distribution circuit. The number of  
10 assets to be replaced per year was determined by maximizing the  
11 number of replacements per year while maintaining system  
12 reliability. NIPSCO will replace the assets on a proactive basis from  
13 a list of predetermined units. NIPSCO selects the particular units to  
14 be replaced in a particular year by considering system constraints,  
15 construction efficiencies, and linkages to other projects.

16 **SYSTEM DELIVERABILITY PROJECTS**

17 **Q65. Please describe the System Deliverability projects included in the 2021-**  
18 **2026 Electric Plan.**

19 **A65. Table 5 shows the System Deliverability projects included in the 2021-2026**  
20 **Electric Plan.**

21 **Table 5 –System Deliverability Projects**

Transmission	
Project ID	Project Name
TSBRU	Breaker & Relay Upgrades Projects
TSTU	Transformer Upgrade Projects
TSNRS	New/Rebuild Substation Projects
TLNRL	New/Rebuild Circuit Projects

Distribution	
Project ID	Project Name
DSBRU	Breaker and Relay Upgrade Projects
DSTU	Transformer Upgrade Projects
DSNRS	New Rebuild Substation Projects
DLNRL	New/Rebuild Circuit Projects

1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16

**Q66. Please describe how NIPSCO identified the System Deliverability investments to include in the 2021-2026 Electric Plan.**

A66. NIPSCO has reliability planning criteria and assessment practices that are used to plan for adequate system deliverability under expected peak load conditions as well as single element or contingency failure loading. Through these criteria and practices, various transmission and distribution projects are identified and evaluated to accommodate customer demands.

For the transmission system, NIPSCO's planning criteria is aligned with the North American Electric Reliability Corporation ("NERC") Reliability Standards, which includes peak load analyses along with other study scenarios targeted at testing the system under stressful situations (e.g., multiple contingencies at the same time). For reference, NIPSCO's Transmission Planning System Assessment Methodology and Planning Criteria dated January 14, 2021, which is also posted on the Midcontinent Independent System Operator, Inc.'s ("MISO") website, is attached hereto

1 as Attachment 2-D. These criteria help ensure a transmission system that  
2 will operate reliably and remain resilient through multiple outages without  
3 causing cascading outages or widespread load loss and can accommodate  
4 near- and long-term customer load growth. These outcomes support not  
5 only NIPSCO's customers, but also the overall reliability of the Bulk Electric  
6 System.

7 For the distribution system, changes in electric demand associated with  
8 current and future customer growth often times require investment in the  
9 form of expanded, upgraded or additional facilities. These investments are  
10 made to ensure sufficient system capacity is available for NIPSCO's  
11 customers under peak load conditions when the system is stressed. The  
12 Company follows planning criteria used to identify areas of needed  
13 improvements under these peak conditions. These criteria call for  
14 mitigation plans to be developed when equipment limits are exceeded for  
15 normal system operations as well as under the single worst contingency.  
16 Distribution operating and design criteria rely on NIPSCO electric line and  
17 substation capacity capabilities are based on NIPSCO's line and substation  
18 design standards, along with specific equipment manufacturer ratings.  
19 Voltage operating criteria are based on the American National Standards



1 Institute ("ANSI") Standard C84.1 ("Electric Power Systems and  
2 Equipment - Voltage Ratings (60 Hertz)") and Indiana Administrative Code  
3 170 IAC 4-1-20 (Standard Voltage and Permissible Voltage Variation).

4 The transmission and distribution planning processes both utilize industry  
5 recognized power system modeling and analysis software to perform their  
6 annual system assessments based on data collected by NIPSCO on a routine  
7 cycle. The Transmission Planning group utilizes models developed  
8 through NERC Eastern Interconnection Reliability Assessment Group  
9 (ERAG). This organization works to develop joint models that the utilities  
10 use in local transmission planning analyses. NIPSCO's Distribution  
11 Planning group utilizes models built locally utilizing NIPSCO's GIS data.  
12 Both the Transmission and Distribution Planning groups use their  
13 respective models to run scenarios that look at current and future projected  
14 conditions including load growth assumptions. These analyses consider  
15 both normal and emergency operating conditions where contingencies are  
16 introduced to stress the system to find vulnerabilities that could impact the  
17 reliability of customers' electric service. Mitigation plans are developed  
18 based on these analyses.

1 In addition to these simulated tests utilizing power system models,  
2 NIPSCO's electric system planners gather input from many teams within  
3 NIPSCO to validate modeled results and to capture issues that may not be  
4 identified in the simulation tests. This input includes operating data such  
5 as bus and line voltages, system equipment, current values, customer  
6 service requests (growth), and system field performance feedback from  
7 various personnel.

8 **Q67. Please describe the 2021 and 2022 System Deliverability projects**  
9 **included in the 2021-2026 Electric Plan.**

10 A67. The 2021 and 2022 Transmission System Deliverability projects include the  
11 rebuilding of two, 69 kV circuits and the extension of one, 69 kV circuit to a  
12 new Distribution Substation. The 2021 and 2022 Distribution System  
13 Deliverability projects include one new distribution substation, the  
14 addition of two new power transformers at two existing substations,  
15 replacement of one existing power transformer with a larger capacity unit,  
16 two new switchgear, the rebuilding of four, 12 kV circuits, and the  
17 reconfiguration of multiple 12 kV circuits and feeders to accommodate the  
18 aforementioned substation upgraders. These projects address system  
19 capacity issues experienced during peak load. These projects are shown on

1 the 2021 and 2022 Project Detail pages of the Plan (Confidential Attachment  
2 2-A, Confidential Appendix B).

3 **Q68. Since the System Deliverability processes you described are performed**  
4 **annually, how did NIPSCO identify the projects for 2023-2026 to be**  
5 **included in the 2021-2026 Electric Plan?**

6 A68. NIPSCO has identified and included in the Plan the System Deliverability  
7 investments that are needed in future years based on the current planning  
8 models. These projects are the product of on-going planning cycle  
9 iterations. The project detail will be provided in a future plan update. It is  
10 important to note that these improvements might change in subsequent  
11 planning cycles as NIPSCO's transmission and distribution system changes  
12 and as new or growing customers are accommodated. In the subsequent  
13 years, NIPSCO anticipates replacing or upgrading existing substation  
14 equipment including transformers, breakers, relays, disconnect switches  
15 and other associated equipment and adding new substations as  
16 demonstrated by the planning process. NIPSCO also anticipates re-  
17 conductoring existing circuits, replacing existing switches with increased  
18 capacity units, as well as adding new circuits. In addition to the specific  
19 line projects included in the Plan for 2021 and 2022, NIPSCO anticipates the

1 construction of one new 138 kV circuit in 2024 and five new 69 kV circuits  
2 – two in 2024 and three in 2025. In addition to the specific substation  
3 projects included in the Plan for 2021 and 2022, NIPSCO anticipates the  
4 construction of a total of three new distribution substations – one in 2024  
5 and two in 2026. NIPSCO has also identified the need to construct two new  
6 transmission substations which are currently planned in 2025 and 2026.  
7 NIPSCO anticipates and has included line construction work associated  
8 with substation source and feeder line extensions and upgrades necessary  
9 to integrate the new substations in the targeted growth areas.

10 **GRID MODERNIZATION PROJECTS**

11 **Q69. Please describe the general Grid Modernization category and the**  
12 **associated benefits.**

13 A69. NIPSCO developed a series of strategic initiatives designed to develop and  
14 enhance the NIPSCO electric system infrastructure. These initiatives are  
15 designed to achieve significant improvements in customer service and  
16 electric service reliability, as well as ensure NIPSCO is positioned to offer  
17 the services customers will expect from a modern utility. Part of the  
18 strategic initiatives includes a new, more robust telecommunications  
19 network, and implementation of modern sensing equipment (i.e., DA, SA,

1       and AMI). The telecommunications network and modern sensing  
2       equipment will work together with a new DSCADA system to create a  
3       network that can identify and isolate faults then restore customers (self-  
4       heal). Through the incorporation of Grid Modernization technologies,  
5       NIPSCO will be able to provide value to its customers through reduced  
6       outage severity and duration improving the customer experience.

7       **Q70. Please describe the Grid Modernization projects included in the 2021-**  
8       **2026 Electric Plan.**

9       A70. The Grid Modernization initiative of DA targets the enhanced reliability of  
10       NIPSCO's distribution circuits. This program includes replacement or  
11       addition of circuit reclosers and communication equipment. The DA  
12       program, which extends beyond 2026, will strategically place  
13       approximately 600-700 electronic reclosers on existing circuits over the span  
14       of the Grid Modernization initiative. During the course of the 2021-2026  
15       Electric Plan, approximately 515 electronic reclosers will be installed. These  
16       reclosers will be configured for either automated or manual operation  
17       aiming to split the circuits into segments that serve approximately 500  
18       customers. NIPSCO is employing a distribution network management  
19       system that utilizes a centralized model. Each substation will have a remote

1 terminal unit (RTU) updated or added as a data consolidation and control  
2 point for the new centralized model. DA is a dedicated program; however,  
3 these technologies are also being implemented on other aging  
4 infrastructure and deliverability projects.

5 The Grid Modernization initiative of SA targets the enhance reliability of  
6 NIPSCO's T&D system, as well as improves the visibility into the health of  
7 its substation assets. SA is comprised of three categories: transformer  
8 monitoring, breaker monitoring/control, and battery monitoring.  
9 Transformer monitors will allow for continuous oil analysis and  
10 temperature monitoring. Battery monitors will collect data and analyze the  
11 health of the batteries. Both of these monitors will allow NIPSCO to gain  
12 better health data on the assets allowing for more proactive maintenance  
13 and/or replacement. Distribution class relays on circuits that are receiving  
14 DA reclosers will be upgraded to microprocessor relays to better coordinate  
15 with the DA reclosers. Similar to the transformer and battery monitors,  
16 upgraded breaker relays will allow for better health data on the assets  
17 allowing for more proactive maintenance and/or replacement. SA is a  
18 dedicated program, however these technologies are also being  
19 implemented on other aging infrastructure and deliverability projects.

1       The new grid modernization design includes comprehensive upgrades to  
2       NIPSCO's legacy communication assets (e.g., towers, radios, fiber optics,  
3       and network configuration). The design employs high capacity digital  
4       microwave radio on lattice towers and monopoles, as well as fiber optics  
5       links configured in a multi-ring network topology. Using both microwave  
6       radio and fiber optics backhaul transport to interconnect and integrate the  
7       transport rings into the overall architecture, and establish contiguous,  
8       diverse communication paths to adjacent nodes and back to the NIPSCO  
9       system control centers. The design also provides for diverse, redundant  
10      paths back to the control centers, as well as provides visibility to  
11      distribution substations that do not currently have communications  
12      connectivity. The new DSCADA system is comprised of a combination of  
13      hardware and software that work together with NIPSCO personnel in a  
14      control center. These components allow for real-time data processing and  
15      supervisory controls to enact the DA and provide NIPSCO with valuable  
16      visibility into the status and condition of the transmission and distribution  
17      systems. Table 6 shows the Grid Modernization projects included in the  
18      2021-2026 Electric Plan.

19

1

**Table 6 – Grid Modernization Projects**

Transmission	
Project ID	Project ID
TSSA	Transmission Substation Automation
TSC	Transmission Substation – Communication
TLF	Transmission Line – Fiber Optic
Distribution	
Project ID	Project Name
DSSA	Distribution Substation Automation
DLDA	Distribution Line Automation
DSC1	Distribution Substation – Communication
DSC2	Distribution SCADA
DLAMI	Advanced Metering Infrastructure (AMI)

2

3 **Q71. Please describe how NIPSCO identified the types of Grid Modernization**  
4 **investments to include in the 2021-2026 Electric Plan and their benefits.**

5 A71. An evaluation was performed by NIPSCO that highlighted areas of  
6 investment that were foundational to the enhancement of NIPSCO’s system  
7 performance and ability to serve its customers.<sup>21</sup> Four of the investment  
8 categories identified were DA, SA, Communication, and AMI. NIPSCO  
9 then used a combination of third party vendors and collaborative sessions  
10 with its peer utilities to establish the performance baseline for  
11 implementation of these initiatives. DA, SA, and communication upgrades  
12 were part of Electric Plan 1, but not as dedicated programs. The description

---

<sup>21</sup> In 2019, NIPSCO assessed various system improvement and modernization efforts that were currently being explored or developed by industry leaders. This effort was performed in collaboration with a McKinsey & Company consulting team.



1 and justification for AMI investments are detailed by Witness Holtz.

2 **Q72. Please describe the process of evaluation, selection and prioritizing the**  
3 **DA investments.**

4 A72. The process of evaluating and prioritizing the implementation of DA  
5 investments is detailed in the Distribution Automation Program Business  
6 Case (Confidential Attachment 2-E). The report details methodology in  
7 developing an economical implementation plan which maximizes benefits  
8 to NIPSCO's customers.

9 As shown in the "Indiana Utility Regulatory Commission Electric Utility  
10 Reliability Report 2019," NIPSCO has maintained its reliability  
11 performance in the over the past five years but trails several of its Indiana  
12 peer utilities. The investment into the DA program for the TDSIC 2021-2026  
13 plan has the potential to positively impact NIPSCO's reliability  
14 performance, as does the broader grid modernization effort. While the  
15 IEEE indices referenced in this report have many drivers, weather events  
16 specific to NIPSCO's territory are a large contributor. With implementation  
17 of the DA program, there is the potential to reduce the impact of these  
18 events to NIPSCO's customers. The circuits were evaluated based upon  
19 customer count and circuit criticality (i.e., hospitals, schools). These circuits

1           were evaluated for segmentation through the deployment of an electronic  
2           recloser. These substations were cross-referenced with existing projects to  
3           ensure upgrades were performed in a timely and efficient manner without  
4           the risk of duplication of effort.

5       **Q73. Please describe the process of evaluation, selection, and prioritization for**  
6       **the SA investments.**

7       A73. As stated before, there are three components within the SA investments.  
8           The first component is associated with the DA program. Distribution  
9           breaker relays were chosen based on the need for enhanced protective  
10          scheme coordination between substation breakers and electronic line  
11          reclosers. This also has the benefit of identifying the approximate fault  
12          location which results in faster restoration times. This need is referenced in  
13          the Distribution Automation Program Business Case (Confidential  
14          Attachment 2-E). The second and third components of Battery and  
15          Transformer monitors were chosen to gain more insight and health data  
16          into our assets. This allows for continuous monitoring to allow for more  
17          proactive replacement. Battery monitors are being deployed within  
18          transmission substations. There are two types of transformer monitors  
19          included in this initiative. The first type of transformer monitor will bring

1 back data points such as temperature allowing for more efficient asset  
2 operation during periods of heavy load through predictive cooling. It also  
3 has the ability to calculate equivalent loss of life from its event history.  
4 These are being deployed on 10 MVA units or larger as they are maintained  
5 or replaced. The second is an online monitor that allows faults to be  
6 detected as early as possible by continuously assessing the levels of harmful  
7 gases in the transformer oil. This second type of monitor will be installed  
8 on our largest transmission transformers.

9 **Q74. Please describe the process of evaluation, selection and prioritization for**  
10 **the Communication investments.**

11 A74. The Communication network upgrade and expansion planning required  
12 external support due to the complexity of future system needs. S&L was  
13 engaged to audit NIPSCO's current communication network, review  
14 current industry best practices, and provide a report that outlines the needs  
15 of NIPSCO's network. This document is provided in the Long-Term  
16 Communications Plan (Confidential Attachment 2-F). The yearly upgrades  
17 start with the construction of the main backhaul centering around  
18 NIPSCO's communication hubs. The project plan targets substations  
19 (including microwave radio and fiber optics ring nodes) for integration into

1 a multiple ring network topology, which will be anchored at NIPSCO's  
2 operational control centers. As the 2021-2026 Electric Plan progresses the  
3 communication expansion build-out extends outward from NIPSCO  
4 control centers, moving toward the edge of the service territory. The  
5 Communication plan will extend past the 2021-2026 Electric Plan. Similar  
6 to the other Grid Modernization efforts, Communications will also be  
7 included in any new substation projects, as has been NIPSCO's practice in  
8 Electric Plan 1.

9 **Q75. Will NIPSCO's Grid Modernization be completed by the end of the 2021-**  
10 **2026 Electric Plan**

11 A75. No. NIPSCO's Grid Modernization plan is a multi-year initiative that will  
12 extend past the end of the 2021-2026 Electric Plan. NIPSCO is not seeking  
13 Commission approval for any portion of the Grid Modernization plan that  
14 is beyond 2026 in this filing.

15 **ECONOMIC DEVELOPMENT PROJECTS**

16 **Q76. Please describe the Economic Development projects included in the 2021-**  
17 **2026 Electric Plan.**

18 A76. As discussed by Witness Becker, the 2021-2026 Electric Plan provides for  
19 targeted economic development projects in the future, although none are

1           proposed at this time.

2    **EXECUTION OF THE 2021-2026 ELECTRIC PLAN**

3    **Q77. Please describe how NIPSCO's process for execution and management of**  
4           **the projects included in the 2021-2026 Electric Plan.**

5    A77. Attachment 2-G includes information supporting NIPSCO's execution and  
6           management of the project included in the 2021-2026 Electric Plan,  
7           including an overview of NIPSCO's (1) execution of the Plan, (2) process for  
8           managing the projects in the Plan, (3) process for managing costs in the  
9           Plan, and (4) project management principles.

10   **Q78. Please explain how NIPSCO has addressed risks associated with the**  
11           **execution of the 2021-2026 Electric Plan.**

12    A78. While any plan has a degree of execution risk, steps have been taken and  
13           plans have been put in place to mitigate risk. It is important to realize, that  
14           while the investments in the Plan are substantial, NIPSCO has experience  
15           completing these type of projects.

16           Safety is in the forefront as a design factor ensuring public safety and  
17           constructability and is also an integral part of project execution to ensure  
18           projects are completed without injury to employees or contract partners.

1 This is accomplished through training, onboarding, and job site  
2 observations. For most projects, project scopes are detailed two years in  
3 advance utilizing standard designs improving estimate accuracy. A  
4 resource plan is developed on an annual basis, leveraging internal and  
5 contract resources with a heavy reliance on unit pricing whenever practical.  
6 Material and inventory needs are forecasted and integrated in the sourcing  
7 strategy focusing on price and volume commitment, as well as product  
8 delivery and quality. These practices are used as a tool to better control  
9 commodity index price variations. Recognizing the Plan covers a 6-year  
10 period, it is not possible to completely mitigate increases in labor or  
11 commodities as market conditions change over time, but NIPSCO has taken  
12 appropriate steps to address these issues.

13 Effective project management processes and skills are important for  
14 efficient plan execution. NIPSCO has a Project Management Team with  
15 specific expertise in managing large projects and large scopes of work such  
16 a project groups. This team successfully managed the previous Electric  
17 Plan 1 and continues to gain experience and expertise utilizing industry  
18 standard project management techniques to ensure safety, schedule, scope  
19 and cost.

1 ELIGIBLE IMPROVEMENTS

2 **Q79. Are all of the projects included in NIPSCO's 2021-2026 Electric Plan**  
3 **undertaken for purposes of safety, reliability, grid modernization, or**  
4 **economic development?**

5 A79. Yes.

6 **Q80. Are any of the projects included in the 2021-2026 Electric Plan included**  
7 **in NIPSCO's current base rates?**

8 A80. No.

9 **Q81. Does the 2021-2026 Electric Plan provide the best estimate of the cost of**  
10 **the eligible improvements?**

11 A81. Yes. This is described in greater detail above and in the 2021-2026 TDSIC  
12 Investment Plan Cost Analysis (Confidential Attachment 2-C).

13 **Q82. Does the public convenience and necessity require or will require the**  
14 **eligible improvements included in the 2021-2026 Electric Plan?**

15 A82. Yes. The eligible improvements included in the 2021-2026 Electric Plan are  
16 required or will be required to maintain the safety, integrity, and reliability  
17 of NIPSCO's transmission and distribution systems consistent with the  
18 public convenience and necessity. This is further discussed by Witness

1           Becker.

2       **Q83. Are the estimated costs of the eligible transmission and distribution**  
3       **system improvements included in the 2021-2026 Electric Plan justified by**  
4       **incremental benefits attributable to the Plan?**

5       A83. Yes. This is described in greater detail above and in the Long-Term  
6       Investment Plan (Confidential Attachment 2-B).

7       **CONCLUSION**


8       **Q84. Does this conclude your prepared direct testimony?**

9       A84. Yes.



## VERIFICATION

I, Charles A. Vamos, Director, Electric T&D Engineering for Northern Indiana Public Service Company LLC, affirm under penalties of perjury that the foregoing representations are true and correct to the best of my knowledge, information and belief.

A handwritten signature in black ink, appearing to read "Ch. A. Vamos", written over a horizontal line.

Charles A. Vamos

Date: June 1, 2021

## NORTHERN INDIANA PUBLIC SERVICE COMPANY

### 6-YEAR ELECTRIC PLAN BY PROJECT CATEGORY

(A) Line No.	(B) Project Category	(C) 2021	(D) 2022	(E) 2023	(F) 2024	(G) 2025	(H) 2026	(I) 6-Year Total
	<b>Direct Capital</b>							
	<u>Transmission Project Category</u>							
1	Transmission Substations	\$26,096,870	\$39,608,052	\$57,910,125	\$60,200,669	\$53,860,233	\$54,852,316	\$292,528,265
2	Transmission Lines	\$14,501,950	\$41,690,816	\$22,276,258	\$46,049,322	\$47,760,270	\$68,286,845	\$240,950,370
3	<b>Total Transmission</b>	<b>\$40,598,820</b>	<b>\$81,298,868</b>	<b>\$80,186,383</b>	<b>\$106,249,991</b>	<b>\$101,620,503</b>	<b>\$123,139,161</b>	<b>\$533,478,635</b>
4	<u>Distribution Project Category</u>							
5	Underground Cable	\$13,652,531	\$20,632,620	\$18,142,533	\$17,380,921	\$16,172,420	\$17,659,875	\$103,255,991
6	Distribution Substations	\$22,361,757	\$52,065,812	\$63,216,937	\$55,231,981	\$69,847,399	\$63,804,727	\$326,528,613
7	Distribution Lines	\$28,711,340	\$68,559,440	\$67,687,589	\$96,366,259	\$89,252,100	\$82,775,448	\$433,352,176
8	<b>Total Distribution</b>	<b>\$64,725,628</b>	<b>\$141,257,872</b>	<b>\$149,047,059</b>	<b>\$168,979,161</b>	<b>\$175,271,919</b>	<b>\$164,240,050</b>	<b>\$863,136,780</b>
9								
10	<b>Total Direct Capital</b>	<b>\$105,324,448</b>	<b>\$222,556,740</b>	<b>\$229,233,442</b>	<b>\$275,229,152</b>	<b>\$276,892,422</b>	<b>\$287,379,211</b>	<b>\$1,396,615,415</b>
11	<b>Indirect Capital</b>	<b>\$13,692,179</b>	<b>\$28,932,376</b>	<b>\$29,800,350</b>	<b>\$35,779,789</b>	<b>\$35,996,017</b>	<b>\$37,359,301</b>	<b>\$181,560,012</b>
12	<b>AFUDC</b>	<b>\$3,570,498</b>	<b>\$7,544,672</b>	<b>\$7,771,017</b>	<b>\$9,330,269</b>	<b>\$9,386,653</b>	<b>\$9,742,161</b>	<b>\$47,345,270</b>
13	<b>Total Capital</b>	<b>\$122,587,125</b>	<b>\$259,033,788</b>	<b>\$266,804,809</b>	<b>\$320,339,210</b>	<b>\$322,275,092</b>	<b>\$334,480,673</b>	<b>\$1,625,520,697</b>
14	<b>Total O&amp;M</b>	<b>\$83,418</b>	<b>\$2,329,335</b>	<b>\$2,263,358</b>	<b>\$2,301,811</b>	<b>\$1,680,577</b>	<b>\$1,356,206</b>	<b>\$10,014,705</b>

## NORTHERN INDIANA PUBLIC SERVICE COMPANY

### 6-YEAR ELECTRIC PLAN BY FERC ACCOUNT

(A) Line No.	(B) FERC Account	(C) 2021	(D) 2022	(E) 2023	(F) 2024	(G) 2025	(H) 2026	(I) 6-Year Total
	<b>Direct Capital</b>							
	<u>Transmission</u>							
1	350 - Land & Land Rights	\$0	\$0	\$0	\$55,583	\$45,131	\$0	\$100,714
2	352 - Structures and Improvements	\$4,407,572	\$6,837,303	\$7,646,927	\$10,035,132	\$7,815,251	\$5,918,546	\$42,660,731
3	353 - Station Equipment	\$22,122,261	\$36,269,815	\$37,886,783	\$48,455,636	\$44,506,311	\$40,299,918	\$229,663,896
4	354 - Towers and Fixtures	\$3,577,174	\$5,153,625	\$8,535,615	\$14,703,666	\$12,269,637	\$6,972,125	\$51,211,842
5	355 - Poles and Fixtures	\$1,051,221	\$2,074,273	\$1,631,082	\$903,448	\$900,000	\$1,048,603	\$7,608,627
6	356 - Overhead Conductors and Devices	\$13,297,563	\$24,947,913	\$11,471,800	\$27,914,925	\$26,165,173	\$41,304,630	\$145,363,741
7	<b>Total Transmission</b>	\$44,455,791	\$75,282,929	\$67,172,207	\$102,068,390	\$91,701,503	\$95,543,822	\$476,609,551
	<u>Distribution</u>							
8	303 - Software	\$330,000	\$5,332,432	\$10,700,931	\$2,054,708	\$2,112,959	\$1,020,396	\$21,551,426
9	360 - Land & Land Rights	\$256,327	\$653,228	\$1,324,222	\$1,661,045	\$2,325,333	\$1,433,200	\$7,653,355
10	361 - Structures and Improvements	\$339,336	\$1,104,300	\$1,025,342	\$1,702,927	\$1,869,670	\$1,556,374	\$7,597,949
11	362 - Station Equipment	\$32,290,248	\$57,149,947	\$60,146,484	\$54,895,391	\$65,679,702	\$61,739,114	\$331,585,259
12	364 - Poles, Towers, and Fixtures	\$12,021,902	\$33,610,299	\$30,248,192	\$24,727,810	\$27,897,015	\$34,729,538	\$163,230,907
13	365 - Overhead Conductors and Devices	\$11,083,040	\$29,929,276	\$18,190,874	\$26,514,390	\$21,150,292	\$24,571,200	\$131,439,073
14	367 - Underground Conductors and Devices	\$2,126,579	\$3,702,846	\$3,199,725	\$3,512,624	\$3,135,359	\$3,468,820	\$19,088,217
15	368 - Line Transformers	\$351,750	\$1,037,193	\$1,059,413	\$1,258,924	\$1,363,569	\$1,332,532	\$6,395,683
16	370.2 - Meters	\$330,000	\$430,035	\$2,398,484	\$31,231,566	\$36,765,487	\$30,951,999	\$102,107,571
17	373 - Street Lighting and Signal Systems	\$854,228	\$1,986,399	\$0	\$0	\$0	\$0	\$2,840,627
18	391.2 - Hardware/Servers	\$0	\$2,150,175	\$1,660,489	\$0	\$0	\$0	\$3,810,664
19	397 - Communication Equipment	\$885,247	\$10,187,681	\$32,107,079	\$25,601,377	\$22,891,533	\$31,032,216	\$122,705,133
20	<b>Total Distribution</b>	\$60,868,657	\$147,273,811	\$162,061,235	\$173,160,762	\$185,190,919	\$191,835,389	\$920,005,864
21	<b>Total Direct Capital</b>	\$105,324,448	\$222,556,740	\$229,233,442	\$275,229,152	\$276,892,422	\$287,379,211	\$1,396,615,415
22	<b>Indirect Capital</b>	\$13,692,179	\$28,932,376	\$29,800,350	\$35,779,789	\$35,996,017	\$37,359,301	\$181,560,012
23	<b>AFUDC</b>	\$3,570,498	\$7,544,672	\$7,771,017	\$9,330,269	\$9,386,653	\$9,742,161	\$47,345,270
24	<b>Total Capital</b>	\$122,587,125	\$259,033,788	\$266,804,809	\$320,339,210	\$322,275,092	\$334,480,673	\$1,625,520,697

**NORTHERN INDIANA PUBLIC SERVICE COMPANY**  
**ELECTRIC 2021 PROJECT DETAIL - DIRECT CAPITAL DOLLARS ONLY**

(A)	(B)	(C)	(D)	(E)	(F)
Line No.	Project ID	Project Category	Project Driver	Project Title	Plan Project Cost (direct dollars)
		<b>Transmission System Investments</b>			
		<b>Transmission Substations</b>			
1	TSA1	Arresters - Transmission	Aging Infrastructure	Arrester Projects - Transmission	
2	TSB1	Batteries - Transmission	Aging Infrastructure	Battery & Charger Equipment Projects - Transmission	
3	TSPT1	Potential Transformers- Transmission	Aging Infrastructure	Potential Transformer Projects - Transmission	
4	TSSW1	Disconnects/Substation Switch Replacements	Aging Infrastructure	Substation Switch Projects - Transmission	
5	TSSA1	Transmission Substation Automation	Grid Modernization	Transmission Substation Automation	
6	TSRU29	Relay Upgrades	Aging Infrastructure	Fiber Optic - Green Acres to St. John - 13888	
7	TSRU58	Relay Upgrades	Aging Infrastructure	Relay & Breaker Upgrades - Dune Acres to Burns Ditch - 13836 N & 13836 S	
8	TSRU59	Relay Upgrades	Aging Infrastructure	Relay & Breaker Upgrades - Dune Acres to Mittal Burns Harbor - 13849 N & 13849 S	
9	TSRU60	Relay Upgrades	Aging Infrastructure	Relay & Breaker Upgrades - Dune Acres to Mittal Burns Harbor - 13848 N & 13848 S	
10	TSRU61	Relay Upgrades	Aging Infrastructure	Relay Upgrades - Green Acres to St John - 13888	
11	TSRU62	Relay Upgrades	Aging Infrastructure	Relay Upgrades - Stillwell to Plymouth - 13896	
12	TSRU67	Relay Upgrades	Aging Infrastructure	Relay Upgrade - Tower Road - #2 XFR	
13	TSRU69	Relay Upgrades	Aging Infrastructure	Relay & Breaker Upgrades - Miller to Beta Steel - 13842	
14	TSBRU19	Breaker Upgrades	Aging Infrastructure	Breaker Upgrade - St. John Upgrades (345kV & 138kV)	
15	TSBRU20	Breaker Upgrades	Aging Infrastructure	Breaker Upgrade - Dune Acres - #3 XFR BKR	
16	TSBRU22	Breaker Upgrades	Aging Infrastructure	Breaker Upgrade - Miller - 13810-42	
17	TSBRU27	Breaker Upgrades	Aging Infrastructure	Breaker Upgrade - Stillwell Upgrades (69kV)	
18	TSTU9	Transformer Upgrade/Replacement	Aging Infrastructure	Transformer Upgrade - Dune Acres #3	
19	TSNRS17	New/Rebuild Substations- Transmission	Aging Infrastructure	New/Rebuild Substation - Green Acres - #1 & #2 138/69kV Transformers; Breaker Upgrades (138kV & 69kV)	
20	TSNRS18	New/Rebuild Substations- Transmission	Aging Infrastructure	New/Rebuild Substation - New Michigan City Substation	
21	TSPC1	Substation Engineering- Transmission	Aging Infrastructure	Substation Pre-construction - Transmission	
22	TSE1	Substation Engineering- Transmission	Aging Infrastructure	Substation Engineering - Transmission	
23				<b>Total Transmission Substations</b>	
		<b>Transmission Lines</b>			
24	TLSW1	Line Switch Replacement	Aging Infrastructure	Line Switch Projects - Transmission	
25	TLST1	Steel Structure Program	Aging Infrastructure	Steel Structure Life Extension Projects - Transmission	
26	TLNRL6	New/Rebuild Line	Aging Infrastructure	Circuit 3465 Rebuild - 69kV Laporte JCT to Tee Lake	
27	TLNRL9	New/Rebuild Line	Aging Infrastructure	Circuit 3465 Rebuild - New Carlisle to Olive	
28	TLNRL19	New/Rebuild Line	Aging Infrastructure	Circuit Rebuild - Monticello - 6907 - Phase 2	
29	TLNRL21	New/Rebuild Line	Aging Infrastructure	Circuit Rebuild - Kosciusko - 6997 - Phase 2	
30	TLPC1	Line Engineering- Transmission	Aging Infrastructure	Line Pre-construction - Transmission	
31	TLE1	Line Engineering- Transmission	Aging Infrastructure	Line Engineering - Transmission	
32				<b>Total Transmission Lines</b>	
33		<b>Total Transmission Investment</b>			<b>\$40,598,820</b>

**NORTHERN INDIANA PUBLIC SERVICE COMPANY**  
**ELECTRIC 2021 PROJECT DETAIL - DIRECT CAPITAL DOLLARS ONLY**

(A) Line No.	(B) Project ID	(C) Project Category	(D) Project Driver	(E) Project Title	(F) Plan Project Cost (direct dollars)
		<b>Distribution System Investments</b>			
		<b>Underground Cable</b>			
34	DUG1	Underground Cable Replacement	Aging Infrastructure	Underground Cable Replacement Projects	
35				<b>Total Underground Cable</b>	
		<b>Distribution Substations</b>			
36	DSA1	Arresters - Distribution	Aging Infrastructure	Arrester Projects - Distribution	
37	DSB1	Batteries- Distribution	Aging Infrastructure	Battery & Charger Equipment Projects - Distribution	
38	DSSW1	Disconnects/Substation Switch Replacements	Aging Infrastructure	Substation Switch Projects - Distribution	
39	DSFC1	Feeder Cable	Aging Infrastructure	Substation Feeder Cable Projects - Distribution	
40	DSTU1	Transformer Upgrade/Replacement	Aging Infrastructure	Power Transformer Projects - Distribution	
41	DSSA1	Distribution Substation Automation	Grid Modernization	Distribution Substation Automation	
42	DSBRU24	Breaker/Recloser Upgrades	Aging Infrastructure	Breaker Upgrade - Michigan City - #11 Transformer Breaker 34kV	
43	DSBRU25	Breaker/Recloser Upgrades	Aging Infrastructure	Breaker Upgrades - Luchtman - 34-124, 34-125	
44	DSBRU28	Breaker/Recloser Upgrades	Aging Infrastructure	Breaker Upgrades - Division - Switchgear	
45	DSBRU33	Breaker/Recloser Upgrades	Aging Infrastructure	Breaker Upgrades - Monticello - Switchgear	
46	DSTU15	Transformer Upgrade/Replacement	Aging Infrastructure	Replace Transformer - Orchard Grove - #1 Transformer	
47	DSTU18	Transformer Upgrade/Replacement	Aging Infrastructure	Replace Transformer - Bourbon #2	
48	DSTU20	Transformer Upgrade/Replacement	Aging Infrastructure	Replace Transformer - Weirick #1	
49	DSTU26	Transformer Upgrade/Replacement	Deliverability	Howe Sub - #2 Transformer & #1 Volt Regs - Inc Capacity	
50	DSNRS26	New/Rebuild Substation - Distribution	Aging Infrastructure	Rebuild Substation - Munster - #3 & #4 Transformer 138/34kV and #3 Transformer Breaker	
51	DSNRS41	New/Rebuild Substation - Distribution	Aging Infrastructure	New/Rebuild Substation - Tod - #5 Transformer & Switchgear	
52	DSPC1	Substation Engineering- Distribution	Aging Infrastructure	Substation Pre-construction - Distribution	
53	DSE1	Substation Engineering- Distribution	Aging Infrastructure	Substation Engineering - Distribution	
54				<b>Total Distribution Substations</b>	
		<b>Distribution Lines</b>			
55	DLCP1	Circuit Performance Improvement	Aging Infrastructure	Circuit Performance Improvement Projects - Distribution	
56	DLWP1	Wood Poles	Aging Infrastructure	Pole Replacement Projects - Distribution	
57	DLSW1	Line Switch Replacement	Aging Infrastructure	Switches to Clear Incoming Lines Projects - Distribution	
58	DLSW2	Line Switch Replacement	Aging Infrastructure	Line Switch Projects - Distribution	
59	DLDA1	Distribution Line - Distribution Automation	Aging Infrastructure	Distribution Line Automation	
60	DLLED1	LED Street Lighting	Aging Infrastructure	LED Street Lighting	
61	DLAMI1	Advanced Metering Infrastructure (AMI)	Grid Modernization	Advanced Metering Infrastructure (AMI)	
62	DLNRL24	New/Rebuild Line	Aging Infrastructure	Circuit 3433 Rebuild - Grandview to Bendix West Side	
63	DLNRL35	New/Rebuild Line	Aging Infrastructure	Circuit Rebuild - Roxana - 12-316	
64	DLNRL42	New/Rebuild Line	Aging Infrastructure	Circuit Rebuild - South Hammond - 12-720	
65	DLNRL62	New/Rebuild Line	Aging Infrastructure	Circuit Rebuild - Laporte 1264	
66	DLNRL63	New/Rebuild Line	Aging Infrastructure	Circuit Rebuild - Woodmar 12-643	
67	DLPC1	Line Engineering- Distribution	Aging Infrastructure	Line Pre-construction - Distribution	
68	DLE1	Line Engineering- Distribution	Aging Infrastructure	Line Engineering - Distribution	
69				<b>Total Distribution Lines</b>	
70		<b>Total Distribution Investment</b>			
71		<b>Total T&amp;D Investment</b>			<b>\$105,324,448</b>
72		<b>Total O&amp;M Investment</b>			<b>\$83,418</b>

**NORTHERN INDIANA PUBLIC SERVICE COMPANY**  
**ELECTRIC 2022 PROJECT DETAIL - DIRECT CAPITAL DOLLARS ONLY**

(A)	(B)	(C)	(D)	(E)	(F)
Line No.	Project ID	Project Category	Project Driver	Project Title	Plan Project Cost (direct dollars)
		<b>Transmission System Investments</b>			
		<b>Transmission Substations</b>			
1	TSA1	Arresters - Transmission	Aging Infrastructure	Arrester Projects - Transmission	
2	TSB1	Batteries - Transmission	Aging Infrastructure	Battery & Charger Equipment Projects - Transmission	
3	TSPT1	Potential Transformers- Transmission	Aging Infrastructure	Potential Transformer Projects - Transmission	
4	TSSW1	Disconnects/Substation Switch Replacements	Aging Infrastructure	Substation Switch Projects - Transmission	
5	TSBRU46	Breaker Upgrades	Aging Infrastructure	Capacitor & Breaker Projects - Transmission	
6	TSC1	Transmission Substation - Communication	Grid Modernization	Comm Upgrade Projects - Transmission	
7	TSSA1	Transmission Substation Automation	Grid Modernization	Transmission Substation Automation	
8	TSRU2	Relay Upgrades	Aging Infrastructure	Annunciator Projects - Transmission	
9	TSRU63	Relay Upgrades	Aging Infrastructure	Relay Upgrades - South Prairie to Westwood (Duke) - 13883	
10	TSRU71	Relay Upgrades	Aging Infrastructure	Fiber Optic - 13806 Dune Acres to Burns Ditch	
11	TSRU75	Relay Upgrades	Aging Infrastructure	Relay Upgrade - Monticello to Springboro -13807	
12	TSBRU19	Breaker Upgrades	Aging Infrastructure	Breaker Upgrade - St. John Upgrades (345kV & 138kV)	
13	TSBRU29	Breaker Upgrades	Aging Infrastructure	Breaker Upgrade - Schahfer 34516 & 34521	
14	TSBRU31	Breaker Upgrades	Aging Infrastructure	Breaker Upgrade - Liberty Park 138kV Bus Tie, #5 XFR & #6 XFR (69kV)	
15	TSBRU36	Breaker Upgrades	Aging Infrastructure	Breaker Upgrade - Barton Lake 69-102, Bus Tie, #1 XFR, & Cap Bank	
16	TSBRU41	Breaker Upgrades	Aging Infrastructure	Breaker Upgrade - Starke 6905, 6919, 6961, 69kV Bus Tie, #1 XFR, & #2 XFR	
17	TSNRS13	New/Rebuild Substations- Transmission	Aging Infrastructure	Rebuild Substation - Maple - #2 138/69kV XFR and 69kV Cap Bank	
18	TSNRS18	New/Rebuild Substations- Transmission	Aging Infrastructure	New/Rebuild Substation - New Michigan City Substation	
19	TSPC1	Substation Engineering- Transmission	Aging Infrastructure	Substation Pre-construction - Transmission	
20	TSE1	Substation Engineering- Transmission	Aging Infrastructure	Substation Engineering - Transmission	
21				<b>Total Transmission Substations</b>	
		<b>Transmission Lines</b>			
22	TLSW1	Line Switch Replacement	Aging Infrastructure	Line Switch Projects - Transmission	
23	TLST1	Steel Structure Program	Aging Infrastructure	Steel Structure Life Extension Projects - Transmission	
24	TLF1	Transmission Line - Fiber Optic	Grid Modernization	Comm Upgrade Fiber - Chicago Avenue to U.S.Steel - Stockton	
25	TLF2	Transmission Line - Fiber Optic	Grid Modernization	Comm Upgrade Fiber - Corporate Information Service Center - Microwave to Munster	
26	TLF3	Transmission Line - Fiber Optic	Grid Modernization	Comm Upgrade Fiber - Corporate Information Service Center - Microwave to NiSource HQ (MW Only)	
27	TLNRL18	New/Rebuild Line	Deliverability	Circuit 6972 Rebuild - South Chalmers - Oakdale	
28	TLNRL26	New/Rebuild Line	Aging Infrastructure	Circuit Rebuild - Kosciusko - 6998	
29	TLNRL28	New/Rebuild Line	Deliverability	Circuit Rebuild - Kosciusko - 6982	
30	TLNRL29	New/Rebuild Line	Deliverability	Circuit Rebuild - Palmira - Extend 2nd 69kV Source Line	
31	TLPC1	Line Engineering- Transmission	Aging Infrastructure	Line Pre-construction - Transmission	
32	TLE1	Line Engineering- Transmission	Aging Infrastructure	Line Engineering - Transmission	
33				<b>Total Transmission Lines</b>	
34		<b>Total Transmission Investment</b>			<b>\$81,298,868</b>

**NORTHERN INDIANA PUBLIC SERVICE COMPANY**  
**ELECTRIC 2022 PROJECT DETAIL - DIRECT CAPITAL DOLLARS ONLY**

(A)	(B)	(C)	(D)	(E)	(F)
Line No.	Project ID	Project Category	Project Driver	Project Title	Plan Project Cost (direct dollars)
		<b>Distribution System Investments</b>			
		<b>Underground Cable</b>			
35	DUG1	Underground Cable Replacement	Aging Infrastructure	Underground Cable Replacement Projects	
36				<b>Total Underground Cable</b>	
		<b>Distribution Substations</b>			
37	DSA1	Arresters - Distribution	Aging Infrastructure	Arrester Projects - Distribution	
38	DSB1	Batteries- Distribution	Aging Infrastructure	Battery & Charger Equipment Projects - Distribution	
39	DSPT1	Potential Transformers- Distribution	Aging Infrastructure	Potential Transformer Projects - Distribution	
40	DSSW1	Disconnects/Substation Switch Replacements	Aging Infrastructure	Substation Switch Projects - Distribution	
41	DSFC1	Feeder Cable	Aging Infrastructure	Substation Feeder Cable Projects - Distribution	
42	DSC1	Distribution Substation - Communication	Grid Modernization	Comm Upgrade Projects - Distribution	
43	DSC2	Distribution Substation - Communication	Grid Modernization	New Distribution SCADA	
44	DSSA1	Distribution Substation Automation	Grid Modernization	Distribution Substation Automation	
45	DSBRU30	Breaker/Recloser Upgrades	Aging Infrastructure	Breaker Upgrades - Gibson - Switchgear	
46	DSBRU39	Breaker/Recloser Upgrades	Aging Infrastructure	Breaker Upgrade - Munster - 3428, 3429, 3430, 3431	
47	DSTU21	Transformer Upgrade/Replacement	Aging Infrastructure	Replace Transformer - Wolf Lake - #2 138/34kV XFR	
48	DSNRS34	New/Rebuild Substation - Distribution	Deliverability	Crocker Substation New Recloser & Incoming Lines	
49	DSNRS35	New/Rebuild Substation - Distribution	Deliverability	New/Rebuild Substation - Creston - Add 2nd Transformer, #1 & #2 Voltage Regulators, Dbl. Switchgear	
50	DSNRS36	New/Rebuild Substation - Distribution	Aging Infrastructure	Rebuild Substation - Illinois - #1 69/12kV XFR and Switchgear Breakers	
51	DSNRS39	New/Rebuild Substation - Distribution	Aging Infrastructure	New/Rebuild Substation - Hanover - #1 & #2 Transformer with Dbl. Switchgear	
52	DSNRS42	New/Rebuild Substation - Distribution	Deliverability	New/Rebuild Substation - Palmira Sub - Add 2nd Transformer, New Dbl. Switchgear	
53	DSNRS43	New/Rebuild Substation - Distribution	Aging Infrastructure	New/Rebuild Substation - Johnson - Switchgear	
54	DSNRS44	New/Rebuild Substation - Distribution	Deliverability	New Heron Lake - New 69/12.5kV Substation	
55	DSPC1	Substation Engineering- Distribution	Aging Infrastructure	Substation Pre-construction - Distribution	
56	DSE1	Substation Engineering- Distribution	Aging Infrastructure	Substation Engineering - Distribution	
57				<b>Total Distribution Substations</b>	
		<b>Distribution Lines</b>			
58	DLCP1	Circuit Performance Improvement	Aging Infrastructure	Circuit Performance Improvement Projects - Distribution	
59	DLWP1	Wood Poles	Aging Infrastructure	Pole Replacement Projects - Distribution	
60	DLSW1	Line Switch Replacement	Aging Infrastructure	Switches to Clear Incoming Lines Projects - Distribution	
61	DLSW2	Line Switch Replacement	Aging Infrastructure	Line Switch Projects - Distribution	
62	DLDA1	Distribution Line - Distribution Automation	Aging Infrastructure	Distribution Line Automation	
63	DLLED1	LED Street Lighting	Aging Infrastructure	LED Street Lighting	
64	DLAMI1	Advanced Metering Infrastructure (AMI)	Grid Modernization	Advanced Metering Infrastructure (AMI)	
65	DLNRL50	New/Rebuild Line	Aging Infrastructure	Circuit Rebuild - Lindbergh - 12-299	
66	DLNRL52	New/Rebuild Line	Aging Infrastructure	Circuit Rebuild - S Hammond - 12-719	
67	DLNRL58	New/Rebuild Line	Aging Infrastructure	Circuit Rebuild - Ainsworth 12-508	
68	DLNRL59	New/Rebuild Line	Aging Infrastructure	Circuit Rebuild - Johnson 12-563	
69	DLNRL60	New/Rebuild Line	Aging Infrastructure	Circuit Rebuild - 120th St 12-572	
70	DLNRL61	New/Rebuild Line	Aging Infrastructure	Circuit Rebuild - Madison 12-625	
71	DLNRL78	New/Rebuild Line	Deliverability	Circuit Rebuild - Crocker New Circuit - Existing Line Reconductor	

**NORTHERN INDIANA PUBLIC SERVICE COMPANY  
ELECTRIC 2022 PROJECT DETAIL - DIRECT CAPITAL DOLLARS ONLY**

(A)	(B)	(C)	(D)	(E)	(F)	
Line No.	Project ID	Project Category	Project Driver	Project Title	Plan Project Cost (direct dollars)	
72	DLNRL79	New/Rebuild Line	Deliverability	Bristol 12-111 / Bonneyville 12-706 Reconductor		
73	DLNRL85	New/Rebuild Line	Deliverability	Circuit Rebuild - Palmira - New 12.5kV Circuit Extension		
74	DLNRL86	New/Rebuild Line	Deliverability	Broadmoor Cir. 12-502 & Fisher 12-294 - Reconductor		
75	DLNRL87	New/Rebuild Line	Deliverability	Center Sub 12-270 - Circuit Reconductor - 0.6 miles w/69kV Overbuild		
76	DLNRL88	New/Rebuild Line	Deliverability	Heron Lake Substation - Line Taps - Ext. 69kV Source and 12.5kV Feeder Lines		
77	DLPC1	Line Engineering- Distribution	Aging Infrastructure	Line Pre-construction - Distribution		
78	DLE1	Line Engineering- Distribution	Aging Infrastructure	Line Engineering - Distribution		
79				<b>Total Distribution Lines</b>		
80		<b>Total Distribution Investment</b>				<b>\$141,257,872</b>
81		<b>Total T&amp;D Investment</b>				<b>\$222,556,740</b>
82		<b>Total O&amp;M Investment</b>			<b>\$2,329,335</b>	



**NORTHERN INDIANA PUBLIC SERVICE COMPANY  
ELECTRIC 2023 PROJECT DETAIL - DIRECT CAPITAL DOLLARS ONLY**

(A) Line No.	(B) Project ID	(C) Project Category	(D) Project Driver	(E) Project Title	(F) Plan Project Cost (direct dollars)
		<b>Transmission System Investments</b>			
		<b>Transmission Substations</b>			
1	TSA1	Arresters - Transmission	Aging Infrastructure	Arrester Projects - Transmission	
2	TSB1	Batteries - Transmission	Aging Infrastructure	Battery & Charger Equipment Projects - Transmission	
3	TSPT1	Potential Transformers- Transmission	Aging Infrastructure	Potential Transformer Projects - Transmission	
4	TSSW1	Disconnects/Substation Switch Replacements	Aging Infrastructure	Substation Switch Projects - Transmission	
5	TSBRU46	Breaker Upgrades	Aging Infrastructure	Capacitor & Breaker Projects - Transmission	
6	TSC1	Transmission Substation - Communication	Grid Modernization	Comm Upgrade Projects - Transmission	
7	TSSA1	Transmission Substation Automation	Grid Modernization	Transmission Substation Automation	
8	TSRU76	Relay Upgrades	Aging Infrastructure	Relay Upgrade - WCE to Praxair # 6 - 13801	
9	TSRU79	Relay Upgrades	Aging Infrastructure	Circuit Protection Upgrade - 13879 Dune Acres to Beta Steel	
10	TSRU80	Relay Upgrades	Aging Infrastructure	Circuit Protection Upgrade - 13806 Dune Acres to Aetna	
11	TSBRU26	Breaker Upgrades	Aging Infrastructure	Breaker Upgrade - East Winamac Upgrades (69kV)	
12	TSBRU30	Breaker Upgrades	Aging Infrastructure	Breaker Upgrade - Chicago Ave. 138104, 13811, 13829, 13831, 13833-104, & 13811-29	
13	TSBRU33	Breaker Upgrades	Aging Infrastructure	Breaker Upgrade - Plymouth 13819-#1 & 13819-21	
14	TSNRS19	New/Rebuild Substations- Transmission	Deliverability	New Marktown 138kV Substation	
15	TSNRS20	New/Rebuild Substations- Transmission	Aging Infrastructure	New/Rebuild Substation - Sheffield - 345/138kV XFR & 13804-#2, 13804-78, 13877-78, & 13893-#2 BRKS	
16	TSPC1	Substation Engineering- Transmission	Aging Infrastructure	Substation Pre-construction - Transmission	
17	TSE1	Substation Engineering- Transmission	Aging Infrastructure	Substation Engineering - Transmission	
18				<b>Total Transmission Substations</b>	
		<b>Transmission Lines</b>			
19	TLSW1	Line Switch Replacement	Aging Infrastructure	Line Switch Projects - Transmission	
20	TLST1	Steel Structure Program	Aging Infrastructure	Steel Structure Life Extension Projects - Transmission	
21	TLF5	Transmission Line - Fiber Optic	Grid Modernization	Comm Upgrade Fiber - NiSource HQ (MW Only) to Tie St. John to Green Acres	
22	TLF6	Transmission Line - Fiber Optic	Grid Modernization	Comm Upgrade Fiber - Plymouth to Burr Oak	
23	TLNRL22	New/Rebuild Line	Deliverability	Circuit Rebuild - Lagrange - 6980	
24	TLNRL28	New/Rebuild Line	Deliverability	Circuit Rebuild - Kosciusko - 6982	
25	TLPC1	Line Engineering- Transmission	Aging Infrastructure	Line Pre-construction - Transmission	
26	TLE1	Line Engineering- Transmission	Aging Infrastructure	Line Engineering - Transmission	
27				<b>Total Transmission Lines</b>	
28		<b>Total Transmission Investment</b>			<b>\$80,186,383</b>

**NORTHERN INDIANA PUBLIC SERVICE COMPANY**  
**ELECTRIC 2023 PROJECT DETAIL - DIRECT CAPITAL DOLLARS ONLY**

(A)	(B)	(C)	(D)	(E)	(F)
Line No.	Project ID	Project Category	Project Driver	Project Title	Plan Project Cost (direct dollars)
		<b>Distribution System Investments</b>			
		<b>Underground Cable</b>			
29	DUG1	Underground Cable Replacement	Aging Infrastructure	Underground Cable Replacement Projects	
30				<b>Total Underground Cable</b>	
		<b>Distribution Substations</b>			
31	DSA1	Arresters - Distribution	Aging Infrastructure	Arrester Projects - Distribution	
32	DSB1	Batteries- Distribution	Aging Infrastructure	Battery & Charger Equipment Projects - Distribution	
33	DSPT1	Potential Transformers- Distribution	Aging Infrastructure	Potential Transformer Projects - Distribution	
34	DSSW1	Disconnects/Substation Switch Replacements	Aging Infrastructure	Substation Switch Projects - Distribution	
35	DSC1	Distribution Substation - Communication	Grid Modernization	Comm Upgrade Projects - Distribution	
36	DSC2	Distribution Substation - Communication	Grid Modernization	New Distribution SCADA	
37	DSSA1	Distribution Substation Automation	Grid Modernization	Distribution Substation Automation	
38	DSBRU34	Breaker/Recloser Upgrades	Aging Infrastructure	Breaker Upgrade - Southlake - Switchgear	
39	DSBRU36	Breaker/Recloser Upgrades	Aging Infrastructure	Breaker Upgrade - Aetna - 3475, 34kV N. Bus, 34kV S. Bus	
40	DSBRU47	Breaker/Recloser Upgrades	Deliverability	Maple Sub - New 12.5kV Circuit Position	
41	DSNRS29	New/Rebuild Substation - Distribution	Aging Infrastructure	Rebuild Substation - Griffith - #1 Transformer & Switchgear	
42	DSNRS31	New/Rebuild Substation - Distribution	Aging Infrastructure	Rebuild Substation - Woodmar - #1 Transformer & Switchgear	
43	DSNRS45	New/Rebuild Substation - Distribution	Aging Infrastructure	New/Rebuild Substation - Novak Road - #1 Transformer & Switchgear	
44	DSNRS46	New/Rebuild Substation - Distribution	Deliverability	New/Rebuild Substation - Pidco - #1 69/12kV Transformer & Add Second Transformer and Switchgear	
45	DSNRS47	New/Rebuild Substation - Distribution	Aging Infrastructure	New/Rebuild Substation - Schererville - #1 & #2 Transformers and Switchgears	
46	DSPC1	Substation Engineering- Distribution	Aging Infrastructure	Substation Pre-construction - Distribution	
47	DSE1	Substation Engineering- Distribution	Aging Infrastructure	Substation Engineering - Distribution	
48				<b>Total Distribution Substations</b>	
		<b>Distribution Lines</b>			
49	DLCP1	Circuit Performance Improvement	Aging Infrastructure	Circuit Performance Improvement Projects - Distribution	
50	DLWP1	Wood Poles	Aging Infrastructure	Pole Replacement Projects - Distribution	
51	DLSW2	Line Switch Replacement	Aging Infrastructure	Line Switch Projects - Distribution	
52	DLDA1	Distribution Line - Distribution Automation	Aging Infrastructure	Distribution Line Automation	
53	DLAM1	Advanced Metering Infrastructure (AMI)	Grid Modernization	Advanced Metering Infrastructure (AMI)	
54	DLNRL53	New/Rebuild Line	Aging Infrastructure	Circuit Rebuild - N Webster - 12-159	
55	DLNRL57	New/Rebuild Line	Aging Infrastructure	Circuit Rebuild - Tod 12-457	
56	DLNRL64	New/Rebuild Line	Aging Infrastructure	Circuit Rebuild - Elliot 12-750	
57	DLNRL68	New/Rebuild Line	Aging Infrastructure	Circuit Rebuild - Decatur - 1209	
58	DLNRL89	New/Rebuild Line	Deliverability	Lines to Support Pidco Substation	
59	DLNRL90	New/Rebuild Line	Deliverability	Maple Sub - New 12.5kV Circuit Line Extension	
60	DLNRL108	New/Rebuild Line	Deliverability	Circuit Rebuild - Court - Extend New 12.5kV Circuit	
61	DLPC1	Line Engineering- Distribution	Aging Infrastructure	Line Pre-construction - Distribution	
62	DLE1	Line Engineering- Distribution	Aging Infrastructure	Line Engineering - Distribution	
63				<b>Total Distribution Lines</b>	
64		<b>Total Distribution Investment</b>			<b>\$149,047,059</b>
65		<b>Total T&amp;D Investment</b>			<b>\$229,233,442</b>
66		<b>Total O&amp;M Investment</b>			<b>\$2,263,358</b>

**NORTHERN INDIANA PUBLIC SERVICE COMPANY**  
**ELECTRIC 2024 PROJECT DETAIL - DIRECT CAPITAL DOLLARS ONLY**

(A)	(B)	(C)	(D)	(E)	(F)
Line No.	Project ID	Project Category	Project Driver	Project Title	Plan Project Cost (direct dollars)
		<b>Transmission System Investments</b>			
		<b>Transmission Substations</b>			
1	TSA1	Arresters - Transmission	Aging Infrastructure	Arrester Projects - Transmission	
2	TSB1	Batteries - Transmission	Aging Infrastructure	Battery & Charger Equipment Projects - Transmission	
3	TSPT1	Potential Transformers- Transmission	Aging Infrastructure	Potential Transformer Projects - Transmission	
4	TSSW1	Disconnects/Substation Switch Replacements	Aging Infrastructure	Substation Switch Projects - Transmission	
5	TSBRU46	Breaker Upgrades	Aging Infrastructure	Capacitor & Breaker Projects - Transmission	
6	TSC1	Transmission Substation - Communication	Grid Modernization	Comm Upgrade Projects - Transmission	
7	TSSA1	Transmission Substation Automation	Grid Modernization	Transmission Substation Automation	
8	TSRU70	Relay Upgrades	Deliverability	Relay & Breaker Upgrades - South Chalmers - Oakdale - 6971 and 6972	
9	TSRU81	Relay Upgrades	Aging Infrastructure	Relay Upgrade - Oakdale - 69kV Bus	
10	TSRU82	Relay Upgrades	Aging Infrastructure	Relay Upgrade - R. M. Schahfer - 138kV Bus	
11	TSRU83	Relay Upgrades	Aging Infrastructure	Circuit Protection Upgrade - 13890 Mittal #8 to Chicago Ave.	
12	TSRU84	Relay Upgrades	Aging Infrastructure	Relay Upgrade - R. M. Schahfer - 345kV Bus	
13	TSBRU24	Breaker Upgrades	Aging Infrastructure	Breaker Upgrade - Northport Upgrades (138kV & 69kV)	
14	TSBRU30	Breaker Upgrades	Aging Infrastructure	Breaker Upgrade - Chicago Ave. 138104, 13811, 13829, 13831, 13833-104, & 13811-29	
15	TSBRU32	Breaker Upgrades	Aging Infrastructure	Breaker Upgrade - Miller 13822	
16	TSBRU47	Breaker Upgrades	Aging Infrastructure	Breaker Upgrade - Kenwood - 138kV Bus Tie	
17	TSNRS19	New/Rebuild Substations- Transmission	Deliverability	New Marktown 138kV Substation	
18	TSNRS21	New/Rebuild Substations- Transmission	Deliverability	New St. John 138kV-69kV Substation	
19	TSNRS22	New/Rebuild Substations- Transmission	Deliverability	Veterans Hwy Sub - Add Automated 69kV Primary Changeover	
20	TSPC1	Substation Engineering- Transmission	Aging Infrastructure	Substation Pre-construction - Transmission	
21	TSE1	Substation Engineering- Transmission	Aging Infrastructure	Substation Engineering - Transmission	
22				<b>Total Transmission Substations</b>	
		<b>Transmission Lines</b>			
23	TLW1	Line Switch Replacement	Aging Infrastructure	Line Switch Projects - Transmission	
24	TLST1	Steel Structure Program	Aging Infrastructure	Steel Structure Life Extension Projects - Transmission	
25	TLF7	Transmission Line - Fiber Optic	Grid Modernization	Comm Upgrade Fiber - Broadway to Tie St. John to Green Acres	
26	TLF8	Transmission Line - Fiber Optic	Grid Modernization	Comm Upgrade Fiber - Corporate Information Service Center - Microwave to Roxana	
27	TLF9	Transmission Line - Fiber Optic	Grid Modernization	Comm Upgrade Fiber - Leesburg to Tie Burr Oak to Hiple	
28	TLF10	Transmission Line - Fiber Optic	Grid Modernization	Comm Upgrade Fiber - Marktown to Mittal Steel Indiana Harbor (East) #7	
29	TLF11	Transmission Line - Fiber Optic	Grid Modernization	Comm Upgrade Fiber - Mittal Steel Indiana Harbor (East) #5 to Mittal Steel Indiana Harbor (East) #7	
30	TLF12	Transmission Line - Fiber Optic	Grid Modernization	Comm Upgrade Fiber - Praxair #1 - East Chicago to Marktown	
31	TLF13	Transmission Line - Fiber Optic	Grid Modernization	Comm Upgrade Fiber - Praxair #3 - Lakeside to Tie Chicago Ave. to U.S.Steel Corp - Stockton	
32	TLF14	Transmission Line - Fiber Optic	Grid Modernization	Comm Upgrade Fiber - Pullman Standard to Tie Corporate Information Service Center - Microwave to Roxana	
33	TLF15	Transmission Line - Fiber Optic	Grid Modernization	Comm Upgrade Fiber - Sheffield to Marktown	
34	TLF16	Transmission Line - Fiber Optic	Grid Modernization	Comm Upgrade Fiber - St. John to R.M.Schahfer	
35	TLF17	Transmission Line - Fiber Optic	Grid Modernization	Comm Upgrade Fiber - Taney to Lake George	

## NORTHERN INDIANA PUBLIC SERVICE COMPANY ELECTRIC 2024 PROJECT DETAIL - DIRECT CAPITAL DOLLARS ONLY

(A)	(B)	(C)	(D)	(E)	(F)
Line No.	Project ID	Project Category	Project Driver	Project Title	Plan Project Cost (direct dollars)
36	TLNRL30	New/Rebuild Line	Deliverability	Circuit Rebuild - New 138kV Line & 6990 - Hiple to Northport	
37	TLNRL31	New/Rebuild Line	Deliverability	Liberty Park 6901 - Ext. to Veterans Hwy Sub	
38	TLNRL32	New/Rebuild Line	Deliverability	New Lines 69kV at St John Transmission Substation 69-116 & 69-117	
39	TLPC1	Line Engineering- Transmission	Aging Infrastructure	Line Pre-construction - Transmission	
40	TLE1	Line Engineering- Transmission	Aging Infrastructure	Line Engineering - Transmission	
41				<b>Total Transmission Lines</b>	
42		<b>Total Transmission Investment</b>			

**NORTHERN INDIANA PUBLIC SERVICE COMPANY**  
**ELECTRIC 2024 PROJECT DETAIL - DIRECT CAPITAL DOLLARS ONLY**

(A)	(B)	(C)	(D)	(E)	(F)
Line No.	Project ID	Project Category	Project Driver	Project Title	Plan Project Cost (direct dollars)
		<b>Distribution System Investments</b>			
		<b>Underground Cable</b>			
43	DUG1	Underground Cable Replacement	Aging Infrastructure	Underground Cable Replacement Projects	
44				<b>Total Underground Cable</b>	
		<b>Distribution Substations</b>			
45	DSA1	Arresters - Distribution	Aging Infrastructure	Arrester Projects - Distribution	
46	DSB1	Batteries- Distribution	Aging Infrastructure	Battery & Charger Equipment Projects - Distribution	
47	DSPT1	Potential Transformers- Distribution	Aging Infrastructure	Potential Transformer Projects - Distribution	
48	DSSW1	Disconnects/Substation Switch Replacements	Aging Infrastructure	Substation Switch Projects - Distribution	
49	DSC1	Distribution Substation - Communication	Grid Modernization	Comm Upgrade Projects - Distribution	
50	DSC2	Distribution Substation - Communication	Grid Modernization	New Distribution SCADA	
51	DSSA1	Distribution Substation Automation	Grid Modernization	Distribution Substation Automation	
52	DSRU9	Relay Upgrades	Aging Infrastructure	Relay Upgrade - R.M.Schahfer - #1 XFR	
53	DSBRU31	Breaker/Recloser Upgrades	Aging Infrastructure	Breaker Upgrades - Hyde Park - Switchgear	
54	DSBRU37	Breaker/Recloser Upgrades	Aging Infrastructure	Breaker Upgrade - Kenwood 34kV Upgrades	
55	DSBRU42	Breaker/Recloser Upgrades	Aging Infrastructure	Breaker Upgrade - Liable - Switchgear	
56	DSTU22	Transformer Upgrade/Replacement	Aging Infrastructure	Replace Transformer - Flint Lake - #8 138/12kV XFR	
57	DSTU24	Transformer Upgrade/Replacement	Deliverability	Transformer Replacement - Midway Sub - #1 XFR - Increase Capacity	
58	DSTU25	Transformer Upgrade/Replacement	Aging Infrastructure	Replace Transformer - Medaryville - #2 69/12kV XFR	
59	DSTU28	Transformer Upgrade/Replacement	Deliverability	Pine Creek Sub - #2 XFR - Add 2nd Set of Voltage Regulators	
60	DSTU29	Transformer Upgrade/Replacement	Deliverability	Fowler Sub - #2 XFR - Add 2nd Set of Voltage Regulators	
61	DSTU30	Transformer Upgrade/Replacement	Deliverability	Horn Ditch - Add 2nd Transformer & Upgrade 12.5kV Switchgear	
62	DSNRS22	New/Rebuild Substation - Distribution	Aging Infrastructure	Rebuild Substation - Lowell - #1 Transformer and #1 Switchgear & #2 Switchgear	
63	DSNRS48	New/Rebuild Substation - Distribution	Deliverability	New Winfield 69/12kV Substation	
64	DSNRS49	New/Rebuild Substation - Distribution	Aging Infrastructure	New/Rebuild Substation - Woodland Park - #1 Transformer & Switchgear	
65	DSPC1	Substation Engineering- Distribution	Aging Infrastructure	Substation Pre-construction - Distribution	
66	DSE1	Substation Engineering- Distribution	Aging Infrastructure	Substation Engineering - Distribution	
67				<b>Total Distribution Substations</b>	
		<b>Distribution Lines</b>			
68	DLCP1	Circuit Performance Improvement	Aging Infrastructure	Circuit Performance Improvement Projects - Distribution	
69	DLWP1	Wood Poles	Aging Infrastructure	Pole Replacement Projects - Distribution	
70	DLSW2	Line Switch Replacement	Aging Infrastructure	Line Switch Projects - Distribution	
71	DLDA1	Distribution Line - Distribution Automation	Aging Infrastructure	Distribution Line Automation	
72	DLAMI1	Advanced Metering Infrastructure (AMI)	Grid Modernization	Advanced Metering Infrastructure (AMI)	
73	DLNRL65	New/Rebuild Line	Aging Infrastructure	Circuit Rebuild - Plymouth 1221	
74	DLNRL67	New/Rebuild Line	Aging Infrastructure	Circuit Rebuild - Liable 12-332	
75	DLNRL70	New/Rebuild Line	Aging Infrastructure	Circuit Rebuild - Dyer - 12-249	
76	DLNRL73	New/Rebuild Line	Aging Infrastructure	Circuit Rebuild - Laporte - 1265	
77	DLNRL76	New/Rebuild Line	Aging Infrastructure	Circuit Rebuild - S. Hammond - 12-524	
78	DLNRL91	New/Rebuild Line	Deliverability	Horn Ditch Sub - 2nd 69kV Source Line	
79	DLNRL92	New/Rebuild Line	Deliverability	Horn Ditch Sub - 69kV and 12.5kV Lines	
80	DLNRL93	New/Rebuild Line	Deliverability	Hanover 12-453 - Reconductor	

**NORTHERN INDIANA PUBLIC SERVICE COMPANY  
ELECTRIC 2024 PROJECT DETAIL - DIRECT CAPITAL DOLLARS ONLY**

(A)	(B)	(C)	(D)	(E)	(F)	
Line No.	Project ID	Project Category	Project Driver	Project Title	Plan Project Cost (direct dollars)	
81	DLNRL94	New/Rebuild Line	Deliverability	Cedar Lake 1207 & Hanover 12-453 - Reconductor		
82	DLNRL95	New/Rebuild Line	Deliverability	Lines to Support Winfield Substation - 69kV and 12.5kV Circuit Extensions		
83	DLNRL96	New/Rebuild Line	Deliverability	Rock Run 12-382 & Model 12-432 DA Tie - Increase Capacity		
84	DLNRL97	New/Rebuild Line	Aging Infrastructure	Circuit Rebuild - Broadway - 12-433		
85	DLNRL98	New/Rebuild Line	Aging Infrastructure	Circuit Rebuild - Broadway - 12-437		
86	DLPC1	Line Engineering- Distribution	Aging Infrastructure	Line Pre-construction - Distribution		
87	DLE1	Line Engineering- Distribution	Aging Infrastructure	Line Engineering - Distribution		
88				<b>Total Distribution Lines</b>		
89		<b>Total Distribution Investment</b>				<b>\$168,979,161</b>
90		<b>Total T&amp;D Investment</b>				<b>\$275,229,152</b>
91		<b>Total O&amp;M Investment</b>			<b>\$2,301,811</b>	



**NORTHERN INDIANA PUBLIC SERVICE COMPANY  
ELECTRIC 2025 PROJECT DETAIL - DIRECT CAPITAL DOLLARS ONLY**

(A) Line No.	(B) Project ID	(C) Project Category	(D) Project Driver	(E) Project Title	(F) Plan Project Cost (direct dollars)
		<b>Transmission System Investments</b>			
		<b>Transmission Substations</b>			
1	TSA1	Arresters - Transmission	Aging Infrastructure	Arrester Projects - Transmission	
2	TSB1	Batteries - Transmission	Aging Infrastructure	Battery & Charger Equipment Projects - Transmission	
3	TSPT1	Potential Transformers- Transmission	Aging Infrastructure	Potential Transformer Projects - Transmission	
4	TSSW1	Disconnects/Substation Switch Replacements	Aging Infrastructure	Substation Switch Projects - Transmission	
5	TSBRU46	Breaker Upgrades	Aging Infrastructure	Capacitor & Breaker Projects - Transmission	
6	TSC1	Transmission Substation - Communication	Grid Modernization	Comm Upgrade Projects - Transmission	
7	TSSA1	Transmission Substation Automation	Grid Modernization	Transmission Substation Automation	
8	TSRU85	Relay Upgrades	Aging Infrastructure	Relay Upgrade - Chicago Ave - 138kV Bus	
9	TSRU86	Relay Upgrades	Aging Infrastructure	Relay Upgrade - Flint Lake - #3 & #4 XFR 69kV	
10	TSRU87	Relay Upgrades	Aging Infrastructure	Relay Upgrade - Flint Lake - 138kV Bus	
11	TSRU88	Relay Upgrades	Aging Infrastructure	Relay Upgrade - Kosciusko - Bus 69kV	
12	TSRU89	Relay Upgrades	Aging Infrastructure	Relay Upgrade - Maple - Bus 69kV	
13	TSRU90	Relay Upgrades	Aging Infrastructure	Relay Upgrade - Munster - 138kV Bus	
14	TSRU91	Relay Upgrades	Aging Infrastructure	Relay Upgrade - Starke - #1 XFR 69kV	
15	TSBRU30	Breaker Upgrades	Aging Infrastructure	Breaker Upgrade - Chicago Ave. 138104, 13811, 13829, 13831, 13833-104, & 13811-29	
16	TSBRU48	Breaker Upgrades	Aging Infrastructure	Breaker Upgrade - Lake George Upgrades	
17	TSTU10	Transformer Upgrade/Replacement	Aging Infrastructure	Replace Transformer - Kreitzburg - #2 138/69kV XFR	
18	TSNRS23	New/Rebuild Substations- Transmission	Deliverability	Hager Sub - 2nd 69kV Source & Primary Changeover	
19	TSNRS24	New/Rebuild Substations- Transmission	Deliverability	New/Rebuild Substation - Menges Ditch	
20	TSPC1	Substation Engineering- Transmission	Aging Infrastructure	Substation Pre-construction - Transmission	
21	TSE1	Substation Engineering- Transmission	Aging Infrastructure	Substation Engineering - Transmission	
22				<b>Total Transmission Substations</b>	
		<b>Transmission Lines</b>			
23	TLSW1	Line Switch Replacement	Aging Infrastructure	Line Switch Projects - Transmission	
24	TLST1	Steel Structure Program	Aging Infrastructure	Steel Structure Life Extension Projects - Transmission	
25	TLF18	Transmission Line - Fiber Optic	Grid Modernization	Comm Upgrade Fiber - Gary Avenue to Tie Roxana to Chicago Avenue	
26	TLF19	Transmission Line - Fiber Optic	Grid Modernization	Comm Upgrade Fiber - Green Acres to Tower Road	
27	TLF20	Transmission Line - Fiber Optic	Grid Modernization	Comm Upgrade Fiber - Hendricks to U.S.Steel Corp - Stockton	
28	TLF21	Transmission Line - Fiber Optic	Grid Modernization	Comm Upgrade Fiber - Mittal Steel Indiana Harbor (West) #2 to Tie Sheffield to Marktown	
29	TLF22	Transmission Line - Fiber Optic	Grid Modernization	Comm Upgrade Fiber - Munster to Hartsdale	
30	TLF23	Transmission Line - Fiber Optic	Grid Modernization	Comm Upgrade Fiber - Roxana to Chicago Avenue	
31	TLF24	Transmission Line - Fiber Optic	Grid Modernization	Comm Upgrade Fiber - Starke to Burr Oak	
32	TLNRL33	New/Rebuild Line	Deliverability	Hager Sub - 2nd 69kV Source & Primary Changeover	
33	TLNRL34	New/Rebuild Line	Deliverability	New Circuits - Menges Ditch (2) 138kV Lines and (3) 69kV Lines	
34	TLPC1	Line Engineering- Transmission	Aging Infrastructure	Line Pre-construction - Transmission	
35	TLE1	Line Engineering- Transmission	Aging Infrastructure	Line Engineering - Transmission	
36				<b>Total Transmission Lines</b>	
37		<b>Total Transmission Investment</b>			<b>\$101,620,503</b>

**NORTHERN INDIANA PUBLIC SERVICE COMPANY**  
**ELECTRIC 2025 PROJECT DETAIL - DIRECT CAPITAL DOLLARS ONLY**

(A)	(B)	(C)	(D)	(E)	(F)
Line No.	Project ID	Project Category	Project Driver	Project Title	Plan Project Cost (direct dollars)
		<b>Distribution System Investments</b>			
		<b>Underground Cable</b>			
38	DUG1	Underground Cable Replacement	Aging Infrastructure	Underground Cable Replacement Projects	
39				<b>Total Underground Cable</b>	
		<b>Distribution Substations</b>			
40	DSA1	Arresters - Distribution	Aging Infrastructure	Arrester Projects - Distribution	
41	DSB1	Batteries- Distribution	Aging Infrastructure	Battery & Charger Equipment Projects - Distribution	
42	DSPT1	Potential Transformers- Distribution	Aging Infrastructure	Potential Transformer Projects - Distribution	
43	DSSW1	Disconnects/Substation Switch Replacements	Aging Infrastructure	Substation Switch Projects - Distribution	
44	DSTU1	Transformer Upgrade/Replacement	Aging Infrastructure	Power Transformer Projects - Distribution	
45	DSC1	Distribution Substation - Communication	Grid Modernization	Comm Upgrade Projects - Distribution	
46	DSSA1	Distribution Substation Automation	Grid Modernization	Distribution Substation Automation	
47	DSBRU40	Breaker/Recloser Upgrades	Aging Infrastructure	Breaker Upgrade - Broadway - Switchgear	
48	DSBRU45	Breaker/Recloser Upgrades	Aging Infrastructure	Breaker Upgrade - Robertsdale - Switchgear	
49	DSBRU48	Breaker Upgrades	Deliverability	Breaker Upgrade - Wayne Substation Upgrades and #2 XFR Add Cooling Fans	
50	DSTU31	Transformer Upgrade/Replacement	Deliverability	Nealon Drive Substation - Add 2nd 34/12kV Transformer and Switchgear	
51	DSTU32	Transformer Upgrade/Replacement	Deliverability	Hanna Substation - #1 Transformer - Add Voltage Regulators	
52	DSTU33	Transformer Upgrade/Replacement	Deliverability	Hebron Substation - #1 & #2 Transformers and Voltage Regulators - Increase Capacity	
53	DSTU34	Transformer Upgrade/Replacement	Deliverability	Maplewood Substation - #1 Transformer - Increase Capacity	
54	DSTU35	Transformer Upgrade/Replacement	Deliverability	Freyer Sub - No.1 Transformer and Voltage Regulators - Increase Capacity	
55	DSTU36	Transformer Upgrade/Replacement	Deliverability	Deer Run Substation - #2 Transformer - Add 2nd Set of Voltage Regulators	
56	DSTU37	Transformer Upgrade/Replacement	Deliverability	Transformer Upgrade - Demotte - 69/12kV #1 XFR	
57	DSTU38	Transformer Upgrade/Replacement	Deliverability	Clay Substation - #1 & #2 Transformers - Increase Capacity	
58	DSTU39	Transformer Upgrade/Replacement	Deliverability	Transformer Upgrade - Maynard - #2 XFR Add Cooling Fans	
59	DSTU40	Transformer Upgrade/Replacement	Aging Infrastructure	Transformer Upgrade - Wheeler - #1 XFR Add Cooling Fans and Upgrade Bus	
60	DSNRS50	New/Rebuild Substation - Distribution	Deliverability	New/Rebuild Substation - Culver - 69/12kV #1 & #2 Transformers, Reclosers	
61	DSNRS51	New/Rebuild Substation - Distribution	Deliverability	New/Rebuild Substation - Knox - (2) 69/12kV Transformers, Reclosers	
62	DSNRS52	New/Rebuild Substation - Distribution	Aging Infrastructure	New/Rebuild Substation - Tilden - #1 & #2 XFRs and #1 & #2 Switchgears	
63	DSNRS53	New/Rebuild Substation - Distribution	Aging Infrastructure	New/Rebuild Substation - University - #1 Transformer and Switchgear	
64	DSPC1	Substation Engineering- Distribution	Aging Infrastructure	Substation Pre-construction - Distribution	
65	DSE1	Substation Engineering- Distribution	Aging Infrastructure	Substation Engineering - Distribution	
66				<b>Total Distribution Substations</b>	



**NORTHERN INDIANA PUBLIC SERVICE COMPANY  
ELECTRIC 2025 PROJECT DETAIL - DIRECT CAPITAL DOLLARS ONLY**

(A) Line No.	(B) Project ID	(C) Project Category	(D) Project Driver	(E) Project Title	(F) Plan Project Cost (direct dollars)
		<b>Distribution Lines</b>			
67	DLCP1	Circuit Performance Improvement	Aging Infrastructure	Circuit Performance Improvement Projects - Distribution	
68	DLWP1	Wood Poles	Aging Infrastructure	Pole Replacement Projects - Distribution	
69	DLSW2	Line Switch Replacement	Aging Infrastructure	Line Switch Projects - Distribution	
70	DLDA1	Distribution Line - Distribution Automation	Aging Infrastructure	Distribution Line Automation	
71	DLAMI1	Advanced Metering Infrastructure (AMI)	Grid Modernization	Advanced Metering Infrastructure (AMI)	
72	DLNRL74	New/Rebuild Line	Aging Infrastructure	Circuit Rebuild - Liberty Park - 12-252	
73	DLNRL75	New/Rebuild Line	Aging Infrastructure	Circuit Rebuild - Liberty Park - 12-254	
74	DLNRL99	New/Rebuild Line	Aging Infrastructure	Line to Support Burns Ditch Substation	
75	DLNRL100	New/Rebuild Line	Aging Infrastructure	Circuit Rebuild - Fisher - 12-294	
76	DLNRL101	New/Rebuild Line	Aging Infrastructure	Circuit Rebuild - Johnson - 12-565	
77	DLNRL102	New/Rebuild Line	Deliverability	Lines to Support Culver Substation - 69kV & 12kV	
78	DLNRL103	New/Rebuild Line	Deliverability	Lines to Support Knox Substation - 12.5kV & 69kV Line Extensions	
79	DLNRL104	New/Rebuild Line	Deliverability	Nealon Drive Sub - Ext. 2nd 34kV Source Line	
80	DLNRL105	New/Rebuild Line	Deliverability	New/Rebuild Line - McCool 12-210 Reconductor	
81	DLPC1	Line Engineering- Distribution	Aging Infrastructure	Line Pre-construction - Distribution	
82	DLE1	Line Engineering- Distribution	Aging Infrastructure	Line Engineering - Distribution	
83				<b>Total Distribution Lines</b>	
84		<b>Total Distribution Investment</b>			<b>\$175,271,919</b>
85		<b>Total T&amp;D Investment</b>			<b>\$276,892,422</b>
86		<b>Total O&amp;M Investment</b>			<b>\$1,680,577</b>

**NORTHERN INDIANA PUBLIC SERVICE COMPANY  
ELECTRIC 2026 PROJECT DETAIL - DIRECT CAPITAL DOLLARS ONLY**

(A) Line No.	(B) Project ID	(C) Project Category	(D) Project Driver	(E) Project Title	(F) Plan Project Cost (direct dollars)
		<b>Transmission System Investments</b>			
		<b>Transmission Substations</b>			
1	TSA1	Arresters - Transmission	Aging Infrastructure	Arrester Projects - Transmission	
2	TSB1	Batteries - Transmission	Aging Infrastructure	Battery & Charger Equipment Projects - Transmission	
3	TSPT1	Potential Transformers- Transmission	Aging Infrastructure	Potential Transformer Projects - Transmission	
4	TSSW1	Disconnects/Substation Switch Replacements	Aging Infrastructure	Substation Switch Projects - Transmission	
5	TSBRU46	Breaker Upgrades	Aging Infrastructure	Capacitor & Breaker Projects - Transmission	
6	TSC1	Transmission Substation - Communication	Grid Modernization	Comm Upgrade Projects - Transmission	
7	TSSA1	Transmission Substation Automation	Grid Modernization	Transmission Substation Automation	
8	TSRU68	Relay Upgrades	Aging Infrastructure	Relay Upgrade - Goshen Junction - #2 XFR	
9	TSRU92	Relay Upgrades	Aging Infrastructure	Relay Upgrade - Miller - 138kV Bus	
10	TSBRU30	Breaker Upgrades	Aging Infrastructure	Breaker Upgrade - Chicago Ave. 138104, 13811, 13829, 13831, 13833-104, & 13811-29	
11	TSBRU37	Breaker Upgrades	Aging Infrastructure	Breaker Upgrade - Flint Lake - 69kV Breakers	
12	TSBRU49	Breaker Upgrades	Aging Infrastructure	Breaker Upgrade - Tower Road - 34507-23 BKR	
13	TSTU11	Transformer Upgrade/Replacement	Deliverability	Transformer Upgrade - Dekalb - 138/69kV #1 XFR	
14	TSNRS12	New/Rebuild Substations- Transmission	Aging Infrastructure	Rebuild Substation - Goshen Junction - #1 138/69kV Transformer and 69kV Relay and Breaker Upgrades	
15	TSNRS25	New/Rebuild Substations- Transmission	Deliverability	Northwood Substation New Changeover	
16	TSNRS26	New/Rebuild Substations- Transmission	Deliverability	New Schrader Ditch Substation	
17	TSPC1	Substation Engineering- Transmission	Aging Infrastructure	Substation Pre-construction - Transmission	
18	TSE1	Substation Engineering- Transmission	Aging Infrastructure	Substation Engineering - Transmission	
19				<b>Total Transmission Substations</b>	
		<b>Transmission Lines</b>			
20	TLSW1	Line Switch Replacement	Aging Infrastructure	Line Switch Projects - Transmission	
21	TLST1	Steel Structure Program	Aging Infrastructure	Steel Structure Life Extension Projects - Transmission	
22	TLF25	Transmission Line - Fiber Optic	Grid Modernization	Comm Upgrade Fiber - Babcock to Stillwell	
23	TLF26	Transmission Line - Fiber Optic	Grid Modernization	Comm Upgrade Fiber - Elmwood to Tie Corporate Information Service Center - Microwave to Munster	
24	TLF27	Transmission Line - Fiber Optic	Grid Modernization	Comm Upgrade Fiber - Goodland Junction to Tie Goodland to Remington	
25	TLF28	Transmission Line - Fiber Optic	Grid Modernization	Comm Upgrade Fiber - Idaho to Aetna	
26	TLF29	Transmission Line - Fiber Optic	Grid Modernization	Comm Upgrade Fiber - Kosciusko to Leesburg	
27	TLF30	Transmission Line - Fiber Optic	Grid Modernization	Comm Upgrade Fiber - Lake George to Babcock	
28	TLF31	Transmission Line - Fiber Optic	Grid Modernization	Comm Upgrade Fiber - Lincoln Square to Broadway	
29	TLF32	Transmission Line - Fiber Optic	Grid Modernization	Comm Upgrade Fiber - Morrison Ditch to Monticello	
30	TLF33	Transmission Line - Fiber Optic	Grid Modernization	Comm Upgrade Fiber - Nealon Drive to Burns Ditch	
31	TLNRL24	New/Rebuild Line	Aging Infrastructure	Circuit Rebuild - Thayer - 6958	
32	TLNRL35	New/Rebuild Line	Deliverability	New 69kV Line to Support New Schrader Ditch Substation	
33	TLNRL36	New/Rebuild Line	Deliverability	Angola-Wolcottville 6959 69kV Line - Reconductor	
34	TLNRL37	New/Rebuild Line	Deliverability	New Northwood 69kV Source	
35	TLPC1	Line Engineering- Transmission	Aging Infrastructure	Line Pre-construction - Transmission	
36	TLE1	Line Engineering- Transmission	Aging Infrastructure	Line Engineering - Transmission	
37				<b>Total Transmission Lines</b>	
38		<b>Total Transmission Investment</b>			<b>\$123,139,161</b>

**NORTHERN INDIANA PUBLIC SERVICE COMPANY**  
**ELECTRIC 2026 PROJECT DETAIL - DIRECT CAPITAL DOLLARS ONLY**

(A) Line No.	(B) Project ID	(C) Project Category	(D) Project Driver	(E) Project Title	(F) Plan Project Cost (direct dollars)
		<b>Distribution System Investments</b>			
		<b>Underground Cable</b>			
39	DUG1	Underground Cable Replacement	Aging Infrastructure	Underground Cable Replacement Projects	
40				<b>Total Underground Cable</b>	
		<b>Distribution Substations</b>			
41	DSA1	Arresters - Distribution	Aging Infrastructure	Arrester Projects - Distribution	
42	DSB1	Batteries- Distribution	Aging Infrastructure	Battery & Charger Equipment Projects - Distribution	
43	DSPT1	Potential Transformers- Distribution	Aging Infrastructure	Potential Transformer Projects - Distribution	
44	DSC1	Distribution Substation - Communication	Grid Modernization	Comm Upgrade Projects - Distribution	
45	DSSA1	Distribution Substation Automation	Grid Modernization	Distribution Substation Automation	
46	DSTU41	Transformer Upgrade/Replacement	Deliverability	Transformer Upgrade - Kingsford Heights - #1 XFR Increase Capacity	
47	DSTU42	Transformer Upgrade/Replacement	Deliverability	Donaldson Sub - #1 Transformer - Increase Transformer and Volt Reg. Capacities	
48	DSTU43	Transformer Upgrade/Replacement	Deliverability	Cedar Lake Sub #2 Transformer - Increase Capacity	
49	DSNRS30	New/Rebuild Substation - Distribution	Aging Infrastructure	Rebuild Substation - Hartsdale - #5 Transformer & #5 Switchgear	
50	DSNRS54	New/Rebuild Substation - Distribution	Deliverability	New Chesterton 69/12.5kV Substation	
51	DSNRS55	New/Rebuild Substation - Distribution	Deliverability	New Southwest Lake County Substation	
52	DSNRS57	New/Rebuild Substation - Distribution	Aging Infrastructure	New/Rebuild Substation - Angola - #3 & #4 Transformers and #3 & #4 Switchgears	
53	DSNRS58	New/Rebuild Substation - Distribution	Deliverability	New/Rebuild Substation - Court - #2 Switchgear - Replace and Add 3rd Circuit & BT	
54	DSNRS56	New/Rebuild Substation - Distribution	Aging Infrastructure	New/Rebuild Substation - 61st Ave - #2 Transformer and #1 & #2 Switchgears	
55	DSNRS59	New/Rebuild Substation - Distribution	Aging Infrastructure	New/Rebuild Substation - Marktown - #3 Transformer and Breaker Upgrades	
56	DSNRS60	New/Rebuild Substation - Distribution	Aging Infrastructure	New/Rebuild Substation - Mitchell - #1 Transformer and 34kV Bus Tie	
57	DSPC1	Substation Engineering- Distribution	Aging Infrastructure	Substation Pre-construction - Distribution	
58	DSE1	Substation Engineering- Distribution	Aging Infrastructure	Substation Engineering - Distribution	
59				<b>Total Distribution Substations</b>	
		<b>Distribution Lines</b>			
60	DLCP1	Circuit Performance Improvement	Aging Infrastructure	Circuit Performance Improvement Projects - Distribution	
61	DLWP1	Wood Poles	Aging Infrastructure	Pole Replacement Projects - Distribution	
62	DLSW2	Line Switch Replacement	Aging Infrastructure	Line Switch Projects - Distribution	
63	DLDA1	Distribution Line - Distribution Automation	Aging Infrastructure	Distribution Line Automation	
64	DLAMI1	Advanced Metering Infrastructure (AMI)	Grid Modernization	Advanced Metering Infrastructure (AMI)	
65	DLNRL106	New/Rebuild Line	Aging Infrastructure	Circuit Rebuild - Indiana Harbor - 12-581	
66	DLNRL107	New/Rebuild Line	Aging Infrastructure	Circuit Rebuild - Chesterton - 12-194	
67	DLNRL110	New/Rebuild Line	Aging Infrastructure	Circuit Rebuild - Roxana - 12-454	
68	DLNRL111	New/Rebuild Line	Deliverability	South Haven Cir 12-715 - Upgrade Capacity	
69	DLNRL112	New/Rebuild Line	Deliverability	Hoosier Hill 12-724 Crooked Lake Tap Reconductor	
70	DLNRL113	New/Rebuild Line	Deliverability	McCool 12-149 - Upgrade Capacity	
71	DLNRL114	New/Rebuild Line	Deliverability	Lines to Support New Chesterton Substation - 69kV and 12.5kV Circuits - Line Extensions	

**NORTHERN INDIANA PUBLIC SERVICE COMPANY  
ELECTRIC 2026 PROJECT DETAIL - DIRECT CAPITAL DOLLARS ONLY**

(A)	(B)	(C)	(D)	(E)	(F)
Line No.	Project ID	Project Category	Project Driver	Project Title	Plan Project Cost (direct dollars)
72	DLNRL115	New/Rebuild Line	Deliverability	Lines to Support New Southwest Lake County Substation - 69kV and 12.5kV Circuits	
73	DLPC1	Line Engineering- Distribution	Aging Infrastructure	Line Pre-construction - Distribution	
74	DLE1	Line Engineering- Distribution	Aging Infrastructure	Line Engineering - Distribution	
75				<b>Total Distribution Lines</b>	
76		<b>Total Distribution Investment</b>			<b>\$164,240,050</b>
77		<b>Total T&amp;D Investment</b>			<b>\$287,379,211</b>
78		<b>Total O&amp;M Investment</b>			<b>\$1,356,206</b>

**NORTHERN INDIANA PUBLIC SERVICE COMPANY  
ELECTRIC FILING PROJECTS YEARLY PLAN AND EXPENSES**

(A)	(B)	(C)	(D)	(E)	(F)	(G)	(H)	(I)	(J)	(K)
Line No.	Project ID	Project Category	Project Title	2021	2022	2023	2024	2025	2026	Total
1	TSA1	Transmission Substations	Arrester Projects - Transmission							
2	TSB1	Transmission Substations	Battery & Charger Equipment Projects - Transmission							
3	TSPT1	Transmission Substations	Potential Transformer Projects - Transmission							
4	TSSW1	Transmission Substations	Substation Switch Projects - Transmission							
5	TSBRU46	Transmission Substations	Capacitor & Breaker Projects - Transmission							
6	TSC1	Transmission Substations	Comm Upgrade Projects - Transmission							
7	TSSA1	Transmission Substations	Transmission Substation Automation							
8	TSRU2	Transmission Substations	Annunciator Projects - Transmission							
9	TSRU29	Transmission Substations	Fiber Optic - Green Acres to St. John - 13888							
10	TSRU58	Transmission Substations	Relay & Breaker Upgrades - Dune Acres to Burns Ditch - 13836 N & 13836 S							
11	TSRU59	Transmission Substations	Relay & Breaker Upgrades - Dune Acres to Mittal Burns Harbor - 13849 N & 13849 S							
12	TSRU60	Transmission Substations	Relay & Breaker Upgrades - Dune Acres to Mittal Burns Harbor - 13848 N & 13848 S							
13	TSRU61	Transmission Substations	Relay Upgrades - Green Acres to St John - 13888							
14	TSRU62	Transmission Substations	Relay Upgrades - Stillwell to Plymouth - 13896							
15	TSRU63	Transmission Substations	Relay Upgrades - South Prairie to Westwood (Duke) - 13883							
16	TSRU67	Transmission Substations	Relay Upgrade - Tower Road - #2 XFR							
17	TSRU68	Transmission Substations	Relay Upgrade - Goshen Junction - #2 XFR							
18	TSRU69	Transmission Substations	Relay & Breaker Upgrades - Miller to Beta Steel - 13842							
19	TSRU70	Transmission Substations	Relay & Breaker Upgrades - South Chalmers - Oakdale - 6971 and 6972							
20	TSRU71	Transmission Substations	Fiber Optic - 13806 Dune Acres to Burns Ditch							
21	TSRU75	Transmission Substations	Relay Upgrade - Monticello to Springboro -13807							
22	TSRU76	Transmission Substations	Relay Upgrade - WCE to Praxair # 6 - 13801							
23	TSRU79	Transmission Substations	Circuit Protection Upgrade - 13879 Dune Acres to Beta Steel							
24	TSRU80	Transmission Substations	Circuit Protection Upgrade - 13806 Dune Acres to Aetna							
25	TSRU81	Transmission Substations	Relay Upgrade - Oakdale - 69kV Bus							
26	TSRU82	Transmission Substations	Relay Upgrade - R. M. Schahfer - 138kV Bus							
27	TSRU83	Transmission Substations	Circuit Protection Upgrade - 13890 Mittal #8 to Chicago Ave.							
28	TSRU84	Transmission Substations	Relay Upgrade - R. M. Schahfer - 345kV Bus							
29	TSRU85	Transmission Substations	Relay Upgrade - Chicago Ave - 138kV Bus							
30	TSRU86	Transmission Substations	Relay Upgrade - Flint Lake - #3 & #4 XFR 69kV							
31	TSRU87	Transmission Substations	Relay Upgrade - Flint Lake - 138kV Bus							
32	TSRU88	Transmission Substations	Relay Upgrade - Kosciusko - Bus 69kV							
33	TSRU89	Transmission Substations	Relay Upgrade - Maple - Bus 69kV							
34	TSRU90	Transmission Substations	Relay Upgrade - Munster - 138kV Bus							
35	TSRU91	Transmission Substations	Relay Upgrade - Starke - #1 XFR 69kV							
36	TSRU92	Transmission Substations	Relay Upgrade - Miller - 138kV Bus							
37	TSBRU19	Transmission Substations	Breaker Upgrade - St. John Upgrades (345kV & 138kV)							
38	TSBRU20	Transmission Substations	Breaker Upgrade - Dune Acres - #3 XFR BKR							
39	TSBRU22	Transmission Substations	Breaker Upgrade - Miller - 13810-42							
40	TSBRU24	Transmission Substations	Breaker Upgrade - Northport Upgrades (138kV & 69kV)							
41	TSBRU26	Transmission Substations	Breaker Upgrade - East Winamac Upgrades (69kV)							
42	TSBRU27	Transmission Substations	Breaker Upgrade - Stillwell Upgrades (69kV)							
43	TSBRU29	Transmission Substations	Breaker Upgrade - Schahfer 34516 & 34521							
44	TSBRU30	Transmission Substations	Breaker Upgrade - Chicago Ave. 138104, 13811, 13829, 13831, 13833-104, & 13811-29							
45	TSBRU31	Transmission Substations	Breaker Upgrade - Liberty Park 138kV Bus Tie, #5 XFR & #6 XFR (69kV)							

**NORTHERN INDIANA PUBLIC SERVICE COMPANY  
ELECTRIC FILING PROJECTS YEARLY PLAN AND EXPENSES**

(A)	(B)	(C)	(D)	(E)	(F)	(G)	(H)	(I)	(J)	(K)
Line No.	Project ID	Project Category	Project Title	2021	2022	2023	2024	2025	2026	Total
46	TSBRU32	Transmission Substations	Breaker Upgrade - Miller 13822							
47	TSBRU33	Transmission Substations	Breaker Upgrade - Plymouth 13819-#1 & 13819-21							
48	TSBRU36	Transmission Substations	Breaker Upgrade - Barton Lake 69-102, Bus Tie, #1 XFR, & Cap Bank							
49	TSBRU37	Transmission Substations	Breaker Upgrade - Flint Lake - 69kV Breakers							
50	TSBRU41	Transmission Substations	Breaker Upgrade - Starke 6905, 6919, 6961, 69kV Bus Tie, #1 XFR, & #2 XFR							
51	TSBRU47	Transmission Substations	Breaker Upgrade - Kenwood - 138kV Bus Tie							
52	TSBRU48	Transmission Substations	Breaker Upgrade - Lake George Upgrades							
53	TSBRU49	Transmission Substations	Breaker Upgrade - Tower Road - 34507-23 BKR							
54	TSTU9	Transmission Substations	Transformer Upgrade - Dune Acres #3							
55	TSTU10	Transmission Substations	Replace Transformer - Kreitzburg - #2 138/69kV XFR							
56	TSTU11	Transmission Substations	Transformer Upgrade - Dekalb - 138/69kV #1 XFR							
57	TSNRS12	Transmission Substations	Rebuild Substation - Goshen Junction - #1 138/69kV Transformer and 69kV Relay and Breaker Upgrades							
58	TSNRS13	Transmission Substations	Rebuild Substation - Maple - #2 138/69kV XFR and 69kV Cap Bank							
59	TSNRS17	Transmission Substations	New/Rebuild Substation - Green Acres - #1 & #2 138/69kV Transformers; Breaker Upgrades (138kV & 69kV)							
60	TSNRS18	Transmission Substations	New/Rebuild Substation - New Michigan City Substation							
61	TSNRS19	Transmission Substations	New Marktown 138kV Substation							
62	TSNRS20	Transmission Substations	New/Rebuild Substation - Sheffield - 345/138kV XFR & 13804-#2, 13804-78, 13877-78, & 13893-#2 BRKS							
63	TSNRS21	Transmission Substations	New St. John 138kV-69kV Substation							
64	TSNRS22	Transmission Substations	Veterans Hwy Sub - Add Automated 69kV Primary Changeover							
65	TSNRS23	Transmission Substations	Hager Sub - 2nd 69kV Source & Primary Changeover							
66	TSNRS24	Transmission Substations	New/Rebuild Substation - Menges Ditch							
67	TSNRS25	Transmission Substations	Northwood Substation New Changeover							
68	TSNRS26	Transmission Substations	New Schrader Ditch Substation							
69	TSPC1	Transmission Substations	Substation Pre-construction - Transmission							
70	TSE1	Transmission Substations	Substation Engineering - Transmission							
71	TLSW1	Transmission Lines	Line Switch Projects - Transmission							
72	TLST1	Transmission Lines	Steel Structure Life Extension Projects - Transmission							
73	TLF1	Transmission Lines	Comm Upgrade Fiber - Chicago Avenue to U.S.Steel - Stockton							
74	TLF2	Transmission Lines	Comm Upgrade Fiber - Corporate Information Service Center - Microwave to Munster							
75	TLF3	Transmission Lines	Comm Upgrade Fiber - Corporate Information Service Center - Microwave to NiSource HQ (MW Only)							
76	TLF5	Transmission Lines	Comm Upgrade Fiber - NiSource HQ (MW Only) to Tie St. John to Green Acres							
77	TLF6	Transmission Lines	Comm Upgrade Fiber - Plymouth to Burr Oak							
78	TLF7	Transmission Lines	Comm Upgrade Fiber - Broadway to Tie St. John to Green Acres							
79	TLF8	Transmission Lines	Comm Upgrade Fiber - Corporate Information Service Center - Microwave to Roxana							
80	TLF9	Transmission Lines	Comm Upgrade Fiber - Leesburg to Tie Burr Oak to Hiple							
81	TLF10	Transmission Lines	Comm Upgrade Fiber - Marktown to Mittal Steel Indiana Harbor (East) #7							
82	TLF11	Transmission Lines	Comm Upgrade Fiber - Mittal Steel Indiana Harbor (East) #5 to Mittal Steel Indiana Harbor (East) #7							
83	TLF12	Transmission Lines	Comm Upgrade Fiber - Praxair #1 - East Chicago to Marktown							
84	TLF13	Transmission Lines	Comm Upgrade Fiber - Praxair #3 - Lakeside to Tie Chicago Ave. to U.S.Steel Corp - Stockton							

**NORTHERN INDIANA PUBLIC SERVICE COMPANY  
ELECTRIC FILING PROJECTS YEARLY PLAN AND EXPENSES**

(A)	(B)	(C)	(D)	(E)	(F)	(G)	(H)	(I)	(J)	(K)
Line No.	Project ID	Project Category	Project Title	2021	2022	2023	2024	2025	2026	Total
85	TLF14	Transmission Lines	Comm Upgrade Fiber - Pullman Standard to Tie Corporate Information Service Center - Microwave to Roxana							
86	TLF15	Transmission Lines	Comm Upgrade Fiber - Sheffield to Marktown							
87	TLF16	Transmission Lines	Comm Upgrade Fiber - St. John to R.M.Schahfer							
88	TLF17	Transmission Lines	Comm Upgrade Fiber - Taney to Lake George							
89	TLF18	Transmission Lines	Comm Upgrade Fiber - Gary Avenue to Tie Roxana to Chicago Avenue							
90	TLF19	Transmission Lines	Comm Upgrade Fiber - Green Acres to Tower Road							
91	TLF20	Transmission Lines	Comm Upgrade Fiber - Hendricks to U.S.Steel Corp - Stockton							
92	TLF21	Transmission Lines	Comm Upgrade Fiber - Mittal Steel Indiana Harbor (West) #2 to Tie Sheffield to Marktown							
93	TLF22	Transmission Lines	Comm Upgrade Fiber - Munster to Hartsdale							
94	TLF23	Transmission Lines	Comm Upgrade Fiber - Roxana to Chicago Avenue							
95	TLF24	Transmission Lines	Comm Upgrade Fiber - Starke to Burr Oak							
96	TLF25	Transmission Lines	Comm Upgrade Fiber - Babcock to Stillwell							
97	TLF26	Transmission Lines	Comm Upgrade Fiber - Elmwood to Tie Corporate Information Service Center - Microwave to Munster							
98	TLF27	Transmission Lines	Comm Upgrade Fiber - Goodland Junction to Tie Goodland to Remington							
99	TLF28	Transmission Lines	Comm Upgrade Fiber - Idaho to Aetna							
100	TLF29	Transmission Lines	Comm Upgrade Fiber - Kosciusko to Leesburg							
101	TLF30	Transmission Lines	Comm Upgrade Fiber - Lake George to Babcock							
102	TLF31	Transmission Lines	Comm Upgrade Fiber - Lincoln Square to Broadway							
103	TLF32	Transmission Lines	Comm Upgrade Fiber - Morrison Ditch to Monticello							
104	TLF33	Transmission Lines	Comm Upgrade Fiber - Nealon Drive to Burns Ditch							
105	TLNRL6	Transmission Lines	Circuit 3465 Rebuild - 69kV Laporte JCT to Tee Lake							
106	TLNRL9	Transmission Lines	Circuit 3465 Rebuild - New Carlisle to Olive							
107	TLNRL18	Transmission Lines	Circuit 6972 Rebuild - South Chalmers - Oakdale							
108	TLNRL33	Transmission Lines	Hager Sub - 2nd 69kV Source & Primary Changeover							
109	TLNRL34	Transmission Lines	New Circuits - Menges Ditch (2) 138kV Lines and (3) 69kV Lines							
110	TLNRL19	Transmission Lines	Circuit Rebuild - Monticello - 6907 - Phase 2							
111	TLNRL21	Transmission Lines	Circuit Rebuild - Kosciusko - 6997 - Phase 2							
112	TLNRL22	Transmission Lines	Circuit Rebuild - Lagrange - 6980							
113	TLNRL24	Transmission Lines	Circuit Rebuild - Thayer - 6958							
114	TLNRL26	Transmission Lines	Circuit Rebuild - Kosciusko - 6998							
115	TLNRL28	Transmission Lines	Circuit Rebuild - Kosciusko - 6982							
116	TLNRL29	Transmission Lines	Circuit Rebuild - Palmira - Extend 2nd 69kV Source Line							
117	TLNRL30	Transmission Lines	Circuit Rebuild - New 138kV Line & 6990 - Hiple to Northport							
118	TLNRL31	Transmission Lines	Liberty Park 6901 - Ext. to Veterans Hwy Sub							
119	TLNRL32	Transmission Lines	New Lines 69kV at St John Transmission Substation 69-116 & 69-117							
120	TLNRL35	Transmission Lines	New 69kV Line to Support New Schrader Ditch Substation							
121	TLNRL36	Transmission Lines	Angola-Wolcottville 6959 69kV Line - Reconductor							
122	TLNRL37	Transmission Lines	New Northwood 69kV Source							
123	TLPC1	Transmission Lines	Line Pre-construction - Transmission							
124	TLE1	Transmission Lines	Line Engineering - Transmission							
125	DUG1	Underground Cable	Underground Cable Replacement Projects							
126	DSA1	Distribution Substations	Arrester Projects - Distribution							
127	DSB1	Distribution Substations	Battery & Charger Equipment Projects - Distribution							
128	DSPT1	Distribution Substations	Potential Transformer Projects - Distribution							
129	DSSW1	Distribution Substations	Substation Switch Projects - Distribution							

**NORTHERN INDIANA PUBLIC SERVICE COMPANY  
ELECTRIC FILING PROJECTS YEARLY PLAN AND EXPENSES**

(A)	(B)	(C)	(D)	(E)	(F)	(G)	(H)	(I)	(J)	(K)
Line No.	Project ID	Project Category	Project Title	2021	2022	2023	2024	2025	2026	Total
130	DSFC1	Distribution Substations	Substation Feeder Cable Projects - Distribution							
131	DSTU1	Distribution Substations	Power Transformer Projects - Distribution							
132	DSC1	Distribution Substations	Comm Upgrade Projects - Distribution							
133	DSC2	Distribution Substations	New Distribution SCADA							
134	DSSA1	Distribution Substations	Distribution Substation Automation							
135	DSRU9	Distribution Substations	Relay Upgrade - R.M.Schahfer - #1 XFR							
136	DSBRU24	Distribution Substations	Breaker Upgrade - Michigan City - #11 Transformer Breaker 34kV							
137	DSBRU25	Distribution Substations	Breaker Upgrades - Luchtman - 34-124, 34-125							
138	DSBRU28	Distribution Substations	Breaker Upgrades - Division - Switchgear							
139	DSBRU30	Distribution Substations	Breaker Upgrades - Gibson - Switchgear							
140	DSBRU31	Distribution Substations	Breaker Upgrades - Hyde Park - Switchgear							
141	DSBRU33	Distribution Substations	Breaker Upgrades - Monticello - Switchgear							
142	DSBRU34	Distribution Substations	Breaker Upgrade - Southlake - Switchgear							
143	DSBRU36	Distribution Substations	Breaker Upgrade - Aetna - 3475, 34kV N. Bus, 34kV S. Bus							
144	DSBRU37	Distribution Substations	Breaker Upgrade - Kenwood 34kV Upgrades							
145	DSBRU39	Distribution Substations	Breaker Upgrade - Munster - 3428, 3429, 3430, 3431							
146	DSBRU40	Distribution Substations	Breaker Upgrade - Broadway - Switchgear							
147	DSBRU42	Distribution Substations	Breaker Upgrade - Liable - Switchgear							
148	DSBRU45	Distribution Substations	Breaker Upgrade - Robertsdale - Switchgear							
149	DSBRU47	Distribution Substations	Maple Sub - New 12.5kV Circuit Position							
150	DSBRU48	Transmission Substations	Breaker Upgrade - Wayne Substation Upgrades and #2 XFR Add Cooling Fans							
151	DSTU15	Distribution Substations	Replace Transformer - Orchard Grove - #1 Transformer							
152	DSTU18	Distribution Substations	Replace Transformer - Bourbon #2							
153	DSTU20	Distribution Substations	Replace Transformer - Weirick #1							
154	DSTU21	Distribution Substations	Replace Transformer - Wolf Lake - #2 138/34kV XFR							
155	DSTU22	Distribution Substations	Replace Transformer - Flint Lake - #8 138/12kV XFR							
156	DSTU24	Distribution Substations	Transformer Replacement - Midway Sub - #1 XFR - Increase Capacity							
157	DSTU25	Distribution Substations	Replace Transformer - Medaryville - #2 69/12kV XFR							
158	DSTU26	Distribution Substations	Howe Sub - #2 Transformer & #1 Volt Regs - Inc Capacity							
159	DSTU28	Distribution Substations	Pine Creek Sub - #2 XFR - Add 2nd Set of Voltage Regulators							
160	DSTU29	Distribution Substations	Fowler Sub - #2 XFR - Add 2nd Set of Voltage Regulators							
161	DSTU30	Distribution Substations	Horn Ditch - Add 2nd Transformer & Upgrade 12.5kV Switchgear							
162	DSTU31	Distribution Substations	Nealon Drive Substation - Add 2nd 34/12kV Transformer and Switchgear							
163	DSTU32	Distribution Substations	Hanna Substation - #1 Transformer - Add Voltage Regulators							
164	DSTU33	Distribution Substations	Hebron Substation - #1 & #2 Transformers and Voltage Regulators - Increase Capacity							
165	DSTU34	Distribution Substations	Maplewood Substation - #1 Transformer - Increase Capacity							
166	DSTU35	Distribution Substations	Freyer Sub - No.1 Transformer and Voltage Regulators - Increase Capacity							
167	DSTU36	Distribution Substations	Deer Run Substation - #2 Transformer - Add 2nd Set of Voltage Regulators							
168	DSTU37	Distribution Substations	Transformer Upgrade - Demotte - 69/12kV #1 XFR							
169	DSTU38	Distribution Substations	Clay Substation - #1 & #2 Transformers - Increase Capacity							
170	DSTU39	Distribution Substations	Transformer Upgrade - Maynard - #2 XFR Add Cooling Fans							
171	DSTU40	Distribution Substations	Transformer Upgrade - Wheeler - #1 XFR Add Cooling Fans and Upgrade Bus							
172	DSTU41	Distribution Substations	Transformer Upgrade - Kingsford Heights - #1 XFR Increase Capacity							



**NORTHERN INDIANA PUBLIC SERVICE COMPANY  
ELECTRIC FILING PROJECTS YEARLY PLAN AND EXPENSES**

(A)	(B)	(C)	(D)	(E)	(F)	(G)	(H)	(I)	(J)	(K)
Line No.	Project ID	Project Category	Project Title	2021	2022	2023	2024	2025	2026	Total
173	DSTU42	Distribution Substations	Donaldson Sub - #1 Transformer - Increase Transformer and Volt Reg. Capacities							
174	DSTU43	Distribution Substations	Cedar Lake Sub #2 Transformer - Increase Capacity							
175	DSNRS22	Distribution Substations	Rebuild Substation - Lowell - #1 Transformer and #1 Switchgear & #2 Switchgear							
176	DSNRS26	Distribution Substations	Rebuild Substation - Munster - #3 & #4 Transformer 138/34kV and #3 Transformer Breaker							
177	DSNRS29	Distribution Substations	Rebuild Substation - Griffith - #1 Transformer & Switchgear							
178	DSNRS30	Distribution Substations	Rebuild Substation - Hartsdale - #5 Transformer & #5 Switchgear							
179	DSNRS31	Distribution Substations	Rebuild Substation - Woodmar - #1 Transformer & Switchgear							
180	DSNRS34	Distribution Substations	Crocker Substation New Recloser & Incoming Lines							
181	DSNRS35	Distribution Substations	New/Rebuild Substation - Creston - Add 2nd Transformer, #1 & #2 Voltage Regulators, Dbl. Switchgear							
182	DSNRS36	Distribution Substations	Rebuild Substation - Illinois - #1 69/12kV XFR and Switchgear Breakers							
183	DSNRS39	Distribution Substations	New/Rebuild Substation - Hanover - #1 & #2 Transformer with Dbl. Switchgear							
184	DSNRS41	Distribution Substations	New/Rebuild Substation - Tod - #5 Transformer & Switchgear							
185	DSNRS42	Distribution Substations	New/Rebuild Substation - Palmira Sub - Add 2nd Transformer, New Dbl. Switchgear							
186	DSNRS43	Distribution Substations	New/Rebuild Substation - Johnson - Switchgear							
187	DSNRS44	Distribution Substations	New Heron Lake - New 69/12 5kV Substation							
188	DSNRS45	Distribution Substations	New/Rebuild Substation - Novak Road - #1 Transformer & Switchgear							
189	DSNRS46	Distribution Substations	New/Rebuild Substation - Pidco - #1 69/12kV Transformer & Add Second Transformer and Switchgear							
190	DSNRS47	Distribution Substations	New/Rebuild Substation - Schererville - #1 & #2 Transformers and Switchgears							
191	DSNRS48	Distribution Substations	New Winfield 69/12kV Substation							
192	DSNRS49	Distribution Substations	New/Rebuild Substation - Woodland Park - #1 Transformer & Switchgear							
193	DSNRS50	Distribution Substations	New/Rebuild Substation - Culver - 69/12kV #1 & #2 Transformers, Reclosers							
194	DSNRS51	Distribution Substations	New/Rebuild Substation - Knox - (2) 69/12kV Transformers, Reclosers							
195	DSNRS52	Distribution Substations	New/Rebuild Substation - Tilden - #1 & #2 XFRs and #1 & #2 Switchgears							
196	DSNRS53	Distribution Substations	New/Rebuild Substation - University - #1 Transformer and Switchgear							
197	DSNRS54	Distribution Substations	New Chesterton 69/12.5kV Substation							
198	DSNRS55	Distribution Substations	New Southwest Lake County Substation							
199	DSNRS57	Distribution Substations	New/Rebuild Substation - Angola - #3 & #4 Transformers and #3 & #4 Switchgears							
200	DSNRS58	Distribution Substations	New/Rebuild Substation - Court - #2 Switchgear - Replace and Add 3rd Circuit & BT							
201	DSNRS56	Distribution Substations	New/Rebuild Substation - 61st Ave - #2 Transformer and #1 & #2 Switchgears							
202	DSNRS59	Distribution Substations	New/Rebuild Substation - Marktown - #3 Transformer and Breaker Upgrades							
203	DSNRS60	Distribution Substations	New/Rebuild Substation - Mitchell - #1 Transformer and 34kV Bus Tie							

**NORTHERN INDIANA PUBLIC SERVICE COMPANY  
ELECTRIC FILING PROJECTS YEARLY PLAN AND EXPENSES**

(A)	(B)	(C)	(D)	(E)	(F)	(G)	(H)	(I)	(J)	(K)
Line No.	Project ID	Project Category	Project Title	2021	2022	2023	2024	2025	2026	Total
204	DSPC1	Distribution Substations	Substation Pre-construction - Distribution							
205	DSE1	Distribution Substations	Substation Engineering - Distribution							
206	DLCP1	Distribution Lines	Circuit Performance Improvement Projects - Distribution							
207	DLWP1	Distribution Lines	Pole Replacement Projects - Distribution							
208	DLSW1	Distribution Lines	Switches to Clear Incoming Lines Projects - Distribution							
209	DLSW2	Distribution Lines	Line Switch Projects - Distribution							
210	DLDA1	Distribution Lines	Distribution Line Automation							
211	DLLED1	Distribution Lines	LED Street Lighting							
212	DLAM11	Distribution Lines	Advanced Metering Infrastructure (AMI)							
213	DLNRL24	Distribution Lines	Circuit 3433 Rebuild - Grandview to Bendix West Side							
214	DLNRL35	Distribution Lines	Circuit Rebuild - Roxana - 12-316							
215	DLNRL42	Distribution Lines	Circuit Rebuild - South Hammond - 12-720							
216	DLNRL50	Distribution Lines	Circuit Rebuild - Lindbergh - 12-299							
217	DLNRL52	Distribution Lines	Circuit Rebuild - S Hammond - 12-719							
218	DLNRL53	Distribution Lines	Circuit Rebuild - N Webster - 12-159							
219	DLNRL57	Distribution Lines	Circuit Rebuild - Tod 12-457							
220	DLNRL58	Distribution Lines	Circuit Rebuild - Ainsworth 12-508							
221	DLNRL59	Distribution Lines	Circuit Rebuild - Johnson 12-563							
222	DLNRL60	Distribution Lines	Circuit Rebuild - 120th St 12-572							
223	DLNRL61	Distribution Lines	Circuit Rebuild - Madison 12-625							
224	DLNRL62	Distribution Lines	Circuit Rebuild - Laporte 1264							
225	DLNRL63	Distribution Lines	Circuit Rebuild - Woodmar 12-643							
226	DLNRL64	Distribution Lines	Circuit Rebuild - Elliot 12-750							
227	DLNRL65	Distribution Lines	Circuit Rebuild - Plymouth 1221							
228	DLNRL67	Distribution Lines	Circuit Rebuild - Liable 12-332							
229	DLNRL68	Distribution Lines	Circuit Rebuild - Decatur - 1209							
230	DLNRL70	Distribution Lines	Circuit Rebuild - Dyer - 12-249							
231	DLNRL73	Distribution Lines	Circuit Rebuild - Laporte - 1265							
232	DLNRL74	Distribution Lines	Circuit Rebuild - Liberty Park - 12-252							
233	DLNRL75	Distribution Lines	Circuit Rebuild - Liberty Park - 12-254							
234	DLNRL76	Distribution Lines	Circuit Rebuild - S. Hammond - 12-524							
235	DLNRL78	Distribution Lines	Circuit Rebuild - Crocker New Circuit - Existing Line Reconductor							
236	DLNRL79	Distribution Lines	Bristol 12-111 / Bonneyville 12-706 Reconductor							
237	DLNRL85	Distribution Lines	Circuit Rebuild - Palmira - New 12.5kV Circuit Extension							
238	DLNRL86	Distribution Lines	Broadmoor Cir. 12-502 & Fisher 12-294 - Reconductor							
239	DLNRL87	Distribution Lines	Center Sub 12-270 - Circuit Reconductor - 0.6 miles w/69kV Overbuild							
240	DLNRL88	Distribution Lines	Heron Lake Substation - Line Taps - Ext. 69kV Source and 12.5kV Feeder Lines							
241	DLNRL89	Distribution Lines	Lines to Support Pidco Substation							
242	DLNRL90	Distribution Lines	Maple Sub - New 12.5kV Circuit Line Extension							
243	DLNRL91	Distribution Lines	Horn Ditch Sub - 2nd 69kV Source Line							
244	DLNRL92	Distribution Lines	Horn Ditch Sub - 69kV and 12.5kV Lines							
245	DLNRL93	Distribution Lines	Hanover 12-453 - Reconductor							
246	DLNRL94	Distribution Lines	Cedar Lake 1207 & Hanover 12-453 - Reconductor							
247	DLNRL95	Distribution Lines	Lines to Support Winfield Substation - 69kV and 12 5kV Circuit Extensions							
248	DLNRL96	Distribution Lines	Rock Run 12-382 & Model 12-432 DA Tie - Increase Capacity							
249	DLNRL97	Distribution Lines	Circuit Rebuild - Broadway - 12-433							
250	DLNRL98	Distribution Lines	Circuit Rebuild - Broadway - 12-437							
251	DLNRL99	Distribution Lines	Line to Support Burns Ditch Substation							

**NORTHERN INDIANA PUBLIC SERVICE COMPANY  
ELECTRIC FILING PROJECTS YEARLY PLAN AND EXPENSES**

(A)	(B)	(C)	(D)	(E)	(F)	(G)	(H)	(I)	(J)	(K)
Line No.	Project ID	Project Category	Project Title	2021	2022	2023	2024	2025	2026	Total
252	DLNRL100	Distribution Lines	Circuit Rebuild - Fisher - 12-294							
253	DLNRL101	Distribution Lines	Circuit Rebuild - Johnson - 12-565							
254	DLNRL102	Distribution Lines	Lines to Support Culver Substation - 69kV & 12kV							
255	DLNRL103	Distribution Lines	Lines to Support Knox Substation - 12 5kV & 69kV Line Extensions							
256	DLNRL104	Distribution Lines	Nealon Drive Sub - Ext. 2nd 34kV Source Line							
257	DLNRL105	Distribution Lines	New/Rebuild Line - McCool 12-210 Reconductor							
258	DLNRL106	Distribution Lines	Circuit Rebuild - Indiana Harbor - 12-581							
259	DLNRL107	Distribution Lines	Circuit Rebuild - Chesterton - 12-194							
260	DLNRL108	Distribution Lines	Circuit Rebuild - Court - Extend New 12.5kV Circuit							
261	DLNRL110	Distribution Lines	Circuit Rebuild - Roxana - 12-454							
262	DLNRL111	Distribution Lines	South Haven Cir 12-715 - Upgrade Capacity							
263	DLNRL112	Distribution Lines	Hoosier Hill 12-724 Crooked Lake Tap Reconductor							
264	DLNRL113	Distribution Lines	McCool 12-149 - Upgrade Capacity							
265	DLNRL114	Distribution Lines	Lines to Support New Chesterton Substation - 69kV and 12.5kV Circuits - Line Extensions							
266	DLNRL115	Distribution Lines	Lines to Support New Southwest Lake County Substation - 69kV and 12.5kV Circuits							
267	DLPC1	Distribution Lines	Line Pre-construction - Distribution							
268	DLE1	Distribution Lines	Line Engineering - Distribution							
269		Total Direct Capital		\$ 105,324,448	\$ 222,556,740	\$ 229,233,442	\$ 275,229,152	\$ 276,892,422	\$ 287,379,211	\$ 1,396,615,415

**Summary by Project Category**

Line No.	Project ID	Project Category	Project Title	2021	2022	2023	2024	2025	2026	Total
270		Transmission Substations		\$ 26,096,870	\$ 39,608,052	\$ 57,910,125	\$ 60,200,669	\$ 54,908,149	\$ 54,852,316	\$ 293,576,181
271		Transmission Lines		\$ 14,501,950	\$ 41,690,816	\$ 22,276,258	\$ 46,049,322	\$ 47,760,270	\$ 68,286,845	\$ 240,565,461
272		Underground Cable		\$ 13,652,531	\$ 20,632,620	\$ 18,142,533	\$ 17,380,921	\$ 16,172,420	\$ 17,659,875	\$ 103,640,900
273		Distribution Substations		\$ 22,361,757	\$ 52,065,812	\$ 63,216,937	\$ 55,231,981	\$ 68,799,483	\$ 63,804,727	\$ 325,480,697
274		Distribution Lines		\$ 28,711,340	\$ 68,559,440	\$ 67,687,589	\$ 96,366,259	\$ 89,252,100	\$ 82,775,448	\$ 433,352,176
275		Total Direct Capital		\$ 105,324,448	\$ 222,556,740	\$ 229,233,442	\$ 275,229,152	\$ 276,892,422	\$ 287,379,211	\$ 1,396,615,415
276		Transmission Total		\$ 40,598,820	\$ 81,298,868	\$ 80,186,383	\$ 106,249,991	\$ 102,668,419	\$ 123,139,161	\$ 534,141,642
277		Distribution Total		\$ 64,725,628	\$ 141,257,872	\$ 149,047,059	\$ 168,979,161	\$ 174,224,003	\$ 164,240,050	\$ 862,473,773
278		Total Direct Capital		\$ 105,324,448	\$ 222,556,740	\$ 229,233,442	\$ 275,229,152	\$ 276,892,422	\$ 287,379,211	\$ 1,396,615,415

Confidential Attachment 2-A (Redacted)

Confidential Appendix A (Redacted)

Page X of 7

Confidential Attachment 2-A (Redacted)

Confidential Appendix B (Redacted)

Page X of 41

Confidential Attachment 2-A (Redacted)

Confidential Appendix C (Redacted)

Page X of 60

Confidential Attachment 2-A (Redacted)

Confidential Appendix D (Redacted)

Page X of 78

Confidential Attachment 2-B (Redacted)  
[2021-2026 TDSIC Investment Plan Business Case]



Confidential Attachment 2-C (Redacted)  
[2021-2026 TDSIC Investment Plan Cost Analysis]



# TRANSMISSION PLANNING ASSESSMENT METHODOLOGY AND CRITERIA

For Compliance with NERC Reliability Standard: TPL-001-4

1/14/2021  
Version: 4.8

## Table of Contents

1	Revision and Approval History .....	2
1.1	Revision History .....	2
1.2	Approval .....	3
2	Annual Planning Assessment .....	4
2.1	Model Data .....	5
2.2	Steady State .....	6
2.2.1	Contingency Analysis .....	7
2.2.2	Steady-State Performance Requirements and Criteria [R5] .....	8
2.3	Stability .....	9
2.3.1	Contingency Events .....	10
2.3.2	Stability Performance Requirements and Criteria [R5] .....	11
2.4	Short Circuit .....	12
2.5	Supplemental Performance Analysis .....	12
2.5.1	Cascading .....	12
2.5.2	Uncontrolled Islanding .....	12
2.5.3	Voltage Stability .....	12
3	Facility Connection, Transmission Service Request Assessments, and Generator Retirements .....	13
3.1	Individual Contribution Test and Cumulative Impact Test (CIT) .....	13
3.2	Energy Storage or Hybrid Facility Interconnections .....	13
	Table 1. Planning and extreme Events .....	14

# 1 REVISION AND APPROVAL HISTORY

This document shall be revised and updated as needed to incorporate changes in methodology and criteria and to reflect changes to the approved NERC Standard requirements.

## 1.1 REVISION HISTORY

Version	Date	Author	Supervisor	Comments
1.0	10/14/2011	Dawn Quick	Robert Fox	Initial document load into the DMS.
2.0	12/31/2012	Dawn Quick	Robert Fox	Annual Review. Seasonal Ratings defined. Internal Communication additions.
3.0	07/18/2013	Dawn Quick	Robert Fox	Add Generator Interconnection Section.
3.1	10/15/2013	Dawn Quick	Robert Fox	Add language for Single Breaker Ratings.
3.2	12/26/2013	Dawn Quick	Robert Fox	Annual Review. No Changes
3.3	03/10/2014	Dawn Quick	Ganesh Velummylum	Annual Review. Section 4.5. Added footnote pertaining to Distribution Factor. Added Specification of NERC categories and Cases to study.
4.0	10/07/2015	Dawn Quick	Lynn Schmidt	Annual Review. Format and Content Changes to align with new TPL Standard
4.1	01/10/2016	Dawn Quick	Lynn Schmidt	Annual Review.
4.2	01/10/2017	Dawn Quick	Lynn Schmidt	Annual Review.
4.3	01/10/2018	Dawn Quick	Lynn Schmidt	Annual Review. Change in document review/revision requirements.
4.4	03/09/2018	Dawn Quick	Lynn Schmidt	Addition of 765kV Voltage Criteria
4.5	05/29/2019	Dawn Quick	Lynn Schmidt	Addition of Energy Storage Interconnection Criteria
4.6	02/06/2020	Dawn Quick	Lynn Schmidt	Added P5 to Facility Connection Criteria
4.7	05/27/2020	Dawn Quick	Lynn Schmidt	GI Cumulative Impact criteria revision
4.8	01/14/2021	Dawn Quick	Lynn Schmidt	Addition of solar plant study criteria. Revision of wind machine voltage criteria

**1.2 APPROVAL**

<b>Version</b>	<b>Supervisor</b>	<b>Title</b>	<b>Electronic Signature Date</b>
1.0	Robert Fox	Leader Transmission Planning	9/28/2011
2.0	Robert Fox	Leader Transmission Planning	12/31/2012
3.0	Robert Fox	Leader Transmission Planning	7/18/2013
3.1	Robert Fox	Leader Transmission Planning	10/15/2013
3.2	Robert Fox	Leader Transmission Planning	12/26/2013
3.3	Ganesh Velummylum	Manager Electric System Planning	3/10/2014
4.0	Lynn Schmidt	Leader Transmission Planning	10/07/2015
4.1	Lynn Schmidt	Leader Transmission Planning	1/10/2016
4.2	Lynn Schmidt	Leader Transmission Planning	01/10/2017
4.3	Lynn Schmidt	Leader Transmission Planning	01/10/2018
4.4	Lynn Schmidt	Leader Transmission Planning	03/09/2018
4.5	Lynn Schmidt	Leader Transmission Planning	05/29/2019
4.6	Lynn Schmidt	Leader Transmission Planning	02/06/2020
4.7	Lynn Schmidt	Leader Transmission Planning	05/27/2020
4.8	Lynn Schmidt	Leader Transmission Planning	01/14/2021

## 2 ANNUAL PLANNING ASSESSMENT

Transmission Planning shall prepare an annual Planning Assessment of the performance of its portion of the BES. This Planning Assessment shall use current or qualified past studies (as indicated below), shall document assumptions, and shall document summarized results of the steady state analyses, short circuit analyses, and Stability analyses. This assessment shall be performed for both the Near-Term and the Long-Term Transmission Planning Horizons. [R2]

Past studies may be used to support the Planning Assessment if they meet the following requirements:

- For steady state, short circuit, or stability analysis: the study shall be five calendar years old or less, unless a technical rationale is provided to demonstrate that the results of an older study are still valid. [R2.6.1]
- For steady state, short circuit, or stability analysis: no material changes have occurred to the System represented in the study. Documentation to support the technical rationale for determining material changes shall be included in the written assessment. [R2.6.2]

For planning events shown in Table 1, when the analysis indicates an inability of the System to meet the required performance criteria, the Planning Assessment shall include Corrective Action Plan(s) addressing how the performance requirements will be met. Revisions to the Corrective Action Plan(s) are allowed in subsequent Planning Assessments but the planned System shall continue to meet the required performance criteria. Corrective Action Plan(s) do not need to be developed solely to meet the performance requirements for a single sensitivity case. For short circuit analysis, if the short circuit current interrupting duty on circuit breakers exceeds their Equipment Rating, the Planning Assessment shall include a Corrective Action Plan to address the Equipment Rating violations. [R2.7] [R2.8]

The Corrective Action Plan(s) shall:

- List System deficiencies and the associated actions needed to achieve required System performance. [R2.7.1] [R2.8.1]
- For Steady state and Stability Studies, include actions to resolve performance deficiencies identified in multiple sensitivity studies or provide a rationale for why actions were not necessary. [R2.7.2]
- Be reviewed in subsequent annual Planning Assessments for continued validity and implementation status of identified System Facilities and Operating Procedures. [R2.7.4] [R2.8.2]

When an entity's spare equipment strategy could result in the unavailability of major Transmission equipment that has a lead time of one year or more (such as a transformer), the impact of this possible unavailability on System performance shall be studied. The studies shall be performed for the P0, P1, and P2 categories identified in Table 1 with the conditions that the System is expected to experience during the possible unavailability of the long lead time equipment. NIPSCO Transmission Planning shall evaluate its current stock and procurement strategy annually. Conclusions of this evaluation shall be stated in the assessment report. [R2.1.5]

In accordance with TPL-001-4 R7, NIPSCO has executed a Coordination Agreement with MISO identifying individual and joint responsibilities for performing the required studies. NIPSCO has not delegated any of their TPL responsibilities to MISO. In addition to any data requests made by MISO required to fulfill their TPL requirements, NIPSCO will also provide results from its Short Circuit studies to MISO. [R7]

Transmission Planning shall distribute its Planning Assessment results to adjacent Planning Coordinators and adjacent Transmission Planners within 90 calendar days of completing its Planning Assessment, and to any functional entity that has a reliability related need and submits a written request for the information within 30 days of such a request. If a recipient of the Planning Assessment results provides documented comments on the results, the respective Planning Coordinator or Transmission Planner shall provide a documented response to that recipient within 90 calendar days of receipt of those comments. Recipients of the Planning Assessment include: MISO, PJM, METC, Duke, and Ameren. [R8] [R8.1]

## ***2.1 MODEL DATA***

NIPSCO Transmission Planning shall maintain System models within the NIPSCO area for performing the studies needed to complete its Planning Assessment. The models are consistent with provisions of the most recent Multiregional Modeling Working Group Procedure Manual and the most recent MOD-32 standard, supplemented by other sources as needed, including items represented in the Corrective Action Plan, and shall represent projected System conditions. This establishes Category P0 as the normal System condition in Table 1. [R1].

System Models Represent:

- Existing Facilities
- Known outage(s) of generation or Transmission Facility(ies) with a duration of at least six months. [R2.1.3]
- New planned Facilities and changes to existing Facilities
- Real and reactive Load forecasts
- Known commitments for Firm Transmission Service and Interchange
- Resources (supply or demand side) required for Load

A project is considered “planned” and is modeled in the base cases when a continuing need has been identified by recent and past study results. The planned project, in general, is needed in the near term and typically has budget approval for engineering or material costs.

A “proposed” project is typically not modeled in base cases. The “proposed” project is being studied for continuing need and timing when project lead time is sufficient. A “proposed” project may also be conceptual in nature. It has been identified as a possible solution in long term studies where violations may be marginal. It may also be identified as a possible solution to stressed or alternative dispatch cases. Alternative projects may be studied for best solution. Proposed projects are given a “planned” status after need has been proven, taking into consideration sufficient lead time.

## 2.2 *STEADY STATE*

In accordance with NERC Standard TPL-001-4, the following system conditions are required for study annually:

- System peak Load for either Year One or year two, and for year five. [R2.1.1]
- System Off-Peak Load for one of the five years [R2.1.2.]
- A current study assessing expected System Peak Load conditions for one of the years in the Long-Term Transmission Planning Horizon and the rationale for why that year was selected. [R2.2.1]

For each of the Near-Term studies described above, sensitivity case(s) shall be utilized to demonstrate the impact of changes to the basic assumptions used in the model. To accomplish this, the sensitivity analysis in the Planning Assessment will vary one or more of the following conditions by a sufficient amount to stress the System within a range of credible conditions that demonstrate a measurable change in System response: [R2.1.4]

- Real and reactive forecasted Load.
- Expected transfers.
- Expected in service dates of new or modified Transmission Facilities.
- Reactive resource capability.
- Generation additions, retirements, or other dispatch scenarios.
- Controllable Loads and Demand Side Management.
- Duration or timing of known Transmission outages.



## 2.2.1 Contingency Analysis

For the steady state portion of the Planning Assessment, Transmission Planning shall perform studies for the Near-Term and Long-Term Transmission Planning Horizons mentioned above. The studies shall be based on computer simulation models using data provided in accordance with TPL-001-4 Requirement R1. [R3]

A list of those Contingencies to be evaluated for System Performance for Planning Events shall be created corresponding to the Planning Events P0-P7 listed in Table 1. For steady state, all planning events are simulated unless contingency outages duplicate the same elements as those of another contingency. Results of these simulations should be assessed to determine whether the BES meets the performance requirements in section 2.2.2. [R3.1] [R3.4]

A list of Contingencies for those extreme events listed in Table 1 that are expected to produce more severe System impacts shall be identified and created. For Steady-State, all extreme events listed in Table 1, extreme events #1 and #2 shall be simulated. Wide-area events affecting the Transmission System, such as those described in Table 1, extreme events #3, may be evaluated. A description and rationale of these wide-area events, if included, will be documented in the assessment. If the analysis concludes there is Cascading caused by the occurrence of extreme events, an evaluation of possible actions designed to reduce the likelihood or mitigate the consequences and adverse impacts of the event(s) shall be conducted. [R3.2] [R3.5]

Transmission Planning shall coordinate with adjacent Planning Coordinators and Transmission Planners to ensure that Contingencies on adjacent Systems which may impact their Systems are included in the Contingency list. [R3.4.1]

Contingency analysis shall simulate the removal of all elements that the Protection System and other automatic controls that are expected to normally clear or disconnect for each Contingency without operator intervention. [R3.3.1]

The analyses shall include the impact of subsequent:

- Tripping of generators where simulations show generator bus voltages or high side of the generation step up (GSU) voltages are less than known or assumed minimum generator steady state or ride through voltage limitations. Synchronous generator terminal voltages will be monitored at 85% for potential tripping. Solar and Wind machine terminal voltages will be monitored at 90% for potential tripping. [R3.3.1.1]
- Tripping of Transmission elements where relay loadability limits are exceeded. A tripping proxy of 125% of Emergency Rating will be used for all lines and transformers. When exceeded, Transmission Planning will consult Protection Engineering to obtain actual trip values and determine if a corrective action plan is necessary. [R3.3.1.2]

Contingency analysis shall simulate the expected automatic operation of existing and planned devices designed to provide steady state control of electrical system quantities when such devices impact the study area. [R3.3.2]

## 2.2.2 Steady-State Performance Requirements and Criteria [R5]

- Voltages, post-contingency voltages, and post-contingency voltage deviations shall be within acceptable limits. See Steady-State Voltage Tables below.
- Applicable Facility Ratings shall not be exceeded. Transmission Planning establishes Normal and Emergency Facility Ratings for summer and winter seasonal periods based on its documented Facility Rating Methodology. Single Breaker Ratings are also established for use in studies where the contingency may cause a facility to have a more limited rating.
- The transmission system shall not experience uncontrolled cascading or islanding. Load loss shall not exceed 300 MWs, excluding consequential load. See section 2.5, Supplemental Performance Analysis. [R6]
- Synchronous generators are projected to trip when the terminal voltage is below 85%. Solar and Wind machines are projected to trip when the terminal voltage is below 90%. [R3.3.1.1]
- Consequential Load Loss as well as generation loss is acceptable as a result of any event excluding category P0 No Contingency.
- The response of voltage sensitive Load that is disconnected from the System by end-user equipment associated with an event shall not be used to meet steady-state performance requirements.

Steady-State Voltage Tables

Location	Normal Condition		Post-Contingency Steady-State		
	Minimum	Maximum	Minimum	Maximum	Deviation
765 kV buses	92%	105%	90%	105%	+/- 10%
345 kV buses	92%	105%	90%	105%	+/- 10%
138 kV buses	92%	105%	90%	105%	+/- 10%
69 kV buses	94%	105%	92%	105%	+/- 10%
On-Line Synchronous Generator Terminals [3.3.1.1]	95%	105%	85%	107%	+/- 10%
On-Line Solar + Wind Machine Terminals [3.3.1.1]	95%	105%	90%	105%	+/- 10%

Location	Normal Condition		Post-Contingency Steady-State		
	Minimum	Maximum	Minimum	Maximum	Deviation
Customer Substation 138kV Buses	95%	105%	90%	110%	+/- 10%

## 2.3 STABILITY

In accordance with NERC Standard TPL-001-4, the following system conditions are required for study annually:

- System peak Load for one of the five years. System peak Load levels shall include a Load model which represents the expected dynamic behavior of Loads that could impact the study area, considering the behavior of induction motor Loads. An aggregate System Load model which represents the overall dynamic behavior of the Load is acceptable. [R2.4.1]
- System Off-Peak Load for one of the five years. [R2.4.2]

For each of the studies described above, sensitivity case(s) shall be utilized to demonstrate the impact of changes to the basic assumptions used in the model. To accomplish this, the sensitivity analysis in the Planning Assessment must vary one or more of the following conditions by a sufficient amount to stress the System within a range of credible conditions that demonstrate a measurable change in performance: [R2.4.3.]

- Load level, Load forecast, or dynamic Load model assumptions.
- Expected transfers.
- Expected in service dates of new or modified Transmission Facilities.
- Reactive resource capability
- Generation additions, retirements, or other dispatch scenarios.

For the Planning Assessment, the Long-Term Transmission Planning Horizon portion of the Stability analysis shall be assessed to address the impact of proposed material generation additions or changes in that timeframe and be supported by current or past studies and shall include documentation to support the technical rationale for determining material changes. [R2.5]

Loads shall be modeled by P (constant current) and Q (constant impedance) which represents the aggregate overall dynamic load behavior. For sensitivity analysis, loads may be modeled by a composite load model considering more detailed behavior of induction motor loads. [R2.4.1]

### 2.3.1 Contingency Events

For the Stability portion of the Planning Assessment, Transmission Planning shall perform the Contingency analyses for the Near-Term and Long-Term Planning Horizons mentioned above. The studies shall be based on computer simulation models using data provided in accordance with TPL-001-4 R1. [R4]

A list of those Contingencies to be evaluated for System Performance for Planning Events shall be created corresponding to the Planning Events P0-P7 listed in Table 1. For transient stability, Planning Events for transmission facilities directly associated to an individual power plant as well as Planning Events for other selected transmission facilities are simulated. [R4.4]

Those extreme events in Table 1 that are expected to produce more severe System impacts shall be identified and a list created of those events to be evaluated for impact to the BES. The rationale for those Contingencies selected for evaluation shall be available as supporting information. If the analysis concludes there is Cascading caused by the occurrence of extreme events, an evaluation of possible actions designed to reduce the likelihood or mitigate the consequences of the event(s) shall be conducted. [R4.2] [R4.5]

Each Planning Coordinator and Transmission Planner shall coordinate with adjacent Planning Coordinators and Transmission Planners to ensure that Contingencies on adjacent Systems which may impact their Systems are included in the Contingency list. [R4.4.1]

Contingency analyses shall simulate the removal of all elements that the Protection System and other automatic controls are expected to disconnect for each Contingency without operator intervention. [R4.3] [R4.3.1]

The contingency analyses shall include the impact of subsequent:

- Successful high speed (less than one second) reclosing and unsuccessful high speed reclosing into a Fault where high speed reclosing is utilized. [R4.3.1.1]
- Tripping of generators where simulations show generator bus voltages or high side of the GSU voltages are less than known or assumed generator low voltage ride through capability. Include in the assessment any assumptions made. [R4.3.1.2]
- Tripping of Transmission lines and transformers where transient swings will cause a Protection System operation based on generic or actual relay models. [R4.3.1.3]

Contingency analyses shall simulate the expected automatic operation of existing and planned devices designed to provide dynamic control of electrical system quantities when such devices impact the study area. These devices may include equipment such as generation exciter control and power system stabilizers, synchronous condensers, static var compensators, power flow controllers, and DC Transmission controllers. [R4.3.2]

Studies shall be performed for planning events to determine whether the BES meets the following stability performance requirements and criteria: [R4.1] [R4.2]

### 2.3.2 Stability Performance Requirements and Criteria [R5]

The transmission system shall not experience uncontrolled cascading or islanding.

For planning event P1: No generating unit shall pull out of synchronism. A generator being disconnected from the System by fault clearing action or by a Special Protection System is not considered pulling out of synchronism. [R4.1.1]

For planning events P2 through P7: When a generator pulls out of synchronism in the simulations, the resulting apparent impedance swings shall not result in the tripping of any Transmission system elements other than the generating unit and its directly connected Facilities. [R4.1.2]

For planning events P1 through P7: Power oscillations shall exhibit acceptable damping. Observed damping ratio ( $\zeta$ ) shall be greater than 0.020. [R4.1.3]

Synchronous Generator Voltage: Voltages at the terminal bus of on-line synchronous generators shall return to the allowable steady-state contingency voltage within five seconds after fault clearing. [R4.3.1.2]

Solar Generating Plant Voltage: Solar plants shall have low voltage ride-through capability monitored at the high-side GSU terminal down to 0% of the rated voltage for 0.150 seconds (9.0 cycles) for three-phase faults and down to 0% of the rated voltage for 0.433 seconds (26.0 cycles) for single-line ground faults. [R4.3.1.2]

Wind Generating Plant Voltage: Wind plants shall have low voltage ride-through capability monitored at the high-side GSU terminal down to 0% of the rated voltage for 0.150 seconds (9.0 cycles) for three-phase faults (Per FERC Order 661-A) and down to 0% of the rated voltage for 0.433 seconds (26.0 cycles) for single-line ground faults. [R4.3.1.2]

Load Bus Voltages: Voltages at load buses should return to the allowable steady-state contingency voltage within five seconds after fault clearing.

## **2.4 SHORT CIRCUIT**

The short circuit analysis portion of the Planning Assessment shall be conducted annually addressing the Near-Term Transmission Planning Horizon and shall be supported by current or qualified past studies. The analysis shall be used to determine whether circuit breakers have the capability to interrupt the maximum short-circuit current the circuit breaker is expected to experience. [R2.3]

The System short-circuit model for the analysis shall be updated annually including planned generation and transmission facilities within NIPSCO, and including planned generation and transmission facilities in adjoining areas within two busses of NIPSCO.

The maximum expected short-circuit current that a circuit breaker is expected to interrupt shall be determined by performing both three-phase (3 $\phi$ ) and single line-to-ground (SLG) fault simulations in accordance with the IEEE standard C37-010-1999 and utilizing the calculation methodology of the ASPEN Oneliner™ Breaker Rating Module. The circuit breaker interrupting rating shall be based on its nameplate value and not derated based on circuit breaker reclosing operations.

Circuit breakers with interrupting duty of 100% or greater of the interrupting rating shall be considered an identified deficiency.

## **2.5 SUPPLEMENTAL PERFORMANCE ANALYSIS**

### **2.5.1 Cascading**

Cascading potential shall be evaluated by sequentially removing those facilities with steady-state loading in excess of 125% of their emergency rating and those generating units with steady-state terminal voltage below their specified voltage criteria. [R6]

### **2.5.2 Uncontrolled Islanding**

Uncontrolled islanding potential shall be evaluated by review of identified cascading outages that result in load being isolated with generation from the interconnected system. [R6]

### **2.5.3 Voltage Stability**

Voltage stability analysis shall be performed for the Near-Term and Long-Term Planning Horizons mentioned above. Voltage stability shall be evaluated through the application of the Fast Voltage Stability Index (FVSI) and Voltage Stability Index Le. Analysis shall be performed for N-0 and N-1 contingency conditions. A voltage stability index value of 1.0 or greater is an indication of voltage instability. [R6]

### **3 FACILITY CONNECTION, TRANSMISSION SERVICE REQUEST ASSESSMENTS, AND GENERATOR RETIREMENTS**

Transmission Reliability Planning Tests are performed on Facility Connection projects, Transmission Service Requests (TSR's), and Generation Retirements to evaluate any Thermal or Voltage criteria violations caused by projects originated through PJM, MISO and NIPSCO processes on NIPSCO's transmission system.

#### ***3.1 INDIVIDUAL CONTRIBUTION TEST AND CUMULATIVE IMPACT TEST (CIT)***

The Facility Connection Projects, TSR's, and Generation Retirements impacting NIPSCO's transmission shall be subject to two tests: the Individual Contribution Test and the Cumulative Impact Test.

The Facility Connections, TSR's, and Generation Retirements screened through the following two tests are studied for their impact on NIPSCO's transmission system. The RTEP and MTEP cases used by PJM and/or MISO will be used in the study process. Peak, off-peak, and high wind cases should be evaluated to determine worst-case impact. Mitigations will be determined for all thermal and/or voltage violations evaluated under NERC Contingency Categories P0, P1, P2, P5 and P7.

##### **Individual Contribution Test:**

The test is performed to identify individual Facility Connections, TSRs, and Generation Retirements affecting NIPSCO's transmission system. For a Facility Connection, TSR, or Generation Retirement to be considered to be impacting the NIPSCO transmission system, it should adhere to one of the two rules:

1. The contribution of the Distribution Factor of the Facility Connection, TSR, or Generation Retirement with magnitude of 3% or greater contributing to an overload on a NIPSCO facility.
2. The Contribution of a Facility Connection, TSR, or Generation Retirement on a NIPSCO facility is equal to or greater than 3% of the facility rating.

##### **Cumulative Impact Test (CIT):**

NIPSCO shall also perform a test to evaluate the cumulative impact of multiple Facility Connections, TSRs, and Generation Retirements when they are grouped together in the same study during the PJM and/or MISO process. The Facility Connections, TSRs, and Generation Retirements having a cumulative impact of at least 10% of the facility rating will be considered as impacting NIPSCO's transmission system. There is no minimum threshold to assign individual impact.

#### ***3.2 ENERGY STORAGE OR HYBRID FACILITY INTERCONNECTIONS***

The maximum expected charging load for any storage or hybrid facility interconnection to NIPSCO's transmission system will be studied as a non-interruptible load in both peak and off-peak conditions according to the most recent NERC TPL-001-4 standard methodology using the most recent NIPSCO transmission planning criteria.

**TABLE 1. PLANNING AND EXTREME EVENTS**

<b>Category</b>	<b>Initial Condition</b>	<b>Event</b>	<b>Fault Type</b>	<b>Notes</b>
P0	Normal System	None	N/A	Initial System Condition
P1 Single Contingency	Normal System	Loss of one of the following: <ol style="list-style-type: none"> <li>1. Generator</li> <li>2. Transmission Circuit</li> <li>3. Transformer</li> <li>4. Shunt Device</li> </ol>	3 $\emptyset$	
P2 Single Contingency	Normal System	<ol style="list-style-type: none"> <li>1. Opening of a line section w/o a fault</li> </ol>	N/A	
		<ol style="list-style-type: none"> <li>2. Bus Section Fault</li> </ol>	SLG	
		<ol style="list-style-type: none"> <li>3. Internal Breaker Fault (non-bus tie)</li> </ol>	SLG	
		<ol style="list-style-type: none"> <li>4. Internal Breaker Fault (Bus-tie Breaker)</li> </ol>	SLG	
P3 Multiple Contingency	Loss of generator unit followed by System Adjustments	Loss of one of the following: <ol style="list-style-type: none"> <li>1. Generator</li> <li>2. Transmission Circuit</li> <li>3. Transformer</li> <li>4. Shunt Device</li> </ol>	3 $\emptyset$	
P4 Multiple Contingency (Fault plus Stuck Breaker)	Normal System	Loss of Multiple Elements Caused by a stuck Breaker (non-bus tie) attempting to clear a fault on one of the following: <ol style="list-style-type: none"> <li>1. Generator</li> <li>2. Transmission Circuit</li> <li>3. Transformer</li> <li>4. Shunt Device</li> <li>5. Bus Section</li> <li>6. Loss of Multiple elements caused by a stuck Bus-tie Breaker attempting to clear a fault on the associated bus.</li> </ol>	SLG	



<b>Category</b>	<b>Initial Condition</b>	<b>Event</b>	<b>Fault Type</b>	<b>Notes</b>
P5	Normal System	Delayed Fault Clearing due to the failure of a non-redundant relay protecting the Faulted element to operate as designed, for one of the following: <ol style="list-style-type: none"> <li>1. Generator</li> <li>2. Transmission Circuit</li> <li>3. Transformer</li> <li>4. Shunt Device</li> <li>5. Bus section</li> </ol>	SLG	
P6 Multiple Contingency	Loss of one of the following followed by System adjustments. Loss of one of the following: <ol style="list-style-type: none"> <li>1. Transmission Circuit</li> <li>2. Transformer</li> <li>3. Shunt Device</li> </ol>	Loss of one of the following: <ol style="list-style-type: none"> <li>1. Transmission Circuit</li> <li>2. Transformer</li> <li>3. Shunt Device</li> </ol>	3 $\emptyset$	Curtailement of Firm Transmission Service is allowed as a System adjustment as identified in the column entitled 'Initial Condition'.
P7 Multiple Contingency	Normal System	The loss of: <ol style="list-style-type: none"> <li>1. Any two adjacent (vertically or horizontally) circuits on common structure.</li> </ol>	SLG	Excludes circuits that share a common structure for 1 mile or less.

<b>Category</b>	<b>Initial Condition</b>	<b>Event</b>	<b>Fault Type</b>	<b>Notes</b>
Extreme Event -Steady State 1	Loss of one of the following: <ol style="list-style-type: none"> <li>1. Generator</li> <li>2. Transmission Circuit</li> <li>3. Transformer</li> <li>4. Shunt Device</li> </ol>	Loss of one of the following: <ol style="list-style-type: none"> <li>1. Generator</li> <li>2. Transmission Circuit</li> <li>3. Transformer</li> <li>4. Shunt Device</li> </ol>	Steady State Only	
Extreme Event -Steady State 2	Normal	Local Area events affecting the Transmission System such as: <ol style="list-style-type: none"> <li>a. Loss of a tower line with three or more circuits.</li> <li>b. Loss of all Transmission lines on a common Right-of-Way.</li> <li>c. Loss of a switching Station or Substation (loss of one voltage level plus transformers)</li> <li>d. Loss of all generating Units a generating Station</li> <li>e. Loss of a large Load or major Load Center</li> </ol>	Steady State Only	
Extreme Event -Steady State 3	Normal System	Wide area events affecting the transmission System based on System Topology such as: <ol style="list-style-type: none"> <li>a. Loss of two generating Stations.</li> <li>b. Other events based upon operating experience that may result in wide area disturbances.</li> </ol>	Steady State Only	

<b>Category</b>	<b>Initial Condition</b>	<b>Event</b>	<b>Fault Type</b>	<b>Notes</b>
Extreme Event -Stability 1	Loss of one of the following: <ol style="list-style-type: none"> <li>1. Generator</li> <li>2. Transmission Circuit</li> <li>3. Transformer</li> <li>4. Shunt Device</li> </ol>	3 $\emptyset$ fault on one of the following: <ol style="list-style-type: none"> <li>1. Generator</li> <li>2. Transmission Circuit</li> <li>3. Transformer</li> <li>4. Shunt Device</li> </ol>	Stability Only -3 $\emptyset$	
Extreme Event -Stability 2	Normal System	Local or wide area events affecting the Transmission System such as: <ol style="list-style-type: none"> <li>a. 3<math>\emptyset</math> fault on generator with stuck breaker or a relay failure resulting in Delayed Fault Clearing.</li> <li>b. 3<math>\emptyset</math> fault on Transmission Circuit with stuck breaker or a relay failure resulting in Delayed Fault Clearing.</li> <li>c. 3<math>\emptyset</math> fault on Transformer with stuck breaker or a relay failure resulting in Delayed Fault Clearing.</li> <li>d. 3<math>\emptyset</math> fault on bus section with stuck breaker or a relay failure resulting in Delayed Fault Clearing.</li> <li>e. 3<math>\emptyset</math> internal breaker fault</li> <li>f. Other events based upon operating experience, such as consideration of initiating events that experience suggests may result in wide area disturbances.</li> </ol>		

Confidential Attachment 2-E (Redacted)

[Distribution Automation Program Business Case]

Confidential Attachment 2-F (Redacted)

[Long-Term Communications Plan]

## **Execution and Management of the Plan**

### **Execution of the Plan**

The Engineering and Asset Risk Management Departments developed the 2021-2026 Electric Plan as well as the cost estimates for the projects. The portfolio of projects included in the 2021-2026 Electric Plan are then assigned to the Scope Development & Estimating, Electric Projects, Project Management and Construction Department for execution and management. The TDSIC Project Controls Team has the primary role of verifying that TDSIC project costs are accurately forecasted and accounted for. This includes obtaining, validating, tracking and paying invoices for the portfolio of projects included in the 2021-2026 Electric Plan. The TDSIC Project Controls Team is also responsible for creating monthly forecasts and accruals with input from the Electric Projects and Construction Department.

### **Management of Projects**

NIPSCO's internal stakeholders worked to develop the 2021-2026 Electric Plan as well as the cost estimates for the projects. The portfolio of projects included in the 2021-2026 Electric Plan are then assigned to the Scope Development & Estimating, Electric Projects, Project Management and Construction Department for execution and management. The TDSIC Project Controls Team has the primary role of verifying that TDSIC project costs are accurately forecasted and accounted for. This includes obtaining, validating, tracking and paying invoices for the portfolio of projects included in the 2021-

2026 Electric Plan. The TDSIC Project Controls Team is also responsible for creating monthly forecasts and accruals with input from the Electric Projects and Construction Department.

### **Management of Costs**

The process for initiating a new TDSIC work order begins with the Project Engineer/Manager submitting a Capital Initiative Form (“CIF”) to the TDSIC Support Budget Analyst. The Budget Analyst routes the CIF to the Plan Owner and the Project Execution Team for two levels of approval. The purpose of the first level of approval, termed “TDSIC Verification,” is to verify that the project and costs are TDSIC eligible. This ensures that only eligible project costs are tracked via the TDSIC tracker. The Plan Owner approves projects for TDSIC eligibility by referring to NIPSCO’s currently approved 2021-2026 Electric Plan. The Plan Owner is responsible for understanding the intent and purpose of the overall Plan, and reviews all requests to determine if the work is approved within the Plan. The Plan Owner also reviews new project requests to be included in the next Plan update and determines if the project is an eligible improvement and necessary for purposes of system reliability and Grid Modernization. This is a critical piece of the TDSIC Plan as it allows the most flexibility for the utility as the system continues to change.

The purpose of the second level of approval, termed “Work Order Approval,” is to authorize the project work. The work order is approved by the Project Execution Leaders depending on the dollar amount of the request. Both TDSIC Verification and Work Order Approval are required before work is performed and project costs are incurred. The only exception to this process is when a work order is needed for an emergency, where approvals are obtained after the work order is provided to the Project Engineer/Manager. If the work order is determined not to be an eligible TDSIC project after it was routed through for formal approval, the work order is cancelled and removed from the TDSIC work order list. The emergency work order process is not a common occurrence, but may occasionally happen.

At the time of request and during the review and approval process, TDSIC work orders are identified and classified by category and sub-category. Once approved, the TDSIC Budget Analyst flags the TDSIC work order in NIPSCO’s Fixed Asset System (PowerPlant) with the specific TDSIC category and sub-category. These identifiers and classifications in PowerPlant assist in ensuring that only TDSIC work orders are included for recovery.

Once a TDSIC work order is initiated, NIPSCO records charges to the work order in accordance with the internal controls discussed below. Capital dollars at NIPSCO are separated into two segments: (1) direct capital and (2) indirect capital. Direct capital



represents costs such as the materials and equipment installed and the labor costs of the workers performing the construction. Typically, these are costs that are incurred at the job site. Indirect costs are associated with capital projects and must be capitalized in order to comply with GAAP. However, these often cannot be charged directly to a specific capital project work order as they cannot be directly linked to one particular project. These capital costs tend to be incurred away from the job site. NIPSCO groups these indirect capital costs into three categories: (1) overheads, (2) stores, freight and handling, and (3) AFUDC. Vendor related direct costs are procured through the use of a Material Requisition ("MR"). A purchase order ("PO") is required to order goods or services. To initiate a PO with a vendor, an MR is initiated and routed for approval. The MRs related to TDSIC projects are labeled with a specific route code to ensure they are first routed to the TDSIC Project Controls Team, who then routes the request for required approvals. The MRs are approved by the Project Execution Leaders depending upon the dollar amount of the request. The Procurement group then generates a PO, which is identified as a TDSIC PO. This TDSIC route code on the PO ensures that TDSIC invoices are routed to the TDSIC Project Controls Team for validation. The TDSIC Project Controls Team routes TDSIC invoices to the TDSIC Project Execution group for two levels of approval.

In addition to the controls discussed above, the TDSIC Project Controls Team provides to the TDSIC Project Managers reports weekly that show the actual project costs recorded to each work order. The TDSIC Project Controls Cost Engineers meet monthly

one-on-one with the TDSIC Project Managers to review actual costs, to estimate accruals, and to forecast the project costs. TDSIC Project Managers also review all project costs to ensure that costs are properly recorded to the TDSIC work orders. This process includes the review of non-vendor payments such as internal labor and other direct costs. The TDSIC Project Manager reviews the detailed project cost reports provided by the TDSIC Project Controls Team to ensure that all vendor payments are properly recorded, and internal labor charges are appropriate. Any unusual charges are investigated and corrected if necessary.

### **Project Management Principles**

NIPSCO's Project Managers have been trained and most have been certified as Project Management Professionals ("PMPs") and follow the Project Management Institute ("PMI") Project Management Body of Knowledge ("PMBOK") principles. The project life cycle is a core concern of NIPSCO's senior leadership, as well as the rest of the organization, and the status of each project is reviewed on a monthly basis. As discussed above, a TDSIC Project Controls Team is in place to ensure that items such as cost, scope, schedule and safety are being properly managed.

## **Inclusion of Contingency in Cost Estimates**

Contingency is an amount added to a project base cost estimate to cover uncertainty and project risk. Incorporation of contingency is critical to creating a realistic estimate of the final project cost and increases the transparency around the expected cost at completion for a project. Projects are developed through a process of progressive elaboration whereby details to complete the scope required to satisfy the project deliverables are developed through an iterative process over time. Projects are generally not fully engineered or bid at the time the cost estimates are developed. To expend the resources required to eliminate uncertainty during early stages of project development would not be cost effective or reasonable.

Contingency is added for several reasons, including but not limited to: (1) covering details that may be identified later in the iterative design process; (2) covering requirements that may not have been reasonably anticipated during the land acquisition or permitting process; (3) addressing responses or exceptions that may not have been reasonably anticipated during the bid process; (4) changes in system configuration or operational constraints; or (5) accounting for field conditions where it is neither possible nor reasonable to identify all construction risks that could be encountered. It is important to note that a contingency may not cover all unanticipated costs. The AACE recognizes use of contingency to mitigate unexpected, additional costs as industry best practices. Without the inclusion of contingency, project estimates would not be “best estimates” as

required by the TDSIC Statute. Once NIPSCO successfully completes various stages of a project, the contingency amount is updated.

Maintaining an appropriate contingency can actually prevent project cost increases by providing a process that avoids costly project interruptions or delays when an issue or risk is realized. The contingency is added to cover estimate uncertainty and risk. Contingency increases transparency for the project stakeholders and provides the Project Manager with an appropriate tool to manage issues or risks that may be realized during project development or execution. It also provides the Project Manager with resources to avoid detrimental trade-offs in schedule, scope, quality, or functionality. Ultimately, an appropriate contingency increases the confidence in completing the project within the estimated cost.

Contingency is a way of accounting for known or potential risks associated with a project, and is not inclusive of every risk that could impact the cost of completion. For example, with construction in northwest Indiana, dewatering can become a significant part of the project expense due to the high ground water table. The estimates provide for normal or reasonably anticipated dewatering costs. The contingency is assigned to at least partially cover unusual conditions where extensive dewatering is required. However, it is not intended to fully cover dewatering from conditions that are historically atypical, such as record levels of precipitation during a particular construction season.

For projects planned for execution further out in the Plan, another risk that is not covered by contingency is the potential for significant changes in costs on materials since material fluctuations can be affected by unforeseen circumstances, as evidenced by recent circumstances related to lumber and other raw materials increasing dramatically. The demand for labor could also increase costs more than the amount that was included in the current estimates.